

GOVERNMENT OF INDIA

DEPARTMENT OF ARCHAEOLOGY

CENTRAL ARCHÆOLOGICAL
LIBRARY

R 417.05/E.I.


CALL NO.


ACG. NO.


69'329

D.G.A. 79.

GIPN—S4—2—D. G. Arch. N. D./57.—25—58—1,00,000.







EPIGRAPHIA INDICA

VOL. XIV. 1917-18.




PUBLISHED BY
THE DIRECTOR GENERAL
ARCHAEOLOGICAL SURVEY OF INDIA
JANPATH, NEW DELHI-110011

1982

Reprinted 1982

©
ARCHAEOLOGICAL SURVEY OF INDIA
GOVERNMENT OF INDIA
1982



Price : Rs. 90

PUBLISHED BY
THE DIRECTOR GENERAL
ARCHAEOLOGICAL SURVEY OF INDIA
JANAKI NEW DELHI-11001

Printed at Pearl Offset Press, 5/33, Kirti Nagar Indl. Area New Delhi-15

PUBLISHED UNDER THE AUTHORITY OF THE GOVERNMENT OF INDIA AS A SUPPLEMENT
TO THE "INDIAN ANTIQUARY."

EPIGRAPHIA INDICA

AND

RECORD OF THE ARCHÆOLOGICAL SURVEY OF INDIA

69329

VOL. XIV. 1917-18.

EDITED BY

F. W. THOMAS, M.A., HON. PH.D.,

HONORARY CORRESPONDENT OF THE GOVERNMENT OF INDIA, ARCHÆOLOGICAL DEPARTMENT.



R417.05
E.I

CALCUTTA:

SUPERINTENDENT GOVERNMENT PRINTING, INDIA.

BOMBAY: BRITISH INDIA PRESS.

LONDON: KEGAN PAUL, TRENCH,
TRÜBNER & Co.

NEW YORK: WESTERMANN & Co.
CHICAGO: S. D. PEET.

PARIS: E. LEROUX.

69329

प्रधान मन्त्री

29/10/82

निर्देश संख्या...

R. 417.05

E.I

नई दिल्ली

केन्द्रीय पुरातत्व प्रस्तावना

258

Vol. XIV, 1918



CONTENTS.

The names of contributors are arranged alphabetically.

	PAGE
R. D. BANERJI:—	
No. 10. Nalhati Grant of Vallala-Bena : the 11th year	156
" 23. Bangarh Grant of Mahi-pala I : the 9th year	324
" 29. A note on King Chandra of the Meharsuli Inscription	368
LIONEL D. BARNETT:—	
No. 14. Lakshmeshwar Pillar Inscription of the Yuvaraja Vikramaditya	188
" 19. Two Inscriptions from Kurgod	265
A.—Of Somesvara IV and the Sinda prince Rachamalla II : Saka 1095 and 1108	265
B.—Of the same reign	278
" 21. Arthuna Inscription of the Paramara Chamundaraja : Vikrama-Samvat 1136	296
" 28. Tuppud-Kurhatti Inscription of Akalavarsha-Krishna III	372
K. N. DIKSHIT:—	
No. 11. Sangoli Plates of Harivarman : the 8th year	163
T. A. GOPINATHA RAO:—	
No. 3. Srirangam Plates of Mummadi Nayaka : Saka-Samvat 1280	83
HIRANAYDA SASTRI:—	
No. 5. Haraha Inscription of the reign of Isanavarman : Vikrama-Samvat 611	110
STEN KONOW:—	
No. 7. Ars Inscription of Kanishka II : the year 41	130
" 8. Sanjan Plates of Buddhavarasa	144
" 20. Taxila Inscription of the year 136	284
GAURISHANKAR HIRACHAND OJHA:—	
No. 13. Partabgarh Inscription of the time of (the Pratihara) King Mahendra-pala II of Mahodaya : Samvat 1003	176
LEWIS RICE:—	
No. 24. Penukonda Plates of Madhava II (III)	331
DAYA RAM SAHNI:—	
No. 15. Chandravati Plates of Chandra-deva : Vikrama-Samvat 1150 and 1156	192
G. RAMADAS:—	
No. 27. Purie Plates of Indravarmas : the (Ganga) year 1189	360
ROBERT SEWELL:—	
No. 1. The True Longitude of the Sun in Hindu Astronomy	1
" 18. " " " " " : The Siddhanta-Siromani	241
Y. S. SUKTHANKAR:—	
No. 4. Porumamilla Tank Inscription of Bhaskara Bhavadura : Saka 1291	97
" 6. Bhan/lak Plates of Krishnaraja I : Saka 694	121
" 9. A new Andhra Inscription of Siri-Pulumavi	153

S. V. VENKATESWARA AND S. V. VISWANATHA :—	PAGE
No. 12. Udayambakam Grant of Krishna-deva-Raya : Saka 1450	163
" 16. Bevinahalli Grant of Sadasiva-Raya : Saka 1473	212
" 17. Kudiyantandal Grant of Vira-Nrisimha : Saka 1429	231
" 22. Kadaladi Plates of Achyuta-Raya : Saka 1451	310
G. VENKOBΑ RAO :—	
No. 2. Dandapalle Plates of Vijaya-Bhupati : Saka-Samvat 1332	68
S. V. VISWANATHA :—	
No. 25. The Kanuma Grant of Sadasiva-Raya : Saka 1470	341
" 26. Melutaka Grant of Mahadevendra Samavati : Saka 1608	354
See also S. V. VENKATESWARA AND S. V. VISWANATHA.	

INDEX	373
Title-page, Contents, List of Plates, and Additions and Corrections	i to ix

LIST OF PLATES.

No. 1.	Dandapalle Plates of Vijaya-Bhupati : Saka-Samvat 1332, i—iva . . .	. between pages	72 & 73
" 2.	" " " " " " " " ivδ—vδ . . .	" "	76 & 77
" 3.	Srirangam Plates of Mummadi Nayaka, is—iiiδ . . .	" "	90 & 91
" 4.	" " " " " " " " ivs—va . . .	" "	94 & 95
" 5.	Portumamilla Tank Inscription : Saka 1291, Plate I . . .	" "	102 & 103
" 6.	" " " " " " " " II . . .	" "	104 & 105
" 7.	Haraha Inscription of the reign of Isanavarman : Vikrama-Samvat 611 . . .	" "	118 & 119
" 8.	Bhandak Plates of Krishnaraja I : Saka 694 . . .	" "	124 & 125
" 9.	Ara Inscription of Kanishka : Samvat 41 . . .	. to face page	143
" 10.	Sanjan Plates of Buddhavarman . . .	. between pages	150 & 151
" 11.	Jangli Gundu Inscription : year 8 of Siri-Pulumavi . . .	. to face page	155
" 12.	Nalhati Grant of Vallala-Sena : the 11th year . . .	. between pages	160 & 161
" 13.	Sangoli Plates of Harivarman : the 8th year . . .	" "	166 & 167
" 14.	Udayambakam Grant of Krishna-deva-Raya : Saka 1450 . . .	" "	172 & 173
" 15.	Partabgarh Inscription of Mahendra-pala II : Samvat 1008 . . .	. to face page	185
" 16.	Lakshmeshwar Inscription of the Yuvaraja Vikramaditya . . .	. between pages	190 & 191
" 17.	Chandravati Plates of Chandra-deva : Vikrama-Samvat 1150, i—iv . . .	" "	194 & 195
" 18.	" " " " " " " " v . . .	. to face page	196
" 19.	" " " " " " " " 1158 . . .	" " "	198
" 20.	Bevinahalli Grant of Sadasiva-Raya : Saka 1473, i—va . . .	. between pages	222 & 223
" 21.	" " " " " " " " vδ—vii . . .	. to face page	223
" 22.	Kudiyantandal Grant of Vira-Nrisinha : Saka 1429, i—iii . . .	. between pages	236 & 237
" 23.	" " " " " " " " iiiδ—iii . . .	" "	238 & 239
" 24.	Kurgod Inscription A : Saka 1096 & 1108 . . .	. to face page	272
" 25.	" " " B : " " " " . . .	" " "	280
" 26.	Taxila Inscription of the year 136 . . .	" " "	295
" 27.	Bangarh Grant of Mahi-pala I : the 9th year . . .	. between pages	326 & 327
" 28.	Pennukonda Plates of Madhava II . . .	" "	334 & 335
" 29.	Kanuma Grant of Sadasiva-Raya : Saka 1470 . . .	" "	348 & 349
" 30.	Melupaka Grant of Mahadevendra Sarasvati : Saka 1608 . . .	" "	358 & 359
" 31.	Parle Plates of Indravarman : the (Ganga) year . . .	. to face page	362
" 32.	Tuppad-Kurhatti Inscription of Saka 868 . . .	" " "	365

ADDITIONS AND CORRECTIONS.

- Page 93, text l. 50,—for मवइ read मवइ.
 „ 93, „ l. 55,—for दावकी read दावकी.
 „ 95, n. 2,—for व read वं.
 „ 96, last line but 2,—for Viltāru read Villāru.
 „ 101, text l. 8,—for सुमवाक्. read सुमवाक्.
 „ 103, „ l. 54,—for युन read युनी.
 „ 118, „ l. 20,—for षट् read षट्.
 „ 124, n. 19,—for स्वमे° read सुमे°.
 „ 158, last two lines,—for Āuhāgaddiā and Āuḍā° read Āḍ°.
 „ 170, n. 2,—for Bhāahage read Bhāshege.
 „ 171, n. 3,—for न read नं.
 „ 171, text l. 16,—[for तं च रायं read तं च रायं. See *Ep. Ind.*, Vol. III, *Add. and Corr.*, p. viii.—H. K. S.]
 „ 172, „ l. 25,—for सतामी[वी]य read सतामी[वी]य.
 „ 172, „ l. 42,—for वचैक read °व.
 „ 172, „ l. 42,—for वलदिव्य read °व.
 „ 179, n. 1,—The Hansot plates were published in *Ep. Ind.*, Vol. XII, pp. 197 sqq.
 „ 185, n. 7,—for कौमवि read °वि.
 „ 187, n. 1,—for °मयइ read °मयइ.
 „ 212, no. 16, col. 3,—for Srivatsa read Śrī°.
 „ 213, no. 24, col. 2, } —for Līngana read Līngana.
 „ 214, no. 52, col. 2, }
 „ 220, text l. 67,—for कुवसय...र read °र.
 „ 223, „ l. 137,—for मवामुइ read °इ.
 „ 231, l. 2,—for Śālivāhana reckoning read cycle.
 „ 272, text l. 41,—for da-volada read ḍa-volada.
 „ 298, v. 3,—for °jvalitair we might read, for the sake of the metre, °janitair.
 „ 301, v. 59,—for vaikalpya read vaikalya ?
 „ 306, n. 2,—The reason why the elephants recoil from drinking the water of the oceans would rather be that it is scented with the ichor of the *dig-gajas*.—H. K. S.
 „ 307, v. 44,—for 'applied his energy to battle' we might read 'bringing them to peace through battle'.
 „ 309, v. 67,—for 'the praise of the blest Maṇḍana' we might read 'the religious foundation (*kīrtana*) of the blest Maṇḍana'.
 „ 312, trans. vv. 37-42,—for in the month Makara read at a Makara-saṅkrānti.

CORRECTIONS BY PROFESSOR HULTZSCH.

VOL. XI.

- Page 84, n. 7,—for संजतः read मुंजतः.
 „ 144, text l. 33,—for पव read पव.
 „ 145, „ l. 45,—for वेम्हान read वेम्हान.
 „ 181, no. 18,—This inscription was published independently by Mr. D. R. Bhandarkar in the *Ind. Ant.*, Vol. XLII, pp. 201 sqq.
 „ 221, text l. 12,—for तिस्रहा read तिस्रहा.

VOL. XII.

- Page 62, n. 45,—for rōshapamū read rōshapamū.
 „ 63, text l. 4,—for वईनी read वईनी.
 „ 63, „ l. 12,—for चावका° read चावका°.
 „ 63, n. 12,—for ब्राहि° read ब्राहि°.
 „ 184, l. 13,—for kṛipta read kṛipta.
 „ 188, l. 23,—for Maghavanmaṇi read Maghavamāṇi.
 „ 192, text l. 42,—for विष्वा read विष्वा°.

Rao Bahadur B. Narasimhachar, M.A., has kindly communicated to me the following corrections of the paper on the Inscriptions of Kurgod in Vol. XIV, pp. 265 ff.

- Page 270, v. 8,—read bālēnduva kaḷe ("the digit of the crescent moon". It became a full moon by Parvatī's lovely glance and the lustre of her moon-face).
 „ 271, v. 13,—*ēḷidan-goy*, "to laugh at". *Ēḷidikkoyane māḍu* means the same. *Āro kōḍuvār*, "who will fight" ?
 „ 271, v. 19,—read adaguntī (=greatness), not aḍaguntī.
 „ 271, v. 20,—*avanibhrit-samaṅgalam*="equal to a mountain, great".
 „ 272, v. 21,—*Āspadey-app-Ēchala* is the correct reading. See verse 10 of inscr. B.
 „ 272, l. 34,—Yugandhara is commonly used in Kanarese inscriptions for Yangan-dharāyapa, the minister of Vatsarāja.
 „ 279, v. 2,—read Nityobhava-vesar-esav-i.
 „ 279, v. 3,—This verse is in praise of Rēchi (not rēji), who is compared to the ocean. *Ratnākara* and *śamudra* are synonymous.
 „ 280, v. 5,—Here there is a play on words. The outer town had *sara*, 'ponds' or 'musical sounds', like (*terade*) Nārada; swans (moon and sun) like the sky; and groves (*rume*=Lakshmi) like Viśhva.
 „ 280, l. 23,—the correct reading is *billam gomdu kalitanada balupin*, "having taken the bow, by the might of his prowess . . .". There is no reference to Nala.
 „ 281, v. 15,—*naij-ōnmantr-ābdi-rājash*=a moon to the ocean of proper policy.

L. D. B.

Rao Bahadur R. Narasimhaachar, M.A., has kindly supplied to me the following corrections to some of my papers in Vols. XIII and XIV of the *Epigraphia Indica*.

VOL. XIII.

- Page 41, l. 5 of text: the construction is *prabandha-kavi-rājam*, "king of poets of compositions". There is no reference to Virāṭ; Brahmā is not mentioned under that name.
- " 44, l. 30 of text: *uru-sere-goffu* = "having become prisoners". *Tannaya keya* should probably be corrected to *tann-arikeya*: 'there were none who did not send precious things and vehicles'. The alteration requires a *r*.
- " 171, l. 26 of text, and Vol. XIV, p. 271, l. 26 of text: *adagunti* should be corrected to *adagunti*, a form which occurs in literature.

VOL. XIV.

- Page 270, l. 13 of text: read *bāl-ēndura kaḷa*, "discard the crescent, now that you have the full moon". The form in -a is used for the regular accusative in -am.
- " 271, l. 17 of text: *kumtaḷa-dēsa* denotes only the place on the head where the locks of hair are; there is no reference here to the country of Kuntala.
- " 271, l. 18 of text: *bhāta* is a mistake for *chūta*.
- " 271, ll. 20-21 of text: *ālāvāḍu* = "to despise", *ālīmāḍu* = "to treat with contempt", *ēḷidirkke-māḍu* = "to mock". *ēḷidirkke* is wrong.
- " 280, l. 10 of text: *torade* is a misreading for *torade*.
- " 280, l. 23 of text: *bilam* is a mistake for *chalam*; and *Kalita-Nala* is an error for *kalitanada*, "of valour".
- Pages 280-1, ll. 25-6 of text: *bhāgadoḷ* is an error for *chāgadoḷ* ("in generosity"), which should be construed with *-udāra-śrīyan* in the previous portion of the verse.
- Page 281, l. 3 from bottom of page: *kulita* here = 'diamond'. Nails are not likened to fish.
- " 282, v. 5: the meaning of this verse is not properly brought out. The outer town with its *sara* (pond, otherwise *stara*, musical notes) resembles the sage Narada; with its *rāja-hamṣa* (royal swans, otherwise the moon, *rāja*, and the sun, *hamṣa*) it is like the sky; with its *ārame* (grove, otherwise *ā Rame*, "the celebrated Lakshmi") it is like Vishnu's breast.
- " 284, ll. 13-14 from top of page: *naij-ōnmantr-ābhāti-rājam* should be translated "a moon to the ocean of his policy", and *suviśhava-sumanō-rājan*, "an Indra in his magnificence".

L. D. R.

EPIGRAPHIA INDICA.

VOLUME XIV.

No. 1.—THE TRUE LONGITUDE OF THE SUN IN HINDU ASTRONOMY.

By ROBERT SEWELL (I.C.S., RETIRED).

(A continuation of the author's "*Indian Chronography*," continued from *Epig. Ind.* XIII. p. 103.)

234. The exact position of the true or apparent sun at sunrise of each civil day, taken for tabular purposes as mean sunrise, is one of the essential elements of Hindu chronography, and the exact position of the true moon is another. From these positions are calculated the beginning and end of each tithi and nakshatra, with the currency of these at sunrise. All over India for many centuries the civil day has been coupled with the true tithi current at sunrise, the nakshatra in which the true moon stands at sunrise being stated in the local almanacks and constantly mentioned in the dates of historical inscriptions. In southern India the nakshatra was considered of such importance that from as early as the tenth century it has regularly given its name to the day. For the proper verification of historical inscription-dates, therefore, it is of the highest importance that we should know the precise position of the true sun at any moment and more especially at the moment of mean sunrise.¹

235. Now the process adopted for this purpose in "*The Indian Calendar*" (Sewell and S. B. Dikshit, 1896), though resulting in a fair approximation, did not, for critical examinations of dates, give a sufficiently close result, as I have already explained in my "*Indian Chronography*," §§ 119, 120, pp. 42-43; something more accurate was required. We want, for each of the Indian astronomical authorities separately, extremely accurate determination of the sun's true longitude each day of the year; and there is only one way to obtain this. For each day a calculation must be made of the exact equation of the sun's centre on the basis of the sun's mean anomaly, according to the Hindu method of computation. This was a formidable undertaking; but it has now been accomplished for the two principal authorities, and the Tables are published herewith. It is to be hoped that they are final. They are intended to fix the true longitude of the sun on any day or at any moment of the day, with an accuracy extending to the hundredth part of a second, the calculation having been each separately carried to eight or nine decimals of a second so as to ensure correctness. I give the result in degrees and parts, and in ten-thousandths of the circle. The former, converted as desired, can be adapted to any system of reckoning; the latter are for use by the *Indian Calendar* system.²

¹ For calculation affecting all parts of India the basis has to be mean sunrise, and this is always taken as mean sunrise at Lanka, or Ujjain.

² The *Indian Calendar* System is the system adopted by Prof. Jacobi (of Bonn) in 1888 (*Indian Antiquary*, Vol. XVII) itself founded on Largeteau (*Connaissance des Temps*, 1845).

236. These calculations are, as I have stated, based purely on the Hindu system of reckoning. I have used for the sun's mean anomaly and longitude the mean position and mean motion of the sun as gathered from each Siddhānta separately, and have used the Hindu values of the sines for computing the amount of the equation of the centre, and thence the sun's true position. The Tables are prepared according to the *First Ārya* and *Present Sūrya Siddhāntas*, the latter both with and without the *biḥa*. The *biḥa*, which came into general use about A.D. 1500, made no change in the length of the solar year or the number of civil days in a mahāyuga, or in the position of the sun's apsis, and therefore none in the sun's longitude, whether true or mean. I shall attempt hereafter to publish similar Tables for the other principal Indian authorities—Tables which will be of great value in the verification of dates, seeing that up to the present time no one knows exactly at what periods and in what tracts these other Siddhāntas were used. (The *Siddhānta-Sirṃmaṇi* Table has been completed and is ready for Press.)

237. Assuming, since these Tables are not intended for any but the initiated, that the *Indian Calendar* process of calculation, which might be termed Prof. Jacobi's first process and which has the advantage of simplicity, is known to readers of the *Epigraphia*, only one or two remarks need be made before entering on details. Since everything depends on the accuracy of the Table-entries, I must call attention to the great help which I received from M. Louis de Ries of Moscow for many months. He takes the greatest interest in Hindu astronomy, and has prepared certain Tables of his own, the publication of which has been delayed by the War. His processes are characterized by the most laborious and painstaking endeavours to obtain extreme accuracy for every result arrived at. Filled with a similar desire, and after my calculations for the sun's exact position (in true longitude for successive 24-hour periods after the true sun's arrival at long. 0°) had been carried out for about one-third of the *Ārya-Siddhānta* year, I asked M. de Ries to calculate some of these positions of the sun by his own method, so that we might compare the results. He most kindly did so; and, when I state that our results, worked in entire independence of one another and by different methods, were found to agree in every respect down to four, and in one case even down to five, decimals of a second, I think that it may be fairly assumed that my Tables may be depended upon.

238. There is more than one reason why the *Indian Calendar* system, though yielding results very fairly approximate, requires some expansion for the purpose of exact calculation. By it we have been in the habit of computing the true moon's place both for the tithi and nakshatra by the *Sūrya-Siddhānta* data, using the same figures for finding the tithi-index, t , and nakshatra-index, n , for all dates, both for inscriptions known to belong to tracts and times when the *Ārya-Siddhānta* was the authority used by the framers of the record, as well as for those which must have been guided by almanacks calculated by the *Sūrya-Siddhānta*. The c of the *Indian Calendar* method, i.e. the sun's mean anomaly at any moment, is always the *Sūrya-Siddhānta* c in thousandths of the circle, and that it differs in various proportions at different times of the year from the c of the *Ārya-Siddhānta* will be apparent to anyone who compares the entries for the same day given in my new Tables XLVIII A and B, cols. 2, 3, in ten-thousandths. At the moment of Mēsha-samkrānti for instance (the first entry in each Table) the c by the *Sūrya* is 2794.0642 in ten-thousandths, and is 279 in thousandths in *Indian Calendar* reckoning; but by the *Ārya-Siddhānta* it is 2774.5577, and so for our ordinary reckoning should be stated as 277. In calculation for the tithi-index, t , in ordinary work this difference has no very great effect, though of course it actually has some, and possibly may in some cases alter the value of t by one unit ($4\frac{1}{2}$ minutes); but it has greater effect when we are calculating the nakshatra, as will presently be explained. As to the difference between the two authorities in the value assigned to the sun's true longitude, s , it will be seen that this varies day by day. About Day 261, i.e. the 261st period of 24 hours each measured from

true Mēsha-samkrānti, the value of s is practically the same by the two authorities; about Day 150 the Ārya s is about $3^{\circ} 36'$ ahead of the Sūrya s . The difference increases and diminishes regularly throughout the year.

The principal reasons for this difference are that by the *Sūrya-Siddhānta* the position of the sun's perigee-point is different from that assumed by the *Ārya-Siddhānta*, and that there is a difference in the two year-lengths.

239. I have stated above that this difference has only a very slight effect as regards the value of the tithi-index; its effect on the ordinary calculation of the nakshatra and lagna must now be noticed. In so doing we take first the nakshatra and note the process by which those who have used the *Indian Calendar* have hitherto calculated its index.

Our method of computing the sun's true longitude, s , by the system of the *Indian Calendar* has been to take the c found for the desired moment, that is to say the value, in thousandths of the circle, of the sun's mean anomaly according to the *Sūrya-Siddhānta*, making this serve for both Siddhāntas; to multiply this c by 10 to get its approximate value in ten-thousandths; to add to it a figure, 7207, representing the longitude of the sun's perigee-point (taken as 7146.3 by the *Sūrya-Siddhānta*) in A.D. 1100 plus a small addition (60.4) rendered necessary by the construction of the Tables in order to avoid the necessity for sometimes adding and sometimes subtracting the equation of the centre¹; to deduct from the result the figure representing this equation; and so to obtain the sun's true longitude, s . The tithi-index, t , having been already found, we add s to t , and find the nakshatra-index n , or the longitude of the true moon; this index shews in which nakshatra she stands at the moment. The result is an approximation, but it is not close enough. If we are working for an *Ārya-Siddhānta* date, we have used *Sūrya-Siddhānta* values (which differ slightly), and we have arrived at the value of s in part by multiplying by 10 a value obtained in thousandths so as to be able to apply it to the other value, that of the moon, which has been obtained in ten-thousandths of the circle. This multiplication by ten creates a possibility of error not inconsiderable. Thus, if we have, in thousandths, the figure $c = 623$, this may stand for any value in ten-thousandths between 6225 and 6235, and may lead to a miscalculation amounting to anything under 10 units in our estimate of the nakshatra index n ; and 10 units represent in time-valuation 39 minutes.

240. All these possibilities of error are entirely removed by the present Tables. The exact value of s by either Siddhānta is easily found—a value which we know to be absolutely correct—and when we add this s to the already found t we know that the result gives the correct nakshatra-index; or at least that the only possibility of error lies in the value found for the tithi. As for this last we must for the present trust to the correctness of Prof. Jacobi's calculations for the moon's place relative to the sun (a) and for the moon's equation (b), correcting the sun's equation by my new Tables.

241. These Tables will also be found very useful for calculating the lagna accurately. Hitherto our process for finding, in working for the lagna, the value of the sun's true longitude, s , at mean sunrise of the day concerned has been the same as the process for finding the nakshatra. We have found the value of s by both Siddhāntas from a calculation really correct only by one Siddhānta, and even that after a rather clumsy multiplication by 10, which itself may cause an error of 39 minutes of time. The present Tables give the accurate s by either Siddhānta, and they give it in degrees, etc., thereby simplifying the calculation.

¹ See *Indian Calendar*, §§ 107, 108; pp. 60, 61.

² The tithi-index, " t ", gives the distance of true moon from true sun, i.e. shews the moon's true place with reference to the true sun. When this is added to the true sun's longitude, we have the true moon's place in the heavens, " n ", or the required nakshatra-index.

EXPLANATION OF THE TABLES.

242. Table XLIII. The details were worked out with great care by M. L. de Ries from the respective lengths of the sidereal solar year, i.e. the time taken by the true sun to travel from 0° to 0° , according to the several Indian authorities.

Table XLIV gives the sun's mean motion per day of 24 hours, and per hour, minute and second, for use in calculation. It is exact for the *Ārya-Siddhānta*, and may be used with care for other authorities, having regard to the footnote.

Table XLIVA. See the heading. It explains itself.

Table XLVA is for use in calculations. Every valuation given in the main Tables XLVIII A and B in ten thousandths of the circle was made by it.

Table XLVB is the reverse of XLVA.

Table XLVI is a revised nakshatra Table, showing the exact ending points of each.

Table XLVII is very important, being a revised Table of sines and equations of the sun's centre, given in full after particularly careful calculation. Its preparation is described below §§ 249-253. The supplementary Table XLVIIA gives, for close work, very full details of the exact equations according to authorities other than the *First Ārya-Siddhānta* and of the differences, in seconds per minute of mean anomaly-arc, between the consecutive base-equations. Table XLVII is for the present to be held inapplicable to the *Brahma-Siddhānta*.

Tables XLVIII A and XLVIII B are the main working Tables, showing, by the *First Ārya* and *Present Sūrya Siddhāntas* (with or without the *bija*), the precise value of the sun's true longitude (s) and equation of the centre at each interval of 24 hours measured from true *Mēsha-samkrānti*, the moment when the true sun arrives each year at celestial longitude 0° ; as well as the sun's mean anomaly and mean longitude. There was no possibility of framing a Table which should give these particulars for mean sunrise of each day, the primary requirement for the verification of Indian dates, because the moment of true *Mēsha-samkrānti* varies each year and the starting-point had to be from that moment. These two Tables therefore give the consecutive 24-hour positions of the mean and true sun after that moment.

Tables XLIX and L enable us to find the sun's true longitude at mean sunrise; the former giving for each group of days the sun's true motion per hour, and the latter giving his mean motion per minute. It is not necessary for general purposes to give his true motion per minute; if required, this can always be obtained by dividing by 60 the details of Table XLIX for one hour of the day.

243. Tables XLVIII to L are used in the following way, when we desire to find the s for mean sunrise. Say that *Mēsha-samkrānti* occurred in the year for which we are working at 12 h. 15 m. after mean sunrise, according to the *Indian Calendar* (Table I, cols. 13 to 17 or 17a). Then for every day of that year Table XLVIII A or B gives us his true longitude, s , at 12 h. 15 m. after mean sunrise; and to obtain the s at mean sunrise on the day in question we have to deduct the sun's true motion during 12 h. and 15 m. We do this by Tables XLIX and L, and so get the exact s for mean sunrise on the day in question.

Table XLIX for hours is exactly correct for the *Ārya-Siddhānta*. When used for the *Sūrya-Siddhānta*, there may be an error amounting, at the time of year when there is the greatest difference between the two authorities, to about one-third of a second per hour or about seven seconds per day. If anyone desires to be absolutely exact by the *Sūrya-Siddhānta*, he should calculate the true sun's motion during the hours and minutes of the day in question by observing in Table XLVIII B the consecutive 24-hour positions, s , of the sun given in the Table for (i) the day in question and (ii) the previous day, and divide the difference by 24 for each hour's, and this result by 60 for each minute's, true motion. Even this, of course, is

not mathematically exact, since the true motion of the sun varies from hour to hour; but it is quite accurate enough.

244. The calculation for the true longitude of the sun each day was made by ascertaining his mean anomaly and then using the sine-Table as finally prepared (Table XLVII) for finding the equation of the centre. The starting point for the year is the value of his mean anomaly at the moment of true Mēsha-samkrānti. This had to be computed with great care. The problem is fully discussed below §§ 254-255.

245. To obtain a correct value of the sun's mean longitude at sunrise of any day, take the value given in Table XLVIII A or B, as the case may be, and deduct for the intervening hours and minutes (*cf. s. 243*) the quantities shewn in Table XLIV for the sun's mean motion. Greater accuracy even than this can be obtained by the use of Table XLIII.

246. I do not enter very fully into the difference in the sun's true longitude brought about, according to the *Sūrya-Siddhānta*, by the shift in the apsis of the sun's orbit, because this seems so slight that it may be ignored. It would amount to about 1" in the last 1500 years (*see below, s. 254, ii*).

Use of the Tables. Rules.

247. That the use of the Tables may be thoroughly understood, I append a few rules of work and examples.

(i) *The nakshatra*.—Work by the usual *Indian Calendar* process for finding t , the tithi-index at mean sunrise of the day in question. Note the serial number of the civil day, ignoring altogether the day of the Hindu solar month. Deduct from this number the serial number of the day on which Mēsha-samkrānti occurred (Table I, col. 13). The result is the number of the day, or 24-hour period, referred to in col. 1 of the new Tables XLVIII A and B. Remembering to use the proper Table for the *Siddhānta* concerned, turn to this number in either of those Tables. Against it in col. 9 will be found the correct value of the sun's longitude, s , on that day at a moment as many hours and minutes after mean sunrise as elapsed between mean sunrise and the moment of Mēsha-samkrānti at the beginning of the solar year (Table I, col. 17 or 17a). Turn to Table XLIX for hours on the day in question and Table L for minutes, and deduct from the s so obtained the values of the sun's motion during those hours and minutes (*above § 243*). This gives the sun's exact true longitude at mean sunrise of the day in question. $s + t = n$, the nakshatra-index. For exact ending points of nakshatras, i.e. the points when the true moon passes out of each, consult Table XLVI (Table VIII of the *Indian Calendar* suffices except in very close cases.) Properly worked, the s so found yields the correct longitude of the true sun within the hundredth part of a second.

(ii) *The tithi*.—[This may be examined by the new Tables, though probably it will not be liable to change, or at any rate not to any change greater than one unit. Until some new Tables are published, we work for the moon's place by Prof. Jacobi's fixtures, and accept them.] The serial number of the day, or 24-hour period, being found as above, note against it in Table XLVIII A or B, cols. 2, 3, the value of the sun's mean anomaly; and for the intervening hours and minutes deduct the sun's mean motion as given in Table XLIV, observing the remarks in the footnote to that Table. This gives the sun's mean anomaly at mean sunrise of the day in question in ten-thousandths of the circle. Take the value in thousandths of the circle by removing the decimal point one place to the left. Refer to Table VII, *Indian Calendar*, and the auxiliary Table for correcting the "equation c " of the calculation, if it does not seem necessary to work with greater exactness than by use of units of about $4\frac{1}{2}$ minutes.

We can find the equation more accurately as follows:—It has been noted in § 239 that, in order that "equation c " in the a, b, c system may always be additive, the quantity 60.4 was taken from a (the mean moon's distance from mean sun) and added to the equation of the centre. Hence we shall have the exact "equation c ", if we deduct from 60.4 the amount of the

equation (given in the new table), when it is *plus* (+), and add to 60.4 the amount of the equation, when it is *minus* (-); the signs are given in the heading of cols. 6, 7, Tables XLVIII and B.

The equation can also be obtained with quite sufficient approximation by noting the difference between the equation of the day and the equation of the previous day (cols. 6, 7), dividing this difference by 24, and applying to the equation of the day the amount proportionate to the hours intervening from mean sunrise (*see example given below*, § 248, ii, B); or, perhaps easier, the true sun's longitude at mean sunrise having already been found, by calculating the mean sun's longitude at mean sunrise, as shown in § 245, and subtracting the one from the other.

(iii) *The lagna*.—To find the time of rising of the named sign on the day concerned, calculate the *s* for mean sunrise as above explained, but this time use degrees, minutes and seconds (col. 8 of either Table XLVIII or B). Table XXII, *Indian Chronography*, gives the beginning and ending points of the named sign. Adding to these 360°, if necessary, deduct from their value the value of *s* at mean sunrise. The result shows the distance from the sun at mean sunrise of the beginning and ending points of the sign. Multiply the degrees by 4 for minutes, and the minutes by 4 for seconds of time. The result gives the times of rising of the beginning and ending points of the named sign.

Examples of Work.

248. Given an inscription date to be examined, with the details Śaka 1412, Friday, the day of Uttara Bhādrapadā, Chaitra kṛishṇa 12, Mithuna lagna.

The year is A.D. 1490-91 (Śaka 1412 expired). Chaitra kṛishṇa 12 will be about 25 days later than the day of Chaitra śukla 1. Work first in the usual way by the *Indian Calendar*.

	Day.	Week-day.	a.	b.	c.
(Table I, cols. 19-25)	81	2	75	430	264
(Table IV for 25 days)	25	4	8466	907	68
	106	6	8541	337	332
(Table VI equation b)	.	.	260		
(Table VII equation c)	.	.	7		

Tithi-index, *t*, = 8808

The day was 106, which (Table IX) = 16 April, A.D. 1490.

Week-day 6 = Friday. The index *t* shows (Table VIII) that the tithi current at mean sunrise was Chaitra kṛishṇa 12. We then work for the nakshatra-index.

$c \times 10$	.	.	.	.	3320
Constant	.	.	.	.	+ 7207
					527
Less for the sun's equation <i>c</i>	.	.	.	-	7
					520
Sun's true longitude, <i>s</i>	.	.	.	.	520
Add the tithi-index, <i>t</i>	.	.	.	.	8808
					9328
Nakshatra-index, <i>n</i>	.	.	.	.	9328

This value of *n* shows (Table VIII) that by the equal-space system the moon at mean sunrise of the given day was in the nakshatra Uttara Bhādrapadā. So far so good. The date seems genuine; but we want to be certain, and we refer to the present Tables.

A. *The exact nakshatra (i) by the First Ārya-Siddhānta.*—Mēsha-samkrānti occurred in the year A.D. 1490 (Table I, cols. 13, 17) at 10 h. 55 m. after mean sunrise on Day 86. The day of the record is 106. $106 - 86 = 20$. Turning to day 20 in Table XLVIII, col. 1, we see that the sun's true longitude, s , was, at 10 h. 55 m. after mean sunrise, 540°6811, in 10,000ths of the circle. Deduct the sun's true motion on Day 20 for 10 hours and 55 minutes; viz. (Table XLIX) for 10 hours 11°2059, and (Table L) for 55 minutes 1°0457, total 12°2516. $540°6811 - 12°2516 = 528°4295$. This is the value of s at mean sunrise on the given day. Add s to t , $528 + 8808$ (in whole numbers) = 9336. This is the proper nakshatra-index, n , for mean sunrise, always supposing the tithi-index, t , to be correct. It differs by 8 units from the Indian Calendar valuation 9328, which is found therefore so much in error. This, in time (Table X), is over half an hour; but we find that the moon was certainly in Uttara Bhādrapadā at mean sunrise.

(ii) *By the Sūrya-Siddhānta.*—The process, *mutatis mutandis*, is similar. Mēsha-samkrānti occurred at 12 h. 44 m. after mean sunrise. On Day 20 (Table XLVIII) s , at 12 h. 44 m. after mean sunrise, was 540°5000. Deduct for the sun's true motion on Day 20, for 12 h. (Table XLIX) 13°4471, and for 44 m. (Table L) 0°8365. Total 14°2836. $540°5000 - 14°2836 = 526°2164$. This was the s at mean sunrise. $s + t = 526 + 8808 = 9334$. This, if the t is correct, is the correct value of the nakshatra-index, n , at mean sunrise; and we see that the Indian Calendar n , 9328, was in error by 6 units, or 24 minutes of time.

B. *The exact tithi (t) by the First Ārya-Siddhānta.*—We first check the mean anomaly of the sun, c . Our preliminary work shewed this to be, in thousandths of the circle, 332. Table XLVIII, col. 3, shews that at 10 h. 55 m. after mean sunrise the mean anomaly was, in ten-thousandths, 3322·1148. Deduct by Table XLIV the sun's mean motion during 10 h. 11°4074, and during 55 m. 1°0457, total 12°4531. $3322·1148 - 12°4531 = 3309°6617$. This is the exact mean anomaly of the sun, c , at mean sunrise. If we work by the simple Table VII of the Indian Calendar and take the c in thousandths as 331, we see that equation c would remain unchanged at the value 7. Hence, accepting the values assumed for the moon's mean place and equation, we find that the tithi-index was actually, as found by us, 8808.

We try this again by the more elaborate, but more accurate process recommended above (§ 247, ii, last para.). By Table XLVIII, col. 7, we have the equation of the centre at 10 h. 55 m. after mean sunrise on Day 20 given as 51·8996 in 10,000ths of the circle. The difference in 24 hours had been (day 19) 52·3833 — (day 20) 51·8996, or 0·4837. A 24th part of this is ·02015, the average difference per hour. Accepting 10 h. 55 m. as 11 h., we have for 11 h. the difference ($·02015 \times 11$)·2216. Call this ·222 and add it to 51·8996. Result gives the equation of the centre at mean sunrise 52·1216. Then $60·4 - 52·1216 = 8·2784$, the value of equation c . This is over 8, and hence we find that the former valuation 7 is incorrect, and that the tithi-index at mean sunrise was really 8809, not 8808, by the Ārya-Siddhānta. But we have also found out a little more regarding the nakshatra-index, n . s was found to be really 528°4295; and if we substitute the full value of equation c , viz. 8·2784, for the value found by the original calculation, viz. 7, we have for the tithi-index:—

a	.	8541
Equation b	.	260
Equation c	.	8·2784
$t =$	.	8809·2784
Add ($s =$)	.	528·4295
$n =$	.	9337·7079, or, say, 9338 in whole numbers.

Thus the real nakshatra-index, n , was 9338, and our *Indian Calendar* process with result 9328 yielded a result in error by 10 units, or 30 minutes of time.

(ii) *By the Sūrya-Siddhānta*.—By Table XLVIII B, col. 3, we have the sun's mean anomaly c at 12 h. 44 m. after mean sunrise = 3341.6212, in ten-thousandths of the circle. Deduct for 12 h. 13.6889 and for 44 m. 0.8365 (Table XLIV) for the sun's mean motion, total 14.5254. $3341.6212 - 14.5254 = 3327.0958$. This was the sun's mean anomaly at mean sunrise. Calling this 333 and consulting *Indian Calendar* Table VII, we should raise equation c in our original work from 7 to 8.

Again we test this by the more accurate process. The equation of the centre on the given day 12 h. 44 m. after mean sunrise was (Table XLVIII B, col. 7) 52.3475. The same for the previous day was 52.8500. Difference = 0.5025. Divided by 24, this gives an average difference per hour of 0.02094. Taking 12 h. 44 m. as 13 h. and multiplying, we have 0.27224. Add 0.2722 to the equation of the day, 52.3475, and we find as the equation of the centre at mean sunrise 52.6197. $60.4 - 52.6179 = 7.7803$. Hence equation c in the original calculation should certainly have been 8, and not 7.

Lastly we substitute the newly found values as before, for *Indian Calendar* calculation, s , having been already determined to have been at mean sunrise by this authority 526.2164.

	d	.	8541
Equation b	.	260	
Equation c	.	7.7803	
	$t =$	.	8808.7803
Add	$s =$	.	526.2164
	$n =$	.	9334.9967 say 9335.

This is as near as we can get to the true nakshatra-index at mean sunrise. It differs by 7 units from the *Indian Calendar* value, which was 9328, or by 28 minutes of time.

(iii) *Allowance for the shift in the sun's perigee-point when working by the Sūrya-Siddhānta*.—I have shown below (§ 254) that, for calculation of the tithi, nakshatra, or lagna, this shift in the apsis may well be ignored; but in case any one should desire to take notice of it I have entered a Table (p. 12 below), giving its exact amount. Its effect on our inscription-date is as follows. Table XLVIII B is calculated for about A.D. 1400. The year of our inscription is A.D. 1490. 90 years after A.D. 1400 the perigee-point had advanced (see Table) 0.0806 from the position we assumed for it. Hence the sun's mean anomaly at mean sunrise of our date was not, as already found, 3327.0958, but this amount less 0.0806, or was actually at 3327.0152. 90 years earlier than A.D. 1400 it would have been 3327.0958 plus 0.0806, or 3327.1764. But this change would have only an infinitesimal effect on the equation of the centre, or, in consequence, on the sun's true longitude, or on the calculated values of the tithi, nakshatra, or lagna.

C. The Yōga, by either Siddhānta.—The formula for this is $2s + t$, and, as the value of s has been correctly found by the above process, no further remark is necessary.

D. The lagna, (i) by the Ārya-Siddhānta.—For this we have to find the correct value of s at mean sunrise in degrees, etc. By Table XLVIII A, col. 6, the s for the day was in our

example above $19^{\circ} 27' 52'' \cdot 27$. Deduct (*Tables XLIX, L*) for, on day 20, 10 hours $24' 12'' \cdot 29$, and for 55 minutes $2' 15'' \cdot 52$, total $26' 27'' \cdot 81$. Then the s for mean sunrise was $19^{\circ} 1' 24'' \cdot 46$. This was the true sun's longitude at that moment on the meridian of Ujjain. The given lagna was the sign Mithuna. The first point of this is 60° , the last 90° . We take the s as 19° , which is sufficiently exact for ordinary purposes. $60^{\circ} - 19^{\circ} = 41^{\circ}$. $41 \times 4 = 164$ m., or 2 h. 44 m. $(90^{\circ} - 19^{\circ}) \times 4 = 284$ m., or 4 h. 44 m. The first point of Mithuna was 41° distant from the true sun at the moment of mean sunrise, the last point 71° . Mithuna was lagna between 2 h. 24 m. and 4 h. 44 m. after mean sunrise on the given day.

(ii) By the *Sārya-Siddhānta*.— $s = (\text{Table XLVIII}) 19^{\circ} 27' 28'' \cdot 80$. Deduct for 12 hours (*Tables XLIX, L*) $29' 2'' \cdot 74$ and for 44 minutes $1' 48'' \cdot 42$, total $30' 51'' \cdot 16$. Remainder, or s for sunrise, $18^{\circ} 56' 37'' \cdot 64$. We may call this 19° , and come to the same result as in the former case. The lagna of Mithuna really began twelve seconds later.

(iii) By the *Indian Calendar process*, and for both *Siddhāntas*.—Here s was found to be in ten-thousandths, 520. Converted by Table VIII B, this $= 18^{\circ} 45'$. This was the sun's true longitude at mean sunrise. The difference between the actual time of the lagna of Mithuna and that found by the *Indian Calendar* is slight.

More accurately worked, the first point of Mithuna was lagna by the *Ārya-Siddhānta* at 2 h. 43 m. 56 s., by the *Sārya-Siddhānta* 2 h. 44 m. 16 s., and by the *Indian Calendar* 2 h. 45 m., after mean sunrise on the day in question.

Construction of the Tables.

A detailed explanation is here given of the construction of the principal Tables, in order to satisfy experts as to their accuracy.

249. *The Hindu Sine-Table*.—The *Sārya-Siddhānta* (ii, 34) gives in minutes the sines of a series of angles, each separated from the other by $3^{\circ} 45'$, twenty-four of these completing the quarter-circle of 90° . These values stand, so far as I can ascertain, for all Indian authorities except the *Brahma-Siddhānta*, which assumes different sine-values. There is no need here to discuss their exact accuracy, as I am concerned solely with chronography as the handmaid of history, and have nothing whatever to do with the casting of horoscopes or any other branch of astrology. The sines, as used in calculations by authorities other than the *Brahma-Siddhānta*, are given in Table XLVII, col. 3, and the differences between them, in minutes, in col. 4. For astronomical purposes the several angles are angles of a planet's mean anomaly, and are so applied to the mean anomaly of both sun and moon.

250. *The equation of the centre*.—For the preparation of the sine and equation Table (XLVII) the equation of the sun's centre for each base-angle of anomaly has been calculated from its sine-value by the proper formula for each *Siddhānta*, the calculation being carried to nine decimals of a second, in order to insure absolute accuracy for the tabulated two decimals. The details for the *First Ārya-Siddhānta* (Table XLVII, cols. 5, 6) are complete in themselves; details for the other authorities are given in full in a supplementary Table (XLVIIA). Table XLVII differs a little, but only in one or two places, from Jacobi's Table XXIV (*Epig. Ind. I*, 459); I have, however, thought it advisable to record two decimals of seconds in all cases.

251. *Equation of centre*.—In Hindu astronomy the sun is treated as a planet, and in all planetary movement a fundamental principle (Jacobi, *Epig. Ind. I*, 441) is contained in the proportion sin. equation : sin. mean anomaly :: minutes in the epicycle : minutes in the orbit. The minutes in the sin. anomaly are given in Table XLVII; the minutes in the epicycle are ascertained from statements made in each *Siddhānta*; the minutes in the orbit of 360° are

always 21600'. The formula then for all authorities, α being the angle of mean anomaly, is :

$$\text{Equation centre}^1 = \frac{\text{minutes in epicycle}}{21600'} \times \sin. \alpha.$$

252 A. The *First Ārya-Siddhānta* gives for the dimension of the epicycle 13° 30' or 810'. Hence by that authority :—

$$\text{Equation centre} = \frac{810}{21600} \sin. \alpha. = \frac{3}{80} \sin. \alpha.$$

Since there are 3° 45' between each base-angle, the difference in minutes between each is 225', and the measure of first or average difference of equation for each intermediate minute of anomaly is the difference between two consecutive equations divided by 225. Taken in seconds, this difference is given in col. 6. Multiply the minutes of difference between the base-angle and the given anomaly-angle by the amount given in col. 6, and, taking the result in seconds, apply it to the base-equation, and you have the correct equation for the given anomaly-angle.

For an example take the 2nd and 3rd sines. The 2nd sine, i.e. of anomaly-angle 7° 30', is 449'. Multiply by 3 and divide by 80. Result 0° 16' 50".25.

The 3rd sine, of anomaly 11° 15', is 671'. Multiply by 3 and divide by 80. Result 0° 25' 9".75.

The difference between the two results is 8' 19".50. This is the total difference in 225', which is the difference between the two anomaly-angles. 8' 19".50 divided by 225 gives for each minute of angle the increment 2".22.

B. *Equation of the centre by the Sūrya-Siddhānta*.—This calculation is made on the same fundamental principle.

The *Sūrya-Siddhānta* (cf. Jacobi, *above*, I, 441) assumes a contraction of the epicycle amounting to 20' at the end of each of the odd quadrants. If this contraction at any point is called q , we have $q : 20' :: \sin. \alpha : \sin. 90^\circ$. $\therefore q = 20 \frac{\sin. \alpha}{\sin. 90^\circ}$. $\sin. 90^\circ = 3438'$ (see Table XLVII).

Hence $q = \frac{20'}{3438'} \sin. \alpha$. The *Sūrya-Siddhānta* gives for the dimension of the epicycle 14°.

Hence the formula for the equation without the contraction would be $\frac{14'}{360'} \sin. \alpha$. With the

contraction it is $\frac{14'}{360'} \sin. \alpha - \frac{20'}{3438' \times 21600'} \sin.^2 \alpha$; or, finally $\frac{14'}{360'} \sin. \alpha - \frac{\sin.^2 \alpha}{3713040'}$.

The best authorities agree that this is the correct formula.

Each equation for the several base angles has been calculated by this formula and fully worked out for nine decimals of a second. The results are given in full in Table XLVIII, col. 7, and in abbreviated form in Table XLVII, col. 7. The difference in equation per minute of anomaly-arc has been calculated by dividing the difference between consecutive base-equations in minutes by 225, and taking the result in seconds. This is tabulated in full in Table XLVIII, col. 8, and in abbreviated form in Table XLVII, col. 8.

253 C. *Equation of the centre by the Second Ārya-Siddhānta and Siddhānta-Siromani*.—The same fundamental principle holds good. The epicycle is (*Epig. Ind. I. 341*) 13°

¹ When an angle is very small, as is the case with even the greatest of the equation-angles, which is only about 2° 10', the sine is taken to be equal to the arc. Hence the presumed equality in the text of "sin. equation" and "equation centre." Table XLVII shows that the sine of 3° 45' is 225', the same as the arc. The sine of 1 is 60', also the same as the arc.

40' or 820'. There is no contraction. Minutes in the orbit, 21600'. Hence the equation is $\frac{820}{21600} \sin. \alpha$, or $\frac{41}{1080} \sin. \alpha$. The entries are made in abbreviated form in Table XLVII, cols. 9, 10, and in full in Table XLVIII, cols. 9, 10.

254. *The sun's mean anomaly, and the starting-point for its valuation.* The sun's daily mean motion, i.e. his mean motion in 24 hours, is given according to the several Hindu authorities in Table XLIII, so that, given his exact mean place at the moment of true Mēsha-samkrānti when the true sun was at 0°, his mean position at the end of every 24-hour period is obtained by simple addition. We must, therefore, fix with great care the value of his mean anomaly when the true sun was at 0°.

(i) *By the First Ārya-Siddhānta.*—S. B. Dikshit's valuation of the equation by this *Siddhānta*, 2° 6' 59".9421, was a trifle too great. Dr. Schram's, 2° 6' 57".323496, is exact down to the fifth decimal. M. de Ries with almost painful accuracy has carried it as far as sixteen decimals of a second. Tested by the sine-table, his valuation is found exact. The equation (I give nine decimals of a second, the amount which I have generally used in these calculations) is + 2° 6' 57".323494885, or, in 10,000ths of the circle, 58'775644170. This is correct for the corresponding mean longitude value 357° 53' 2".676505115, or 357° 53' 044608419, or in 10,000ths of circle 9941'224355830, the two added together amounting to exactly 360°. Thus, the perigee-point of the orbit being by this *Siddhānta* fixed at 258°, or, in 10,000ths of the circle, 7166'6, we have found the sun's mean anomaly at true Mēsha-samkrānti to have been 99° 53' 2".676505115 or 99° 53' 044608419, or in ten-thousandths of the circle 2774'557689163 (i.e. 9941'224355830 — 7166'6). This then is our starting-point for cols. 2, 3, 4, 5, of Table XLVIII.

(ii) *By the Present Sūrya-Siddhānta.*—In this case we have to deal with an authority which postulates a slight movement in the line of apsides of the sun's orbit, the apogees and perigee-points moving eastwards at the rate of 0".1161 per ann.; and before working for a correct valuation of the sun's mean anomaly at true Mēsha-samkrānti in any year, we have first to decide which year to select as base of operations. I have chosen the year K. Y. 4500 or A.D. 1399-1400, roughly A.D. 1400, for reasons which follow. The period covered by Indian Epigraphy, the historical period, that is, of Indian History, may be taken as the period K. Y. 3500 to 5000, A.D. 400 to 1900, or the last 1500 years, the bulk of the inscriptions belonging to the last millennium K. Y. 4000 to 5000 or A.D. 900 to 1900. I take the central year of this millennium as my base. In K. Y. 4000 the perigee-point was at 257° 15' 32".4, and in K. Y. 5000 it was at 257° 17' 28".5. Hence in K. Y. 4500, say A.D. 1400, it was 257° 16' 30".45, or, in 10,000ths of the circle 7146'53125.¹ The difference in the sun's equation of the centre and true longitude, caused by this shift of the apsis, is exceedingly small and may well be ignored.

For we are concerned only with the period A.D. 400 to 1900; and calculation by the equation-table on the value of the sun's mean anomaly at the beginning of the Hindu solar year A.D. 400-01 and at the beginning of A.D. 1900-01, allowing for the shift of the perigee-point, proves that the total difference in the equation in the whole period of 1500 years was 1".0739. This constitutes also the total difference in the sun's true longitude, which is his mean longitude ± the equation, the mean longitude remaining the same whatever way be the shift in the line of apsides.

To assist those interested, however, I append a Table shewing the cumulative change of position of the apsidal points.

¹ Actually, for nine decimals, 7146'531250000

The annual shift is a forward one, and, as the longitude of perigee increases, so the mean anomaly decreases. Hence for years earlier than K. Y. 4500, A.D. 1400, the amounts entered in col. 3 must be added to, and for years later deducted from, the sun's mean anomaly as found by calculation.

Change of position of sun's apsidal points according to the Present Sūrya-Siddhānta.

No. of Years.	Change.		No. of Years.	Change.		No. of Years.	Change.	
1	2	3	1	2	3	1	2	3
	*	10,000ths of circle		*	10,000ths of circle		*	10,000ths of circle
1	0.1161	0.0009	10	1.161	0.0090	100	0 11.61	0.0896
2	0.2322	0.0018	20	2.322	0.0179	200	0 23.22	0.1792
3	0.3483	0.0027	30	3.483	0.0269	300	0 34.83	0.2687
4	0.4644	0.0036	40	4.644	0.0358	400	0 46.44	0.3583
5	0.5805	0.0045	50	5.805	0.0448	500	0 58.05	0.4479
6	0.6966	0.0054	60	6.966	0.0537	600	1 9.66	0.5375
7	0.8127	0.0063	70	8.127	0.0627	700	1 21.27	0.6271
8	0.9288	0.0072	80	9.288	0.0717	800	1 32.88	0.7167
9	1.0449	0.0081	90	10.449	0.0806	900	1 44.49	0.8062
						1000	1 56.1	0.8958

255. Dr. Schram's valuation of the equation of the centre according to the *Ārya-Siddhānta* was proved to be so accurate that we need not have any hesitation in accepting his similar valuation of the same by the *Sūrya-Siddhānta*. He fixes this for K. Y. 4000 as $2^{\circ} 8' 18''.472169$, and for K. Y. 5000 as $2^{\circ} 8' 19''.1842321$. The equation, therefore, in K. Y. 4500, the base-year of my Table, was $2^{\circ} 8' 18''.828200553$, or in ten-thousandths of the circle 59.404538584.

The sun's mean anomaly at the moment of true Mēsha-samkrānti is 360° less the combined longitude of perigee and equation of centre, or $360^{\circ} - (257^{\circ} 16' 30''.45 + 2^{\circ} 8' 18''.828200553)$. The mean anomaly was therefore $100^{\circ} 35' 10''.721799447$, or $100^{\circ} 35' 17.8696657$, or in ten-thousandths of the circle 2794.064211415. This is the valuation which I have adopted for the starting-point for cols. 2, 3, of Table XLVIII.

The sun's mean longitude at the same moment, true Mēsha-samkrānti, is his mean anomaly plus the longitude of perigee, i.e. $100^{\circ} 35' 10''.721799447 + 257^{\circ} 16' 30''.45$. It was, therefore, $357^{\circ} 51' 41''.171799447$, or in ten-thousandths of the circle 9940.595161415. Table XLVIII, cols. 4, 5, start from this point.

256. In calculating the true sun's correct longitude and equation for each day for the preparation of Tables XLVIII and B I have obtained the equation by using the first or average difference in seconds as given in Table XLVII, cols. 6, 8, for each minute of anomaly-angle between the base-angle of the Table and the given angle, in the belief that this represents the practice of the Hindus in bygone centuries. It is possible to calculate with still greater minuteness. We might perhaps be able, by use of some complicated formula, to find out a more exact value of the difference in seconds applicable to the anomaly-angle under consideration; but this system would be so troublesome that it may be reasonably assumed to have never been adopted.

256 a. An example will best illustrate how each calculation for the 24-hour periods given in Tables XLVIII and XLVIII A was made. The value of the equation is based on the angle of mean anomaly, c , given in col. 2. The base-equation used is that for the base-angle next lower in the sine-table (XLVII, col. 5 or 7), the increment in the equation for the difference in angle between the base-angle and the given angle of anomaly being found by multiplying that difference in minutes and decimals by the amount given (col. 6 or 8) in seconds (this being the equation-difference per minute of anomaly-difference). The increment is added to or subtracted from the base-equations according as the consecutive base-equations are increasing or diminishing. The result is the exact equation for the given anomaly-angle, and this is entered in Table XLVIII A or B, cols. 6, 7. This equation is added to or subtracted from the mean longitude of the sun (Table XLVIII A or B, cols. 4, 5), and the result is the sun's true longitude, s (cols. 8, 9). The heading of the sine-Table (cols. 2, 11) shows whether the equation is *plus* or *minus*.

For an example I take Day 27 and work by the *Ārya-Siddhānta*, using only the number of decimals given in my Tables.

Mean anomaly (Table XLVIII A, col. 2)		126° 29' 72124
Next-lower base-anomaly (Table XLVII, col. 2)		-123 45
Difference		2° 44' 72124
2° 44' = 164'. The multiplier per minute of difference is (col. 6) 1° 31.		
164' 72124 × 1° 31 = 215° 7848244. 215° = 3° 35'. Hence		
Base equation for anomaly 123° 45' (Table XLVII, col. 5)		1° 47' 12° 75
Difference in equation above found, deducted since the values in col. 5 are diminishing		3 35-7848244
Exact equation for given anomaly		1° 43' 36° 9651756
Sun's mean longitude (Table XLVIII A, col. 4)		24° 29' 43° 27
Equation found (for sign column-heading)		+1 43 36 97
Exact value of sun's true longitude, s		26° 13' 20° 24

This is converted into 10,000ths of the circle by Table XLVA, and both values are entered in cols. 8, 9, of Table XLVIII. Work by the other *Siddhāntas* is precisely the same, the base-equations and multipliers being used, each set for its own authority.

In this way every figure of equation and true longitude has been worked out for every day of the year.

In applying these results to inscription-dates we calculate the s for mean sunrise as described above, § 238.

If anyone should wish to calculate with a greater number of decimals than the four given in the principal Tables he can work as follows. In § 254 above I have given by both the *Siddhāntas*, with nine decimals of a second, the exact mean anomaly of the sun and mean longitude at true Mēsha-samkrānti each year. Add for the intervening days, i.e. from the day on which Mēsha-samkrānti occurred down to the day in question (included), the quantity obtained by multiplying the figure given for one day in Table XLIII by the number of intervening days. This gives, with eight decimals of a second, the value of mean anomaly and mean longitude for the day. In calculating for the equation note that the base-equations according to the *Ārya-Siddhānta* are complete as given in Table XLVII. They are given in full for the other authorities in Table XLVIII.

TABLE XLIII.

MEAN MOTION OF THE SUN IN THE ECLIPTIC
according to the several Hindu astronomical authorities,
(Details worked out by M. Louis de Ries.)

Serial number as in Table XXXVII of "Indian Chronography."	Hindu authority.	Per Day of 24 hours.		Per Hour.	
		Parts of degrees.	10,000ths of circle.	Parts of degrees.	10,000ths of circle.
		' "	' "	' "	' "
5, 6	Original <i>Sūrya-Siddhānta</i> . Utpala's <i>Paulīya-Siddhānta</i> .	59 8-16961,948	27-37785,2002	2 27-84040,081	1-14074,3833
7	<i>First Ārya-Siddhānta</i> (the <i>Āryabhaṭīya</i>).	59 8-17029,407	27-37785,7207	2 27-84042,892	1-14074,4050
8, 13	<i>Brahma-Siddhānta</i> . <i>Siddhānta-Śirōmaṇi</i> .	59 8-17265,515	27-37787,5426	2 27-84052,989	1-14074,4829
9	<i>Parāra-Siddhānta</i> . . .	59 8-17013,667	27-37785,5993	2 27-84042,236	1-14074,4000
10	<i>Second Ārya-Siddhānta</i> . . .	59 8-17019,963	27-37785,6479	2 27-84042,498	1-14074,4020
11	<i>Rājamrigāṅka</i> . . .	59 8-17019,064	27-37785,6409	2 27-84042,461	1-14074,4017
12	Present <i>Sūrya-Siddhānta</i> (with or without the <i>bija</i>).	59 8-16955,652	27-37785,1516	2 27-84039,819	1-14074,3813
	Hindu authority.	Per minute.		Per second.	
		Parts of degrees.	10,000ths of circle.	Parts of degrees.	10,000ths of circle.
		' "	' "	' "	' "
5, 6	Original <i>Sūrya-Siddhānta</i> . Utpala's <i>Paulīya-Siddhānta</i> .	2-46400,6680	0-01901,2397	0-04106,6778	} 0-00031,6873
7	<i>First Ārya-Siddhānta</i> (the <i>Āryabhaṭīya</i>).	2-46400,7149	0-01901,2401	0-04106,6786	
8, 13	<i>Brahma-Siddhānta</i> . <i>Siddhānta-Śirōmaṇi</i> .	2-46400,8788	0-01901,2414	0-04106,6813	
9	<i>Parāra-Siddhānta</i> . . .	2-46400,7039	0-01901,24000	0-04106,6784	
10	<i>Second Ārya-Siddhānta</i> . . .	2-46400,7083	0-01901,24003	0-04106,6785	
11	<i>Rājamrigāṅka</i> . . .	2-46400,7077	0-01901,24003	0-04106,6785	
12	Present <i>Sūrya-Siddhānta</i> (with or without the <i>bija</i>).	2-46400,6636	0-01901,2397	0-04106,6777	

16	15	46	10-72	438-0457	16	30	25-45	18-2519	16	0	39-42	0-3042	46	1	53-34	0-8746	16	0-66	0-0034	46	1-89	0-0145
17	16	45	18-90	435-4286	17	41	53-29	19-3926	17	0	41-89	0-3232	47	1	55-81	0-8936	17	0-70	0-0054	47	1-93	0-0149
18	17	44	27-07	432-8014	18	44	21-13	20-5834	18	0	44-35	0-3422	48	1	58-27	0-9136	18	0-74	0-0057	48	1-97	0-0152
19	18	43	35-24	430-1783	19	46	48-97	21-0741	19	0	46-82	0-3612	49	2	0-74	0-9316	19	0-78	0-0060	49	2-01	0-0155
20	19	42	43-41	427-5571	20	49	16-81	22-8149	20	0	49-28	0-3802	50	2	3-20	0-9506	20	0-82	0-0063	50	2-05	0-0158
21	20	41	51-58	424-9350	21	51	44-65	23-9558	21	0	51-74	0-3993	51	2	5-06	0-9696	21	0-86	0-0067	51	2-09	0-0162
22	21	40	59-75	422-3129	22	54	12-49	25-0961	22	0	54-21	0-4183	52	2	8-13	0-9886	22	0-90	0-0070	52	2-14	0-0165
23	22	40	7-92	419-6907	23	56	40-33	26-2371	23	0	56-67	0-4373	53	2	10-59	1-0077	23	0-94	0-0073	53	2-18	0-0168
24	23	39	16-09	417-0686					24	0	59-14	0-4563	54	2	13-06	1-0267	24	0-99	0-0076	54	2-22	0-0171
25	24	38	24-26	414-4464					25	1	1-00	0-4753	55	2	15-52	1-0457	25	1-03	0-0079	55	2-26	0-0174
26	25	37	32-43	411-8243					26	1	4-08	0-4943	56	2	17-98	1-0647	26	1-07	0-0082	56	2-30	0-0177
27	26	36	40-60	409-2021					27	1	6-53	0-5133	57	2	20-45	1-0837	27	1-11	0-0086	57	2-34	0-0181
28	27	35	48-77	406-5800					28	1	8-99	0-5323	58	2	22-91	1-1027	28	1-15	0-0089	58	2-38	0-0184
29	28	34	56-94	403-9579					29	1	11-46	0-5514	59	2	25-38	1-1217	29	1-19	0-0092	59	2-42	0-0187
30	29	34	5-11	401-3357					30	1	13-92	0-5704					30	1-23	0-0095			
31	30	33	13-28	398-7136																		
100	98	33	37-03	2737-7557																		
200	197	7	14-06	5475-5714																		
300	295	40	51-09	8213-3572																		
365	359	44	42-16	9992-9179																		

Note.—The Table figures are calculated by the *First Arya-Siddhanta*. The difference between these and the same according to the *Present Sūrya-Siddhanta*, *Parāpara* and *Second Arya-Siddhanta* and the *Rājāmrigāṅka* is negligible. For the total of 365 days according to the *Brāhma-Siddhanta* and *Siddhanta-Sūryamasi* the difference amounts to 0°.86 or (in 10,000ths of the circle) 0-0086, by which these are greater than the figures given, their total for 365 days being 365° 44' 43".02 or (in 10,000ths of the circle) 9992-9245. It is not necessary for historical purposes to trouble about the *Original Sūrya* or *Purāṇa-Siddhanta*. Any one desiring to do so can calculate them from Table XLIII.

TABLE XLIVA.

LONGITUDE OF SUN'S APSIS (PERIGEE) AND EQUATION OF CENTRE
at different millennia, according to the Hindu standard authorities.

[Position of apsis is given according to Jacobi, Epig. Ind. I, 440, 450; the equation has been
calculated by Dr. Schram.]

First <i>Ārya-Siddhānta</i> (<i>Āryabhaṭṭa</i>).				Present <i>Sūrya-Siddhānta</i> .			
Kali-yuga.	Christian year (roughly)	Long. of sun's apsis (perigee).	Sun's equation of centre at true Mēṣa-samkrānti.	Kali-yuga.	Christian year (roughly)	Long. of sun's apsis (perigee).	Sun's equation of centre at true Mēṣa-samkrānti.
	B.C.	" " "	" " "		B.C.	" " "	" " "
0	3100	258 0 0	2 6 57-323494885	0	3100	257 7 48-0	2 8 15-623883311
1000	2100			1000	2100	257 9 44-1	2 8 16-335959734
2000	1100			2000	1100	257 11 40-2	2 8 17-048932824
3000	100			3000	100	257 13 36-3	2 8 17-760102582
	A.D.				A.D.		
4000	900	257 15 32-4	2 8 18-472162007	4000	900	257 15 32-4	2 8 18-472162007
5000	1900			5000	1900	257 17 28-5	2 8 19-184232099
<i>Brahma-Siddhānta</i> .				<i>Siddhānta-Śirōmaṇi</i> .			
	B.C.				B.C.		
0	3100	257 45 36	2 8 28-527631345	0	3100	257 45 36	2 8 26-527631345
1000	2100	257 48 0	2 8 27-432241607	1000	2100	258 3 0	2 8 33-086055747
2000	1100	257 50 24	2 8 28-336851869	2000	1100	258 20 24	2 8 39-644480150
3000	100	257 52 48	2 8 29-241462132	3000	100	258 37 48	2 8 46-202904552
	A.D.				A.D.		
4000	900	257 55 12	2 8 30-140072394	4000	900	258 55 12	2 8 52-761328955
5000	1900	257 57 36	2 8 31-050682657	5000	1900	259 12 36	2 8 59-319753357
<i>Second Ārya-Siddhānta</i> .							
	B.C.						
0	3100	257 45 36-0	2 8 28-527631345				
1900	2100	257 47 54-3	2 8 27-396434118				
2000	1100	257 50 12-6	2 8 28-265236890				
3000	100	257 52 30-2	2 8 29-134039663				
	A.D.						
4000	900	257 54 49-2	2 8 30-002842436				
5000	1900	257 57 7-5	2 8 30-871845209				

TABLE XLVA.

FOR CONVERSION OF DEGREES, MINUTES AND SECONDS INTO MEASUREMENT BY 10,000THS OF THE CIRCLE.

DEGREES (°).				MINUTES (').				SECONDS (").				DECIMALS OF SECONDS (").	
No.	10,000ths of circle.	No.	10,000ths of circle.	No.	10,000ths of circle.	No.	10,000ths of circle.	No.	10,000ths of circle.	No.	10,000ths of circle.	No.	10,000ths of circle.
1	27° 3'	46	1237° 7'	91	2527° 7'	1	0° 46' 29"	31	14° 55' 18"	1	0° 007,716,949	31	0° 239,187,531
2	28° 3'	47	1245° 5'	92	2535° 5'	2	0° 025"	32	14° 5' 14"	2	0° 015,432,090	32	0° 240,913,589
3	29° 3'	48	1253° 3'	93	2543° 3'	3	1° 29'	33	15° 27'	3	0° 023,148"	33	0° 254,629"
4	111° 1'	49	1261° 1'	94	2551° 1'	4	1° 51'	34	15° 7' 40"	4	0° 030,864,197	34	0° 262,845,679
5	128° 5'	50	1268° 5'	95	2558° 5'	5	2° 31' 48"	35	15° 20' 37"	5	0° 038,580,247	35	0° 270,061,729
6	186° 6'	51	1416° 6'	96	2566° 6'	6	3° 7'	36	16° 6'	6	0° 046,29"	36	0° 277"
7	194° 4'	52	1444° 4'	97	2594° 4'	7	3° 24' 07"	37	17° 12' 06"	7	0° 054,012,346	37	0° 285,493,827
8	212° 2'	53	1472° 2'	98	2722° 2'	8	3° 7' 03"	38	17° 50' 5"	8	0° 061,728,395	38	0° 293,293,877
9	250	54	1500	99	2750	9	4° 16'	39	18° 05'	9	0° 069"	39	0° 300,925"
10	277° 7'	55	1527° 7'	100	2777° 7'	10	4° 529"	40	18° 51' 8"	10	0° 077,160,494	40	0° 308,641,976
11	305° 5'	56	1555° 5'	110	3055° 5'	11	5° 0025"	41	18° 56' 14"	11	0° 084,876,543	41	0° 316,358,025
12	333° 3'	57	1583° 3'	120	3333° 3'	12	5° 5'	42	19° 4'	12	0° 0925"	42	0° 324,07"
13	361° 1'	58	1611° 1'	130	3611° 1'	13	6° 01' 55"	43	19° 50' 74"	13	0° 100,308,642	43	0° 331,730,124
14	398° 5'	59	1638° 5'	140	3988° 5'	14	6° 481"	44	20° 37' 0"	14	0° 108,024,031	44	0° 339,506,173
15	416° 6'	60	1666° 6'	150	4166° 6'	15	6° 04'	45	20° 33'	15	0° 115,790"	45	0° 3472"
16	444° 4'	61	1694° 4'	160	4444° 4'	16	7° 407"	46	21° 292"	16	0° 123,426,700	46	0° 354,098,272
17	472° 2'	62	1722° 2'	170	4722° 2'	17	7° 57' 03"	47	21° 7' 592"	17	0° 131,172,840	47	0° 362,654,321
18	500	63	1750	180	5000	18	8° 3'	48	22° 2'	18	0° 138"	48	0° 370"
19	527° 7'	64	1777° 7'	190	5277° 7'	19	8° 7' 062"	49	22° 65' 1"	19	0° 146,004,938	49	0° 378,686,420
20	555° 5'	65	1805° 5'	200	5555° 5'	20	9° 259"	50	23° 1' 28"	20	0° 154,320,098	50	0° 385,802,469
21	583° 3'	66	1833° 3'	210	5833° 3'	21	9° 72"	51	23° 61"	21	0° 162,037"	51	0° 393,518"
22	611° 1'	67	1861° 1'	220	6111° 1'	22	10° 1' 55"	52	24° 57' 4"	22	0° 169,753,096	52	0° 401,234,568
23	638° 5'	68	1888° 5'	230	6388° 5'	23	10° 64' 83"	53	24° 53' 70"	23	0° 177,469,136	53	0° 408,950,617
24	666° 6'	69	1916° 6'	240	6666° 6'	24	11° 1'	54	25"	24	0° 185"	54	0° 416"
25	694° 4'	70	1944° 4'	250	6944° 4'	25	11° 57' 45"	55	25° 40' 29"	25	0° 192,901,235	55	0° 424,362,718
26	722° 2'	71	1972° 2'	260	7222° 2'	26	12° 037"	56	26° 523"	26	0° 200,617,284	56	0° 432,008,765
27	750	72	2000	270	7500	27	12° 5'	57	26° 28"	27	0° 2083"	57	0° 439,814"
28	777° 7'	73	2027° 7'	280	7777° 7'	28	12° 562"	58	26° 331"	28	0° 216,049,383	58	0° 447,520,864
29	805° 5'	74	2055° 5'	290	8055° 5'	29	12° 4219"	59	27° 31' 48"	29	0° 223,765,422	59	0° 455,240,914
30	833° 3'	75	2083° 3'	300	8333° 3'	30	13° 8'	60	27° 7'	30	0° 231,48"	60	0° 4629"
31	861° 1'	76	2111° 1'	310	8611° 1'								
32	888° 5'	77	2138° 5'	320	8888° 5'								
33	916° 6'	78	2166° 6'	330	9166° 6'								
34	944° 4'	79	2194° 4'	340	9444° 4'								
35	972° 2'	80	2222° 2'	350	9722° 2'								
36	1000	81	2250	360	10,000								
37	1027° 7'	82	2277° 7'										
38	1055° 5'	83	2305° 5'										
39	1083° 3'	84	2333° 3'										
40	1111° 1'	85	2361° 1'										
41	1138° 5'	86	2388° 5'										
42	1166° 6'	87	2416° 6'										
43	1194° 4'	88	2444° 4'										
44	1222° 2'	89	2472° 2'										
45	1250	90	2500										

TABLE XLVB.

FOR CONVERSION OF MEASUREMENT BY 10,000THS OF THE CIRCLE INTO MEASUREMENT BY DEGREES, MINUTES AND SECONDS ($^{\circ}$ ' ").

10,000ths of circle.	"	10,000ths of circle.	"	10,000ths of circle.	"	10,000ths of circle.	"	10,000ths of circle.	"
1000	36 0	100	3 36	1	0 3 36	41	1 28 33.6	81	2 44 57.6
2000	72 0	200	7 12	2	0 4 19.2	42	1 30 43.2	82	2 47 7.2
3000	108 0	300	10 48	3	0 6 28.8	43	1 32 52.8	83	2 50 16.8
4000	144 0	400	14 24	4	0 8 38.4	44	1 35 2.4	84	3 1 26.4
5000	180 0	500	18 0	5	0 10 48.0	45	1 37 12.0	85	3 3 36.0
6000	216 0	600	21 36	6	0 12 57.6	46	1 39 21.6	86	3 5 45.6
7000	252 0	700	25 12	7	0 15 7.2	47	1 41 31.2	87	3 7 55.2
8000	288 0	800	28 48	8	0 17 16.8	48	1 43 40.8	88	3 10 4.8
9000	324 0	900	32 24	9	0 19 26.4	49	1 45 50.4	89	3 12 14.4
10,000	360 0	1000	36 0	10	0 21 36.0	50	1 48 0.0	90	3 14 24.0
				11	0 23 45.6	51	1 50 9.6	91	3 16 33.6
				12	0 25 55.2	52	1 52 19.2	92	3 18 43.2
				13	0 28 4.8	53	1 54 28.8	93	3 20 52.8
				14	0 30 14.4	54	1 56 38.4	94	3 23 2.4
				15	0 32 24.0	55	1 58 48.0	95	3 25 12.0
				16	0 34 33.6	56	2 0 57.6	96	3 27 21.6
				17	0 36 43.2	57	2 3 7.2	97	3 29 31.2
				18	0 38 52.8	58	2 5 16.8	98	3 31 40.8
				19	0 41 2.4	59	2 7 26.4	99	3 33 50.4
				20	0 43 12.0	60	2 9 36.0	100	3 36 0.0
				21	0 44 21.6	61	2 11 45.6		
				22	0 46 31.2	62	2 13 55.2		
				23	0 48 40.8	63	2 15 4.8		
				24	0 50 50.4	64	2 17 14.4		
				25	0 52 0.0	65	2 19 24.0		
				26	0 54 9.6	66	2 21 33.6		
				27	0 56 19.2	67	2 23 43.2		
				28	1 0 28.8	68	2 25 52.8		
				29	1 2 38.4	69	2 28 2.4		
				30	1 4 48.0	70	2 31 12.0		
				31	1 6 57.6	71	2 33 21.6		
				32	1 9 7.2	72	2 35 31.2		
				33	1 11 16.8	73	2 37 40.8		
				34	1 13 26.4	74	2 39 50.4		
				35	1 15 36.0	75	2 42 0.0		
				36	1 17 45.6	76	2 44 9.6		
				37	1 19 55.2	77	2 46 19.2		
				38	1 22 4.8	78	2 48 28.8		
				39	1 24 14.4	79	2 50 38.4		
				40	1 26 24.0	80	2 53 48.0		

DECIMALS OF UNITS.
(10,000ths of circle.)

Unit.	"	Unit.	"
0.1	0 12.96	0.01	1.296
0.2	0 25.92	0.02	2.592
0.3	0 38.88	0.03	3.888
0.4	0 51.84	0.04	5.184
0.5	1 4.80	0.05	6.480
0.6	1 17.76	0.06	7.776
0.7	1 30.72	0.07	9.072
0.8	1 43.68	0.08	10.368
0.9	1 56.64	0.09	11.664

For every successive decimal of unit
move the decimal point of seconds one
place to left.

TABLE XLVI.

INDICES OF NAKSHATRAS AND YOGAS.

To take for close work the place of Table VIII, cols. 6 to 13, of the "*Indian Calendar*."

NAKSHATRA.								YOGA.		
Serial number.	Name.	Ending point by the Equal-space system.		Ending point by the system of Garga.		Ending point by the Brahma- Siddhānta.		Serial number.	Name.	Ending point.
		" ,	10,000ths of circle.	" ,	10,000ths of circle.	" ,	10,000ths of circle.			
1	2	3	4	5	6	7	8	9	10	11
1	Āśvinī* . .	18 20	370-370	13 20	370-370	13 10 35	366-0109	1	Vishkambha	The ending point is the same as in the case of the equal-space nakshatra (number by number) as given in cols. 3, 4.
2	Bharanī . .	26 40	740-740	20 0	555-5	19 45 52½	549-0051	2	Priti . .	
3	Kṛttikā . .	40 0	1111-1	33 20	925-925	32 56 27½	915-0270	3	Āyushman . .	
4	Rōhiṇī . .	53 20	1481-481	53 20	1481-481	52 42 20	1464-0432	4	Saubhāgya . .	
5	Mṛgaśīras . .	66 40	1851-551	66 40	1851-551	65 52 55	1830-0540	5	Sōbhana . .	
6	Ārdrā . .	80 0	2222-2	73 20	2037-037	72 28 12½	2013-0594	6	Atigandā . .	
7	Punarvasu . .	93 20	2592-592	93 20	2592-592	92 14 5	2562-0756	7	Sukrman . .	
8	Pushya . .	106 40	2962-962	106 40	2962-962	105 24 40	2928-0864	8	Dhṛiti . .	
9	Āślēṣhā . .	120 0	3333-3	113 20	3148-148	111 59 57½	3111-0915	9	Śūla . .	
10	Maghā . .	133 20	3703-703	126 40	3518-518	125 10 32½	3477-1026	10	Gandā . .	
11	Pūrva Phalgunī	146 40	4074-074	140 0	3888-8	138 21 7½	3843-1134	11	Vṛiddhi . .	
12	Uttara Phalgunī	160 0	4444-4	160 0	4444-4	158 7 0	4392-1296	12	Dhṛva . .	
13	Hastā . .	173 20	4814-814	173 20	4814-814	171 17 35	4758-1404	13	Vyāghātā . .	
14	Chitrā . .	186 40	5185-185	186 40	5185-185	184 28 10	5124-1512	14	Harshaṇa . .	
15	Svātī . .	200 0	5555-5	193 20	5370-370	191 3 27½	5307-1568	15	Vajra . .	
16	Vishākhā . .	213 20	5925-925	213 20	5925-925	210 49 20	5856-1728	16	Siddhi, or Aśrij.	
17	Anurādhā . .	226 40	6296-296	226 40	6296-296	223 59 55	6222-1836	17	Vyastipāta . .	
18	Jyēṣṭhā . .	240 0	6666-6	233 20	6481-481	230 35 12½	6405-1890	18	Variyas . .	
19	Mūla . .	253 20	7037-037	246 40	6851-851	243 45 47½	6771-1998	19	Parigha . .	
20	Pūrva Āshādhā .	266 40	7407-407	260 0	7222-2	256 56 22½	7137-2106	20	Śiva . .	
21	Uttara Āshādhā .	280 0	7777-7	280 0	7777-7	276 42 15	7686-2269	21	Siddha . .	
	Abhijit . .					280 56 30	7803-2352			
22	Śrāvāṇa . .	293 20	8148-148	293 20	8148-148	294 7 5	8169-2400	22	Sādhya . .	
23	Dhanishṭhā or Śravisṭhā .	306 40	8518-518	306 40	8518-518	307 17 40	8535-2568	23	Śubha . .	
24	Śatabhishaj or Śatatārakā .	320 0	8988-8	313 20	8703-703	313 52 57½	8718-2622	24	Śukla . .	
25	Pūrva Bhādra- padā .	333 20	9259-559	326 40	9074-074	327 3 32½	9084-2730	25	Brahman . .	
26	Uttara Bhādra- padā .	346 40	9629-629	346 40	9629-629	346 49 25	9633-2892	26	Indra . .	
27	Rēvati . .	360	10,000	360	10,000	360	10,000	27	Vaidhṛiti . .	

* Āśvinī begins at 0° by all systems.

† Though, properly speaking, there is no Abhijit in the equal-space system in ordinary use, sometimes it is referred to as a secondary detail. When this is the case, it has the same limits as fixed by the *Brahma-Siddhānta*, viz. 276° 42' 15" to 280° 56' 30", or, in 10,000ths of the circle, 7686-2269 to 7803-2352.

The ending point is the same as in the case of the equal-space nakshatra (number by number) as given in cols. 3, 4.

TABLE XLVII.

HINDU SINES, AND EQUATIONS OF SUN'S CENTRE.

N.B. i.—The sines, col. 3, stand, it is believed, for all authorities except the *Brahma-Siddhānta* (see *Sūrya-Siddhānta*, ii 15-27).

ii.—“Equation +” or “—” means that the amount of the equation, added to or subtracted from the sun's mean long., gives his true or apparent long.

iii.—This Table is assimilated to that of Prof. Jacobi (*Epig. Ind.*, I. 459).

iv.—First *Ārya* figures are exact. For fuller details see next Table.

Serial number of sine.	SUN'S MEAN ANOMALY.		SINE OF MEAN ANOM. ANGLE.		SUN'S EQUATION OF THE CENTRE ACCORDING TO THE						SUN'S MEAN ANOMALY.		Serial number of sine.
					First Ārya-Siddhānta.	Present Sūrya-Siddhānta.	Second Ārya-and Siddhānta-Sirōmaṇi.						
								Base-equation.	Diff. per min. of anom.	Base-equation.			
	Equation +	Minutes.	Diff.	Equation —									
1	2	3	4	5	6	7	8	9	10	11	1		
0	0 0	199 0	0	225	0 0 0	2-25	0 0 0	2-23	0 0 0	2-28	180 0	300 0 0	
1	3 45	176 15	225	224	0 8 26-25	2-24	0 8 44-18	2-31	0 8 32-50	2-27	183 45	356 15 1	
2	7 30	172 30	449	222	0 16 50-25	2-22	0 17 24-41	2-28	0 17 2-72	2-25	187 30	352 30 2	
3	11 15	168 45	671	219	0 25 9-75	2-19	0 25 58-39	2-25	0 25 28-39	2-22	191 15	348 45 3	
4	15 0	165 0	890	215	0 33 22-50	2-16	0 34 23-87	2-20	0 33 47-22	2-18	195 0	345 0 4	
5	18 45	161 15	1105	210	0 41 26-25	2-10	0 42 38-50	2-14	0 41 56-94	2-12	198 45	341 15 5	
6	22 30	157 30	1315	205	0 49 18-75	2-05	0 50 40-39	2-08	0 49 55-28	2-08	202 30	337 30 6	
7	26 15	153 45	1520	199	0 57 0-0	1-99	0 58 29-33	2-02	0 57 42-22	2-01	206 15	333 45 7	
8	30 0	150 0	1719	191	1 4 27-75	1-91	1 6 3-25	1-93	1 5 15-50	1-93	210 0	330 0 8	
9	33 45	146 15	1910	183	1 11 37-50	1-83	1 13 17-72	1-85	1 12 30-56	1-85	213 45	326 15 9	
10	37 30	142 30	2093	174	1 18 29-25	1-74	1 20 12-88	1-75	1 19 27-39	1-76	217 30	322 30 10	
11	41 15	138 45	2267	164	1 25 0-75	1-64	1 26 46-82	1-65	1 26 3-72	1-66	221 15	318 45 11	
12	45 0	135 0	2434	154	1 31 9-75	1-54	1 32 56-84	1-54	1 32 17-28	1-56	225 0	315 0 12	
13	48 45	131 15	2585	143	1 36 56-25	1-43	1 38 43-69	1-43	1 38 8-06	1-45	228 45	311 15 13	
14	52 30	127 30	2728	131	1 43 18-0	1-41	1 44 4-96	1-31	1 43 33-78	1-33	232 30	307 30 14	
15	56 15	123 45	2859	119	1 47 12-75	1-19	1 48 58-92	1-18	1 48 32-17	1-20	236 15	303 45 15	
16	60 0	120 0	2978	106	1 51 40-50	1-06	1 53 25-36	1-06	1 53 3-22	1-07	240 0	300 0 16	
17	63 45	116 15	3084	93	1 55 39-0	0-93	1 57 22-31	0-92	1 57 4-67	0-94	243 45	296 15 17	
18	67 30	112 30	3177	79	1 59 8-25	0-79	2 0 49-90	0-78	2 0 36-50	0-80	247 30	292 30 18	
19	71 15	108 45	3256	65	2 3 6-0	0-65	2 3 46-02	0-64	2 3 36-44	0-66	251 15	288 45 19	
20	75 0	105 0	3321	51	2 4 32-25	0-51	2 6 10-78	0-50	2 6 4-50	0-52	255 0	285 0 20	
21	78 45	101 15	3372	37	2 6 27-0	0-37	2 8 4-26	0-37	2 8 0-67	0-37	258 45	281 15 21	
22	82 30	97 30	3409	22	2 7 50-25	0-22	2 9 26-54	0-22	2 9 24-94	0-22	262 30	277 30 22	
23	86 15	93 45	3431	7	2 8 30-75	0-07	2 10 15-44	0-07	2 10 15-06	0-07	266 15	273 45 23	
24	90 0	90 0	3438		2 8 55-50		2 10 31-0		2 10 31-0		270 0	270 0 24	

TABLE XLVITA.

(Supplementary to the Sine and Equation Table)

Giving fuller details of the entries in Table XLVII, cols. 7, 8, 9, 10, viz. base-equations and differences per minute of arc, for use in close calculation, according to—

(i) The *Present Sūrya-Siddhānta*,(ii) The *Second Ārya-Siddhānta* and *Siddhānta-Sirōmaṇi*.

Serial number of sine.	<i>Present Sūrya-Siddhānta.</i>			<i>2nd Ārya-Siddhānta and Siddhānta-Sirōmaṇi.</i>		
	Base-equation.		Diff. per minute of anom. arc.	Base-equation.		Diff. per minute of anom. arc.
1	7		8	9		10
	°	'	"	°	'	"
0	0	0	0.0	0	0	0.0
1	0	8	44.18193720	0	8	32.5
2	0	17	24.40894254	0	17	2.72
3	0	25	58.39110270	0	25	28.38
4	0	34	23.86691232	0	33	47.2
5	0	42	38.60246580	0	41	56.34
6	0	50	40.39032702	0	49	55.27
7	0	58	29.33229913	0	57	42.2
8	1	6	3.25	1	5	15.5
9	1	13	17.71604934	1	12	30.5
10	1	20	12.87859542	1	19	27.38
11	1	26	46.61953014	1	26	3.72
12	1	32	56.83576962	1	32	17.27
13	1	38	43.68681726	1	38	8.05
14	1	44	4.95633636	1	43	33.7
15	1	48	58.91608494	1	48	32.16
16	1	53	25.35847716	1	53	3.2
17	1	57	22.30831578	1	57	4.6
18	2	0	49.89921462	2	0	36.5
19	2	3	48.02029604	2	3	36.4
20	2	6	10.77879176	2	6	4.5
21	2	8	4.26294360	2	8	0.6
22	2	9	26.54196564	2	9	24.94
23	2	10	15.44365260	2	10	15.05
24	2	10	31.0	2	10	31.0

N.B.—In col. 9 under " (seconds) and opposite lines Nos. 1, 8, 18, 20, the last figure, "-5", is not, like the rest, a recurring decimal.

TABLES XLVIII A AND B.

Elements of the Sun's Longitude for the Hindu Solar Year.

First Ārya and Sūrya Siddhāntas.

1	2	3	4	5	6	7	8	9						
16	115	39-22335	13	39	13-40	379-2701	1	56	12-27	53-7084	15	35	25-67	433-0685
17	116	38-35952	14	38	21-37	406-6479	1	55	14-24	53-3506	16	33	35-81	459-9985
18	117	37-49570	15	37	29-74	434-0258	1	54	11-55	52-8069	17	31	41-30	486-8927
19	118	36-63187	16	36	37-01	461-4036	1	53	8-87	52-3832	18	29	46-78	513-7869
20	119	35-76804	17	35	46-08	488-7815	1	52	6-19	51-8996	19	27	52-27	540-6811
21	120	34-90421	18	34	54-25	516-1594	1	50	58-96	51-3808	20	25	53-22	567-5402
22	121	34-04038	19	34	2-42	543-5372	1	49	48-59	50-8379	21	23	51-01	594-3761
23	122	33-17655	20	33	10-59	570-9151	1	48	38-22	50-2949	22	21	48-81	621-2100
24	123	32-31273	21	32	18-76	598-2929	1	47	27-85	49-7519	23	19	46-61	648-0448
25	124	31-44890	22	31	26-93	625-6708	1	46	11-90	49-1659	24	17	38-84	674-8367
26	125	30-58507	23	30	35-10	653-0486	1	44	54-43	48-5682	25	15	29-54	701-6168
27	126	29-72124	24	29	43-27	680-4265	1	43	36-97	47-9704	26	13	20-24	728-3969
28	127	28-85741	25	28	51-44	707-8044	1	42	19-50	47-3727	27	11	10-94	755-1770
29	128	27-99358	26	27	59-62	735-1822	1	40	55-07	46-7212	28	8	54-68	781-9034
30	129	27-12976	27	27	7-79	762-5601	1	39	30-50	46-0687	29	6	38-29	808-6238
At true Vrishabha-sank.									39	0	0-0	833-3		
31	130	26-26593	28	26	15-96	789-9379	1	38	5-94	45-4162	30	4	21-90	835-3541
32	131	25-40210	29	25	24-13	817-3158	1	36	40-23	44-7648	31	2	4-36	862-0706
33	132	24-53827	30	24	32-30	844-6936	1	35	19-16	44-0522	31	59	41-46	888-7458
34	133	23-67444	31	23	40-47	872-0715	1	33	38-09	43-3495	32	57	18-56	915-4210
35	134	22-81061	32	22	48-64	899-4494	1	32	7-02	42-0408	33	54	55-66	942-0961
36	135	21-94678	33	21	56-81	926-8272	1	30	33-76	41-9271	34	52	30-56	968-7544
37	136	21-08296	34	21	4-98	954-2051	1	28	56-77	41-1788	35	50	1-75	995-3839
38	137	20-21913	35	20	13-15	981-5829	1	27	19-79	40-4305	36	47	32-94	1022-0134
39	138	19-35530	36	19	21-32	1008-9608	1	25	42-81	39-6821	37	45	4-13	1048-0420
40	139	18-49147	37	18	29-49	1036-3386	1	24	2-47	38-9080	38	42	31-96	1075-2460
41	140	17-62764	38	17	37-66	1063-7165	1	22	19-58	38-1140	39	39	57-24	1101-9305
42	141	16-76381	39	16	45-83	1091-0944	1	20	36-08	37-3201	40	37	22-51	1128-4144
43	142	15-89999	40	15	54-00	1118-4722	1	18	53-78	36-6261	41	34	47-78	1154-9983
44	143	15-03616	41	15	2-17	1145-8501	1	17	6-83	35-7090	42	32	9-00	1181-5510
45	144	14-17233	42	14	10-34	1173-2279	1	15	18-61	34-8959	43	29	28-95	1208-9838
46	145	13-30850	43	13	18-51	1200-6058	1	13	30-40	34-0308	44	26	48-91	1234-6366
47	146	12-44407	44	12	26-68	1227-9836	1	11	42-18	33-1958	45	24	8-86	1261-1794
48	147	11-58084	45	11	34-85	1255-3615	1	9	49-43	32-3259	46	21	24-28	1287-9874
49	148	10-71702	46	10	43-02	1282-7394	1	7	56-48	31-4543	47	18	39-50	1314-1937
50	149	9-85319	47	9	51-19	1310-1172	1	6	3-53	30-5828	48	15	54-72	1340-7000

TABLE XLVIII A—Contd.

1st Arya-Siddhanta.

24-hour periods from true Mīśha-saṅkrānti.	Sun's mean anomaly (or mean sun's distance from perigeo- point) ($^{\circ} 0''$).			Sun's mean Longitude,			Sun's equation of the centre +			Sun's true Longitude ($^{\circ} 8''$).		
	1	2	3	4	5	6	7	8	9	10,000ths of circle.	10,000ths of circle.	10,000ths of circle.
		0	10,000ths of circle.	0	10,000ths of circle.	0	10,000ths of circle.	0	10,000ths of circle.	0	10,000ths of circle.	0
61	150	8-98936	4170-8284	48	8 59-36	1337-4051	1	4 9-86	29-7057	49	13 0-22	1307-2008
62	151	8-12533	4198-2063	49	8 7-53	1364-8729	1	2 12-18	28-7977	50	10 10-71	1393-6706
63	152	7-20170	4225-6841	50	7 15-70	1392-2508	1	0 14-50	27-8897	51	7 30-20	1420-1404
64	153	6-39787	4252-9620	51	6 23-87	1419-6286	0	58 16-82	26-9817	52	4 40-69	1446-6103
65	154	5-53404	4280-3398	52	5 32-04	1447-0065	0	50 17-91	26-0641	53	1 49-05	1473-0706
66	155	4-67022	4307-7177	53	4 40-21	1474-3844	0	54 16-68	25-1287	53	58 50-89	1499-5130
67	156	3-80639	4335-0955	54	3 48-38	1501-7622	0	52 15-45	24-1933	54	56 3-83	1525-9555
68	157	2-94256	4362-4734	55	2 56-55	1529-1401	0	50 14-22	23-2579	55	53 10-77	1552-3979
69	158	2-07873	4389-8513	56	2 4-72	1556-5179	0	48 11-38	22-3101	56	50 16-11	1578-8280
70	159	1-21490	4417-2291	57	1 12-89	1583-8958	0	46 7-20	21-3518	57	47 20-09	1605-2476
61	160	0-35107	4444-6070	58	0 21-06	1611-2736	0	44 3-01	20-3936	58	44 24-08	1631-6673
62	160	59-48725	4471-9848	58	59 29-23	1638-6315	0	41 58-83	19-4354	59	41 28-06	1658-0869
At true brāhmi.	161	18-69490	4498-3772	59	18 41-69	1647-5439	0	41 18-31	19-1927	60	0 0-0	1666-6
63	161	58-62342	4499-3927	59	58 37-41	1666-0294	0	39 52-46	18-4603	60	38 29-86	1684-4897
64	162	57-75959	4526-7406	60	57 45-58	1693-4072	0	37 45-32	17-4703	61	35 30-89	1710-8805
65	163	56-89576	4554-1184	61	56 53-75	1720-7851	0	35 38-17	16-4983	62	33 31-92	1737-2853
66	164	56-03193	4581-4963	62	56 1-92	1748-1629	0	33 31-03	15-5172	63	29 32-95	1763-6801
67	165	55-16810	4608-8741	63	55 10-09	1775-5408	0	31 21-68	14-5191	64	26 31-77	1790-0599
68	166	54-30428	4636-2520	64	54 18-26	1802-9186	0	29 12-17	13-5199	65	23 30-43	1816-4385
69	167	53-44045	4663-6298	65	53 26-43	1830-2965	0	27 2-67	12-5206	66	20 29-09	1842-8171
70	168	52-57662	4691-0077	66	52 34-60	1857-6744	0	24 52-93	11-5195	67	17 27-53	1869-1939
71	169	51-71279	4718-3856	67	51 42-77	1885-0522	0	22 41-65	10-5065	68	14 24-41	1895-5588
72	170	50-84896	4745-7634	68	50 50-94	1912-4301	0	20 30-37	9-4936	69	11 21-30	1921-9236

1	2	3	4	5	6	7	8	9
73	171 40-98513	4773-1413	69 40 50-11	1039-8079	0 18 19-08	8-4800	70 8 18-19	1948-2885
74	172 40-12130	4800-6101	70 40 7-28	1067-1858	0 16 7-42	7-4646	71 5 14-76	1974-6504
75	173 48-25748	4827-8970	71 48 18-45	1094-5636	0 13 54-65	6-4425	72 2 10-40	2001-0002
76	174 47-30365	4855-2748	72 47 23-62	2021-9415	0 11 42-49	5-4304	72 59 6-11	2027-3019
77	175 46-32082	4882-6027	73 46 31-79	2049-3194	0 9 30-02	4-3983	73 56 1-81	2053-7177
78	176 45-06599	4910-0300	74 45 39-06	2076-6972	0 7 17-25	3-3739	74 52 57-21	2080-0711
79	177 44-80216	4937-4084	75 44 48-13	2104-0751	0 5 4-20	2-3472	75 40 52-32	2100-4223
80	178 43-63833	4964-7863	76 43 56-30	2131-4529	0 2 51-14	1-3205	76 46 47-44	2132-7734
81	179 43-07451	4992-1041	77 43 4-47	2158-8308	0 0 38-08	0-2938	77 43 42-55	2159-1240
<i>Sun at 78° (oppose)</i>								
	180 0-0	5000-0	78 0 0-0	2166-6	0 0 0-0	0-0	78 0 0-0	2166-6
<i>(Sun's equation of centre is minus, —, after his mean anomaly is 180° till it reaches 360° or 0°.)</i>								
<i>Sun's equation of the centre.</i>								
82	180 42-21008	5019-5420	78 42 12-64	2186-2086	0 1 34-97	0-7328	78 40 37-07	2185-4758
83	181 41-34685	5046-0198	79 41 20-81	2213-5805	0 3 48-03	1-7595	79 37 32-78	2211-8270
84	182 40-48302	5074-2977	80 40 28-98	2240-9644	0 6 1-09	2-7862	80 34 27-89	2238-1782
85	183 39-61919	5101-6756	81 39 37-15	2268-3422	0 8 14-14	3-8128	81 31 23-01	2264-5294
86	184 38-75536	5129-0534	82 38 45-32	2295-7201	0 10 26-06	4-8354	82 28 18-60	2290-8847
87	185 37-89153	5156-4313	83 37 53-49	2323-0979	0 12 39-13	5-8575	83 25 14-37	2317-2405
88	186 37-02771	5183-8091	84 37 1-60	2350-4758	0 14 51-59	6-8796	84 22 10-07	2343-5092
89	187 36-16388	5211-1870	85 36 9-83	2377-8536	0 17 3-93	7-9007	85 19 5-90	2369-9529
90	188 35-30005	5238-5648	86 35 18-00	2405-2315	0 19 15-22	8-9137	86 16 2-79	2396-3178
91	189 34-43622	5265-9427	87 34 26-17	2432-6094	0 21 26-50	9-9207	87 12 59-67	2422-6827
92	190 33-57239	5293-3206	88 33 34-34	2459-9872	0 23 37-78	10-9307	88 9 56-56	2449-0476
93	191 32-70856	5320-6984	89 32 42-51	2487-3651	0 25 48-53	11-9485	89 6 53-98	2475-4165
<i>At true Karika-samkrāntis</i>								
94	192 31-84474	5348-2122	90 27 49-23	2512-8798	0 27 49-23	12-8798	90 0 0-0	2500-0
95	193 30-98091	5375-4541	91 30 58-85	2540-7429	0 27 58-04	12-9478	90 3 53-64	2501-7051
96	194 30-11708	5402-8330	92 30 7-02	2568-6060	0 30 7-55	13-0471	91 0 51-31	2528-1737
97	195 29-25325	5430-2098	93 29 15-20	2596-4705	0 32 17-06	14-0464	91 57 49-97	2554-6522
98	196 28-38942	5457-5877	94 28 23-37	2624-3354	0 34 25-39	15-0307	92 54 49-80	2580-9298
					0 36 32-54	16-0177	93 51 50-83	2607-3366

TABLE XLVIII A—Contd.

1st Arya-Siddhanta.

24-hour periods from true Mēsa-sankrānti.	Sun's mean anomaly or (mean sun's distance from perigee- point) ($\pm 0^{\circ}$).				Sun's mean Longitude, λ			Sun's equation of the centre, —			Sun's true Longitude ($\pm 8^{\circ}$).				
	2		3		4		5		6		7		8		9
	o /		10,000ths of circle,		o /		10,000ths of circle,		o /		10,000ths of circle,		o /		
99	197	27-63559	5484-9050	95	27	31-54	2651-6322	0	38	39-68	17-8988	04	48	51-86	2633-7335
100	198	26-66177	5512-3434	96	26	39-71	2679-0101	0	40	46-82	18-8798	05	45	52-88	2660-1303
101	199	25-79794	5539-7213	97	25	47-88	2706-3870	0	42	51-93	19-8451	06	42	55-95	2686-5428
102	200	24-93411	5567-0991	98	24	56-05	2733-7658	0	44	56-11	20-8033	07	39	59-93	2712-9625
103	201	24-07028	5594-4770	99	24	4-22	2761-1436	0	47	0-30	21-7616	08	37	3-92	2739-3821
104	202	23-20645	5621-8548	100	23	12-39	2788-5215	0	49	4-48	22-7198	09	34	7-90	2765-8017
105	203	22-34262	5649-2327	101	22	20-56	2815-8994	0	51	6-05	23-6578	100	31	14-51	2792-2416
106	204	21-47879	5676-6106	102	21	28-73	2843-2772	0	53	7-28	24-5932	101	28	21-45	2818-6840
107	205	20-61497	5703-9884	103	20	36-90	2870-6551	0	55	8-51	25-5286	102	25	28-39	2845-1264
108	206	19-75114	5731-3663	104	19	45-07	2898-0329	0	57	9-45	26-4618	103	22	35-61	2871-5711
109	207	18-88731	5758-7441	105	18	53-24	2925-4108	0	59	7-14	27-3699	104	19	46-10	2898-0409
110	208	18-02348	5786-1220	106	18	1-41	2952-7886	1	1	4-82	28-2779	105	16	56-59	2924-5107
111	209	17-15965	5813-4998	107	17	9-58	2980-1665	1	3	2-50	29-1859	106	14	7-08	2950-9806
112	210	16-29582	5840-8777	108	16	17-75	3007-5444	1	4	58-88	30-0839	107	11	18-87	2977-4605
113	211	15-43200	5868-2556	109	15	25-92	3034-9222	1	6	51-83	30-9554	108	8	34-09	3003-9668
114	212	14-56817	5895-6334	110	14	34-09	3062-3001	1	8	44-78	31-8270	109	5	49-31	3030-4731
115	213	13-70434	5923-0113	111	13	42-26	3089-6779	1	10	37-73	32-6985	110	3	4-54	3056-9794
116	214	12-84051	5950-3891	112	12	50-43	3117-0558	1	12	28-45	33-5528	111	0	21-98	3083-5030
117	215	11-97668	5977-7670	113	11	58-60	3144-4336	1	14	16-67	34-3879	111	57	41-93	3110-0458
118	216	11-11285	6005-1448	114	11	6-77	3171-8115	1	16	4-89	35-2229	112	55	1-88	3136-5886
119	217	10-24902	6033-5227	115	10	14-64	3199-1894	1	17	53-11	36-0579	113	52	21-83	3163-1314
120	218	9-38520	6059-9006	116	9	23-11	3226-5672	1	19	37-78	36-8656	114	49	45-33	3189-7016
121	219	8-52137	6087-2784	117	8	31-28	3253-9451	1	21	20-68	37-6395	115	47	19-61	3216-2855
122	220	7-65754	6114-6563	118	7	39-45	3281-3229	1	23	3-67	38-4535	116	44	35-88	3242-8694
123	221	6-79371	6142-0341	119	6	47-62	3308-7008	1	25	46-47	39-2475	117	42	1-15	3269-4533
124	222	5-9298	6169-4120	120	5	55-79	3336-0786	1	26	24-27	40-0021	118	39	31-52	3296-0763
125	223	5-06605	6196-7898	121	5	3-96	3363-4565	1	28	1-26	40-7505	119	37	2-71	3322-7061

1	2	3	4	5	6	7	8	9
<i>At true Simha-sankranti</i>								
126	223 28-66604	6297-7153	127 28 39-96	3374-3824	1 28 39-96	41-0191	129 0 0-0	3333-3
127	224 4-20223	6294-1677	122 4 13-13	3390-8344	1 29 38-24	41-4088	120 34 33-89	3349-3356
128	225 3-33840	6251-6456	123 3 20-30	3418-2122	1 31 14-80	42-2445	121 33 5-41	3375-9077
129	226 2-47457	6278-9234	124 2 28-47	3445-5801	1 32 45-96	42-9472	122 29 42-51	3402-6429
130	227 1-61074	6306-3013	125 1 30-64	3472-9079	1 34 17-03	43-0490	123 27 19-61	3429-3180
	228 0-74691	6333-6791	126 0 44-81	3500-3458	1 35 48-10	44-3526	124 24 56-71	3455-9932
131	228 59-68308	6361-0570	126 59 52-96	3527-7236	1 37 17-53	45-0427	125 22 25-45	3482-6810
132	229 59-01926	6388-4348	127 59 1-16	3556-1015	1 38 42-10	45-6952	126 20 19-06	3509-4093
133	230 58-15543	6415-8127	128 58 9-33	3582-4794	1 40 0-66	46-3477	127 18 2-66	3536-1317
134	231 57-29160	6443-1906	129 57 17-50	3609-8572	1 41 31-23	47-0002	128 15 46-27	3562-8570
135	232 56-42777	6470-5684	130 56 26-67	3637-2351	1 42 52-62	47-6282	129 13 33-05	3589-6048
136	233 55-56394	6497-9463	131 55 33-84	3664-6129	1 44 10-09	48-2251	130 11 23-75	3616-3869
137	234 54-70011	6525-3241	132 54 42-01	3691-9908	1 45 27-56	48-8238	131 9 14-45	3643-1670
138	235 53-83628	6552-7020	133 53 50-18	3719-3687	1 46 45-03	49-4215	132 7 5-15	3669-9472
139	236 52-97246	6580-0798	134 52 58-35	3746-7465	1 47 57-94	49-9841	133 5 0-41	3696-7624
140	237 52-10863	6607-4577	135 52 6-52	3774-1244	1 49 8-31	50-5271	134 2 58-21	3723-5973
141	238 51-24480	6634-8356	136 51 14-69	3801-5022	1 50 18-68	51-0701	135 0 56-01	3750-4323
142	239 50-38097	6662-2134	137 50 22-86	3828-8801	1 51 29-05	51-6131	135 58 53-80	3777-2670
143	240 49-51714	6689-5913	138 49 31-03	3856-2579	1 52 32-99	52-1064	136 56 58-04	3804-1515
144	241 48-65331	6716-9691	139 48 39-20	3883-6358	1 53 35-67	52-5901	137 55 3-53	3831-0457
145	242 47-78949	6744-3470	140 47 47-37	3911-0137	1 54 38-30	53-0737	138 53 9-01	3857-9399
146	243 46-92566	6771-7248	141 46 55-54	3938-3915	1 55 41-04	53-5574	139 51 14-50	3884-8341
147	244 46-06183	6799-1027	142 46 3-71	3965-7694	1 56 35-70	53-9798	140 49 27-92	3911-7895
148	245 45-19800	6826-4890	143 45 11-88	3993-1472	1 57 30-78	54-4042	141 47 41-10	3938-7430
149	246 44-33417	6853-8584	144 44 20-05	4020-5251	1 58 25-78	54-8286	142 45 54-27	3965-6965
150	247 43-47034	6881-2363	145 43 28-22	4047-9029	1 59 18-80	55-2384	143 44 9-33	3992-6646
151	248 42-60652	6908-6141	146 42 36-39	4075-2808	2 0 5-61	55-5988	144 42 30-78	4019-6820
152	249 41-74269	6935-9920	147 41 44-56	4102-6587	2 0 52-33	55-9593	145 40 52-23	4046-6993
153	250 40-87886	6963-3698	148 40 52-73	4130-0365	2 1 39-04	56-3198	146 39 13-69	4073-7167
154	251 40-01503	6990-7477	149 40 0-90	4157-4144	2 2 22-26	56-6532	147 37 38-64	4100-7611
155	252 39-15120	7018-1256	150 39 9-07	4184-7922	2 3 0-70	56-9498	148 36 8-37	4127-8424
156	253 38-28737	7045-5034	151 38 17-24	4212-1701	2 3 39-14	57-2464	149 34 38-11	4154-9237

TABLE XLVIII A—Contd.

1st Ārya-Siddhānta.

24-hour periods from true Māha-samkrānti.	Sun's mean anomaly (or mean sun's distance from perige- point) ($^{\circ}$ $0'$ $''$).		Sun's mean Longitude.		Sun's equation of the centre.		Sun's true Longitude ($^{\circ}$ $0'$ $''$).	
	3		4		5		6	
	0	1	0	1	0	1	0	1
1	10,000ths of circle.		10,000ths of circle.		10,000ths of circle.		10,000ths of circle.	
	254	3-03008	152	3 55-80	4224-0417	2 3 55-80	57-3751	150 0 0-0
At true Kanyā-samkrānti								4166-6
157	254	37-42354	152	37 25-41	4239-5470	2 4 17-58	57-5430	150 33 7-84
158	255	30-55072	153	36 33-58	4266-0258	2 4 50-00	57-8001	151 31 42-69
159	256	35-69589	154	35 41-75	4294-3037	2 5 21-05	58-0328	152 30 20-70
160	257	34-83206	155	34 40-02	4321-0815	2 5 51-21	58-2655	153 28 58-71
161	258	33-96823	156	33 58-09	4349-0594	2 6 21-37	58-4983	154 27 36-72
162	259	33-10440	157	33 6-26	4376-4372	2 6 44-80	58-6700	155 26 21-47
163	260	32-24057	158	32 14-43	4403-8151	2 7 6-08	58-8478	156 25 7-76
164	261	31-37675	159	31 22-60	4431-1929	2 7 28-50	59-0167	157 23 54-05
165	262	30-51292	160	30 30-78	4458-6708	2 7 50-36	59-1849	158 22 40-41
166	263	29-64909	161	29 38-95	4485-9487	2 8 3-37	59-3533	159 21 35-57
167	264	28-78526	162	28 47-12	4513-3265	2 8 16-38	59-5217	160 20 30-73
168	265	27-92143	163	27 55-29	4540-7044	2 8 29-39	59-6901	161 19 25-89
169	266	27-05760	164	27 3-46	4568-0822	2 8 40-50	59-8585	162 18 22-86
170	267	26-19377	165	26 11-63	4595-4601	2 8 44-73	59-0044	163 17 20-80
171	268	25-32995	166	25 19-80	4622-8379	2 8 48-87	59-1504	164 16 30-92
172	269	24-46612	167	24 27-97	4650-2158	2 8 53-01	59-3062	165 15 34-05
173	270	23-60229	168	23 36-14	4677-5937	2 8 53-85	59-4748	166 14 42-29
174	271	22-73846	169	22 44-31	4704-9715	2 8 49-71	59-6428	167 13 54-60
175	272	21-87463	170	21 53-48	4732-3494	2 8 45-57	59-8109	168 13 6-01
176	273	21-01080	171	21 0-65	4759-7272	2 8 41-43	59-9789	169 12 19-22
177	274	20-14698	172	20 8-82	4787-1051	2 8 32-02	60-1469	170 11 30-80
178	275	19-28315	173	19 16-99	4814-4829	2 8 19-01	60-3149	171 10 57-98
179	276	18-41932	174	18 25-16	4841-8608	2 8 6-00	60-4829	172 10 19-16
180	277	17-55540	175	17 33-33	4869-2387	2 7 52-59	60-6509	173 9 40-34
181	278	16-69158	176	16 41-50	4896-6165	2 7 32-07	60-8189	174 9 8-53

1	2	3	4	5	6	7	8	9
182	279 15-52783	7757-3277	177 15 49-67	4923-9044	2 7 11-00	58-8819	175 8 38-56	4805-1125
183	280 14-06401	7784-7056	178 14 57-84	4951-3722	2 6 49-21	58-7131	176 8 8-63	4802-6592
184	281 14-00018	7812-0634	179 14 6-01	4978-7501	2 6 27-33	58-6442	177 7 38-68	4920-2008
185	282 13-23635	7839-4613	180 13 14-18	5006-1279	2 5 57-30	58-3125	178 7 16-88	4947-8154
186	283 12-37252	7866-8361	181 12 22-35	5033-5058	2 5 27-14	58-0798	179 6 55-21	4975-4280
<i>At true Tulā-śamkrānti</i>								
284	5-00196	7891-2060	182 5 0-20	5057-8727	2 5 0-30	57-8727	180 0 0-0	5000-0
285	11-50869	7894-2170	182 11 30-52	5080-8837	2 4 50-08	57-8471	180 6 33-54	5003-0366
286	10-04486	7921-5948	183 10 38-69	5088-2615	2 4 25-33	57-0629	181 6 13-36	5030-6586
287	9-78103	7948-0727	184 9 46-86	5115-0394	2 3 46-80	57-3063	182 5 09-97	5058-3331
288	8-91721	7976-3506	185 8 55-03	5143-0172	2 3 8-45	57-0697	183 5 46-08	5086-0076
289	8-05338	8003-7284	186 8 3-20	5170-3951	2 2 30-02	56-7131	184 5 33-19	5113-6820
290	7-18955	8031-1063	187 7 11-37	5197-7729	2 1 48-47	56-3925	185 5 22-00	5141-3804
291	6-32572	8058-4841	188 6 19-54	5225-1508	2 1 1-75	56-0320	186 5 17-79	5169-1186
292	5-46189	8085-8020	189 5 27-71	5252-5287	2 0 15-04	55-4716	187 5 12-08	5196-8571
293	4-59806	8113-2598	190 4 35-88	5279-9065	1 59 28-32	55-3111	188 5 7-57	5224-0954
294	3-73423	8140-6177	191 3 44-05	5307-2844	1 58 36-88	54-9142	189 5 7-18	5252-3702
295	2-87041	8167-9956	192 2 52-22	5334-6622	1 57 41-88	54-4898	190 5 10-34	5280-9746
296	2-00658	8195-3734	193 2 0-39	5362-0401	1 56 46-85	54-0655	191 5 13-51	5307-9746
297	1-14275	8222-7513	194 1 8-57	5389-4178	1 55 51-80	53-6411	192 5 16-68	5335-7708
298	0-27892	8250-1291	195 0 16-74	5416-7958	1 54 51-00	53-1713	193 5 25-73	5363-6245
299	0-41509	8277-5070	196 0 24-91	5444-1737	1 53 48-32	52-6877	194 5 36-59	5391-4890
300	58-55127	8304-8848	196 58 33-08	5471-5515	1 52 45-64	52-2040	195 5 47-44	5419-3475
301	57-68744	8332-2627	197 57 41-25	5498-9294	1 51 42-95	51-7203	196 5 58-29	5447-2091
302	56-82361	8359-6406	198 56 49-42	5526-3072	1 50 32-88	51-1766	197 5 16-54	5475-1276
303	55-95978	8387-0184	199 55 57-09	5553-6851	1 49 22-51	50-6366	198 5 35-08	5503-0484
304	55-09595	8414-3963	200 55 5-76	5581-0629	1 48 12-14	50-0936	199 5 53-62	5530-9693
305	54-23212	8441-7741	201 54 13-03	5608-4408	1 47 0-66	49-5421	200 7 13-27	5558-8987
306	53-36829	8469-1020	202 53 22-10	5635-8187	1 45 43-19	48-0443	201 7 38-91	5586-8743
307	52-50447	8496-5298	203 52 30-27	5663-1965	1 44 25-72	46-3466	202 8 4-55	5614-8499
308	51-64064	8523-9077	204 51 38-44	5690-5744	1 43 8-25	47-7488	203 8 30-19	5642-8255
309	50-77681	8551-2856	205 50 46-01	5717-9522	1 41 48-29	47-1319	204 8 58-32	5670-8204
310	49-91298	8578-0634	206 49 54-78	5745-3301	1 40 23-72	46-4794	205 9 31-05	5698-8507
311	49-04915	8606-0413	207 49 2-95	5772-7079	1 38 59-16	45-8268	206 10 3-79	5726-8811
312	48-18532	8633-4191	208 48 11-12	5800-0858	1 37 34-59	45-1743	207 10 36-02	5754-9115
313	47-32150	8660-7970	209 47 19-29	5827-4637	1 36 6-47	44-4044	208 11 12-81	5782-9693
314	46-45767	8686-1748	210 46 27-46	5854-8415	1 34 35-41	43-7917	209 11 52-06	5811-0498

TABLE XLVIII A—Contd.

Int Arya-Siddhanta.

TABLE XLVIII. A—CONTD.

24-hour periods from true Meeha-sankranti.	Sun's mean anomaly (or mean sun's distance from perige- point) (⁶⁶ 0 ¹⁷).			Sun's mean Longitude.			Sun's equation of the centre.			Sun's true Longitude (⁶⁶ 8 ¹⁷).		
	2		3	4		5	6		7	8		9
	o	'	10,000ths of circle.	o	'	10,000ths of circle.	o	'	10,000ths of circle.	o	'	10,000ths of circle.
At true Pritchika-sankh.	313	33-35561	8769-9007	211	33 23-14	5876-5674	1	33 23-14	43-2341	210	0 0-0	5833-3
	217	313 45-39384	8715-5027	211	45 35-83	5882-2104	1	33 4-34	43-0890	210	12 31-29	5839-1304
	218	314 44-73001	8742-9306	212	44 43-80	5903-5972	1	31 33-27	42-3863	211	13 10-53	5867-2109
	219	316 43-86618	8770-3084	213	43 51-07	5936-9781	1	29 57-81	41-0498	212	13 54-16	5895-3253
	220	316 43-00235	8797-6863	214	43 0-14	5964-4329	1	28 20-83	40-9014	213	14 30-32	5923-4615
	221	317 42-18853	8825-0641	215	42 8-31	5991-7308	1	26 43-84	40-1631	214	15 24-47	5951-5777
	222	318 41-27470	8852-4420	216	41 16-48	6019-1087	1	25 6-86	39-4048	215	16 9-62	5979-7039
	223	319 40-41087	8879-8198	217	40 24-65	6046-4865	1	23 24-34	38-6137	216	17 0-32	6007-8728
	224	320 39-54704	8907-1977	218	39 32-82	6073-8644	1	21 41-44	37-8197	217	17 51-38	6036-0446
	225	321 38-68321	8934-5756	219	38 40-99	6101-2422	1	19 58-54	37-0256	218	18 42-45	6064-2164
At true Pritchika-sankh.	226	322 37-81938	8961-9534	220	37 49-16	6128-6201	1	18 14-94	36-2364	219	19 34-23	6092-3937
	227	323 36-95555	8989-3313	221	36 57-33	6155-9979	1	16 26-72	35-3914	220	20 30-61	6120-6006
	228	324 36-09173	9016-7091	222	35 5-50	6183-3758	1	14 38-50	34-5563	221	21 27-00	6148-8195
	229	325 35-22790	9044-0870	223	35 13-67	6210-7537	1	12 50-28	33-7213	222	22 23-39	6177-0323
	230	326 34-36407	9071-4648	224	34 21-84	6238-1315	1	11 0-51	32-8743	223	23 21-33	6205-2572
	231	327 33-50024	9098-8427	225	33 30-01	6265-5094	1	9 7-56	32-0028	224	24 22-45	6233-5066
	232	328 32-63641	9126-2206	226	32 38-18	6292-8872	1	7 14-61	31-1313	225	25 23-57	6261-7559
	233	329 31-77258	9153-5984	227	31 46-36	6320-2651	1	5 21-66	30-2598	226	26 24-09	6290-0053
	234	330 30-90876	9180-9763	228	30 54-52	6347-6429	1	3 26-24	29-3691	227	27 28-28	6318-2738
	235	331 30-04493	9208-3541	229	30 2-70	6375-0208	1	1 28-56	28-4611	228	28 34-13	6346-5597
At true Pritchika-sankh.	236	332 29-18110	9235-7320	230	29 10-87	6402-3987	0	59 30-88	27-5531	229	29 39-09	6374-8456
	237	333 28-31727	9263-1098	231	28 19-04	6429-7765	0	57 33-20	26-6451	230	30 45-84	6403-1315
	238	334 27-45344	9290-4877	232	27 27-21	6457-1544	0	55 32-97	25-7174	231	31 54-24	6431-4370
	239	335 26-58961	9317-8656	233	26 35-38	6484-5322	0	53 31-74	24-7820	232	33 3-64	6459-7503
	240	336 25-72578	9345-2434	234	25 43-55	6511-9101	0	51 30-51	23-8405	233	34 13-03	6488-0635
	241	337 24-86196	9372-6213	235	24 51-72	6539-2879	0	49 29-28	22-9111	234	35 22-43	6516-3708
	242	338 24-00000	9400-0000	236	24 00-00	6566-5648	0	47 28-05	22-0000	235	36 31-54	6544-6841
	243	339 23-13800	9427-2728	237	23 07-23	6593-8417	0	45 26-42	21-1111	236	37 41-05	6572-9974
	244	340 22-27600	9454-5456	238	22 14-46	6620-1186	0	43 25-19	20-2222	237	38 50-16	6601-3087
	245	341 21-41400	9481-8184	239	21 21-69	6647-3955	0	41 24-00	20-0000	238	39 58-27	6631-6200

1	2	3	4	5	6	7	8	9
242	338	9399-8991	236	6566-6658	0 47	25-35	235	6544-7109
243	339	9427-3770	237	6594-0437	0 45	21-17	236	6573-0470
244	340	9454-7548	238	6621-4215	0 43	16-08	237	6601-3831
245	341	9482-1327	239	6648-7994	0 41	12-48	238	6629-7216
246	342	9509-5106	240	6676-1772	0 39	9-53	239	6658-0805
	343	9537-7997	241	6684-4663	0 38	26-84	240	6666-6
	344	9566-8884	242	6703-9329	0 36	58-19	241	6686-4394
	345	9591-0441	243	6728-3108	0 34	51-05	242	6714-7983
	346	9619-0230	244	6753-6887	0 32	43-19	243	6743-1628
	347	9646-3998	245	6781-0665	0 30	33-08	244	6771-5399
	348	9673-7777	246	6813-0665	0 28	24-17	245	6799-0171
	349	9701-1556	247	6840-4444	0 26	14-06	246	6828-2942
	350	9728-5334	248	6867-8222	0 24	4-27	247	6856-6782
	351	9755-9113	249	6895-2001	0 21	52-99	248	6885-0690
	352	9783-2891	250	6922-5779	0 19	41-70	249	6913-4569
	353	9810-6670	251	6949-9558	0 17	30-42	250	6941-8507
	354	9838-0448	252	6977-3337	0 15	18-32	251	6970-2479
	355	9865-4227	253	7004-7115	0 13	5-85	252	6998-6478
	356	9892-8006	254	7032-0894	0 10	53-39	253	7027-0478
	357	9920-1784	255	7059-4672	0 8	40-92	254	7055-4478
	358	9947-5563	256	7086-8451	0 6	27-43	255	7083-8518
	359	9974-9341	257	7114-2229	0 4	14-88	256	7112-2503
	360	10000-0	258	7141-6068	0 2	1-82	257	7140-6608
	361		259	7166-6	0 0	0-0	258	7166-6
	362		260		0 0	0-0	259	
	363		261		0 0	0-0	260	
	364		262		0 0	0-0	261	
	365		263		0 0	0-0	262	
	366		264		0 0	0-0	263	
	367		265		0 0	0-0	264	
	368		266		0 0	0-0	265	
	369		267		0 0	0-0	266	
	370		268		0 0	0-0	267	
	371		269		0 0	0-0	268	
	372		270		0 0	0-0	269	
	373		271		0 0	0-0	270	
	374		272		0 0	0-0	271	
	375		273		0 0	0-0	272	
	376		274		0 0	0-0	273	
	377		275		0 0	0-0	274	
	378		276		0 0	0-0	275	
	379		277		0 0	0-0	276	
	380		278		0 0	0-0	277	
	381		279		0 0	0-0	278	
	382		280		0 0	0-0	279	
	383		281		0 0	0-0	280	
	384		282		0 0	0-0	281	
	385		283		0 0	0-0	282	
	386		284		0 0	0-0	283	
	387		285		0 0	0-0	284	
	388		286		0 0	0-0	285	
	389		287		0 0	0-0	286	
	390		288		0 0	0-0	287	
	391		289		0 0	0-0	288	
	392		290		0 0	0-0	289	
	393		291		0 0	0-0	290	
	394		292		0 0	0-0	291	
	395		293		0 0	0-0	292	
	396		294		0 0	0-0	293	
	397		295		0 0	0-0	294	
	398		296		0 0	0-0	295	
	399		297		0 0	0-0	296	
	400		298		0 0	0-0	297	
	401		299		0 0	0-0	298	
	402		300		0 0	0-0	299	
	403		301		0 0	0-0	300	
	404		302		0 0	0-0	301	
	405		303		0 0	0-0	302	
	406		304		0 0	0-0	303	
	407		305		0 0	0-0	304	
	408		306		0 0	0-0	305	
	409		307		0 0	0-0	306	
	410		308		0 0	0-0	307	
	411		309		0 0	0-0	308	
	412		310		0 0	0-0	309	
	413		311		0 0	0-0	310	
	414		312		0 0	0-0	311	
	415		313		0 0	0-0	312	
	416		314		0 0	0-0	313	
	417		315		0 0	0-0	314	
	418		316		0 0	0-0	315	
	419		317		0 0	0-0	316	
	420		318		0 0	0-0	317	
	421		319		0 0	0-0	318	
	422		320		0 0	0-0	319	
	423		321		0 0	0-0	320	
	424		322		0 0	0-0	321	
	425		323		0 0	0-0	322	
	426		324		0 0	0-0	323	
	427		325		0 0	0-0	324	
	428		326		0 0	0-0	325	
	429		327		0 0	0-0	326	
	430		328		0 0	0-0	327	
	431		329		0 0	0-0	328	
	432		330		0 0	0-0	329	
	433		331		0 0	0-0	330	
	434		332		0 0	0-0	331	
	435		333		0 0	0-0	332	
	436		334		0 0	0-0	333	
	437		335		0 0	0-0	334	
	438		336		0 0	0-0	335	
	439		337		0 0	0-0	336	
	440		338		0 0	0-0	337	
	441		339		0 0	0-0	338	
	442		340		0 0	0-0	339	
	443		341		0 0	0-0	340	
	444		342		0 0	0-0	341	
	445		343		0 0	0-0	342	
	446		344		0 0	0-0	343	
	447		345		0 0	0-0	344	
	448		346		0 0	0-0	345	
	449		347		0 0	0-0	346	
	450		348		0 0	0-0	347	
	451		349		0 0	0-0	348	
	452		350		0 0	0-0	349	
	453		351		0 0	0-0	350	
	454		352		0 0	0-0	351	
	455		353		0 0	0-0	352	
	456		354		0 0	0-0	353	
	457		355		0 0	0-0	354	
	458		356		0 0	0-0	355	
	459		357		0 0	0-0	356	
	460		358		0 0	0-0	357	
	461		359		0 0	0-0	358	
	462		360		0 0	0-0	359	
	463		361		0 0	0-0	360	
	464		362		0 0	0-0	361	
	465		363		0 0	0-0	362	
	466		364		0 0	0-0	363	
	467		365		0 0	0-0	364	
	468		366		0 0	0-0	365	
	469		367		0 0	0-0	366	
	470		368		0 0	0-0	367	
	471		369		0 0	0-0	368	
	472		370		0 0	0-0	369	
	473		371		0 0	0-0	370	
	474		372		0 0	0-0	371	
	475		373		0 0	0-0	372	
	476		374		0 0	0-0	373	
	477		375		0 0	0-0	374	
	478		376		0 0	0-0	375	
	479		377		0 0	0-0	376	
	480		378		0 0	0-0	377	
	481		379		0 0	0-0	378	
	482		380		0 0	0-0	379	
	483		381		0 0	0-0	380	
	484		382		0 0	0-0	381	
	485		383		0 0	0-0	382	
	486		384		0 0	0-0	383	
	487		385		0 0	0-0	384	
	488		386		0 0	0-0	385	
	489		387		0 0	0-0	386	
	490		388		0 0	0-0	387	
	491		389		0 0	0-0	388	
	492		390		0 0	0-0	389	
	493		391		0 0	0-0	390	
	494		392		0 0	0-0	391	
	495		393		0 0	0-0	392	
	496		394		0 0	0-0	393	
	497		395		0 0	0-0	394	
	498		396		0 0	0-0	395	
	499		397		0 0	0-0	396	
	500		398		0 0	0-0	397	
	501		399		0 0	0-0	398	
	502		400		0 0	0-0	399	
	503		401		0 0	0-0	400	
	504		402		0 0	0-0	401	
	505		403		0 0	0-0	402	
	506		404		0 0	0-0	403	
	507		405		0 0	0-0	404	
	508		406		0 0	0-0	405	
	509		407		0 0	0-0	406	
	510		408		0 0	0-0	407	
	511		409		0 0	0-0	408	
	512		410		0 0	0-0	409	
	513		411		0 0	0-0	410	
	514		412		0 0	0-0	411	
	515		413		0 0	0-0	412	
	516		414		0 0	0-0	413	
	517		415		0 0	0-0	414	
	518		416		0 0	0-0	415	
	519		417		0 0	0-0	416	
	520		418		0 0	0-0	417	
	521		419		0 0	0-0	418	
	5							

TABLE XLVIII A—Contd.

24-hour periods from true Mēṣa-samkrānti.		Sun's mean anomaly (or mean sun's distance from perige- point) ($^{\circ}$ $'$ $''$).			Sun's mean Longitude.			Sun's equation of the centre +			Sun's true Longitude ($^{\circ}$ $'$ $''$).		
1		2	3	4	5	6	7	8	9				
		° ' "	10,000ths of circle.	° ' "	10,000ths of circle.	° ' "	10,000ths of circle.	° ' "	10,000ths of circle.				
269		5 0-47476	139-2013	263 0 40-49	7305-8679	0 11 15-76	5-2142	263 11 56-25	7311-0822				
270		5 59-81093	166-5791	263 59 48-66	7333-2458	0 13 28-23	6-2303	264 13 16-88	7339-4821				
271		6 58-94710	193-8570	264 58 50-83	7360-6237	0 15 40-69	7-2584	265 14 37-52	7367-8821				
272		7 58-08327	221-3348	265 58 5-00	7388-0015	0 17 52-59	8-2762	266 15 57-59	7396-2777				
273		8 57-21945	248-7127	266 57 13-17	7415-3794	0 20 3-88	9-2892	267 17 17-04	7424-0684				
274		9 56-35-62	276-0906	267 56 21-34	7442-7572	0 22 15-16	10-3022	268 18 36-30	7453-0594				
275		10 55-49179	303-4684	268 55 29-51	7470-1351	0 24 26-44	11-3151	269 19 52-05	7481-8502				
At true krānti.		11 34-13893	321-3607	269 34 8-34	7488-0273	0 25 51-66	11-9727	270 0 0-0	7500-0				
276		11 54-62706	330-8463	269 54 37-68	7497-5129	0 26 36-54	12-3189	270 21 14-21	7509-8319				
277		12 53-76413	358-2241	270 53 45-85	7524-8908	0 28 46-04	13-3182	271 22 31-89	7538-2090				
278		13 52-90030	385-6020	271 52 54-02	7552-2687	0 30 55-55	14-3175	272 23 49-57	7566-5862				
279		14 52-03948	412-9798	272 52 2-19	7579-6405	0 33 6-06	15-3168	273 25 7-25	7594-9633				
280		15 51-17265	440-3577	273 51 10-36	7607-0244	0 35 12-52	16-3063	274 26 22-88	7623-3247				
281		16 50-30882	467-7356	274 50 18-53	7634-4022	0 37 19-66	17-2814	275 27 38-10	7651-6836				
282		17 49-44499	495-1134	275 49 26-70	7661-7801	0 39 26-81	18-2624	276 28 53-51	7680-0425				
283		18 48-58116	522-4913	276 48 34-87	7689-1579	0 41 33-77	19-2421	277 30 8-64	7708-4000				
284		19 47-71733	549-8691	277 47 43-04	7716-5358	0 43 37-90	20-2003	278 31 21-00	7736-7361				
285		20 46-85351	577-2470	278 46 51-21	7743-9137	0 45 42-14	21-1583	279 32 33-35	7765-0722				
286		21 45-98908	604-6249	279 45 59-38	7771-2915	0 47 46-33	22-1167	280 33 45-71	7793-4082				
287		22 45-12555	632-0027	280 45 7-55	7798-0694	0 49 49-76	23-0991	281 34 57-31	7821-7386				
288		23 44-26202	659-3806	281 44 15-72	7825-0472	0 51 50-99	24-0845	282 36 6-71	7850-0518				
289		24 43-39819	686-7584	282 43 23-89	7853-4251	0 53 52-22	24-6369	283 37 16-11	7878-3650				
290		25 42-53436	714-1363	283 42 32-06	7880-8029	0 55 53-45	25-8754	284 38 25-51	7906-0783				

1	2	3	4	5	6	7	8	9
201	26 41-07053	741-5141	284 41 40-23	7908-1808	57 53-07	26-7984	285 39 33-31	7934-7792
202	27 40-80671	708-8920	285 40 48-40	7935-5587	0 59 50-76	27-7064	286 40 39-16	7903-2651
203	28 39-94288	706-2699	286 39 56-57	7962-0365	1 1 48-44	28-6145	287 41 45-01	7961-0510
204	29 39-07905	823-6477	287 39 4-74	7990-3144	1 3 40-12	29-5225	288 42 50-86	8019-8309
205	30 38-21522	851-0256	288 38 12-91	8017-6922	1 5 49-74	30-4070	289 43 53-65	8045-0992
206	31 37-55139	878-4034	289 37 21-08	8045-0701	1 7 33-09	31-2785	290 44 54-77	8076-3486
207	32 36-48756	905-7813	290 36 29-25	8072-4479	1 9 26-64	32-1500	291 45 55-00	8104-0980
208	33 35-02374	933-1591	291 35 37-42	8099-8258	1 11 19-59	33-0216	292 46 57-02	8132-8473
209	34 34-75991	960-5370	292 34 45-59	8127-2037	1 13 8-56	33-8623	293 47 54-16	8161-0660
200	35 33-89008	987-9149	293 33 53-76	8154-5815	1 14 56-78	34-6974	294 48 50-54	8189-2789
301	36 33-03225	1015-2927	294 33 1-94	8181-0594	1 16 45-00	35-5324	295 49 46-03	8217-8918
302	37 32-16842	1042-0706	295 32 10-11	8209-3372	1 18 33-02	36-3659	296 50 43-13	8245-7032
303	38 31-30459	1070-0484	296 31 18-28	8236-7151	1 20 15-92	37-1089	297 51 34-20	8273-8750
304	39 30-44077	1097-4288	297 30 26-45	8264-0929	1 21 58-82	37-9538	298 52 25-26	8302-0468
305	40 29-57694	1124-8041	298 29 34-62	8291-4708	1 23 41-71	38-7478	299 53 16-33	8330-2180
<i>At. true</i>	<i>36-11516</i>	<i>1127-8312</i>	<i>298 36 6-91</i>	<i>8291-4978</i>	<i>1 23 53-09</i>	<i>38-8355</i>	<i>300 0 0-0</i>	<i>8353-3</i>
<i>Arāṇi.</i>								
306	41 28-71311	1152-1820	299 28 42-79	8318-8487	1 25 23-24	39-5312	300 54 6-03	8358-3798
307	42 27-84928	1179-5599	300 27 50-96	8349-3265	1 27 0-22	40-2785	301 54 51-18	8386-5060
308	43 26-98545	1206-0377	301 26 59-13	8373-0044	1 28 37-21	41-0278	302 55 36-33	8414-0322
309	44 26-12162	1234-3156	302 26 7-30	8400-9822	1 30 14-19	41-7702	303 56 21-40	8442-7584
310	45 25-25779	1261-6934	303 25 15-47	8428-3601	1 31 48-66	42-5051	304 57 4-12	8470-8051
311	46 24-39397	1289-0713	304 24 23-64	8456-7379	1 33 19-72	43-2077	305 57 43-35	8498-9456
312	47 23-53014	1316-4491	305 23 31-81	8483-1158	1 34 50-79	43-9104	306 58 22-59	8527-0262
313	48 22-66631	1343-8270	306 22 39-98	8510-4937	1 36 21-86	44-6131	307 59 1-83	8555-1067
314	49 21-80248	1371-2049	307 21 48-15	8537-8715	1 37 48-88	45-2845	308 59 37-03	8583-1361
315	50 20-93865	1398-5827	308 20 56-32	8565-2494	1 39 13-44	45-9371	310 0 9-76	8611-1864
316	51 20-07482	1425-9006	309 20 4-49	8592-6272	1 40 38-01	46-5896	311 0 42-50	8639-2168
317	52 19-21100	1453-3384	310 19 12-06	8620-0051	1 42 2-57	47-2421	312 1 15-23	8667-2471
318	53 18-34717	1480-7163	311 18 20-83	8647-3829	1 43 21-33	47-8498	313 1 42-10	8695-2328
319	54 17-48334	1508-0941	312 17 29-00	8674-7608	1 44 38-80	48-4476	314 2 7-80	8723-2684
320	55 16-61951	1535-4720	313 16 37-17	8702-1387	1 45 56-27	49-0453	315 2 33-44	8751-1840
321	56 15-75568	1562-8499	314 15 45-34	8729-5165	1 47 13-05	49-6424	316 2 58-99	8779-1589
322	57 14-89185	1590-2277	315 14 53-51	8756-8944	1 48 24-02	50-1853	317 3 17-53	8807-0797
323	58 14-02802	1617-6056	316 14 1-68	8784-2722	1 49 34-39	50-7283	318 3 36-07	8835-0000
324	59 13-16420	1644-0834	317 13 9-85	8811-6501	1 50 44-77	51-2713	319 3 54-62	8862-9214
325	60 12-30037	1672-3013	318 12 18-02	8839-0279	1 51 53-54	51-8020	320 4 11-56	8890-8299

TABLE XLVIII A—Concl'd.

1st Arya-Siddhanta.

24-hour periods from true Mēsa-samkrānti.	Sun's mean anomaly (or mean sun's distance from perigeo- point) ($^{\circ} \text{ } ^{\circ} \text{ } ^{\circ}$).			Sun's mean Longitude.			Sun's equation of the centre. +			Sun's true Longitude ($^{\circ} \text{ } ^{\circ} \text{ } ^{\circ}$).		
1	2	3	4	5	6	7	8	9	10	11	12	13
		10,000ths of circle.	$\circ$ / ' "	10,000ths of circle.	$\circ$ / ' "	10,000ths of circle.	$\circ$ / ' "	10,000ths of circle.	$\circ$ / ' "	10,000ths of circle.	$\circ$ / ' "	10,000ths of circle.
326	61 11-43654	1099-7391	319 11 26-19	8906-4058	1 52 56-22	52-2857	321 4 22-42	8918-6915				
327	62 10-57271	1727-1170	320 10 34-36	8893-7837	1 53 58-01	52-7093	322 4 33-27	8946-5530				
328	63 9-70888	1754-4949	321 9 42-53	8921-1615	1 55 1-59	53-2530	323 4 44-12	8974-4145				
329	64 8-84505	1781-8727	322 8 50-70	8948-0394	1 56 1-18	53-7128	324 4 51-88	9002-2529				
330	65 7-98123	1809-2506	323 7 58-87	8975-9172	1 56 56-17	54-1371	325 4 55-05	9030-0544				
331	66 7-11740	1836-8284	324 7 7-04	9003-2951	1 57 51-17	54-5615	326 4 58-21	9057-8566				
332	67 6-25357	1864-0063	325 6 16-21	9030-0729	1 58 46-17	54-9858	327 5 1-38	9085-0588				
333	68 5-38974	1891-3841	326 5 23-38	9058-0508	1 59 36-21	55-3730	328 4 59-50	9113-4228				
334	69 4-52591	1918-7620	327 4 31-55	9085-4287	2 0 22-93	55-7324	329 4 54-48	9141-1611				
335	69 55-50196	1945-9361	327 55 54-12	9110-6028	2 1 5-38	55-9613	330 0 0-0	9166-6				
336	70 3-60308	1946-1399	328 3 30-73	9112-8065	2 1 9-54	56-0629	330 4 49-37	9168-8994				
337	71 2-70826	1973-5177	329 2 47-00	9140-1844	2 1 56-36	56-4534	331 4 44-26	9196-0378				
338	72 1-03443	2000-8966	330 1 56-07	9167-5622	2 2 36-51	56-7832	332 4 32-57	9224-3254				
339	73 1-07060	2028-2734	331 1 4-24	9194-0401	2 3 14-95	57-0508	333 4 19-18	9251-9999				
340	74 0-20077	2055-6513	332 0 12-41	9222-3179	2 3 53-38	57-3564	334 4 5-79	9279-6743				
341	74 59-34294	2083-0201	332 59 20-58	9249-6958	2 4 31-82	57-6530	335 3 52-40	9307-3488				
342	75 58-47911	2110-4070	333 58 28-75	9277-0737	2 5 2-07	57-8864	336 3 30-82	9334-0600				
343	76 57-61528	2137-7849	334 57 36-92	9304-4515	2 5 32-23	58-1191	337 3 9-15	9362-5706				
344	77 56-75146	2165-1627	335 56 45-00	9331-8294	2 6 2-39	58-3518	338 2 47-48	9390-1812				
345	78 55-88763	2192-9406	336 55 53-36	9359-2072	2 6 31-03	58-5728	339 2 24-29	9417-7800				
346	79 55-02380	2219-9184	337 55 1-43	9386-5851	2 6 52-91	58-7416	340 1 54-34	9445-3297				
347	80 54-15997	2247-2863	338 54 9-60	9413-9629	2 7 14-79	58-9104	341 1 24-39	9472-8734				
348	81 53-29614	2274-9741	339 53 17-77	9441-3408	2 7 38-67	59-0792	342 0 54-44	9500-4200				
349	82 52-43231	2302-0620	340 52 25-94	9468-7187	2 7 55-19	59-2221	343 0 21-12	9527-9408				
350	83 51-56849	2329-4290	341 51 34-11	9496-0965	2 8 8-20	59-3225	343 59 42-30	9555-4190				

At true Mīna-samkrānti

1	2	3	4	5	6	7	8	9
350	84 50-70466	2356-8077	342 50 42-28	9523-4744	2 8 21-21	59-4229	344 59 3-48	9582-8973
351	85 49-84083	2384-1856	343 49 50-45	9550-8522	2 8 34-21	59-5233	345 58 24-06	9610-3755
352	86 48-97700	2411-5034	344 48 58-02	9578-2301	2 8 43-13	59-5843	346 57 40-75	9637-8144
353	87 48-11317	2438-9413	345 48 6-79	9605-9080	2 8 48-27	59-6163	347 56 53-06	9665-2242
354	88 47-24934	2466-3191	346 47 14-96	9632-9858	2 8 50-41	59-6482	348 56 5-37	9692-8340
355	89 46-38651	2493-6970	347 46 23-13	9660-3637	2 8 54-55	59-6801	349 55 17-08	9720-0438
356	90 45-52169	2521-0749	348 45 31-30	9687-7415	2 8 59-31	59-6629	350 54 23-01	9747-4044
357	91 44-65786	2548-4527	349 44 39-47	9715-1194	2 8 48-17	59-6310	351 53 27-65	9774-7504
358	92 43-70403	2575-8306	350 43 47-64	9742-4972	2 8 44-03	59-5990	352 52 31-68	9802-0963
359	93 42-93020	2603-2084	351 42 55-81	9769-8751	2 8 39-89	59-5671	353 51 35-71	9829-4422
360	94 42-06637	2630-5863	352 42 3-98	9797-2530	2 8 27-20	59-4691	354 50 31-18	9856-7221
361	95 41-20254	2657-9641	353 41 12-15	9824-6308	2 8 14-19	59-3687	355 49 26-34	9883-9995
362	96 40-33872	2685-3420	354 40 20-32	9852-0087	2 8 1-18	59-2683	356 48 21-50	9911-2770
363	97 39-47489	2712-7199	355 39 28-49	9879-3865	2 7 46-74	59-1670	357 47 15-24	9938-5435
364	98 38-61106	2740-0977	356 38 36-66	9906-7044	2 7 24-86	58-9881	358 46 1-53	9965-7525
365	99 37-74723	2767-4756	357 37 44-83	9934-1422	2 7 2-98	58-8193	359 44 47-82	9992-9616

1	2	3	4	5	6	7	8	9
36	116 21-35725	3232-1098	13 37 51-68	378-6411	1 57 15-03	54-2873	15 35 7-52	432-9284
37	117 20-46340	3259-4877	14 37 0-05	406-0189	1 56 13-54	53-8082	16 33 13-60	459-8271
38	118 19-62950	3286-8655	15 36 8-22	433-3968	1 55 11-45	53-3291	17 31 19-67	486-7250
39	119 18-76672	3314-2434	16 35 16-39	460-7746	1 54 9-35	52-8500	18 29 25-75	513-6246
40	120 17-90188	3341-6212	17 34 24-58	488-1625	1 53 4-23	52-3475	19 27 38-80	540-9000
41	121 17-03804	3368-0691	18 33 32-73	515-5303	1 51 54-45	51-8001	20 25 27-19	567-3304
42	122 16-17420	3396-3769	19 32 40-00	542-9082	1 50 44-07	51-2708	21 23 25-57	594-1788
43	123 15-31036	3423-7548	20 31 49-07	570-2860	1 49 34-89	50-7322	22 21 23-96	621-0182
44	124 14-44652	3451-1326	21 30 57-24	597-6639	1 48 20-34	50-1570	23 19 17-58	647-8209
45	125 13-58268	3478-5105	22 30 5-41	625-0417	1 47 2-87	49-5592	24 17 8-28	674-6010
46	126 12-71884	3505-8884	23 29 13-68	652-4196	1 45 45-40	48-9615	25 14 58-98	701-3811
47	127 11-85500	3533-2662	24 28 21-75	679-7975	1 44 27-94	48-3637	26 12 49-69	728-1012
48	128 10-99116	3560-6441	25 27 29-92	707-1753	1 43 6-34	47-7341	27 10 36-26	754-9094
49	129 10-12732	3588-0219	26 26 38-09	734-5532	1 41 41-77	47-0816	28 8 19-86	781-0347
50	130 9-26347	3615-3998	27 25 46-26	761-9310	1 40 17-21	46-4201	29 6 3-47	808-3601
51	131 8-39963	3642-7776	28 24 54-43	789-3089	1 38 52-64	45-7766	30 3 47-07	835-0854
52	132 7-53579	3670-1555	29 24 2-60	816-6867	1 37 22-78	45-0832	31 1 25-39	861-7099
53	133 6-67195	3697-5333	30 23 10-77	844-0646	1 35 51-71	44-3805	31 59 2-48	888-4451
54	134 5-80811	3724-9112	31 22 18-94	871-4424	1 34 20-64	43-6778	32 56 39-58	915-1202
55	135 4-94427	3752-2890	32 21 27-11	898-8203	1 32 48-68	42-9682	33 54 15-78	941-7885
56	136 4-08043	3779-6669	33 20 35-28	926-1981	1 31 11-10	42-2153	34 51 46-38	968-4134
57	137 3-21659	3807-0447	34 19 43-45	953-5760	1 29 33-53	41-4624	35 49 16-97	995-0384
58	138 2-35275	3834-4226	35 18 51-61	980-9538	1 27 55-05	40-7095	36 46 47-57	1021-6633
59	139 1-48891	3861-8004	36 17 59-78	1008-3317	1 26 17-76	39-9519	37 44 17-55	1048-2836
60	140 0-62507	3889-1783	37 17 7-95	1035-7095	1 24 34-28	39-1634	38 41 42-23	1074-8029
61	140 59-76123	3916-5561	38 16 16-12	1063-0874	1 22 50-79	38-3548	39 39 6-91	1101-4422
62	141 58-89789	3943-9340	39 15 24-29	1090-4652	1 21 7-30	37-5563	40 36 31-59	1128-0215
63	142 58-03355	3971-3118	40 14 32-46	1117-8431	1 19 21-02	36-7362	41 33 53-48	1154-5793
64	143 57-16970	3998-6897	41 13 40-63	1145-3209	1 17 31-61	35-8921	42 31 12-25	1181-1130
65	144 56-30586	4026-0675	42 12 48-80	1172-5988	1 15 42-31	35-0479	43 28 31-01	1207-6467
66	145 55-44202	4053-4454	43 11 56-97	1199-9766	1 13 52-81	34-2038	44 25 49-78	1234-1894
67	146 54-57818	4080-8232	44 11 5-14	1227-3545	1 12 1-33	33-3436	45 23 6-47	1260-6981
68	147 53-71434	4108-2011	45 10 13-31	1254-7323	1 10 7-20	32-4629	46 20 20-51	1287-1953
69	148 52-85050	4135-5789	46 9 21-48	1280-1102	1 8 13-06	31-5823	47 17 34-44	1313-6925
70	149 51-98666	4162-9568	47 8 29-65	1306-4880	1 6 18-03	30-7016	48 14 48-58	1340-1897

TABLE XLVIII B—Contd.

24 hour periods from true Mīha-sankrāntī.	Sun's mean anomaly (or mean sun's distance from perice- point) ($^{\circ}$ & $''$).		Sun's mean Longitude.		Sun's equation of the centre. +		Sun's true Longitude ($^{\circ}$ & $''$).	
	1	2	3	4	5	6	7	8
		o	10,000ths of circle.	o	10,000ths of circle.	o	10,000ths of circle.	o
61	150	51-12282	4190-3946	48	7 37-82	1 4 19-98	29-7838	49 11 57-80
62	151	50-25898	4217-7125	49	6 45-60	1 2 20-53	28-8621	50 9 6-52
63	152	49-39514	4245-0903	50	5 54-16	1 0 21-07	27-9404	51 6 15-23
64	153	48-53130	4272-4682	51	5 2-33	0 58 21-09	27-0215	52 3 24-32
65	154	47-66746	4299-8460	52	4 10-50	0 56 18-08	26-0724	53 0 29-48
66	155	46-80362	4327-2239	53	3 18-67	0 54 15-08	25-1233	53 57 34-65
67	156	45-93978	4354-6017	54	2 26-84	0 52 12-08	24-1742	54 54 30-81
68	157	45-07593	4381-9796	55	1 35-01	0 50 8-13	23-2109	55 51 43-13
69	158	44-21209	4409-3575	56	0 43-18	0 48 1-58	22-2344	56 48 44-75
70	159	43-34825	4436-7353	56	59 51-35	0 45 50-03	21-2579	57 45 46-37
71	160	42-48441	4464-1132	57	58 59-51	0 43 48-47	20-2814	58 42 47-99
72	161	41-62057	4491-4910	58	58 7-68	0 41 40-04	19-2904	59 39 47-72
73	162	40-75673	4518-8689	59	57 15-85	0 39 29-94	18-2886	60 36 45-79
74	163	39-89289	4546-2467	60	56 24-02	0 37 19-84	17-2827	61 33 43-86
75	164	39-02905	4573-6246	61	55 32-19	0 35 9-74	16-2788	62 30 41-92
76	165	38-16521	4601-0024	62	54 40-36	0 32 57-99	15-2623	63 27 38-36
77	166	37-30137	4628-3803	63	53 48-53	0 30 44-04	14-2358	64 24 33-47
78	167	36-43753	4655-7581	64	52 56-70	0 28 31-88	13-2090	65 21 28-58
79	168	35-57369	4683-1360	65	52 4-87	0 26 18-83	12-1823	66 18 23-70
80	169	34-70985	4710-5138	66	51 13-04	0 24 5-05	11-1501	67 15 18-09
81	170	33-84601	4737-8917	67	50 21-21	0 21 50-22	10-1097	68 12 11-43
82	171	32-98216	4765-2695	68	49 29-38	0 19 35-39	9-0694	69 9 4-77
83	172	32-11832	4792-6474	69	48 37-55	1 17 19-53	8-0210	70 5 57-07
84	173	31-25448	4820-0252	70	47 45-72	0 15 2-01	6-9669	71 2 48-63
85	174	30-39064	4847-4031	71	46 53-89	0 12 46-31	5-9129	71 59 40-20
86	175							
87	176							
88	177							
89	178							
90	179							
91	180							
92	181							
93	182							
94	183							
95	184							
96	185							
97	186							
98	187							
99	188							
100	189							

1	2	3	4	5	6	7	8	9
76	175 29-52080	4874-7809	72 46 2-06	2021-3122	0 10 20-70	4-8588	72 56 31-76	2026-1710
77	176 28-66396	4902-1688	73 46 10-23	2048-6900	0 8 12-35	3-7090	73 53 22-57	2052-4890
78	177 27-79012	4929-5306	74 44 18-40	2076-0679	0 5 54-56	2-7358	74 50 12-60	2078-8037
79	178 26-96528	4956-0145	75 43 26-57	2103-4457	0 3 36-77	1-6726	75 47 3-34	2105-1184
80	179 26-07144	4984-2923	76 42 34-74	2130-8236	0 1 18-99	0-6095	76 43 53-72	2131-4330
<i>Sun in apogee</i>								
	180 0-0	5000-0	77 16 30-45	2156-5313	0 0 0-0	0-0	77 16 30-45	2146-5313
<i>(The sun's equation of the centre is —, minus, after his mean anow: = 180° till it reaches 360° or 0°)</i>								
				Sun's equation of the centre				
81	180 25-20760	5011-6702	77 41 42-91	2158-2014	0 0 58-73	0-4532	77 40 44-17	2157-7482
82	181 24-34376	5039-0480	78 40 51-08	2186-6793	0 3 16-52	1-5164	78 37 34-55	2184-0629
83	182 23-47092	5066-4259	79 39 59-24	2212-0571	0 5 34-31	2-5795	79 34 24-04	2210-3776
84	183 22-61608	5093-8037	80 39 7-41	2240-3350	0 7 52-10	3-6427	80 31 14-32	2236-6923
85	184 21-75224	5121-1816	81 38 15-58	2267-7128	0 10 9-08	4-6997	81 28 6-50	2263-0132
86	185 20-88839	5148-5594	82 37 23-75	2295-0907	0 12 25-08	5-7537	82 24 58-07	2289-3370
87	186 20-02455	5175-9373	83 36 31-92	2322-4685	0 14 42-29	6-8078	83 21 49-63	2316-6608
88	187 19-16071	5203-3151	84 35 40-09	2349-8464	0 16 58-89	7-8618	84 18 41-30	2341-9846
89	188 18-29687	5230-6930	85 34 48-26	2377-2242	0 19 14-53	8-9084	85 15 53-74	2368-3159
90	189 17-43303	5258-0708	86 33 56-43	2404-6021	0 21 29-36	9-9487	86 12 27-08	2394-6534
91	190 16-56919	5285-4487	87 33 4-60	2431-9790	0 23 44-19	10-9891	87 9 20-41	2420-9809
92	191 15-70535	5312-8266	88 32 12-77	2459-3578	0 25 59-98	12-0399	88 6 12-79	2447-3209
93	192 14-84151	5340-2044	89 31 20-94	2486-7357	0 28 13-03	13-0935	89 3 7-91	2473-6721
94	193 13-97767	5367-5823	90 30 29-11	2514-1135	0 30 29-09	14-0902	90 0 3-02	2500-0233
95	194 13-11383	5394-9601	91 29 37-28	2541-4914	0 32 39-15	15-1169	90 56 58-13	2526-3745
96	195 12-24999	5422-3380	92 28 45-45	2568-8692	0 34 50-82	16-1328	91 53 54-63	2552-7364
97	196 11-38615	5449-7158	93 27 53-62	2596-2471	0 37 0-92	17-1367	92 50 52-70	2579-1104
98	197 10-52231	5477-0937	94 27 1-79	2623-6249	0 39 11-02	18-1406	93 47 50-77	2605-4844
99	198 9-65846	5504-4715	95 26 9-96	2651-0028	0 41 21-12	19-1444	94 44 48-84	2631-8584
100	199 8-79462	5531-8494	96 25 18-13	2678-3806	0 43 29-52	20-1352	95 41 48-60	2658-2454
101	200 7-93078	5559-2272	97 24 26-30	2705-7585	0 45 36-07	21-1117	96 38 50-22	2684-6408
102	201 7-06694	5586-6051	98 23 34-47	2733-1363	0 47 42-63	22-0882	97 35 51-84	2711-0482
103	202 6-20310	5613-9829	99 22 42-64	2760-5142	0 49 49-18	23-0646	98 32 53-46	2737-4495
104	203 5-33926	5641-3608	100 21 50-81	2787-8920	0 51 53-90	24-0270	99 29 56-91	2763-8650
105	204 4-47542	5668-7386	101 20 58-98	2815-2699	0 53 56-90	24-9761	100 27 2-08	2790-2838

TABLE XLVIII B—Contd.

24-hour periods from true Māsa-samkrānti.	Sun's mean anomaly (or mean sun's distance from perige- point) ($^{\circ}$ $0'$ $''$).			Sun's mean Longitude.			Sun's equation of the centre.			Present Sūrya-Siddhānta.		
										Sun's true Longitude ($^{\circ}$ $0'$ $''$).		
	1	2	3	4	5	6	7	8	9	10,000ths of circle.	10,000ths of circle.	10,000ths of circle.
106	205	3-61158	5996-1105	102 20 7-14	2842-6477	0 55 59-00	25-9252	101 24 7-24	2816-7225			
107	206	2-74774	5723-4943	103 19 15-31	2870-0256	0 58 2-91	26-8743	102 21 12-41	2843-1513			
108	207	1-88300	6750-8722	104 18 23-48	2897-4034	1 0 4-04	27-8080	103 18 19-45	2869-5045			
109	208	1-02006	6778-2500	105 17 31-65	2924-7813	1 2 3-40	28-7307	104 15 28-10	2890-0506			
110	209	0-15622	5805-6279	106 16 39-82	2952-1591	1 4 2-95	29-6524	105 12 36-88	2922-5068			
111	209	50-29238	5833-0057	107 15 47-09	2979-6370	1 6 2-40	30-5741	106 9 45-59	2948-9029			
112	210	58-45854	5860-3836	108 14 56-16	3006-9148	1 7 56-02	31-4597	107 7 0-15	2975-4641			
113	211	57-68469	5887-7814	109 14 4-33	3034-2927	1 9 50-15	32-3314	108 4 14-18	3001-0613			
114	212	56-70085	5915-1363	110 13 12-50	3061-6705	1 11 44-28	33-2121	109 1 28-22	3028-4385			
115	213	55-83701	5942-5171	111 12 20-67	3089-0484	1 13 37-76	34-0877	109 58 42-91	3054-9607			
116	214	54-97317	5969-8950	112 11 28-84	3116-4262	1 15 27-17	34-9318	110 56 1-67	3081-4941			
117	215	54-19933	5997-2728	113 10 37-01	3143-8041	1 17 16-57	35-7760	111 53 29-44	3108-0281			
118	216	53-24549	6024-6507	114 9 45-18	3171-1819	1 19 5-97	36-6291	112 50 39-21	3134-5618			
119	217	52-38105	6052-0285	115 8 53-35	3198-5598	1 20 52-05	37-4380	113 48 1-30	3161-1212			
120	218	51-51781	6079-4064	116 8 1-52	3225-9376	1 22 35-53	38-2372	114 45 25-08	3187-7005			
121	219	50-65307	6106-7842	117 7 9-69	3253-3155	1 24 10-02	39-0357	115 42 50-67	3214-2798			
122	220	49-79013	6134-1621	118 6 17-85	3280-6933	1 26 2-51	39-8342	116 40 15-35	3240-8502			
123	221	48-92620	6161-5399	119 5 26-03	3308-0712	1 27 43-00	40-6065	117 37 43-43	3267-4647			
124	222	48-06245	6188-9178	120 4 34-20	3335-4490	1 29 20-17	41-3594	118 35 14-02	3294-0897			
125	223	47-19861	6216-2957	121 3 42-37	3362-8269	1 30 57-75	42-1122	119 42 44-62	3320-7147			
126	224	46-33477	6243-6735	122 2 50-54	3390-2048	1 32 35-32	42-8651	120 39 15-21	3347-3396			
127	225	45-47092	6271-0514	123 1 58-71	3417-5826	1 34 6-86	43-6715	121 27 52-10	3374-0111			
128	226	44-60708	6298-4292	124 1 6-88	3444-9605	1 35 37-83	44-2742	122 25 28-04	3400-0803			
129	227	43-74324	6325-8071	125 0 15-04	3472-3383	1 37 9-00	44-9706	123 23 6-04	3427-3615			
130	228	42-87940	6353-1849	125 59 23-21	3499-7162	1 38 40-07	45-6796	124 20 13-14	3454-0390			

1	2	3	4	5	6	7	8	9
131	229 42-01526	6380-5628	126 58 31-38	3627-0640	1 40 5-22	46-3365	125 18 26-16	3480-7574
132	230 41-15172	6407-0406	127 57 39-55	3554-4719	1 41 20-78	46-9891	126 16 9-77	3507-4828
133	231 40-28788	6435-3185	128 56 47-72	3581-8497	1 42 54-35	47-0416	127 13 53-38	3534-2081
134	232 39-42404	6462-0903	129 55 55-89	3609-2276	1 44 17-30	48-2816	128 11 38-59	3560-9459
135	233 38-56020	6490-0742	130 55 4-06	3636-0054	1 45 34-77	48-8704	129 9 29-29	3587-7266
136	234 37-69636	6517-4520	131 54 12-23	3663-9833	1 46 52-24	49-4771	130 7 19-99	3614-5001
137	235 36-83252	6544-8209	132 53 20-40	3691-3611	1 48 0-71	50-0749	131 5 10-09	3641-2862
138	236 35-96868	6572-2077	133 52 28-57	3718-7390	1 49 23-60	50-6455	132 3 4-01	3668-0635
139	237 35-10484	6600-5856	134 51 36-74	3746-1168	1 50 33-44	51-1839	133 1 3-30	3694-9359
140	238 34-24100	6628-9634	135 50 44-91	3773-4947	1 51 43-22	51-7224	133 59 1-69	3721-7723
141	239 33-37715	6654-3413	136 49 53-08	3800-8725	1 52 53-00	52-2608	134 57 0-08	3748-6117
142	240 32-51331	6681-7101	137 49 1-26	3828-2504	1 53 59-50	52-7739	135 55 1-75	3775-4765
143	241 31-64947	6709-0970	138 48 9-42	3855-6282	1 55 1-59	53-2530	136 53 7-83	3802-3702
144	242 30-78563	6736-4748	139 47 17-59	3883-0061	1 56 3-68	53-7321	137 51 13-90	3829-2740
145	243 29-92179	6763-8527	140 46 25-76	3910-3839	1 57 5-78	54-2112	138 49 19-08	3856-1727
146	244 29-05795	6791-2305	141 45 33-93	3937-7618	1 58 2-84	54-6816	139 47 31-09	3883-1102
147	245 28-19411	6818-6084	142 44 42-10	3965-1396	1 58 57-25	55-0714	140 45 44-85	3910-0683
148	246 27-33027	6845-9862	143 43 50-27	3992-5175	1 59 51-05	55-4912	141 43 58-61	3937-0263
149	247 26-46643	6873-3641	144 42 58-44	4019-8953	2 0 46-06	55-9110	142 42 12-38	3963-9844
150	248 25-60259	6900-7419	145 42 6-01	4047-2732	2 1 33-27	56-2752	143 40 33-34	3990-9980
151	249 24-73875	6928-1198	146 41 14-77	4074-6510	2 2 19-40	56-6311	144 38 55-38	4015-0199
152	250 23-87491	6955-4976	147 40 22-94	4102-0289	2 3 5-52	56-9870	145 37 17-42	4045-0418
153	251 23-01107	6982-8755	148 39 31-11	4129-4067	2 3 51-15	57-3391	146 35 39-97	4072-0676
154	252 22-14723	7010-2533	149 38 39-28	4156-7846	2 4 28-99	57-6311	147 34 10-29	4099-1035
155	253 21-28338	7037-6312	150 37 47-45	4184-1624	2 5 6-84	57-9232	148 32 40-61	4126-2393
156	254 20-41954	7065-0090	151 36 55-62	4211-5403	2 5 44-69	58-2152	149 31 10-63	4153-3251
157	255 19-55570	7092-3869	152 36 3-79	4238-9181	2 6 20-56	58-4919	150 29 43-24	4180-4262
158	256 18-69186	7119-7648	153 35 11-96	4266-2960	2 6 50-12	58-7801	151 28 21-84	4207-6759
159	257 17-82802	7147-1426	154 34 20-13	4293-6739	2 7 19-69	58-9482	152 27 0-44	4234-7256
160	258 16-96418	7174-5205	155 33 28-30	4321-0517	2 7 49-26	59-1764	153 25 39-04	4261-8753
161	259 16-10034	7201-8983	156 32 36-47	4348-4296	2 8 15-77	59-3809	154 24 20-70	4289-0486
162	260 15-23650	7229-2762	157 31 44-64	4375-8074	2 8 37-65	59-5498	155 23 6-99	4316-2676
163	261 14-37266	7256-6540	158 30 52-81	4403-1853	2 8 59-53	59-7186	156 21 53-28	4343-4767
164	262 13-50882	7284-0319	159 30 0-98	4430-5631	2 9 21-41	59-8874	157 20 39-57	4370-6757
165	263 12-64498	7311-4097	160 29 9-15	4457-9410	2 9 35-92	59-9994	158 19 33-22	4397-9415

TABLE XLVIII B—Contd.

TABLE XLVIII B—Contd.														
24-hour period from true Mēṣa-samkrānti.	Sun mean anomaly or (mean sun's distance from perige- point) ($66^{\circ} 0'$).			Sun's mean Longitude.			Sun's equation of the centre.			Sun's true Longitude ($66^{\circ} 8' 37''$).				
	2		3	4		5	6		7	8		9		
	o	'	10,000ths of circle.	o	'	10,000ths of circle.	o	'	10,000ths of circle.	o	'	10,000ths of circle.		
166	264	11-78114	7338-7876	161	28	17-32	4485-3188	2	9	48-03	159	18	28-38	4425-2190
167	265	10-91730	7366-1854	162	27	25-49	4512-6967	2	10	1-94	160	17	23-54	4452-4965
168	266	10-08345	7393-5433	163	26	33-06	4540-0745	2	10	14-95	161	16	18-70	4479-7739
169	267	9-19961	7420-9211	164	25	41-83	4567-4524	2	10	19-24	162	15	22-59	4507-1187
170	268	8-32577	7448-2990	165	24	50-00	4594-8302	2	10	23-38	163	14	26-62	4534-4647
171	269	7-40193	7475-6768	166	23	58-17	4622-2081	2	10	27-52	164	13	30-65	4561-8106
172	270	6-59809	7503-0547	167	23	6-34	4649-5859	2	10	30-54	165	12	35-80	4589-1651
173	271	5-73425	7530-4325	168	22	14-51	4676-9638	2	10	26-40	166	11	48-11	4616-5749
174	272	4-87041	7557-8104	169	21	22-67	4704-3416	2	10	23-26	167	11	0-42	4643-9847
175	273	4-00657	7585-1882	170	20	30-84	4731-7195	2	10	18-12	168	10	12-73	4671-3945
176	274	3-14273	7612-5661	171	19	39-01	4759-0973	2	10	11-45	169	9	27-56	4698-8238
177	275	2-27889	7639-9439	172	18	47-18	4786-4752	2	9	58-44	170	8	48-74	4726-3020
178	276	1-41505	7667-3218	173	17	55-35	4813-8530	2	9	45-43	171	8	9-02	4753-7803
179	277	0-55121	7694-6996	174	17	3-52	4841-2309	2	9	32-42	172	7	31-10	4781-2585
180	277	59-68737	7722-0775	175	16	11-69	4868-6087	2	9	15-56	173	6	56-13	4808-7665
181	278	58-82353	7749-4553	176	15	19-86	4895-9866	2	8	53-08	174	6	26-18	4836-3132
182	279	57-95968	7776-8332	177	14	28-03	4923-3644	2	8	31-80	175	5	56-23	4863-8598
183	280	57-09584	7804-2110	178	13	36-20	4950-7423	2	8	9-02	176	5	26-28	4891-4045
184	281	56-23200	7831-5889	179	12	44-37	4978-1201	2	7	43-65	177	5	0-72	4918-9871
185	282	55-36816	7858-9667	180	11	52-54	5005-4980	2	7	14-08	178	4	38-46	4946-5931
186	283	54-50432	7886-3446	181	11	0-71	5032-8758	2	6	44-51	179	4	16-20	4974-1991
187	284	53-64048	7913-7224	182	10	8-88	5060-2537	2	6	14-94	180	3	53-94	5001-8051
188	285	52-77664	7941-1003	183	9	17-05	5087-6315	2	5	37-00	181	3	40-05	5029-4757
189	286	51-91280	7968-4781	184	8	25-22	5115-0094	2	4	59-15	182	3	24-00	5057-1466
190	287	51-04896	7995-8560	185	7	33-39	5142-3872	2	4	21-31	183	3	12-08	5084-8154

1	2	3	4	5	6	7	8	9						
191	288	50-18512	186	6	41-56	5109-7651	2	3	41-98	57-2683	184	2	59-58	5112-4968
192	289	49-32128	187	5	49-73	5197-1430	2	2	55-85	56-0124	185	2	53-88	5140-2305
193	290	48-45744	188	4	57-90	5224-5208	2	2	9-72	56-5565	186	2	48-17	5167-9643
194	291	47-59360	189	4	6-07	5251-8987	2	1	23-00	56-2006	187	2	42-47	5195-0981
195	292	46-72976	190	3	14-24	5279-2765	2	0	34-51	55-8218	188	2	39-73	5223-4547
196	293	45-86591	191	2	22-40	5306-0544	1	59	40-10	55-4020	189	2	42-30	5251-2523
197	294	45-00207	192	1	30-57	5334-0322	1	58	45-70	54-9822	190	2	44-88	5279-0500
198	295	44-13823	193	0	38-74	5361-4101	1	57	51-29	54-5624	191	2	47-45	5306-8476
199	296	43-27439	193	59	46-91	5388-7879	1	56	53-02	54-1097	192	2	54-29	5334-6782
200	297	42-41055	194	58	55-08	5416-1658	1	55	50-53	53-6306	193	3	4-50	5362-5351
201	298	41-54071	195	58	3-25	5443-5436	1	54	48-43	53-1515	194	3	14-82	5390-3921
202	299	40-68587	196	57	11-42	5470-9215	1	53	46-34	52-0724	195	3	25-08	5418-2491
203	300	39-81903	197	56	19-59	5498-2953	1	52	38-37	52-1479	196	3	41-22	5446-1514
204	301	38-95522	198	55	27-76	5525-6772	1	51	28-59	51-0065	197	3	50-17	5474-0877
205	302	38-09135	199	54	35-93	5553-0550	1	50	18-81	51-0711	198	4	17-12	5501-9840
206	303	37-22751	200	53	44-10	5580-4329	1	49	9-03	50-5326	199	4	35-07	5529-9002
207	304	36-36367	201	52	52-27	5607-8107	1	47	51-43	49-9354	200	5	0-64	5557-8753
208	305	35-49983	202	52	0-44	5635-1886	1	46	34-16	49-3377	201	5	26-28	5585-8509
209	306	34-63599	203	51	8-61	5662-5604	1	45	16-69	48-7399	202	5	51-02	5613-8265
210	307	33-72214	204	50	16-78	5689-9443	1	43	59-56	48-1448	203	6	17-22	5641-7985
211	308	32-90830	205	49	24-95	5717-3221	1	42	35-00	47-4923	204	6	49-95	5669-8290
212	309	32-04446	206	48	32-12	5744-7000	1	41	10-43	46-8398	205	7	22-69	5697-8602
213	310	31-18062	207	47	41-29	5772-0778	1	39	45-87	46-1873	206	7	55-42	5725-8900
214	311	30-31678	208	46	49-46	5799-4557	1	38	20-10	45-5255	207	8	29-36	5753-9302
215	312	29-45294	209	45	57-63	5826-8335	1	36	49-03	44-8228	208	9	8-60	5782-0108
216	313	28-56910	210	45	5-80	5854-2114	1	35	17-96	44-1201	209	9	47-84	5810-0613
217	314	27-72526	211	44	13-97	5881-5892	1	33	46-89	43-4174	210	10	27-08	5838-1719
218	315	26-86142	212	43	22-14	5908-9671	1	32	12-51	42-6892	211	11	9-02	5866-2779
219	316	25-99758	213	42	30-30	5936-3449	1	30	34-04	41-9363	212	11	55-36	5894-4087
220	317	25-13374	214	41	38-47	5963-7228	1	28	57-37	41-1834	213	12	41-11	5922-5394
221	318	24-26990	215	40	46-64	5991-1006	1	27	19-79	40-4305	214	13	26-85	5950-6702
222	319	23-40606	216	39	54-81	6018-4785	1	25	39-41	39-6559	215	14	15-40	5978-8226
223	320	22-54222	217	39	2-98	6045-8563	1	23	55-02	38-8574	216	15	7-06	6006-9989
224	321	21-67837	218	38	11-15	6073-2342	1	22	12-43	38-0589	217	15	68-72	6035-1753
225	322	20-81453	219	37	19-32	6100-6121	1	20	28-04	37-2604	218	16	50-38	6063-3517

TABLE XLVIII B—Contd.

TABLE XLIII B—Contd.										Present Śārya-Siddhānta.					
24-hour periods from true Kāśha-sādhakṛtsūti.	Sun's mean anomaly (or mean sun's distance from perigeo- point) ($^{\circ}$ $0'$ $''$).			Sun's mean Longitude.			Sun's equation of the centre.			Sun's true Longitude ($^{\circ}$ $0'$ $''$).					
	2		3	4		5	6		7	8		9			
	0	'	10,000ths of circle.	0	'	10,000ths of circle.	0	'	10,000ths of circle.	0	'	10,000ths of circle.			
226	323	19-05069	9081-4587	220	36	27-49	6127-0869	1	18	40-47	316-4234	219'	17	47-02	6091-5365
227	324	19-08885	9008-8305	221	35	36-06	6155-3678	1	16	51-07	316-5702	220	18	44-59	6119-7885
228	325	18-22301	9036-2144	222	34	43-83	6182-7456	1	15	1-07	317-7051	221	19	42-16	6148-0106
229	326	17-35917	9063-5922	223	33	53-00	6210-1235	1	13	13-16	318-8379	222	20	38-84	6176-2256
230	327	16-49533	9090-9701	224	33	0-17	6237-5013	1	11	19-03	319-9702	223	21	41-14	6204-4841
231	328	15-63149	9118-3479	225	32	8-34	6264-8792	1	9	24-90	321-1066	224	22	43-44	6232-7426
232	329	14-76765	9145-7258	226	31	16-51	6292-2570	1	7	30-76	31-2539	225	23	45-74	6261-0011
233	330	13-90381	9173-1036	227	30	24-08	6319-6349	1	5	35-16	30-3639	226	24	49-51	6289-2709
234	331	13-03997	9200-4815	228	29	32-85	6347-0127	1	3	35-71	29-4422	227	25	57-14	6317-5705
235	332	12-17613	9227-8593	229	28	41-02	6374-3906	1	1	36-25	28-5205	228	27	4-75	6345-8701
236	333	11-31229	9255-2372	230	27	49-19	6401-7684	0	59	36-80	27-5986	229	28	12-39	6374-1097
237	334	10-44844	9282-6150	231	26	57-36	6429-1463	0	57	36-40	26-6607	230	29	20-06	6402-4765
238	335	9-58460	9309-9929	232	25	5-53	6456-5241	0	55	33-40	25-7207	231	30	32-13	6430-8035
239	336	8-72076	9337-3707	233	25	13-70	6483-9020	0	53	30-39	24-7716	232	31	43-30	6459-1304
240	337	7-85692	9364-7486	234	24	21-87	6511-2798	0	51	27-39	23-8225	233	32	54-48	6487-4574
241	338	6-99308	9392-1264	235	23	39-03	6539-6577	0	49	21-23	22-8490	234	34	8-81	6516-8087
242	339	6-12924	9419-5043	236	22	38-20	6566-0355	0	47	14-47	21-8725	235	35	23-53	6544-1630
243	340	5-26540	9446-8821	237	21	46-37	6593-4134	0	45	8-12	20-8960	236	36	38-25	6572-5174
244	341	4-40156	9474-2600	238	20	54-54	6620-7912	0	43	1-57	19-9195	237	37	52-97	6600-8717
245	342	3-53772	9501-6378	239	20	2-71	6648-1691	0	40	51-82	18-9184	238	39	10-89	6629-2507
246	343	2-67388	9529-0157	240	19	10-88	6675-5469	0	38	41-72	17-9145	239	40	29-16	6657-6324
247	344	1-81004	9556-3935	241	18	19-05	6702-9248	0	36	31-02	16-9107	240	41	47-43	6686-0141
248	345	0-94620	9583-7714	242	17	27-22	6730-3026	0	34	21-74	15-9085	241	43	5-48	6714-3942
249	346	0-08236	9611-1492	243	16	35-39	6757-6805	0	32	8-66	14-8818	242	44	26-71	6742-7987
250	346	59-21802	9638-527	244	15	43-56	6785-0583	0	29	55-63	13-8551	243	45	47-04	6771-2032

1	2	3	4	5	6	7	8	9
251	347 58-35467	9665-9049	245 14 51-73	6812-4362	0 27 43-57	19-8285	244 47 9-16	6790-6077
252	348 57-49083	9693-2828	246 13 59-00	6830-8140	0 25 20-91	11-8049	245 48 29-92	6828-0092
253	349 56-62099	9720-6006	247 13 8-07	6867-1919	0 23 15-08	10-7645	246 49 52-90	6858-4374
254	350 55-70315	9748-0385	248 12 16-24	6894-5697	0 21 0-45	9-7242	247 51 15-99	6884-8456
255	351 54-80631	9776-4163	249 11 24-41	6921-9470	0 18 45-42	8-6838	248 52 38-99	6913-2638
256	352 54-03547	9802-7042	250 10 32-58	6949-3254	0 16 28-80	7-6303	249 54 3-69	6941-6061
257	353 53-17163	9830-1721	251 9 40-75	6976-7033	0 14 12-28	6-5763	250 55 28-47	6970-1570
258	354 52-80779	9857-5490	252 8 48-02	7004-0812	0 11 55-68	5-5222	251 56 53-24	6998-5589
259	355 51-44395	9884-0277	253 7 57-09	7031-4590	0 9 30-07	4-4682	252 58 18-01	7026-9908
260	356 50-58011	9912-3056	254 7 5-26	7058-8369	0 7 21-28	3-4049	253 59 43-08	7055-4319
261	357 49-71027	9939-6835	255 6 13-43	7086-2147	0 5 3-49	2-3418	255 1 9-93	7083-8729
262	358 48-85243	9967-0613	256 5 21-60	7113-5926	0 2 45-71	1-2786	256 2 35-89	7112-3140
263	359 47-98859	9994-4393	257 4 29-77	7140-9704	0 0 27-02	0-2154	257 4 1-85	7140-7550
264	360 0-0	10000-0	257 16 30-45	7168-5313	0 0 0-0	0-0	257 16 30-45	7168-5313

(The Sun's equation of centre is +, plus, after his mean anomaly = 360° till it reaches 180°).

264	265	266	267	268	269	270	271	272	273	274	275	276	277	278	279	280	281	282	283
0 47-12475	1 46-26090	2 45-39706	3 44-53322	4 43-66938	5 42-80554	6 41-94170	7 41-07786	8 40-21402	9 39-35018	10 38-48634	11 37-62250	12 36-75866	13 35-89482	14 35-03098	15 34-16713	16 33-30329	17 32-43945	18 31-57561	19 30-71177
21-8170	49-1949	76-5727	103-9506	131-3284	158-7063	186-0841	213-4620	240-8398	268-2177	295-5955	322-9734	350-3512	377-7291	405-1069	432-4848	459-8626	487-2405	514-6183	541-9962
258 3 37-93	259 2 46-10	260 1 54-27	261 1 2-44	262 0 10-61	263 59 18-78	264 58 26-95	265 57 35-12	266 56 43-29	267 55 51-46	268 54 59-63	269 53 67-80	270 52 75-97	271 51 84-14	272 50 92-31	273 49 40-48	274 48 48-65	275 47 56-82	276 46 64-99	277 45 73-16
7168-3483	7195-7261	7223-1040	7250-4818	7277-8597	7305-2375	7332-6154	7359-9932	7387-3711	7414-7489	7442-1268	7469-5046	7496-8825	7524-2603	7551-6382	7579-0160	7606-3939	7633-7717	7661-1496	7688-5274
0 1 49-89	0 4 7-59	0 6 25-38	0 8 43-16	0 10 59-71	0 13 16-31	0 15 32-92	0 17 49-67	0 20 4-50	0 22 19-33	0 24 34-16	0 26 49-29	0 29 2-35	0 31 15-40	0 33 28-46	0 35 39-03	0 37 49-13	0 39 59-23	0 42 9-33	0 44 16-43
0-8472	1-9104	2-9736	4-0367	5-0993	6-1444	7-1984	8-2536	9-2940	10-3343	11-3747	12-4174	13-4440	14-4707	15-4974	16-5049	17-5088	18-5126	19-5165	20-4971
258 5 27-74	259 6 53-89	260 8 19-65	261 9 45-61	262 11 10-32	263 12 35-10	264 13 59-87	265 15 24-79	266 16 47-79	267 18 10-79	268 19 33-79	269 20 57-09	270 22 18-32	271 23 39-54	272 25 0-77	273 26 19-51	274 27 37-78	275 28 56-05	276 30 14-32	277 31 39-08
7169-1955	7197-6365	7226-0775	7254-5186	7282-9500	7311-3819	7339-8138	7368-2468	7396-6690	7425-0832	7453-5015	7481-9230	7510-3255	7538-7310	7567-1358	7595-5209	7623-9026	7652-2843	7680-6660	7708-0246

Sun in perigee

TABLE XLVIII B—Contd.

Present Sārya-Siddhānta.

24-hour periods from true Māsha-nakhrānti.	Sun's mean anomaly (or mean sun's distance from perige- point) ($^{\circ} \text{ } ^{\circ} \text{ } ^{\circ}$).		Sun's mean Longitude.		Sun's equation of the centre +		Sun's true Longitude ($^{\circ} \text{ } ^{\circ} \text{ } ^{\circ}$).		
	0.	1.	3	4	5	6	7	8	9
284	20	29984793	569-1740	277 46 21-33	7715-9053	0 46 22-68	21-4730	278 32 44-30	7737-3789
285	21	28-98409	596-7519	278 45 29-50	7743-2831	0 48 29-53	22-4501	279 33 59-02	7765-7332
286	22	28-12025	624-1297	279 44 37-66	7770-6610	0 50 36-08	23-4205	280 35 13-74	7794-0876
287	23	27-25641	651-5076	280 43 45-83	7798-0388	0 52 39-48	24-3787	281 36 25-32	7822-4176
288	24	26-39257	678-8854	281 42 54-00	7825-4167	0 54 42-49	25-3278	282 39 36-49	7850-7445
289	25	25-52873	706-2633	282 42 2-17	7852-7945	0 56 45-49	26-2769	283 38 47-66	7879-0715
290	26	24-66489	733-6412	283 41 10-34	7880-1724	0 58 48-86	27-2288	284 39 59-20	7907-4012
291	27	23-80105	761-0190	284 40 18-51	7907-5503	1 0 48-31	28-1905	285 41 0-82	7935-7008
292	28	22-93721	789-3969	285 39 26-68	7934-9281	1 2 47-77	29-0723	286 42 14-45	7964-0004
293	29	22-07336	815-7747	286 38 34-85	7962-3060	1 4 47-22	29-9940	287 43 22-07	7992-2699
294	30	21-20952	843-1536	287 37 43-02	7989-6838	1 6 44-18	30-8965	288 44 27-21	8020-5803
295	31	20-34568	870-8304	288 36 51-19	8017-0617	1 8 38-32	31-7771	289 45 29-51	8048-8388
296	32	19-48184	897-9083	289 35 59-36	8044-4395	1 10 32-45	32-6578	290 46 31-81	8077-0973
297	33	18-61801	925-2861	290 35 7-53	8071-8174	1 12 26-58	33-5384	291 47 34-11	8105-3558
298	34	17-75416	952-6640	291 34 15-70	8099-1952	1 14 18-31	34-4005	292 48 34-01	8133-5958
299	35	16-89032	980-0418	292 33 23-87	8126-5731	1 16 7-71	35-2447	293 49 31-58	8161-8178
300	36	16-02648	1007-4197	293 32 32-04	8153-9509	1 17 57-12	36-0866	294 50 29-15	8190-0369
301	37	15-16264	1034-7975	294 31 40-21	8181-3288	1 19 46-52	36-9330	295 51 26-73	8218-2618
302	38	14-29880	1062-1754	295 30 48-38	8208-7066	1 21 30-40	37-7346	296 52 18-78	8246-4412
303	39	13-43496	1089-5532	296 29 56-55	8236-0845	1 23 13-89	38-5331	297 53 10-44	8274-6176
304	40	12-57112	1116-9311	297 29 4-72	8263-4623	1 24 57-38	39-3316	298 54 2-10	8302-7939
305	41	11-70728	1144-3089	298 28 12-89	8290-8402	1 26 40-87	40-1301	299 54 53-75	8330-9703
306	42	10-84343	1171-6868	299 27 21-06	8318-2180	1 28 18-76	40-8855	300 55 39-82	8359-1035
307	43	9-97959	1199-0646	300 26 29-23	8345-5959	1 29 56-34	41-6384	301 56 25-56	8387-2343
308	44	9-11575	1226-4425	301 25 37-40	8372-9737	1 31 33-91	42-3913	302 57 11-31	8415-3650

1	2	3	4	5	6	7	8	9						
309	45	8-25101	302	24	45-56	8400-3516	1	33	9-54	43-1292	303	57	55-11	8443-4808
310	46	7-38807	303	23	53-73	8427-7294	1	34	40-61	43-8319	304	58	34-35	8471-5613
311	47	6-52423	304	23	1-90	8455-1073	1	35	11-08	44-5346	305	59	13-59	8499-6419
312	48	6-60039	305	22	10-07	8482-4851	1	37	42-75	45-2273	306	59	52-83	8527-7224
313	49	4-79655	306	21	18-24	8500-8030	1	39	12-00	45-9259	308	0	30-24	8555-7889
314	50	3-03271	307	20	26-41	8537-2408	1	40	36-56	46-5784	309	1	2-97	8583-8192
315	51	3-06887	308	19	34-58	8564-6187	1	42	1-13	47-2969	310	1	35-71	8611-8496
316	52	2-20503	309	18	42-75	8591-0965	1	43	25-69	47-8834	311	2	8-44	8639-8800
317	53	1-34118	310	17	50-92	8619-3744	1	44	46-01	48-5032	312	2	30-03	8667-8776
318	54	0-47735	311	16	59-00	8646-7522	1	46	3-48	49-1009	313	3	2-57	8695-8532
319	55	0-61351	312	16	7-26	8674-1301	1	47	20-95	49-6987	314	3	28-21	8723-8288
320	56	0-74066	313	15	15-43	8701-5079	1	48	38-42	50-2964	315	3	53-85	8751-8044
321	57	0-88582	314	14	23-60	8728-8858	1	49	49-52	50-8451	316	4	13-12	8779-7309
322	57	0-92198	315	13	13-77	8756-2636	1	50	59-30	51-3835	317	4	31-07	8807-6472
323	58	0-95814	316	12	39-04	8783-6415	1	52	9-08	51-9219	318	4	49-02	8835-5634
324	59	0-99430	317	11	48-11	8811-0194	1	53	18-86	52-4604	319	5	6-97	8863-4707
325	60	0-43046	318	10	56-28	8838-3972	1	54	22-51	52-9515	320	5	18-79	8891-3487
326	61	0-536002	319	10	4-45	8865-7751	1	55	24-60	53-4306	321	5	29-05	8919-2056
327	62	0-70278	320	9	12-62	8893-1529	1	56	26-70	53-9097	322	5	39-31	8947-0626
328	63	0-83804	321	8	20-79	8920-5308	1	57	28-60	54-3873	323	5	49-39	8974-9181
329	64	0-97510	322	7	28-96	8947-9086	1	58	23-01	54-8671	324	5	51-06	9002-7168
330	65	0-11126	323	6	37-13	8975-2865	1	59	17-41	55-2249	325	5	54-54	9030-5134
331	66	0-24742	324	5	45-30	9002-6643	2	0	11-82	55-6407	326	5	57-11	9058-3110
332	67	48-38358	325	4	53-46	9030-0422	2	1	4-24	56-0512	327	5	57-70	9086-0934
333	68	47-51974	326	4	1-63	9057-4200	2	1	50-36	56-4071	328	5	52-00	9113-8272
334	69	46-65289	327	3	9-80	9084-7979	2	2	36-49	56-7630	329	5	46-29	9141-5609
335	70	45-76205	328	2	17-97	9112-1767	2	3	22-62	57-1190	330	5	40-59	9169-2947
336	71	44-02821	329	1	26-14	9139-5536	2	4	6-17	57-4473	331	5	31-32	9197-0009
337	72	44-06437	330	0	34-31	9166-9314	2	4	43-02	57-7894	332	5	17-33	9224-0708
338	73	43-20053	331	59	42-48	9194-3093	2	5	20-87	58-0314	333	5	3-35	9252-3407
339	74	42-33069	332	58	50-65	9221-6871	2	5	58-72	58-3234	334	4	49-37	9280-0105
340	75	41-47285	333	57	6-00	9249-0650	2	6	31-51	58-5765	335	4	30-34	9307-6415
341	76	40-60901	334	56	9-99	9276-4428	2	7	1-08	58-8047	336	4	8-07	9335-2475
342	77	39-74517	335	56	15-16	9303-8207	2	7	30-65	59-0328	337	3	45-81	9363-8535
343	78	38-88133	336	55	23-33	9331-1985	2	8	0-22	59-2610	338	3	23-53	9390-4595

69329

TABLE XLVIII B—Contd.

Present Sūrya-Siddhānta.

24-hour periods from true Māsa-samkrānti.	Sun's mean anomaly or (mean sun's distance from perige- point) ($^{\circ} 0^{\circ} 30'$).			Sun's mean Longitude.		Sun's equation of the centre. +		Sun's true Longitude ($^{\circ} 0^{\circ} 30'$).	
	1	2	3	4	5	6	7	8	10,000ths of circle.
		0	10,000ths of circle.	0	10,000ths of circle.	0	10,000ths of circle.	0	
344	79	38-01749	2212-0451	336 54 31-50	9358-5764	2 8 23-88	59-4435	339 2 55-38	9418-0199
345	80	37-16365	2239-4230	337 53 39-67	9385-6542	2 8 45-76	59-6123	340 2 25-43	9445-5666
346	81	36-28981	2266-8008	338 52 47-84	9413-3321	2 9 7-04	59-7812	341 1 55-48	9473-1133
347	82	35-42597	2294-1787	339 51 56-01	9440-7099	2 9 27-74	59-9502	342 1 23-74	9500-6462
348	83	34-56212	2321-5565	340 51 4-18	9468-0878	2 9 40-75	60-0366	343 0 44-92	9528-1244
349	84	33-69828	2348-9344	341 50 12-35	9495-4656	2 9 53-76	60-1370	344 0 6-10	9555-6026
350	85	32-83444	2376-3122	342 49 20-52	9522-8435	2 10 6-77	60-2374	344 59 27-28	9583-0809
351	86	31-97060	2403-6901	343 48 28-69	9550-2213	2 10 16-64	60-3136	345 58 45-33	9610-5349
352	87	31-10676	2431-0679	344 47 36-86	9577-5992	2 10 29-77	60-3455	346 57 57-63	9637-9447
353	88	30-24292	2458-4458	345 46 45-03	9604-9770	2 10 24-91	60-3774	347 57 9-94	9665-3544
354	89	29-37908	2485-8236	346 45 53-19	9632-3549	2 10 29-05	60-4093	348 56 22-24	9692-7642
355	90	28-51524	2513-2015	347 45 1-36	9659-7327	2 10 29-00	60-4090	349 55 30-37	9720-1417
356	91	27-65140	2540-5794	348 44 9-53	9687-1106	2 10 24-86	60-3770	350 54 34-40	9747-4876
357	92	26-78756	2567-9572	349 43 17-70	9714-4885	2 10 20-72	60-3451	351 53 38-43	9774-8336
358	93	25-92372	2595-3351	350 42 25-87	9741-8663	2 10 16-59	60-3132	352 52 42-46	9802-1795
359	94	25-05988	2622-7129	351 41 34-04	9769-2442	2 10 6-63	60-2863	353 51 40-67	9829-4805
360	95	24-19604	2650-0908	352 40 42-21	9796-6220	2 9 53-62	60-1360	354 50 35-83	9856-7580
361	96	23-33216	2677-4686	353 39 50-38	9823-9999	2 9 40-61	60-0356	355 49 30-99	9884-0364
362	97	22-46835	2704-8465	354 38 58-55	9851-3777	2 9 27-60	59-9552	356 48 26-15	9911-3129
363	98	21-60451	2732-2243	355 38 6-72	9878-7556	2 9 7-45	59-7797	357 47 14-17	9938-5353
364	99	20-74067	2759-6022	356 37 14-89	9906-1334	2 8 45-57	59-6109	358 46 0-46	9965-7443
365	100	19-87683	2786-9800	357 36 22-06	9933-5113	2 8 23-69	59-4420	359 44 46-75	9992-9533

TABLE XLIX.

ELEMENTS OF THE SUN'S TRUE LONGITUDE.

HOURS.

N. B.—Column 1 corresponds to the 24-hour periods, measured from true Mēsha-saṅkrānti, entered in Col. 1, Tables XLVIII A and B. In the present Table they are grouped in conformity with the Hindu Sine-Table. Figures in Columns 4 to 6 give the actual arcs travelled on the ecliptic by the true sun in the given number of hours. For minutes see Table L, following. The Table is exact for the First Ārya-Siddhānta, but can be used for all the Hindu authorities.

Grouping of the days.

(a) Days 1 to 85 in order, and in reverse order days 86 to 164.

(b) Days 165 to 267 in order, and in reverse order days 268 to 363.

(c) Days 363 to 365 are grouped with Day 1.

This arrangement had to be adopted to prevent the size of the Table being doubled.

24-hour periods from true Mēsha-saṅkrānti (inclusive).	Arc travelled by true sun in 24 hours.			Arc travelled by true sun per hour.				
	° ' "	10,000ths of circle.	No. of Hours.	° ' "	10,000ths of circle.	No. of hours.	° ' "	10,000ths of circle.
1	2	3	4	5	6	4	5	6
363 to 1 } 162 to 164 }	0 58 46-29	27-2090	1 2 26-93 2 4 53-86 3 7 20-79 4 9 47-71 5 12 14-64 6 14 41-57 7 17 8-50 8 19 35-43 9 22 2-36 10 24 29-29 11 26 56-22 12 29 23-14	1-1337 2-2674 3-4011 4-5348 5-6685 6-8023 7-9360 8-10697 9-12034 10-13371 11-14708 12-16045	13 14 15 16 17 18 19 20 21 22 23	31 50-07 34 17-00 36 43-93 39 10-86 41 37-79 44 4-72 46 31-65 48 58-57 51 25-50 53 52-43 56 19-36	14-7382 15-8719 17-0056 18-1394 19-2731 20-4068 21-5405 22-6742 23-8079 24-9416 26-0753	
2 to 5 } 168 to 161 }	0 58 38-01	27-1451	1 2 26-58 2 4 53-17 3 7 19-75 4 9 46-34 5 12 12-92 6 14 39-50 7 17 6-09 8 19 32-67 9 21 59-25 10 24 25-84 11 26 52-42 12 29 19-01	1-1310 2-2621 3-3931 4-5242 5-6552 6-7863 7-9173 8-10484 9-11794 10-13105 11-14415 12-15726	13 14 15 16 17 18 19 20 21 22 23	31 45-59 34 12-17 36 38-76 39 5-34 41 31-92 43 58-51 46 25-09 48 51-68 51 18-26 53 44-84 56 11-43	14-7036 15-8347 16-9657 18-0968 19-2278 20-3589 21-4899 22-6210 23-7520 24-8831 26-0141	

TABLE XLIX—Contd.

24-hour periods from true Mēsha- sankranti (inclusive).	Arc travelled by true sun in 24 hours.		Arc travelled by true sun per hour.					
	° ' "	10,000ths of circle.	No. of Hours.	° ' "	10,000ths of circle.	No. of Hours.	° ' "	10,000ths of circle.
1	2	3	4	5	6	4	5	6
6 to 8 } 154 to 157 }	0 58 29.73	27.0813	1 2 26.24 2 4 52.48 3 7 18.72 4 9 44.96 5 12 11.19 6 14 37.43 7 17 3.67 8 19 29.91 9 21 56.15 10 24 22.39 11 26 48.63 12 29 14.87	1.1284 2.2568 3.3852 4.5135 5.6419 6.7703 7.8987 9.0271 10.1555 11.2839 12.4122 13.5406	13 14 15 16 17 18 19 20 21 22 23	31 41.10 34 7.34 36 33.58 38 59.82 41 26.06 43 52.30 46 18.54 48 44.78 51 11.02 53 37.25 56 3.49	14.6690 15.7974 16.9258 18.0542 19.1826 20.3109 21.4393 22.5677 23.6961 24.8245 25.9529	
9 to 12 } 150 to 153 }	0 58 21.45	27.0174	1 2 25.89 2 4 51.79 3 7 17.68 4 9 43.58 5 12 9.47 6 14 35.36 7 17 1.26 8 19 27.15 9 21 53.04 10 24 18.94 11 26 44.83 12 29 10.73	1.1257 2.2514 3.3772 4.5029 5.6286 6.7543 7.8801 9.0058 10.1315 11.2572 12.3830 13.5087	13 14 15 16 17 18 19 20 21 22 23	31 36.62 34 2.51 36 28.41 38 54.30 41 20.20 43 46.09 46 11.98 48 37.88 51 3.77 53 29.66 55 55.56	14.6344 15.7601 16.8859 18.0116 19.1373 20.2630 21.3888 22.5145 23.6402 24.7659 25.8917	
13 to 16 } 147 to 149 }	0 58 13.17	26.9535	1 2 25.55 2 4 51.10 3 7 16.65 4 9 42.20 5 12 7.74 6 14 33.29 7 16 58.84 8 19 24.39 9 21 49.94 10 24 15.49 11 26 41.04 12 29 6.59	1.1231 2.2461 3.3692 4.4923 5.6153 6.7384 7.8614 8.9845 10.1076 11.2306 12.3537 13.4768	13 14 15 16 17 18 19 20 21 22 23	31 32.14 33 57.68 36 23.23 38 48.78 41 14.33 43 39.88 46 5.43 48 30.98 50 56.53 53 22.08 55 47.62	14.5998 15.7229 16.8459 17.9690 19.0921 20.2151 21.3382 22.4613 23.5843 24.7074 25.8304	
17 to 20 } 143 to 146 }	0 58 5.40	26.8942	1 2 25.23 2 4 50.46 3 7 15.69 4 9 40.91 5 12 6.14 6 14 31.37 7 16 56.60 8 19 21.83 9 21 47.06 10 24 12.29 11 26 37.51 12 29 2.74	1.1206 2.2412 3.3618 4.4824 5.6030 6.7235 7.8441 8.9647 10.0853 11.2059 12.3265 13.4471	13 14 15 16 17 18 19 20 21 22 23	31 27.97 33 53.20 36 18.43 38 43.66 41 8.89 43 34.11 45 59.34 48 24.57 50 49.80 53 15.03 55 40.26	14.5677 15.6883 16.8089 17.9295 19.0500 20.1706 21.2912 22.4118 23.5324 24.6530 25.7736	

TABLE XLIX—*Contd.*

24-hour periods from true Mēsha- samkrānti (inclusive).	Arc travelled by true sun in 24 hours.		Arc travelled by true sun per hour.					
	° ' "	10,000ths of circle.	No. of Hours.	' "	10,000ths of circle.	No. of Hours.	' "	10,000ths of circle.
1	2	3	4	5	6	4	5	6
21 to 24 } 139 to 142 }	0 57 57-80	26-8349	1 2 24-01		1-1181	13 31 23-81		14-5356
			2 4 49-82		2-2362	14 33 48-72		15-6537
			3 7 14-72		3-3544	15 36 13-62		16-7718
			4 9 39-63		4-4725	16 38 38-53		17-8899
			5 12 4-54		5-5906	17 41 3-44		19-0080
			6 14 29-45		6-7087	18 43 28-35		20-1261
			7 16 54-36		7-8268	19 45 53-26		21-2443
			8 19 19-27		8-9450	20 48 18-17		22-3624
			9 21 44-17		10-0631	21 50 43-07		23-4805
			10 24 9-08		11-1812	22 53 7-98		24-5986
			11 26 33-99		12-2993	23 55 32-89		25-7167
			12 28 58-90		13-4174			
25 to 28 } 135 to 138 }	0 57 50-70	26-7801	1 2 24-61		1-1158	13 51 19-96		14-5059
			2 4 49-23		2-2317	14 33 44-58		15-6217
			3 7 13-84		3-3475	15 36 9-19		16-7376
			4 9 38-45		4-4634	16 38 33-80		17-8534
			5 12 3-06		5-5792	17 40 58-41		18-9693
			6 14 27-68		6-6950	18 43 23-03		20-0851
			7 16 52-29		7-8109	19 45 47-64		21-2009
			8 19 16-90		8-9267	20 48 12-25		22-3168
			9 21 41-51		10-0425	21 50 36-86		23-4326
			10 24 6-13		11-1584	22 53 1-48		24-5485
			11 26 30-74		12-2742	23 55 26-09		25-6643
			12 28 55-35		13-3901			
29 to 31 } 131 to 134 }	0 57 43-60	26-7254	1 2 24-32		1-1136	13 31 16-11		14-4762
			2 4 48-63		2-2271	14 33 40-43		15-5898
			3 7 12-95		3-3407	15 36 4-75		16-7033
			4 9 37-27		4-4542	16 38 29-06		17-8169
			5 12 1-58		5-5678	17 40 53-38		18-9305
			6 14 25-90		6-6813	18 43 17-70		20-0440
			7 16 50-22		7-7949	19 45 42-01		21-1576
			8 19 14-53		8-9085	20 48 6-33		22-2711
			9 21 38-85		10-0220	21 50 30-65		23-3847
			10 24 3-17		11-1356	22 52 54-96		24-4982
			11 26 27-48		12-2491	23 55 19-28		25-6118
			12 28 51-80		13-3627			
32 to 35 } 127 to 130 }	0 57 37-10	26-6752	1 2 24-05		1-1115	13 31 12-60		14-4400
			2 4 48-09		2-2239	14 33 36-64		15-5505
			3 7 12-14		3-3344	15 36 0-69		16-6720
			4 9 36-18		4-4459	16 38 24-73		17-7834
			5 12 0-23		5-5573	17 40 48-78		18-8949
			6 14 24-28		6-6688	18 43 12-83		20-0064
			7 16 48-32		7-7803	19 45 36-87		21-1178
			8 19 12-37		8-8917	20 48 0-92		22-2293
			9 21 36-41		10-0032	21 50 24-96		23-3408
			10 24 0-46		11-1147	22 52 49-01		24-4522
			11 26 24-50		12-2261	23 55 13-05		25-5637
			12 28 48-55		13-3376			

TABLE XLIX—Contd.

24-hour periods from true Mēsha-sankrānti (inclusive).	Arc travelled by true sun in 24 hours.		Are travelled by true sun per hour.					
	° ' "	10,000ths of circle.	No. of Hours.	' "	10,000ths of circle.	No. of Hours.	' "	10,000ths of circle.
1	2	3	4	5	6	4	5	6
36 to 39 } 124 to 126 }	0 57 31-19	26-6295	1 2 23-80 2 4 47-60 3 7 11-40 4 9 35-20 5 11 59-00 6 14 22-80 7 16 46-60 8 19 10-40 9 21 34-20 10 23 57-99 11 26 21-79 12 28 45-59	1-1096 2-2191 3-3287 4-4383 5-5478 6-6574 7-7669 8-8765 9-9861 11-0956 12-2052 13-3148	13 14 15 16 17 18 19 20 21 22 23	31 9-30 33 33-19 35 56-99 38 20-79 40 44-59 43 8-39 45 32-19 47 55-99 50 19-79 52 43-59 55 7-39	14-4243 15-5339 16-6435 17-7530 18-8626 19-9721 21-0817 22-1913 23-3008 24-4104 25-5200	
40 to 43 } 120 to 123 }	0 57 25-27	26-5839	1 2 23-55 2 4 47-11 3 7 10-66 4 9 34-21 5 11 57-77 6 14 21-32 7 16 44-87 8 19 8-42 9 21 31-98 10 23 55-53 11 26 19-08 12 28 42-64	1-1077 2-2153 3-3230 4-4306 5-5383 6-6460 7-7536 8-8613 9-9690 11-0766 12-1843 13-2919	13 14 15 16 17 18 19 20 21 22 23	31 6-19 33 29-74 35 53-30 38 16-85 40 40-40 43 3-96 45 27-51 47 51-06 50 14-61 52 38-17 55 1-72	14-3996 15-5073 16-6149 17-7226 18-8303 19-9379 21-0456 22-1532 23-2609 24-3686 25-4762	
44 to 47 } 116 to 119 }	0 57 19-95	26-5428	1 2 23-33 2 4 46-66 3 7 9-99 4 9 33-33 5 11 56-66 6 14 19-99 7 16 43-32 8 19 6-65 9 21 21-98 10 23 53-31 11 26 16-64 12 28 39-98	1-1066 2-2119 3-3179 4-4238 5-5298 6-6357 7-7417 8-8476 9-9536 11-0595 12-1655 13-2714	13 14 15 16 17 18 19 20 21 22 23	31 3-31 33 26-64 35 49-97 38 13-30 40 36-63 42 59-96 45 23-29 47 46-63 50 9-96 52 33-29 54 56-62	14-3774 15-4833 16-5893 17-6952 18-8012 19-9071 21-0131 22-1190 23-2250 24-3309 25-4369	
48 to 50 } 112 to 115 }	0 57 15-22	26-5063	1 2 23-13 2 4 46-27 3 7 9-40 4 9 32-54 5 11 55-67 6 14 18-81 7 16 41-94 8 19 5-07 9 21 28-21 10 23 51-34 11 26 14-48 12 28 37-61	1-1044 2-2089 3-3133 4-4177 5-5222 6-6266 7-7310 8-8354 9-9399 11-0443 12-1487 13-2532	13 14 15 16 17 18 19 20 21 22 23	31 0-74 33 23-88 35 47-01 38 10-15 40 33-28 42 56-42 45 19-55 47 42-68 50 5-82 52 28-95 54 52-09	14-3576 15-4620 16-5665 17-6709 18-7753 19-8797 20-9842 22-0886 23-1930 24-2975 25-4019	

TABLE XLIX—Contd.

24-hour periods from true Mēsha- sankranti (inclusive).	Are travelled by true sun in 24 hours.		Are travelled by true sun per hour.						
	°	'	10,000ths of circle.	No. of Hours.	'	10,000ths of circle.	No. of Hours.	'	10,000ths of circle.
1	2	3	4	5	6	4	5	6	
51 to 54 } 108 to 111 }	0 57 10-40	26-4698	1 2 22-94 2 4 45-87 3 7 8-81 4 9 31-75 5 11 54-69 6 14 17-62 7 16 40-56 8 19 3-50 9 21 26-43 10 23 49-37 11 26 12-31 12 28 35-24	1-1029 2-2058 3-3087 4-4116 5-5145 6-6175 7-7204 8-8233 9-9262 11-0291 12-1320 13-2349	13 14 15 16 17 18 19 20 21 22 23	30 58-18 33 21-12 35 44-06 38 6-99 40 29-93 42 52-87 45 15-80 47 38-74 50 1-68 52 24-62 54 47-55	14-3378 15-4407 16-5436 17-6466 18-7495 19-8524 20-9553 22-0582 23-1611 24-2640 25-3669		
55 to 58 } 105 to 107 }	0 57 6-94	26-4424	1 2 22-79 2 4 45-58 3 7 8-37 4 9 31-16 5 11 53-95 6 14 16-74 7 16 39-52 8 19 2-31 9 21 25-10 10 23 47-89 11 26 10-68 12 28 33-47	1-1018 2-2035 3-3053 4-4071 5-5088 6-6106 7-7124 8-8141 9-9159 11-0177 12-1195 13-2212	13 14 15 16 17 18 19 20 21 22 23	30 56-26 33 19-05 35 41-84 38 4-63 40 27-42 42 50-21 45 13-00 47 35-78 49 58-57 52 21-36 54 44-15	14-3230 15-4248 16-5265 17-6283 18-7301 19-8318 20-9336 22-0354 23-1371 24-2389 25-3407		
59 to 62 } 101 to 104 }	0 57 3-98	26-4196	1 2 22-67 2 4 45-33 3 7 8-00 4 9 30-66 5 11 53-33 6 14 16-00 7 16 38-66 8 19 1-33 9 21 23-99 10 23 46-66 11 26 9-33 12 28 31-99	1-1008 2-2016 3-3025 4-4033 5-5041 6-6049 7-7057 8-8065 9-9074 11-0082 12-1090 13-2098	13 14 15 16 17 18 19 20 21 22 23	30 54-66 33 17-32 35 39-99 38 2-66 40 25-32 42 47-99 45 10-65 47 33-32 49 55-99 52 18-65 54 41-32	14-3106 15-4115 16-5123 17-6131 18-7139 19-8147 20-9155 22-0164 23-1172 24-2180 25-3188		
63 to 66 } 97 to 100 }	0 57 1-03	26-3968	1 2 22-54 2 4 45-09 3 7 7-63 4 9 30-17 5 11 52-71 6 14 15-26 7 16 37-80 8 19 0-34 9 21 22-89 10 23 45-43 11 26 7-97 12 28 30-51	1-0999 2-1997 3-2996 4-3995 5-4993 6-5992 7-6991 8-7989 9-8988 10-9987 12-0985 13-1984	13 14 15 16 17 18 19 20 21 22 23	30 53-06 33 15-60 35 38-14 38 0-69 40 23-23 42 45-77 45 8-31 47 30-86 49 53-40 52 15-94 54 38-48	14-2983 15-3981 16-4980 17-5979 18-6977 19-7976 20-8975 21-9973 23-0972 24-1971 25-2970		

TABLE XLIX—Contd.

24-hour periods from true Mēsha- sankranti (inclusive).	Are travelled by true sun in 24 hours.			Are travelled by true sun per hour.				
	° ' "	10,000ths of circle.	No. of Hours.	° ' "	10,000ths of circle.	No. of Hours.	° ' "	10,000ths of circle.
1	2	3	4	5	6	4	5	6
67 to 69 } 93 to 96 }	0 56 58-66	26-3786	1 2 22-44 2 4 44-89 3 7 7-33 4 9 29-78 5 11 52-22 6 14 14-67 7 16 37-11 8 18 59-55 9 21 22-00 10 23 44-44 11 26 6-89 12 28 29-33	1-0991 2-1982 3-2973 4-3964 5-4955 6-5946 7-6937 8-7929 9-8920 10-9911 12-0902 13-1893	13 14 15 16 17 18 19 20 21 22 23	30 51-78 33 14-22 35 6-66 37 59-11 40 21-55 42 44-00 45 6-44 47 28-89 49 51-33 52 13-77 54 36-22	14-2384 15-3875 16-4866 17-5857 18-6848 19-7839 20-8830 21-9821 23-0812 24-1804 25-2795	
70 to 73 } 89 to 92 }	0 56 56-89	26-3649	1 2 22-37 2 4 44-74 3 7 7-11 4 9 29-48 5 11 51-85 6 14 14-22 7 16 36-59 8 18 58-06 9 21 21-33 10 23 43-70 11 26 6-07 12 28 28-44	1-0985 2-1971 3-2956 4-3941 5-4927 6-5912 7-6898 8-7883 9-8868 10-9854 12-0839 13-1824	13 14 15 16 17 18 19 20 21 22 23	30 50-81 33 13-18 35 35-55 37 57-93 40 20-30 42 42-67 45 5-04 47 27-41 49 49-78 52 12-15 54 34-52	14-2810 15-3795 16-4780 17-5766 18-6751 19-7737 20-8722 21-9707 23-0693 24-1678 25-2663	
74 to 77 } 86 to 88 }	0 56 55-71	26-3558	1 2 22-32 2 4 44-64 3 7 6-96 4 9 29-28 5 11 51-61 6 14 13-93 7 16 36-25 8 18 58-57 9 21 20-89 10 23 43-21 11 26 5-53 12 28 27-85	1-0982 2-1963 3-2945 4-3926 5-4908 6-5889 7-6871 8-7853 9-8834 10-9816 12-0797 13-1779	13 14 15 16 17 18 19 20 21 22 23	30 50-17 33 12-49 35 34-82 37 57-14 40 19-46 42 41-78 45 4-10 47 26-42 49 48-74 52 11-06 54 33-38	14-2760 15-3742 16-4723 17-5705 18-6687 19-7668 20-8650 21-9631 23-0613 24-1594 25-2576	
78 to 85 } (True sun in apogee on Day 81).	0 56 55-11	26-3512	1 2 22-30 2 4 44-59 3 7 6-89 4 9 29-19 5 11 51-48 6 14 13-78 7 16 36-07 8 18 58-37 9 21 20-67 10 23 42-96 11 26 5-26 12 28 27-56	1-0980 2-1959 3-2939 4-3919 5-4898 6-5878 7-6858 8-7837 9-8817 10-9797 12-0776 13-1756	13 14 15 16 17 18 19 20 21 22 23	30 49-85 33 12-15 35 34-45 37 56-74 40 19-04 42 41-34 45 3-63 47 29-93 49 48-22 52 10-52 54 32-82	14-2738 15-3715 16-4695 17-5675 18-6654 19-7634 20-8614 21-9593 23-0573 24-1553 25-2532	

TABLE XLIX—Contd.

24-hour periods from true Mēṣha samskrānti (inclusive).	Are travelled by true sun in 24 hours.			Are travelled by true sun per hour.				
	0	1	2	No. of Hours.	10,000ths of circle.	No. of Hours.	10,000ths of circle.	No. of Hours.
1	2	3	4	5	6	4	5	6
<i>For all days (Column 1) from 86 to 164 see above, taking the numbers of days backwards.</i>								
165 to 168, 360 to 362,	0 58 55-16	27-2775	1 2 27-30	1-1366	13	31 54-88	14-7753	
			2 4 54-00	2-2731	14	34 22-18	15-9119	
			3 7 21-90	3-4097	15	36 49-48	17-0484	
			4 9 49-19	4-5462	16	39 16-77	18-1850	
			5 12 16-49	5-6828	17	41 44-07	19-3215	
			6 14 43-79	6-8194	18	44 11-37	20-4581	
			7 17 11-09	7-9559	19	46 38-67	21-5947	
			8 19 38-39	9-0925	20	49 5-97	22-7312	
			9 22 5-69	10-2291	21	51 33-27	23-8678	
			10 24 32-98	11-3656	22	54 0-56	25-0043	
			11 27 0-28	12-5022	23	56 27-86	26-1409	
			12 29 27-58	13-6387				
169 to 172, 366 to 369,	0 59 4-03	27-3459	1 2 27-67	1-1394	13	31 59-68	14-8124	
			2 4 55-31	2-2788	14	34 27-35	15-9513	
			3 7 23-00	3-4182	15	36 55-02	17-0912	
			4 9 50-67	4-5577	16	39 22-69	18-2306	
			5 12 18-34	5-6971	17	41 50-36	19-3700	
			6 14 46-01	6-8365	18	44 18-02	20-5094	
			7 17 13-68	7-9759	19	46 45-69	21-6489	
			8 19 41-34	9-1153	20	49 13-36	22-7883	
			9 22 9-01	10-2547	21	51 41-03	23-9277	
			10 24 36-68	11-3941	22	54 8-69	25-0671	
			11 27 4-35	12-5335	23	56 36-36	26-2065	
			12 29 32-02	13-6730				
173 to 176, 352 to 355,	0 59 12-31	27-4098	1 2 28-01	1-1421	13	32 4-17	14-8470	
			2 4 56-03	2-2841	14	34 32-18	15-9890	
			3 7 24-04	3-4262	15	37 0-19	17-1311	
			4 9 52-05	4-5683	16	39 28-21	18-2732	
			5 12 20-06	5-7104	17	41 56-22	19-4153	
			6 14 48-08	6-8524	18	44 24-23	20-5573	
			7 17 16-09	7-9945	19	46 52-25	21-6994	
			8 19 44-10	9-1366	20	49 20-26	22-8415	
			9 22 12-12	10-2787	21	51 48-27	23-9836	
			10 24 40-13	11-4207	22	54 16-28	25-1256	
			11 27 8-14	12-5628	23	56 44-30	26-2677	
			12 29 36-15	13-7049				
177 to 180, 348 to 351,	0 59 21-18	27-4782	1 2 28-38	1-1449	13	32 8-97	14-8840	
			2 4 56-77	2-2899	14	34 37-36	16-0290	
			3 7 25-15	3-4348	15	37 5-74	17-1739	
			4 9 53-53	4-5797	16	39 34-12	18-3188	
			5 12 21-91	5-7246	17	42 2-50	19-4638	
			6 14 50-30	6-8696	18	44 30-89	20-6087	
			7 17 18-68	8-0145	19	46 59-27	21-7536	
			8 19 47-06	9-1594	20	49 27-65	22-8985	
			9 22 15-44	10-3043	21	51 56-03	24-0435	
			10 24 43-83	11-4493	22	54 24-42	25-1884	
			11 27 12-21	12-5942	23	56 52-80	26-3333	
			12 29 40-59	13-7391				

TABLE XLIX—Contd.

24-hour periods from true Mēsha-samkrānti (inclusive).	Arc travelled by true sun in 24 hours.		Arc travelled by true sun per hour.					
	° ' "	10,000ths of circle.	No. of Hours.	° ' "	10,000ths of circle.	No. of Hours.	° ' "	10,000ths of circle.
1	2	3	4	5	6	4	5	6
181 to 184 } 344 to 347 }	0 59 30-05	27-5467	1 2 28-75 2 4 57-50 3 7 26-26 4 9 55-01 5 12 23-76 6 14 52-51 7 17 21-26 8 19 50-02 9 22 18-77 10 24 47-52 11 27 16-27 12 29 45-03	1-1478 2-2956 3-4433 4-5911 5-7389 6-8867 8-0345 9-1822 10-3300 11-4778 12-6256 13-7733	13 14 15 16 17 18 19 20 21 22 23	32 13-78 34 42-53 37 11-38 39 40-03 42 8-79 44 37-54 47 6-29 49 35-04 52 3-79 54 32-55 57 1-30	14-9211 16-0689 17-2167 18-3645 19-5122 20-6600 21-8078 22-9556 24-1034 25-2511 26-3989	
185 to 187 } 341 to 343 }	0 59 38-33	27-6106	1 2 29-10 2 4 58-19 3 7 27-29 4 9 56-39 5 12 25-49 6 14 54-58 7 17 23-68 8 19 53-78 9 22 21-87 10 24 50-97 11 27 20-07 12 29 49-16	1-1504 2-3009 3-4513 4-6018 5-7522 6-9026 8-0531 9-2035 10-3540 11-5044 12-6548 13-8053	13 14 15 16 17 18 19 20 21 22 23	32 18-26 34 47-36 37 16-46 39 45-55 42 14-65 44 43-75 47 12-84 49 41-94 52 11-04 54 40-14 57 9-23	14-9557 16-1062 17-2566 18-4070 19-5575 20-7079 21-8584 23-0088 24-1592 25-3097 26-4601	
188 to 191 } 337 to 340 }	0 59 46-01	27-6745	1 2 29-44 2 4 58-88 3 7 28-33 4 9 57-77 5 12 27-21 6 14 56-65 7 17 26-09 8 19 55-54 9 22 24-98 10 24 54-42 11 27 23-86 12 29 53-30	1-1531 2-3062 3-4593 4-6124 5-7655 6-9186 8-0717 9-2248 10-3779 11-5310 12-6841 13-8372	13 14 15 16 17 18 19 20 21 22 23	32 22-75 34 52-19 37 21-63 39 51-07 42 20-51 44 49-96 47 19-40 49 48-84 52 18-28 54 47-72 57 17-17	14-9903 16-1434 17-2965 18-4496 19-6027 20-7558 21-9089 23-0620 24-2151 25-3682 26-5213	
192 to 195 } 333 to 336 }	0 59 54-89	27-7383	1 2 29-79 2 4 59-57 3 7 29-36 4 9 59-15 5 12 28-63 6 14 58-72 7 17 28-51 8 19 58-30 9 22 28-08 10 24 57-87 11 27 27-66 12 29 57-44	1-1558 2-3115 3-4673 4-6231 5-7788 6-9346 8-0903 9-2461 10-4019 11-5576 12-7134 13-8692	13 14 15 16 17 18 19 20 21 22 23	32 27-23 34 57-02 37 26-80 39 56-59 42 26-38 44 56-17 47 26-95 49 55-74 52 25-53 54 55-31 57 25-10	15-0249 16-1807 17-3365 18-4922 19-6480 20-8037 21-9595 23-1153 24-2710 25-4268 26-5826	

TABLE XLIX—Contd.

24-hour periods from true Mēsha-sankrānti (inclusive).	Arc travelled by true sun in 24 hours.		Arc travelled by true sun per hour.					
	° ' "	10,000ths of circle.	No. of Hours.	' "	10,000ths of circle.	No. of hours.	' "	10,000ths of circle.
1	2	3	4	5	6	4	5	6
196 to 199 } 329 to 332 }	1 0 3-17	27-8022	1 2 30-13 2 5 0-28 3 7 30-40 4 10 0-53 5 12 30-66 6 15 0-79 7 17 30-92 8 20 1-06 9 22 31-19 10 25 1-32 11 27 31-45 12 30 1-58	1-1584 2-3169 3-4753 4-6337 5-7921 6-9506 8-1090 9-2764 10-4258 11-5843 12-7427 13-9011	13 14 15 16 17 18 19 20 21 22 23	32 31-72 35 1-85 37 31-98 40 2-11 42 32-24 45 2-38 47 32-51 50 2-64 52 32-77 55 2-90 57 33-03	15-0595 16-2180 17-3764 18-5348 19-6932 20-8517 22-0101 23-1685 24-3269 25-4854 26-6438	
200 to 203 } 325 to 328 }	1 0 10-85	27-8615	1 2 30-45 2 5 0-60 3 7 31-36 4 10 1-81 5 12 32-26 6 15 2-71 7 17 33-17 8 20 3-62 9 22 34-07 10 25 4-52 11 27 34-98 12 30 5-43	1-1609 2-3218 3-4827 4-6436 5-8045 6-9654 8-1263 9-2872 10-4481 11-6090 12-7699 13-9308	13 14 15 16 17 18 19 20 21 22 23	32 35-88 35 6-33 37 36-78 40 7-24 42 37-69 45 8-14 47 38-59 50 9-05 52 59-50 55 9-05 57 40-40	15-0917 16-2526 17-4135 18-5744 19-7353 20-8961 22-0570 23-2179 24-3788 25-5397 26-7006	
204 to 206 } 321 to 324 }	1 0 18-54	27-9209	1 2 30-77 2 5 1-55 3 7 32-32 4 10 3-09 5 12 33-86 6 15 4-64 7 17 35-41 8 20 6-18 9 22 36-95 10 25 7-73 11 27 38-50 12 30 9-27	1-1634 2-3267 3-4901 4-6535 5-8168 6-9802 8-1436 9-3070 10-4703 11-6337 12-7971 13-9604	13 14 15 16 17 18 19 20 21 22 23	32 40-04 35 10-82 37 41-59 40 12-36 42 43-13 45 13-91 47 44-68 50 15-45 52 46-22 55 17-00 57 47-77	15-1238 16-2872 17-7505 18-6139 19-7773 20-9406 22-1040 23-2674 24-4307 25-5941 26-7575	
207 to 210 } 318 to 320 }	1 0 25-64	27-9756	1 2 31-07 2 5 2-14 3 7 33-20 4 10 4-27 5 12 35-34 6 15 6-41 7 17 37-48 8 20 8-55 9 22 39-61 10 25 10-68 11 27 41-75 12 30 12-82	1-1657 2-3313 3-4970 4-6626 5-8283 6-9939 8-1596 9-3252 10-4909 11-6565 12-8222 13-9878	13 14 15 16 17 18 19 20 21 22 23	32 43-89 35 14-76 37 46-02 40 17-09 42 48-16 45 19-23 47 50-30 50 21-37 52 52-43 55 23-50 57 54-57	15-1535 16-3191 17-4848 18-6504 19-8161 20-9817 22-1474 23-3130 24-4787 25-6443 26-8100	

TABLE XLIX—*Contd.*

24-hour periods from true Mēsha- sankrānti (inclus.ve.).	Arc travelled by true sun in 24 hours.			Arc travelled by true sun per hour.					
	°	' "	10,000ths of circle.	No. of Hours.	' "	10,000ths of circle.	No. of Hours.	' "	10,000ths of circle.
1	2	3	4	5	6	4	5	6	
211 to 214) 314 to 317)	1	0 32-74	28-0304	1 2 31-36 2 5 2-73 3 7 31-09 4 10 5-46 5 12 36-82 6 15 8-18 7 17 39-55 8 20 10-91 9 22 42-28 10 25 13-64 11 27 45-00 12 30 16-37	1 1679 2 3359 3 5038 4 6717 5 8397 6 10076 7 11755 8 13435 9 15114 10 16793 11 18472 12 20152	13 32 47-73 14 35 19-10 15 37 50-40 16 40 21-82 17 42 53-19 18 45 24-55 19 47 55-92 20 50 27-28 21 52 58-64 22 55 30-01 23 58 1-37	15-1831 16-3510 17-5190 18-6869 19-8548 21-0228 22-1907 23-3586 24-5266 25-6945 26-8624		
215 to 218) 310 to 313)	1	0 39-24	28-0806	1 2 31-63 2 5 3-27 3 7 34-90 4 10 6-54 5 12 38-17 6 15 9-81 7 17 41-44 8 20 13-08 9 22 44-71 10 25 16-35 11 27 47-98 12 30 19-62	1 1760 2 3400 3 5101 4 6801 5 8501 6 10201 7 11902 8 13602 9 15302 10 17002 11 18703 12 20403	13 32 51-25 14 35 22-89 15 37 54-52 16 40 26-16 17 42 57-79 18 45 29-43 19 48 1-06 20 50 32-70 21 53 4-33 22 55 35-97 23 58 7-60	15-2103 16-3803 17-5503 18-7204 19-8904 21-0604 22-2304 23-4005 24-5705 25-7405 26-9105		
219 to 222) 306 to 309)	1	0 45-15	28-1262	1 2 31-88 2 5 3-76 3 7 35-64 4 10 7-53 5 12 39-41 6 15 11-29 7 17 43-17 8 20 15-05 9 22 46-93 10 25 18-81 11 27 50-70 12 30 22-58	1 1719 2 3438 3 5158 4 6877 5 8596 6 10315 7 12035 8 13754 9 15473 10 17192 11 18912 12 20631	13 32 54-46 14 35 25-34 15 37 58-22 16 40 30-10 17 43 1-98 18 45 33-87 19 48 5-75 20 50 37-63 21 53 9-51 22 55 41-39 23 58 13-27	15-2350 16-4069 17-5789 18-7508 19-9227 21-0946 22-2666 23-4385 24-6104 25-7823 26-9543		
223 to 226) 302 to 305)	1	0 51-07	28-1718	1 2 32-13 2 5 4-26 3 7 36-38 4 10 8-51 5 12 40-64 6 15 12-77 7 17 44-89 8 20 17-02 9 22 49-15 10 25 21-28 11 27 53-41 12 30 25-53	1 1738 2 3477 3 5215 4 6953 5 8691 6 10430 7 12168 8 13906 9 15644 10 17383 11 19121 12 20859	13 32 57-66 14 35 29-79 15 38 1-92 16 40 34-04 17 43 6-17 18 45 38-30 19 48 10-43 20 50 42-56 21 53 14-68 22 55 46-81 23 58 18-94	15-2597 16-4336 17-6074 18-7812 19-9550 21-1289 22-3027 23-4765 24-6503 25-8242 26-9980		

TABLE XLIX—Contd.

24-hour periods from true Mīsha-sankranti (inclusive).	Arc travelled by true sun in 24 hours.		Arc travelled by true sun per hour.					
	° ' "	10,000ths of circle.	No. of Hours.	' "	10,000ths of circle.	No. of Hours.	' "	10,000ths of circle.
1	2	3	4	5	6	4	5	6
226 to 229 } 299 to 301 }	1 0 56-39	28-2129	1 2 32-35 2 5 4-70 3 7 37-05 4 10 9-40 5 12 41-75 6 15 14-10 7 17 46-45 8 20 18-80 9 22 51-15 10 25 23-50 11 27 55-85 12 30 28-19	1-1755 2-3511 3-5266 4-7021 5-8777 6-0532 7-2288 8-4043 9-5798 10-7554 11-9309 12-1064	13 33 0-54 14 35 32-89 15 38 5-24 16 40 37-59 17 43 9-04 18 45 42-29 19 48 14-64 20 50 46-99 21 53 19-34 22 55 51-69 23 58 24-04	15-2820 16-4575 17-6331 18-8086 19-9841 21-1597 22-3352 23-5107 24-6863 25-8618 27-0373		
230 to 233 } 295 to 298 }	1 1 1-12	28-2494	1 2 32-55 2 5 5-09 3 7 37-64 4 10 10-19 5 12 42-73 6 15 15-28 7 17 47-83 8 20 20-37 9 22 52-92 10 25 25-47 11 27 58-01 12 30 30-56	1-1771 2-3541 3-5312 4-7082 5-8853 6-0623 7-2394 8-4165 9-5935 10-7706 11-9476 12-1247	13 33 3-11 14 35 35-65 15 38 8-20 16 40 40-75 17 43 13-29 18 45 45-84 19 48 18-39 20 50 50-93 21 53 23-48 22 55 56-03 23 58 28-57	15-3108 16-4788 17-6559 18-8329 20-0100 21-1870 22-3641 23-5412 24-7182 25-8953 27-0723		
234 to 237 } 291 to 294 }	1 1 5-85	28-2859	1 2 32-74 2 5 5-49 3 7 38-23 4 10 10-98 5 12 43-72 6 15 16-46 7 17 49-21 8 20 21-95 9 22 54-69 10 25 27-44 11 28 0-18 12 30 32-93	1-1786 2-3572 3-5357 4-7143 5-8929 6-0715 7-2501 8-4286 9-6072 10-7858 11-9644 12-1429	13 33 5-67 14 35 38-41 15 38 11-16 16 40 43-90 17 43 16-64 18 45 49-39 19 48 22-13 20 50 54-88 21 53 27-62 22 56 0-36 23 58 33-11	15-3215 16-5001 17-6787 18-8573 20-0358 21-2144 22-3940 23-5716 24-7502 25-9287 27-1073		
238 to 241 } 287 to 290 }	1 1 9-40	28-3133	1 2 32-89 2 5 5-78 3 7 38-67 4 10 11-67 5 12 44-46 6 15 17-35 7 17 50-24 8 20 23-13 9 22 56-02 10 25 28-92 11 28 1-81 12 30 34-70	1-1797 2-3594 3-5392 4-7189 5-8986 6-0783 7-2580 8-4378 9-6175 10-7972 11-9769 12-1566	13 33 7-59 14 35 40-48 15 38 13-37 16 40 46-27 17 43 19-16 18 45 52-05 19 48 24-94 20 50 57-83 21 53 30-72 22 56 3-62 23 58 36-51	15-3364 16-5161 17-6958 18-8755 20-0552 21-2350 22-4147 23-5944 24-7741 25-9538 27-1335		

TABLE XLIX—Contd.

24-hour periods from true Māha- sākrānti (inclusive).	Arc travelled by true sun in 24 hours.			Arc travelled by true sun per hour.								
	°	'	"	10,000ths of circle.	No. of Hours.	'	"	10,000ths of circle.	No. of Hours.	'	"	10,000ths of circle.
1	2	3	4	5	6	4	5	6	4	5	6	
242 to 244 } 283 to 286 }	1	1	12-36	28-3361	1	2	33-01	1-1807	13	33	9-19	15-3487
					2	5	6-03	2-3613	14	35	42-21	16-5294
					3	7	39-04	3-5420	15	38	15-22	17-7101
					4	10	12-06	4-7227	16	40	48-24	18-8907
					5	12	45-07	5-9034	17	43	21-25	20-0714
					6	15	18-09	7-0840	18	45	54-27	21-2521
					7	17	51-10	8-2647	19	48	27-28	22-4327
					8	20	24-12	9-4454	20	51	0-30	23-6134
					9	22	57-13	10-6260	21	53	33-31	24-7941
					10	25	30-15	11-8067	22	56	6-33	25-9747
					11	28	3-16	12-9874	23	58	39-34	27-1554
					12	30	36-18	14-1680				
245 to 248 } 280 to 282 }	1	1	15-31	28-3589	1	2	33-14	1-1816	13	33	10-79	15-3611
					2	5	6-28	2-3632	14	35	43-93	16-5427
					3	7	39-41	3-5449	15	38	17-07	17-7243
					4	10	12-55	4-7265	16	40	50-21	18-9059
					5	12	45-69	5-9081	17	43	23-35	20-0876
					6	15	18-83	7-0897	18	45	56-48	21-2692
					7	17	51-97	8-2713	19	48	29-62	22-4508
					8	20	25-10	9-4530	20	51	3-76	23-6324
					9	22	58-24	10-6346	21	53	35-90	24-8140
					10	25	31-38	11-8162	22	56	9-04	25-9957
					11	28	4-52	12-9978	23	58	42-18	27-1773
					12	30	37-66	14-1794				
249 to 252 } 276 to 279 }	1	1	16-03	28-3771	1	2	33-17	1-1824	13	33	11-18	15-3710
					2	5	6-34	2-3648	14	35	44-35	16-5533
					3	7	39-50	3-5471	15	38	17-52	17-7357
					4	10	12-67	4-7295	16	40	50-69	18-9181
					5	12	45-84	5-9119	17	43	23-86	20-1005
					6	15	19-01	7-0943	18	45	57-02	21-2829
					7	17	52-18	8-2767	19	48	30-19	22-4652
					8	20	25-34	9-4590	20	51	3-36	23-6476
					9	22	58-51	10-6414	21	53	36-53	24-8300
					10	25	31-68	11-8238	22	56	9-70	25-0124
					11	28	4-85	13-0062	23	58	42-86	27-1948
					12	30	38-02	14-1886				
253 to 256 } 272 to 275 }	1	1	19-45	28-3908	1	2	33-31	1-1830	13	33	13-04	15-3784
					2	5	6-52	2-3659	14	35	46-35	16-5613
					3	7	39-93	3-5489	15	38	19-66	17-7443
					4	10	13-24	4-7218	16	40	52-97	18-9272
					5	12	46-55	5-9148	17	43	26-28	20-1102
					6	15	19-86	7-0977	18	45	59-59	21-2931
					7	17	53-17	8-2807	19	48	32-90	22-4761
					8	20	26-48	9-4636	20	51	6-21	23-6596
					9	22	59-79	10-6466	21	53	39-52	24-8420
					10	25	33-11	11-8295	22	56	12-83	25-0248
					11	28	6-42	13-0125	23	58	46-14	27-2078
					12	30	39-73	14-1954				

TABLE XLIX—Contd.

24-hour periods from true Mēsha-samkrānti (inclusive).	Arc travelled by true sun in 24 hours.		Arc travelled by true sun per hour.					
	° ' "	10,000ths of circle.	No. of Hours.	' "	10,000ths of circle.	No. of Hours.	' "	10,000ths of circle.
1	2	3	4	5	6	4	5	6
257 to 260 } 268 to 271 }	1 1 20-64	28-4000	1 2 33-36 2 5 6-72 3 7 40-08 4 10 13-44 5 12 46-80 6 15 20-16 7 17 53-52 8 20 26-88 9 23 0-24 10 25 33-60 11 28 6-96 12 30 40-32		1-1833 2-3667 3-5500 4-7333 5-9167 7-1000 8-2833 9-4667 10-6500 11-8333 13-0166 14-2000	13 14 15 16 17 18 19 20 21 22 23	33 13-68 35 47-04 38 20-40 40 53-76 43 27-12 46 0-48 48 33-84 51 7-20 53 40-56 56 13-92 58 47-28	15-3833 16-5666 17-7500 18-9333 20-1166 21-3000 22-4833 23-6666 24-8500 25-0333 26-2166
261 to 267 } (True sun in perigee, on Day 263.)	1 1 21-23	28-4045	1 2 33-38 2 5 6-77 3 7 40-15 4 10 13-54 5 12 46-92 6 15 20-31 7 17 53-69 8 20 27-08 9 23 0-46 10 25 33-84 11 28 7-23 12 30 40-61		1-1835 2-3670 3-5506 4-7341 5-9176 7-1011 8-2847 9-4682 10-6517 11-8352 13-0187 14-2023	13 14 15 16 17 18 19 20 21 22 23	33 14-00 35 47-38 38 20-77 40 54-15 43 27-54 46 0-92 48 34-30 51 7-69 53 41-07 56 14-46 58 47-84	15-3858 16-5693 17-7528 18-9364 20-1199 21-3034 22-4869 23-6704 24-8540 26-0375 27-2210

TABLE L.

ELEMENTS OF THE SUN'S LONGITUDE.

MINUTES.

The figures in Columns 2, 3, show the sun's *mean* movement during the times noted in Column I.

Time Mins.			10,000ths of circle.	Time Mins.			10,000ths of circle.	Time Mins.			10,000ths of circle.
1	2		3	1	2		3	1	2		3
1	0	1-23	0-0095								
2	0	2-46	0-0190	21	0	51-74	0-3993	41	1	41-02	0-7793
3	0	4-33	0-0380	22	0	54-21	0-4183	42	1	43-49	0-7983
4	0	7-39	0-0570	23	0	56-67	0-4373	43	1	45-95	0-8173
5	0	9-86	0-0760	24	0	59-14	0-4563	44	1	48-42	0-8363
6	0	12-32	0-0951	25	1	1-60	0-4753	45	1	50-88	0-8553
7	0	14-78	0-1141	26	1	4-06	0-4943	46	1	53-34	0-8743
8	0	17-25	0-1331	27	1	6-53	0-5133	47	1	55-81	0-8933
9	0	19-71	0-1521	28	1	8-99	0-5323	48	1	58-27	0-9123
10	0	22-18	0-1711	29	1	11-46	0-5514	49	2	0-74	0-9313
11	0	24-64	0-1901	30	1	13-92	0-5704	50	2	3-20	0-9503
12	0	27-10	0-2091	31	1	16-38	0-5894	51	2	5-66	0-9693
13	0	29-57	0-2281	32	1	18-85	0-6084	52	2	8-13	0-9883
14	0	32-03	0-2472	33	1	21-31	0-6274	53	2	10-59	1-0073
15	0	34-50	0-2662	34	1	23-78	0-6464	54	2	13-06	1-0263
16	0	36-96	0-2852	35	1	26-24	0-6654	55	2	15-52	1-0453
17	0	39-42	0-3042	36	1	28-70	0-6844	56	2	17-98	1-0643
18	0	41-89	0-3232	37	1	31-17	0-7035	57	2	20-45	1-0833
19	0	44-35	0-3422	38	1	33-63	0-7225	58	2	22-91	1-1023
20	0	46-82	0-3612	39	1	36-10	0-7415	59	2	25-38	1-1213
	0	49-28	0-3802	40	1	38-56	0-7605	60	2	27-84	1-1403

N. B.—Since this Table shows the sun's *mean* motion during the number of minutes indicated, a slight correction must be made, in order to ascertain his *true* motion, if very great accuracy is required. The largest possible correction, namely for 59 minutes on the days 81 and 263 (when the sun is in apogee and perigee and is therefore at his slowest and quickest) is on Day 81 minus 5'-4516 or 0-0421, and on Day 263 plus the same.

Hence on Day 81 the true sun's journey in 59 m. must be taken as (by the Table, 2' 25'-38—5'-45=) 2' 19'-93, or (by the Table, 1-1217—0-0421=) 1-0796; and on Day 263 as (2' 25'-38+5'-45=) 2' 30'-83, or (1-1217+0-0421=) 1-1638.

It is not necessary to frame a Table to meet corrections less than this. Calculation can always be made by taking from the Hour Table (Table XLIX) the true sun's motion in one hour on the day in question, dividing this by 60, and multiplying the result by the number of minutes concerned.

TABLE L-A.

ELEMENTS OF THE SUN'S LONGITUDE.

SECONDS.

Cols. 2, 3, shew the Sun's *mean* movement during times noted in Col. 1.

Time seconds.	#	10,000ths of circle.	Time seconds.	#	10,000ths of circle.	Time seconds.	#	10,000ths of circle.
1	2	3	1	2	3	1	2	3
1	0-041	0-0003	21	0-852	0-0067	41	1-684	0-0130
2	0-082	0-0006	22	0-903	0-0070	42	1-725	0-0133
3	0-123	0-0010	23	0-945	0-0073	43	1-766	0-0136
4	0-164	0-0013	24	0-986	0-0076	44	1-807	0-0139
5	0-205	0-0016	25	1-027	0-0079	45	1-848	0-0142
6	0-246	0-0019	26	1-068	0-0082	46	1-889	0-0145
7	0-287	0-0022	27	1-109	0-0086	47	1-930	0-0149
8	0-329	0-0025	28	1-150	0-0089	48	1-971	0-0152
9	0-370	0-0029	29	1-191	0-0092	49	2-012	0-0155
10	0-411	0-0032	30	1-232	0-0095	50	2-053	0-0158
11	0-452	0-0035	31	1-273	0-0098	51	2-094	0-0162
12	0-493	0-0038	32	1-314	0-0101	52	2-135	0-0165
13	0-534	0-0041	33	1-355	0-0105	53	2-177	0-0168
14	0-575	0-0044	34	1-396	0-0108	54	2-218	0-0171
15	0-616	0-0048	35	1-437	0-0111	55	2-259	0-0174
16	0-657	0-0051	36	1-478	0-0114	56	2-300	0-0177
17	0-698	0-0054	37	1-519	0-0117	57	2-341	0-0181
18	0-739	0-0057	38	1-561	0-0120	58	2-382	0-0184
19	0-780	0-0060	39	1-602	0-0124	59	2-423	0-0187
20	0-821	0-0063	40	1-643	0-0127	60	2-464	0-0190

The Table follows M. de Ries's fixture of the sun's *mean* movement in 1 time-minute by the *Siddhānta*.
firṣmaṣi 2'-454,005,788, or 0-019,012,414.

No. 2.—DANDAPALLE PLATES OF VIJAYA-BHUPATI: SAKA-SAMVAT 1332.

By G. VENKOTA RAO, MADRAS.

The copper-plates which bear the subjoined inscription were obtained by me on a short loan from the *monagar* of Dandapalle,¹ a village in the Palamner *taluka* of the Chittoor district, during my official tour in 1913. They have been briefly noticed in the Madras Epigraphical Report for 1913, page 119, paragraph 53.

The plates are five in number, each measuring about 9½" by 5½". The edges are folded over, flattened and slightly raised into rims, in order to secure the protection of the writing from coming into contact with the written sides of the adjoining plates. The tops are neatly curved in the form of a bow slightly turned upwards at the edges where these meet the plates. The curved tops have, as usual, a hole in the centre to allow the copper-ring to pass through. The ring, which is plain and circular, bears no seal attached to it. It had been cut before the plates were secured by me.

The first plate bears writing only on its inner side, while the remaining four are written on both their sides. Plates one to four are numbered in Telugu-Kanarese numerals on their first written sides. The fourth plate, ending with the usual imprecatory verses, indicates that the record must have closed with it. The fifth plate bears no number, and there are no rims on its inner face, which bears writing; this shows that the writing on that side of the plate may not have been originally intended. Consequently the last plate must have been added subsequently as a post-script whereon the boundaries of the land granted had to be engraved in the vernacular of the country.

The engraving is fairly deep and well executed. The characters are Nandināgarī, almost of the same type as those of the Satyamaṅgalam plates of Dēvarāya II, published with a facsimile plate on pp. 35 to 41 of *Ep. Ind.*, Vol. III; and the languages employed are Sanskrit verse² and Kanarese prose.³ The signature of the king at the end appears as "Śrī Triyambaka" in Kannada characters.⁴

The following palæographical and orthographical peculiarities are worth noting. The use of the *anusvāra* is very arbitrary. In cases where naturally a class nasal or a final *m* would be used the *anusvāra* is substituted. The vowel *ṁ* is throughout written as *ṁ*, and in two cases (ll. 144 *स्नानं* and 163 *स्नानं*) with superscript *ṁ*. Very little difference in form is perceptible between *bha* and *la*. The double letters *dda* and *ppa* are represented by two full forms of *da* and *pa* written side by side with a single top line, and the conjunct consonant *kḥa* in ll. 121 and 126 by *kḥkḥa*. The symbols for *tḥa* and *dḥa* are the same as the modern symbols, but *vice versa*. The hard or intensified *ṛ* is represented by *ṛ̣* (ll. 123, 135, 154, 175, 177, 186 and 191). The difference between *ja* and *la* is indicated by a ligature in the case of the former, which is absent in the latter. We often find the dental *la* used instead of the cerebral *ja*, evidently owing to Sanskrit influence, even though the latter is expected according to the vernacular pronunciation, e.g. *मुत्तमि* (l. 55), *दंडे* (l. 56) and *उत्तम* (l. 145). *Vice versa*, *ja* is used for *la* in *Kaṣyapa*

¹ In his *List of Antiquities*, Vol. I, p. 159, Mr. Sewell has noted the existence of these plates. It may be added that these have since been presented by the owner to the Madras Museum and are deposited there.

² Ll. 100 to 102 after v. 45, ll. 109 to 110 after v. 48, ll. 116 to 118 after v. 49, l. 130 after v. 55 and ll. 139 to 142 after v. 59 consist only of portions of verses. Probably there has been some mistake in the engraving of the text. It is not impossible that the first and the third fragments, which are both half-verses in the *Mandākrāntā* metre, should be read together to form one verse. In the second, fourth and fifth we have portions of *Anuśṭup*, *Sāli* and *Indravajrā*.

³ Ll. 144 to 146 and ll. 153 to 192.

⁴ The Madras Museum plates of Śrīgiri-Bhūpāla of about this period (*Ep. Ind.*, Vol. VIII, p. 306 ff.) are attested similarly.

(l. 1) and *lālītānighri* (l. 11) and *Mahāśakāhmi* (l. 34). A consonant after *anuvāra* and the *vāra* is doubled, as in Telugu and Kanarese inscriptions, e.g. *सूचि* in l. 7, *चि* in l. 42, *युषवन्* in l. 40, *राय* in l. 83 and *इति* in l. 86; in *विद्वान्* (l. 99) the consonant is doubled before *ra*. The *virāma* is used with the letters *त* in ll. 13, 15, 17, 57, 66 and 106, *न* in ll. 17, 27 and 73 and *क* in ll. 81 and 137. The rules of Sandhi are not observed in the following cases:—The *visarga* does not assimilate with the following consonant except in *इति* in l. 14. *कौशिकी* *सन्धि* for *कौशिक* *सन्धि* in l. 78 and *विद्वानि* *सन्धि* for *विद्वानि* *सन्धि* in l. 126; *चमूतृ* for *चमूतृ* occurs in l. 15, *मित्रात्* *प्राच्य* for *मित्रा* *प्राच्य* in l. 44, *सन्धि* *चौवरी* for *सन्धि* *चौवरी* in l. 106 and *सन्धि* *चौवरी* for *सन्धि* *चौवरी* in l. 120. *चाद्व* for *चाद्व* in ll. 55 f. and 61, *येकै* for *एकै* in l. 146 f., and *सिंहा* for *सिंहा* in ll. 26 and 27 are evidently due to a wrong pronunciation very common in later Vijayanagara inscriptions. One grammatical mistake is *इति* *सन्धि* for *इति* *सन्धि* in l. 143.

After invoking Gaṇeśa and the boar incarnation of Viṣṇu, the record begins as usual by tracing the First Vijayanagara dynasty from the Moon. In the lunar race was born Bukka-Rāya (I). His son was Harihara (II), and his son Dēvarāya (I), who ruled at Vijaya-puri (Vijayanagara). He had a son Vijaya-Bhūpati by his wife Dēvāmbikā, who was herself the daughter of a certain Nūka-Bhūpāla of the Solar race (v. 17). Kriyāsakti-dēśika was the spiritual teacher of Vijaya-Bhūpati (v. 20). This king Vijaya, having founded in the division called Muḷvāgila *rājya*, in the district Huli *nādu*, in Daṇḍēhalli *sthala*, a new village called Kriyāsakti-pura, granted it to Kṛishṇa-Paṇḍita in the Śaka year reckoned by the chronogram *raṅgaloka* (i.e. 1332), corresponding to the cyclic year Vikṛiti, in the bright half of Bhādrapada, when (the nakṣatra) Śrāvaṇa was combined with Monday, on the Ēkādaśī *tithi* (and) the Lakṣmīnārāyaṇa *yōga* (vv. 26 to 30). Verses 21 to 25, which introduce the donee Kṛishṇa-Paṇḍita, state that his parents were Mēchāmbikā and Śīṅgaṇārya,¹ that he belonged to the Bhāradvāja *gōtra* and that his younger brother was Annadāta, in company with whom he served the king Vijaya faithfully. Kṛishṇa-Paṇḍita constructed in Kriyāsakti-pura a tank called Vijaya-samudra (v. 31), and, having secured the permission of the king, made a grant of the village and the tank to Brāhmaṇas of different *gōtras* (vv. 34 and 35). As stated in the Kanarese passage (ll. 144 to 146), the village consisted of 82 *vr̥ttis*. From the post-script which describes the boundaries of the village we learn that Kriyāsakti-pura, on being granted to Brāhmaṇas, received the name Abhinava-Vijaya-Bukkarāya-samudra, evidently after Vijaya-Bukka, one of the surnames of king Vijaya-Bhūpati.

The date of the grant has been verified with the help of Dewan Bahadur Swamikannu Pillai's *Ephemeris*. In the year Vikṛiti, corresponding to A.D. 1410, Bhādrapada was intercalary. On Monday in the bright half of *nija*-Bhādrapada the *tithi* *dasami* (i.e. the 10th day) ended at 38 after mean sunrise, and the nakṣatra Uttara-Āshādhā similarly ended at 48 after mean sunrise. Thus the given *tithi* (i.e. the 11th) and the nakṣatra Śrāvaṇa were in combination with Monday only in the last quarter of that day. If such a choice of an auspicious moment in the early hours before sunrise is possible, the English equivalent would be the last quarter of A.D. 1410, September 10, Monday.

Very few stone inscriptions of Vijaya-Bhūpati have been found. The present record, accordingly, is one of extreme interest, being the first copper-plate inscription of his time discovered up to now. Professor Kielhorn's *List of Southern Inscriptions*, No. 480, says that Vijaya's father Dēvarāya I ascended the throne in Śaka-Samvat 1328 (=A.D. 1406-07).² It must have been soon after this that Vijaya-Bhūpati was installed as viceroy at Muḷbāgal in

¹ In the list of donees he is incidentally also mentioned as Śīṅgaṇāchārya, father of Rāmakṛishṇa (i.e. Kṛishṇa-Paṇḍita) and Annadāta.

² From No. 345 of the Madras Epigraphical Collection for 1905 it may also be surmised that the coronation of Dēvarāya I took place in A.D. 1406-07.

the Mysore State.¹ The earliest date known for Vijaya is Śaka 1331, the cyclic year Virōdhi, corresponding to A.D. 1409-10.² In Śaka 1344 (Śubhakṛit=A.D. 1422-23) he assumed the title of paramount sovereign.³ From an inscription found at Bārnkūr it has been ascertained that Dēvarāya II, son of Vijaya, commenced to reign in Śaka 1343 (Śārvarin).⁴ The interval between the latest known date of Dēvarāya I (viz. Śaka 1340) and the accession of Dēvarāya II (viz. Śaka 1343) is very little, and it is, therefore, difficult to reconcile the statement of Nuniz that he reigned for 6 years at the capital Vijaya-nagara, except on the supposition, as surmised by Mr. H. Krishna Sastri, that Vijaya was co-regent with his son Dēvarāya II and also with his father Dēvarāya I.⁵ In inscriptions of the Tamil country Vijaya-Bhūpati assumes the names Vira-Vijaya, Vira-Bukka and Vijaya-Bukka. Vijaya-Bhūpati of our record should not however be confounded with Vira-Bhūpati, son of Bukka II, whose records of about the same period are also found in the south.⁶

It may be observed that Vijaya's mother is herein called Dēmāmbikā, while other records mention her name as Hēmāmbikā.⁷ She was the daughter of Nūka-Bhūpāla of the Solar race. This Nūka-Bhūpāla may be identified with the Redḍi chief Nūka or Nalla-Nūka, who married Vēmasāni, sister of Annavēma.⁸ We are aware of a similar matrimonial alliance between the Redḍis and the Vijayanagara family. The Vēnavaram plates of Allaya-Vēma refer to a Kāṭaprabhu as the son-in-law of Harihara (III).⁹

The full name of the Śaiva teacher in whose honour Vijaya-Bhūpati founded the village Kriyāsakti-pura was perhaps Kāśivāsa Kriyāsakti, referred to in terms of high esteem in the records of Bukka I. He was also the teacher of Harihara II and of his general Muddanna-Daṇḍanāyaka.¹⁰ Viṭṭhanna-Oḍeya, a viceroy under Harihara II and Dēvarāya I, was also a follower of Kriyāsakti.

Of the 82 *ṛittis* into which Vijaya-Bukkarāya-samudra was divided the temples of Gopīnātha and Rāmēśa (Rāmēśvara), evidently located at that village, received each a *ṛitti*. Among the Brahman recipients figure Chaṇḍapārya of the Vasishṭha *gōtra*, Sōma, son of Chaṇḍapārya of the same *gōtra*, Annadātā, son of Śiṅgaṇāchārya of the Bhāradvāja *gōtra*, and Duggapārya, son of Annadātā of the same *gōtra*, each of whom obtained 2 *ṛittis*. The names of Chaṇḍapārya and his son Sōma of the Vasishṭha *gōtra* are interesting, inasmuch as the former is known to us as the author of the Śranta work *Prayōgaratnamālā*. Another son of Chaṇḍapārya, Chaṇḍapāchārya or Chaṇḍapāmātya was Nāgaya-mantrin mentioned in a

¹ *Ep. Carn.*, Vol. X., Intr. p. xxxv., No. 824 of the Madras Epigraphist's Collection for 1912, from Karaṇapalle of the Poṅganūr Zamindari, informs us that in Śaka 1332, the same year as that of our grant, prince Vijayarāya-Uḍayar was ruling as viceroy at Muḷvāyil (Muḷbāgal). A subordinate of his was the Chōja chief Vira-Ōbaladēva Chōlamahārāja of the Sammatṭi family, which Mr. H. Krishna Sastri identifies with Sommatṭa, the family to which Lakkaya-dēva Mahārāja and Bommayya-dēva Mahārāja, who were dependants of Dēvarāya II, belonged.

² No. 658 of the Madras Epigraphical Collection for 1905.

³ *Ep. Carn.*, Vol. VII, Sk. 93.

⁴ No. 160 of the Epigraphist's Collection for 1901 and *Arch. Sur. Rep.* for 1907-08, p. 247.

⁵ *Arch. Sur. Rep.* for 1907-08, p. 248.

⁶ See the genealogical table on p. 86 of the Madras Epigraphical Report for 1907. Inscriptions of Vira-Bhūpati are found at Tiruvārūr and Tiruppūndurutti in the Tanjore district (No. 575 of 1904 and *Christian College Magazine* for 1930, p. 105).

⁷ The Satyasaṅgama Plates of Dēvarāya II give the name Dēmāmbikā (*Ep. Ind.*, Vol. III, p. 37, text-line 18); but on the authority of an inscription of Vira-Vijaya published in the *Madras Journal of Lit. and Sc.* for 1881 it was corrected by Professor Hultzsch into Hēmāmbikā (*ibid.*, note 7). The *caria lectio* is due probably to the similarity of form of the letters *ha* and *da* in Nandināgarī.

⁸ *Ep. Ind.*, Vol. III, p. 267. The Redḍis, so far as we know, do not claim any connection with the Solar race.

⁹ Madras Epigraphical Report for 1900, p. 26, paragraph 63.

¹⁰ *Arch. Sur. Rep.* for 1907-08, p. 242, foot-note 12.

Tripurāntakam inscription.¹ The donees Annadātā and Duggappārya were apparently related to the donor, the one being his brother and the other his nephew. Under his full name Kṛishṇa-Paṇḍita was evidently the Rāmakṛishṇa who reserved for himself 20 shares in the village.² He was well versed in the Yajur-Vēda and belonged to the Bhāradvāja gōtra. His younger brother Annadātā must be distinguished from his namesake, the son of Chauṇḍapāmātya, which latter belonged to the Vasishṭha gōtra.

Danḍehalli, near which was situated the granted village Kriyāsakti-pura or Abhinava-Vijaya-Bukkarāya-samudra, is the same as the modern Danḍapalle, where these plates were found. Of the places mentioned among the boundaries Eḍūru is a village very near Danḍapalle. Tirumaladāri, i.e. the road leading to Tirumala, must have been a recognised pilgrim-route which passed the granted village. I am unable to identify Tālakuṇṭe or Tāḷakuṇṭe and Arasāṇḍeyahalli, the two other villages mentioned in the plates.

TEXT.³

[Metre of verses 1-44, *Anuṣṭubh*; of 45, *Mandākrāntā*; of 46-48, *Anuṣṭubh*; of 49, *Mandākrāntā*; of 50-55, *Anuṣṭubh*; v. 56—please see note 2, page 63 above; of 57-61, *Anuṣṭubh*; and of 62, *Śalīlī*.]

First plate.

- 1 शुभमस्तु । कळ्याणाय गणाधोशः
- 2 कारुण्यांभोधिरस्तु वः । सदा गंडस्वली
- 3 यस्व सरसा दानकुल्या(-) ।[1१*] संपत्तिं श्री
- 4 वराहो वः संपादयतु भूयसी । सा-
- 5 मोदासुदहन् भूमिं समुद्रसलि-
- 6 लाघुतां⁴ ।[1२*] त्रियः कुलद्वयं शौरिः शय्या-
- 7 मूर्तिरुमापतेः । सृष्टिराद्या विधेरस्तु जी-
- 8 वनं जीवनाय वः ।[1३*] अस्ति चंद्रः सुधासूति-
- 9 रमलात्मा कलानिधिः । संजातः चीर-
- 10 पायोघी⁵ श्लाघ्यो लक्ष्मीसहोदरः ।[1४*] सुरा-
- 11 सुराशिरोरज्ज्वालितान्निसरोरुहः । ज्ञा-
- 12 चमान⁶ स्वयं धत्ते⁷ शिरसा यं सदाशिवः ।[1५*]
- 13 वसुधायां जगत्ख्यातो वंशस्तस्य समे-
- 14 धत्ते । जातो यत्र हरिस्त्राचाज्जगतां प्र-
- 15 भवो विभुः ।[1६*] अभूत्⁸ गुणगणांभोधि[र]-
- 16 व्याहतपराक्रमः । बुक्करायस्तपस्त-

¹ No. 255 of the Madras Epigraphical Collection for 1905.

² The honorific epithet *svāmī* given to Kṛishṇa-Paṇḍita in l. 90 and the way in which his name is introduced in v. 21 immediately after the description of Kriyāsakti lead us to suspect that these may have been identical.

³ From the original plates.

⁴ ३ was first written ३ and then corrected.

⁵ ज्ञा is corrected from य.

⁶ Read °मानः.

⁷ The symbol for s is added in error by the engraver to the preceding letter वि instead of to य.

⁸ Read अभूत्^०.

- 17 क्षिन् दिक्षु विख्यातवैभवः ।[१७*] संपत्प-
 18 रंपरोदारसर्वदिग्विजयक्रमः । एकै-
 19 कदिकपतीं देवानिंद्रादीनत्यशेत यः ।[१८*]
 20 तपोविशेषैस्तस्यामीत्तनयः 'पूर्वसंचितैः' ।[*]
 21 पुष्प[ः] पूर्ववृपालिषु गण्यो हरिहरेश्वरः ।[१९*]
 22 त्रिया संसेव्यमानस्य सर्वज्ञस्यातिश-

Second plate ; first side.

- 23 लिनः । समौ हरिहरौ यस्य जाने तावैव नाप-²
 24 रः ।[१९०*] तस्य राजाधिराजस्य श्रीराजपरमे-
 25 श्वरः । तनयो जयति क्षीणां देवरायमहीप-
 26 तिः ।[१९१*] पिब्ये 'सिंहासने यस्मिन्मित्रैश्चर्य-
 27 प्रदे स्थिते । 'शत्रुसिंहासनान्वासन् द्विजैः
 28 शून्यानि वासरैः ।[१९२*] नलनाभागभरतनहु-⁴
 29 पादीश्वरेश्वरान् । 'विश्वेरा यद्गुणस्तोमै-
 30 र्विष्मरत्नैव' मेदिनी ।[१९३*] श्रीदस्येवात्त-
 31 का श्लाघ्या शक्रस्यैवामरावती' ।[*] विजयोप-
 32 पदा यस्य विख्याता' वसतिः पुरी ।[१९४*] नाम्ना
 33 देमांविका तस्य नूकभूपालनंदिनी । महि-
 34 षी माधवस्यैव महाकृष्णीः 'समधते ।[१९५*] ¹⁰पु-
 35 चरूपं तयोरेकं पूर्वजन्मतपःफलं । श्री-
 36 मान्विजयते तेजःसीमा विजयभूपतिः¹¹
 37 ।[१९६*] कूटस्थौ वंशयोर्यस्य कुसुदांभोजवांधवौ ।
 38 वास्या क्षीणा च लक्ष्म्या च वल्लभो यः स्वयंवृ-
 39 तः ।[१९७*] प्रतापकीर्त्तितयोः प्रभोर्यस्य समिद्धयोः¹² [*]
 40 पुष्पाणि ¹³तटितस्ताराः पुष्पवंत्तौ¹³ च तौ

¹ Read पूर्व.

² The letter प looks more like व.

³ Read सिंहा°.

⁴ The letter त of भरत looks like व.

⁵ An extra vertical stroke has been erased between स्मै and रा.

⁶ An extra vertical stroke between the letters स्मै and व has been erased.

⁷ The syllable व is corrected from द्वि.

⁸ The letter स्था is engraved like स्मा.

⁹ Read समिद्धौ.

¹⁰ The first half of this verse is the same as verse 14 of the Satyamāngalam plates of Dvārākya II, except that तयोरेकं appears as तयोः श्लाघा in those plates.

¹¹ The *visarga* is engraved at the beginning of the next line.

¹² Read तटित°.

¹³ Read पुष्पवन्तौ; पु is written like वु, and there is an additional stroke added to it at the bottom, which makes the w-sign look long.

2
4
6
8
10
12
14
16
18
20
22

24
26
28
30
32
34
36
38
40
42
44

48 48 50 52 54 56 58 60 62 64 66



68 सप्तः पुत्रो न जगद्विजयवतो गीता ब
69 लमका गुरुससाउसमेरुना लोला
70 न तन्मो वल्लु की य स र ग कि व त य व
71 ना प्रतापता हरा त वि नु विता ग साते
72 ना तु नरातः प्रासासक प्रपांडु ते वि
73 प्रसासक त वा नृ ता वि व गुण क वि धिः प्र
74 मोता गिन स वि क द्या त बा ह्या त्र माः
75 रीणा पी ना घ रा मे यो रा म र क्ता र ह्यो
76 व च नो वि न व द वा वु ना वे के क ता गि ना
77 नु सि द्द ग य गो वि दः को रि को नै क ता ग
78 को ग नि द नुः सै क ता गः को रि को नु ग
79 दा न लः को रि को वि ह वः सै क ता ग र
80 मा थ वी मा षः वि स्वा मि नः का मा यो
81 ना मा उ वि वि ता ग ना क गो त री या
82 कु षः सै क वृ त्ति र प मा के रा व क्ता य
83 ना या कु षः सै क वृ त्ति मा रा य ति क
84 य न सि हो मा उ नै क ता गः का रा
85 ना या कु षः रा डि नो या कु षः स म
86 त्रि द वा य प द दा माः को डि नो या कु षः
87 सै क वृ त्ति ना ग य वे द दा माः को डि नो
88 उ नै क ता ग द्वा यी ना ग य ति म यः



90 रा ति स्वा मि नः रा गी ता य स्य मु ना व
91 य कु लि थे हा री रा यो मु षः सै क ता गः
92 यो म गा ना य नुः के रा वा न हे रिः सै क ता
93 गः को रि क या मु षः को डि नो या कु षः
94 सै क वृ त्ति र प मा स म पः को डि नो राः
95 गो ता ग द्वा यी री उ प मा ना य नुः ना व
96 दा मा य कु र थि ग मा ता ग य म र्था
97 त्री द ग्वा मा यीः सै क ल गा ना वा न द्वा
98 ता य सु नु ना ग द्वा द्वा न र ह य कु व द
99 वि द्दा म च दौ ना उ दा नः सै क ल ग
100 ना वा न प मा ना वा य सु नुः ना उ दा न
101 सु वि क त थो उ व ना ग द्वा यी रा री म र्था
102 रा ति त न न वी वृ द्धि मा ना न वी यः ना री
103 ना व द्वा यी ना ग द्वा यी सु यो य स म पः
104 पु सि ला ब द्वा ना ग द्वा यी वा हा य स म पः
105 त मा ना व द्वा वा वे यो दा तो गे म र्था य
106 ना ग य वृ द्धि र उ वि द्वा री व र्था चै क ता य
107 ना क री व र्था य कु षः सै क ता गः रा ग र
108 ति म यः का र य दौ व द्वा वः सै क वृ त्ति ना
109 य ति म यः रा डि नो व द्वा वः सै क वृ
110 डि नै र य य म गा नाः



312 श्री कृष्ण त ना ग द्वा य त य स हि ता रा गी ता वी य
313 मं वृ ता न द्वा को य ड् वि क त थो उ व दा न
314 यो व य ता उ दा को न हः चि त व द्या ना
315 ग य म र्था के त री म र्था व ति न
316 थि गु ना वृ डि मी द नः उ वा न्द न
317 ना उ दा को य कु षि म ति म र्था व ति
318 मं वृ ता री मा न ना ग द्वा य स हि
319 तो ल वि न द्वा री व यी हा नी तो उ व द
320 प्र दानि क रा व द व य रा गी ता य द्वा यो
321 यो र हा नी तो सै क ता ग ना क वि ह द
322 प्रि दै क वृ त्ति र प मा ना य रा ग वि ह
323 व द्वा यी दै क वृ त्ति म र्था व ति म र्था
324 मं वृ ता री मा न ना ग द्वा य स हि
325 मं वृ ता री मा न ना ग द्वा य स हि
326 मं वृ ता री मा न ना ग द्वा य स हि
327 मं वृ ता री मा न ना ग द्वा य स हि
328 मं वृ ता री मा न ना ग द्वा य स हि
329 मं वृ ता री मा न ना ग द्वा य स हि
330 मं वृ ता री मा न ना ग द्वा य स हि

- 41 फले ।[१८*] अभंगमंगकाकिंगवंगा[द्या]चामरा-
 42 दिभिः । राजानो यं विवेवन्ते राजचिह्नै स्त्र-
 43 यंधृतैः ।[१८*] राजानं दधतो मूर्धा राज्ञां मौलौ दिशन्
 44 पदं । शिवात् स्नाय्यो गुरुयस्य श्रीक्रियाशक्ति-

Second plate ; second side.

- 45 देशिकः ।[२०*] प्रभोर्वहुमतस्तस्य प्रयते कृष्णपंडि-
 46 तः । महनीयगुणांभोधिर्मदिरं सर्वसंपदां ।[१२१*]
 47 स्नाय्या मेचांशिका येन शिंगणायंश्च दंपती ।
 48 पुत्रेण भुवने नीतौ पुत्रिणामप्रगल्भतां ।[१२२*] यक्ष-
 49 वेदादिषु स्यातिं यस्यामस्यान्वयाधिपः । व-
 50 सिष्टाद्यैर्भरद्वाजो वर्धते वंशकर्तृभिः ।[१२३*] अ-
 51 न्वयी भूपयन् संज्ञामनंदानैरहर्निशं । धन्यो
 52 यस्यानुजो धीमाननंदाता समेधते ।[१२४*] भूषो-
 53 र्विजयभूपस्य भूतलेंद्रयशोनिधेः । आश्विने-
 54 योपमां यातः^४ पार्श्वं तावद्यजानुजौ ।[१२५*] रा-
 55 जा श्रीविजयः सोयं राज्ये सुत्वागिलांश्च^५
 56 ये । हुलिनाडौ फलोदारे दंडेहस्तिखले य[मे] ।[१२६*]
 57 श्रीमत्क्षेत्रगृहारासमीमानिर्माणशोभितं ।
 58 क्रियाशक्तिपुरं कृत्वा ग्रामं प्रतिनवं कृती ।[१२७*]
 59 शकान्दे रंगलोकात्ते वीरो विज्जतिवत्सरे ।[१*] प-
 60 चे भाद्रपदे शुक्ले सोमश्रवणसंयुते ।[१२८*] एकाद-
 61 श्यां तिथौ योगे लक्ष्मीनारायणांश्च^६ । स[१]-
 62 दृभोगं सर्वमान्यं धारापूर्वं सदक्षिणं ।[१२९*] मंडि-
 63 तः सनुषैः कृष्णपंडिताय कृपानिधिः । प्रादित
 64 श्र्यंबकप्रीत्यै पृथिवीकल्पपादपैः ।[१३०*] स क-
 65 णपंडितस्तत्र समुद्रं विजयादिकं । तटाक-
 66 क्षितसौभाग्यं तटाकं निरमाययत् ।[१३१*] अष्टौद-
 67 ख प्रसंगोपि तुच्छो यद्वर्णनाक्रमे । मानसं [च]

^१ Read निवेवन्ते.

^२ Read चिह्नैस्त्र.

^३ Read शिवाभ्यास्यो.

^४ यातः is the third person dual of the root या 'to become.'

^५ Read सुत्वागिलांश्च.

^६ नारायणांश्च.

^७ Read दित्.

Third plate ; first side.

- 68 सरः 'पुंसां मानसाय न रोचते ।[132*] रणम्[रा]-
 69 लमंजीरा रसकारसमेखला । लीला[नृ]-
 70 तं तनोतीव लक्ष्मीर्यत्पद्मराजिषु ।[133*] तटाके-
 71 न[1]यहारं 'तं तादृशेन विभूषितं । राज्ञा ते-
 72 न[1]भ्यनुज्ञातः प्राज्ञोसौ कृष्णपंडितः ।[134*] वि-
 73 प्रसात्कृतवान् धन्यो विवेकगुणवारिधिः । क-
 74 भिष भागिनस्तेपि कथ्यन्ते ब्राह्मणोत्तमाः ।[135*]
 75 श्रीगोपीनाथरामेशौ ग्रामरक्षणदक्षि[षौ] [1*]
 76 प्रसन्नौ नित्यवरदातुभावेकैकभागिनौ ॥[136*]
 77 ऋत्विद्रंगयगोविंदः कौशिकोवैकभाग[1]-
 78 क् । गोविंदभूः सैकभागः कौशिको ऋत्वि-
 79 दोभक्तः ।[137*] कौशिको बहुचः सैकभागः श्री-
 80 भाधवांशपः । विश्वामित्रः कामयथी-
 81 रामो ऋत्विहिभागभाक् ।[138*] गौतमो या-
 82 जुषः सैकहस्तिरप्यणकेशवः । काश्य-
 83 पो याजुषः सैकहस्तिर्मारुतिप-
 84 यः ।[139*] रुसिंहो भारजश्चैकभागः काश्य-
 85 पयाजुषः । शांडिल्यो याजुषः सैकपृ-
 86 तिर्द्वैवार्यपेक्षः ।[140*] कौडिन्यो याजुषः
 87 सैकहस्तिर्गार्ग्यपेक्षः । कौडिन्यो या-
 88 जुषो भागद्वयो नागार्ग्यतिमयः ।[141*]

Third plate ; second side.

- 89 भागाः श्रीरामकृष्णस्य भारद्वाजस्य वि-
 90 शतिः । स्वाग्निः शिंगणार्यस्य सूनोरण
 91 यजुर्निधेः ।[142*] हारीतो याजुषः सैकभागः
 92 श्रीगंगणाय्यलुः । केशवो रुहरिः सैकभा-
 93 गः कौशिकयाजुषः ।[143*] कौडिन्यो याजुषः[ः]
 94 सैकहस्तिरप्यणसोमपः [1*] कौडिन्यो याजु-
 95 षो भागद्वयो श्रीधर्याय्यलुः ।[144*] भार-

* Read पुंसां.

* It is very peculiarly formed.

* Read "दिनाय".

- 96 हाजो यजुरधिगमो भागयुग्मस्य क-¹
 97 कर्ता दुग्मप्यार्यः सकलगुणवान्नदा-
 98 तार्यसूनुः । भागद्वंद्वप्रभुरिह यजुर्वेद-
 99 विद्वामचंद्रो भारद्वाजः सकलगु-
 100 णवानप्यणाचार्यसूनुः । [184*] भारद्वाजो य-
 101 जुषि कृतधीरव भागद्वयेशः श्रीमन्नक्ष्मी-
 102 पतितनुभवो बुद्धिमानौभलाय्यः । हारी-
 103 तो बह्वचो भागद्वयी सूर्यार्यसोमपः । (1)
 104 वसिष्ठो बह्वचो भागद्वयी चौडार्यसोमपः [184*]
 105 तिमणो बह्वचाचेयो द्विभागो मज्जपार्यजः [1*]
 106 नागार्थनृहरी ऋग्वित् श्रीवत्सोच्चैकभाग-
 107 भाक् [185*] श्रीवत्सो याजुषः सैकभागः शिंगार्य-
 108 तिमयः । काश्यपो बह्वचः सैकवृत्ती रामा-
 109 र्यतिमयः । [186*] शांडिल्यो बह्वचः सैकवृ-
 110 त्तिर्न्याय्यमंगणः ॥—॥

Fourth plate ; first side.

- 111 अस्मिन् भागद्वितयसहितः शिंगणाचार्य-
 112 सूनुभारद्वाजो यजुषि कृतधीरवदाता-
 113 र्यवर्यः । भारद्वाजो नृहरितनयो भा-
 114 गयुग्मस्य कर्ता श्रीमन्नक्ष्मीपतिर-
 115 धिगुणो बुद्धिमान्याजुषोस्मिन् [187*]
 116 भारद्वाजो यजुषि मतिमानप्यणाचा-
 117 र्यसूनुः श्रीमान् भागद्वितयसहित-
 118 तो मज्जिमहार्यवर्यः । हारीतोऋग्विदे-
 119 कवृत्तिः केशवदेवपः । शिंगार्यनृहरी ऋ-
 120 ग्वित् हारीतोच्चैकभागभाक् [188*] विष्णुहृषो

¹ Perhaps we have to correct क into म. The same word is used in l. 114.

² Read "विद्वाम".

³ Read सुनुमी

⁴ Read भर्ता; as in l. 98 f.

⁵ The syllable सू looks like म्; the horizontal stroke in the middle which distinguishes सू from म् seems to have been marked by mistake at the top.

⁶ The metre requires one more syllable for the first quarter; perhaps the reading meant was हारीतोचो.

⁷ Read "विहारीतो".

- 121 ऋग्विदेकवृत्तिर्ह्यपलपयणः¹ । विष्णु-
 122 वृत्तो ऋग्विदेकवृत्तिर्माधवहंपणः । [१५१*]
 123 याजुषो वृषवंशेकवृत्तो रवकृतोक्तपः । रवकार्यः
 124 सैकवृत्तिर्याजुषो जनभूर्वृषः । [१५२*] कौडिन्यो या-
 125 जुषः सार्धवृत्तिस्तिष्यार्थवज्रभः । गौतमो याजु-
 126 षः सार्धवृत्तिः कौमणलपयणः । [१५३*] विश्वामित्रो ऋग्वि-
 127 देववृत्तिर्नागार्थगोपणः । कौशिको याजुषः सार्ध-
 128 वृत्तिरक्षार्थमाधवः । [१५४*] कौशिको² याजुषः सार्धवृत्तिरे-
 129 क्षार्थवज्रभः । कौशिको याजुषः सार्धवृत्तिर्मन्त्रार्थव-
 130 ज्रभः । [१५५*] कौशिको याजुषः सार्धवृत्तिर्मन्त्रार्थविष्णुणः ।
 131 लिंगार्थजो बह्वृचजामदन्यवत्तोर्वृत्तिः [स्त्वह स]त[न]ावः [१*]

Fourth plate ; second side.

- 132 वासिष्ठोऽस्मिन् बह्वृचो योगसूनुः चंद्रप्या-
 133 र्यः सार्धवृत्तिद्वयेशः । [१५६*]³ गार्ग्यः [१*] श्रीयाजुषः
 134 सार्धवृत्तिः शिगार्थजाण्वः । याजुषो वृषः⁴
 135 वंशोर्वृत्तो रवकृतोक्तपः । [१५७*] श्रीवत्सो
 136 याजुषः सैकवृत्तिर्विह्वलपयणः । कौडि-
 137 न्यो या[जु]षः सौम्यो नृहरिः पादभागभाक् [१५८*]
 138 सार्धवृत्तिः कूचिरामः शा[लं]कायनयाजुषः । बह्वृचो वृ-
 139 णपाचार्यतनू⁵भूमाधवस्तुधीः [१५९*] पादोन-
 140 वृत्तिद्वयवान्विष्णुवर्धनगोचजः । विश्वामि-
 141 त्रो बह्वृचस्तिष्यणार्थो [१*] भागवयो गंगण-
 142 सूनुव । भारद्वाजः पादभागी याजु-
 143 षः सूर्यतिमयः । कौशिकः पादोनवृ-
 144 त्तिर्ऋग्विष्टिष्टेणकेशवः । [१६०*] अंतु देव-
 145 भाग सह वृत्तिगुरु ८२⁶ ष-

¹ The second वृ is incomplete. See the same conjunct consonant in l. 126 below.

² Read कौशिकी.

³ The two halves of which this verse is made up belong respectively to the metres *Indrasajrā* and *Śālit*.

⁴ Read वृष^०.

⁵ Read भूमा^०.

⁶ Read "सौ षभि^०."

⁷ In Telugu-Kanarese numerals and throughout.

- 146 चरदलु इवे ऐभत्त येरडु हत्ति [1*] ये¹
 147 कैव भगिनो लोके सर्वधामेव भूमज्ज[1] [1*]
 148 न भोज्या न करयाद्या विप्रदत्ता वसु-
 149 धरा ॥[६१*] सामान्योय² धर्मसितुनृपाणां का[ले]
 150 काले पालनीयो भवद्भिः । सर्वानेतान् भ[1]-
 151 विनः पार्थिवैद्रान् भूयो भूया³ याचते
 152 रामचंद्रः ॥[६२*] श्री श्री श्री ॥—॥

Fifth plate ; first side.

- 153 अभिनवविजयवुक्करायसमुद्रद सी-
 154 मे । करैय वडगण कोडिय तटि-
 155 नलु येडूरुगि आग्नेयदलु हुणिशिम-
 156 रगळिगि पडुवण नट कळु १⁴ अदके
 157 मूडलु हुणिशिमरद वडगण नट
 158 कळु १ अदके ईशान्यदलु हुणिशिम-
 159 रळे वडगण नट कळु १ अदके मू-
 160 डलु नट गुंडिनलु अचरव वरशि-
 161 द कळु १ अदके मूडलु येडूरु ताल-
 162 कुंटेय सीमेय हुणिशिमरद के-
 163 [ळ]गि कळु १ तालकुंटेय नैर्ऋत्यदलु
 164 नट कळु १ अदके मूडलु तालकुं-
 165 टेगि तेंकलु अलदमरद वडग-
 166 ण नट कळु १ अदके ईशान्य-
 167 दलु तालकुंटेय मूडण हुणिशिम-
 168 रदलु नट कळु १ अदके
 169 मूडलु कुंटेय मूडणकोडिय
 170 वेलदमरदलु कळु १ अदके
 171 मूडलु तुंगिलमरद केळुगि न-

Fifth plate ; second side.

- 172 इ कळु १ अदके मूडलु [अरें]ग[ळु] १ अदके मूडलु कगळलु
 173 वरद शासन १ अदके मूडलु तालकुंटेय अरसाडियह[कि]-

¹ Read एवे.

² Read "जीव".

³ Read भूयो.

⁴ In Telugu-Kanarese numerals and throughout.

- 174 ય સીમેય હુણિશેમરદલુ નદ કલુ ૧ અદકે આ[ન્ને]-
 175 યદલુ કૂડનહક્કિંગે વડ ગલુ તોરંગે તેકળ દડદ તા-
 176 રૈમરદ ઉત્તિન વડગળ નદ કલુ ૧ કૂડનહક્કિંગે પ-
 177 હુવલુ અરંગે મૂડળ નદ કલુ ૧ આ અરૈય મેલે વરદ
 178 શાસન ૧ અદકે પહુવલુ હુણિશેમરકે મૂડળ નદકલુ
 179 ૧ [અદકે] પહુવલુ તિરુમલેદારિય હુણિશેમરદ પહુવ-
 180 ણ નદ કલુ ૧ અદકે પહુવલુ તુમિલમરદ નદ ક-
 181 લુ ૧ અદકે પહુવલુ હુણિશેમરકે પહુવલુ નદક-
 182 લુ ૧ અદકે પહુવલુ દંડેહક્કિયસીમેય હુણિશે-
 183 મરદલુ નદ કલુ ૧ અદકે તેકલુ તુંવરદ મરદ પહુવળ
 184 નદ કલુ ૧ અદકે પહુવલુ વસુરિયમરકે મૂડ-
 185 ણ નદ કલુ ૧ અદકે વડગલુ તિરુમલેયદારિય
 186 અરમેલે હોયિશિદ 'શાસન ૧ અદકે પહુવલુ હુણિશે-
 187 મરકે તેકળ નદ કલુ ૧ અદકે પહુવલુ આલદમરદ ઉ-
 188 ત્તિન નદ કલુ ૧ અદકે પહુવલુ દંડેહક્કિંગે તેકલુ નદ ગું-
 189 ઢિનલુ હોયિશિદ શાસન ૧ અદકે તેકલુ તુમિલમરદ ઉત્તિ-
 190 ન નદ કલુ ૧ અદકે તેકલુ આલદમરદ યડેવિદ મૂડ-
 191 [લુ] નદ અરંગેગ્ગિન ઉત્તિનલુ નદ કલુ ૧ અદકે પહુવલુ કં-
 192 ગાણિયહક્કિય હોલમેરે સીમે ।
 193 ત્રીચિયંવક

ABRIDGED TRANSLATION.

L. 1. Let there be prosperity !

(Verse 1.) Let Gaṇeśa, who is an ocean of compassion and whose cheek is moist with incessant flow of rut, take an interest in our welfare.

(V. 2.) Let the glorious Varāha, who bore aloft the delighted Earth sunk in the waters of the ocean, procure fortune to us in abundance.

(V. 3.) Let water (*jivana*), which is the abode of Lakshmi,¹ the bed of Śaury (Vishnu), the body corporeal of Umāpati (Śiva) and the first (*object of*) creation of Brahmā, exist for our subsistence.

(Vv. 4 and 5.) The moon—the birth place of nectar, of pure body, the embodiment of sixteen parts and the esteemed brother² of Lakshmi—whom Sadāśiva, whose lotus-like feet are fondled by the crest jewels of the gods and the demons, himself proudly wears, was born from the milky ocean.

¹ Read શાસન.

² The goddess Lakshmi is said to have come out of the milky ocean, when it was churned.

³ The moon is the brother of Lakshmi, as both of them were produced from the milky ocean.

(V. 6.) There flourishes on earth the world-famed family of his (*i.e.* the moon's), in which the omnipresent Hari, the creator of the worlds, himself was born.¹

(Vv. 7 and 8.) In that (*family*) was sprung king Bukka-Rāya, the ocean of a multitude of good qualities, of irresistible valour, whose exalted position was well known in all quarters—whose course of conquests extended to all directions with the grandeur of continuous success and who (*as such*) surpassed the gods Indra and the rest, who were lords each of a single quarter.

(Vv. 9 and 10.) To him was born by virtue of superior penance accumulated in former (*births*) a virtuous son Hariharēśvara, who was to be reckoned among the ancient kings. To him, well served by Śrī (*i.e.* Lakshmi) and famous as the all-knowing (*Sarvajña*), only Hari and Hara were equal and none else.²

(V. 11.) Victorious on this earth is the prosperous Rājaparamēśvara, king Dēvarāya, the son of this Rājādhirāja.

(V. 12.) While this king sate on the ancestral throne, bestowing wealth on his friends, the thrones of his enemies became vacant in two or three days.

(V. 13.) Amazed at his excellent virtues, the earth actually forgets the sovereigns Naja, Nābhāga, Bharata, Nahusha and others.

(V. 14.) Like unto (*the city of*) Alakā of (Kubēra) the giver of wealth, and unto Amarāvati of Indra, the excellent and famous city which has for its prefix the word Vijaya (*i.e.* Vijaya-nagara) was his residence (*vasati*).³

(V. 15.) His consort Dēmāmbikā by name, the daughter of Nāka-Bhūpāla, is prosperous like Mahā-Lakshmi, the consort of Mādhava.

(V. 16.) The illustrious Vijaya-Bhūpati, the chief fruit, in the form of a son, of their (*i.e.* of the parents') penance (*practised*) in former births, is victorious as the (farther) limit of prowess.

(V. 17.) At the root of whose lineage are (the Moon and the Sun),⁴ the friends of the white and red lotuses (respectively); and who is voluntarily chosen as lord by (*the goddesses*) Sarasvati, the Earth and Lakshmi.

(V. 18.) The lightning and the stars (*were*) the flowers and the sun and the moon (*were*) the fruits of the two well-grown creepers, the valour and fame of this lord.⁵

(V. 19.) Upon whom the kings of Aṅga, Kāliṅga, Vaṅga and the rest always attend holding *chauris*, etc., the insignia of royalty, themselves.

(V. 20.) His (*i.e.* Vijaya-Bhūpati's) spiritual teacher was Kriyāśakti-dāśika who, placing his foot on the diadems of kings (*rājā*), became more illustrious than Śiva carrying the moon (*rājā*) on his head.⁶

(V. 21.) Kṛishṇa Paṇḍita, the ocean of good qualities and the abode of every fortune, is highly esteemed by that king and is famous.

¹ This is the Yādava family, in which Kṛishṇa was born.

² Hari (Viṣṇu) is the husband of Lakshmi and Sarvajña is a recognised surname of Hara (Śiva).

³ In the Eastern Gāṅga grants *vāsuka* appears in the sense of *rājadhāni*; above, Vol. III, p. 20, note 2.

⁴ Vijaya-Bhūpati was born in the race of the moon. His mother Dēmāmbikā was born of the Solar race.

⁵ *I.e.* his fame and valour reached even unto the sky. This verse is the same as verse 12 of the *Satya-mahāgalam* plates of Dēvarāya II; *Ep. Ind.*, Vol. III, p. 37, text lines 20 f.

⁶ Kriyāśakti-dāśika is greater than Śiva, because the *rājā* carried on his head by the latter was merely trodden by the former.

(V. 22.) By (*possessing*) this son (*i.e.* Kṛishṇa-Paṇḍita) the praiseworthy couple Mōchām-bikā and Śīṅgaṇārya came to be ranked foremost among parents (*lit.* those *possessing* children) in this world.

(V. 23.) The founder of the lineage of (Kṛishṇa-Paṇḍita), who has obtained fame in the Yajur-Vēda and so on, is Bharadvāja, praised by founders of families like Vasiṣṭha and others.

(V. 24.) His younger brother, the wise and fortunate Annadātā, prospers well, making his designation literally appropriate by feeding (the needy) day and night.

(V. 25.) These (*two*) elder and younger brothers, serving by the side of the famous king Vijaya-Bhāpati, who was an Indra on earth, resembled (the two celestial brothers) the Aśvins.¹

(Vv. 26 to 30.) This illustrious and virtuous ruler, the heroic Vijaya, who was a celestial tree on earth and a mine of compassion, and who was ornamented with good qualities, having founded the new village called Kriyāsakti-pura, adorned with rich fields, houses, pleasure-gardens and boundary marks, in the auspicious Daṇḍāhaḷli *sthala*² in Huli nāḍa of great yield, in the Muḷvāgila rājya, gave (*it*) as a free gift, together with the eight kinds of easements, to Kṛishṇa Paṇḍita, accompanied by the pouring of water and a fee, in order to propitiate (the god) Tryambaka, in the Śaka year expressed by the (chronogram) *raṅgalōka* (*i.e.* 1332), in the (cyclic) year Vikṛitti, on the day of Śravaṇa which corresponded to a Monday, the 11th *tithi* of the bright fortnight in the month of Bhādrapada and was coupled with the *yōga* (called) Lakṣmi-Nārāyaṇa.

(V. 31.) (*Subsequently*) this Kṛishṇa-Paṇḍita founded in that place a tank called Vijaya-samudra endowed with charm all round.

(V. 32.) Even to speak of (the lake) Achchhōḍa, while describing it (*i.e.* tank), is vain, even the Mānasa-saras (the tank of the gods) does not become attractive to the minds of the people (after once seeing this).³

(V. 33.) It seems as if Lakṣmi performs her sportive dance over the cluster of lotuses (in this tank),—the swans (being) her noisy anklets and the (row of) *sārasa* birds her jingling girdle.

(Vv. 34 and 35.) The wise, wealthy, virtuous and discriminate Kṛishṇa-Paṇḍita, with the permission of the king, made a gift of the *agrahāra* adorned by the tank above described to Brāhmaṇas. The best of the Brāhmaṇas who received shares are enumerated in regular order.

(Ll. 75 to 146.) List of donees :—

No.	Name of the donee.	Father's name.	Gōtra.	Vēda.	No. of shares.
1	Gōpinātha (Viṣṇu) . . .				1
2	Rāmōḍa (Śiva) . . .				1
3	Gōvinda	Raṅgaya	Kauśika	Rich	1
4	Obhaja	Gōvinda	Do.	Do.	1

¹ The Aśvins are the inseparable twins who serve as physicians to the gods.

² Daṇḍāhaḷli *sthala* may have been the lowest territorial division in which the village Kriyāsakti-pura was situated. The word *sthala* in this sense corresponds to *śāḍa* or *śāḍya* of other inscriptions and is etymologically connected with them.

³ Achchhōḍa and Mānasa-saras are two famous lakes in the Himalayas.

No.	Name of the donee.	Father's name.	Gōtra.	Vēda.	No. of shares.
5	Appapa	Mādhava	Kauśika	Bahvricha	1
6	Śrīrāma	Kāmaya	Viśvāmitra	Rich	2
7	Kēśava	Appapa	Gautama	Yajus	1
8	Tippaya	Mārāya	Kāśyapa	Do. . . .	1
9	Nṛsiṃha	Māra	Do. . . .	Do. . . .	1
10	Peddapa	Dēvāya	Śāṇḍilya	Do. . . .	1
11	Do. . . .	Nāgāya	Kauṇḍinya	Do. . . .	1
12	Timmaya	Do. . . .	Do. . . .	Do. . . .	2
13	Rāma-Kṛishṇa	Śīṅgaṇāya	Bhāradvāja	Do. . . .	20
14	Ayyala	Guṇḡapa	Hārīta	Do. . . .	1
15	Nṛihari	Kēśava	Kauśika	Do. . . .	1
16	Sōmapa	Appapa	Kauṇḍinya	Do. . . .	1
17	Ayyala	Do. . . .	Do. . . .	Do. . . .	2
18	Duggappāya	Annadātāya	Bhāradvāja	Do. . . .	2
19	Rāmachandra	Appanāchāya	Do. . . .	Do. . . .	2
20	Aubhalāya	Lakshmiṇi	Do. . . .	Do. . . .	2
21	Sōmapa	Sūryāya	Hārīta	Bahvricha	2
22	Do. . . .	Chauṇḍāya	Vasishṭha	Do. . . .	2
23	Timmapa	Mallapāya	Ātrēya	Do. . . .	2
24	Nṛihari	Nāgāya	Śrīvatsa	Rich	1
25	Timmaya	Śīṅgāya	Do. . . .	Yajus	1
26	Do. . . .	Rāmāya	Kāśyapa	Bahvricha	1
27	Maṅga	Mēyāya	Śāṇḍilya	Do. . . .	1
28	Annadātāya	Śīṅgaṇāchāya	Bhāradvāja	Yajus	2
29	Lakshmiṇi	Nṛihari	Do. . . .	Do. . . .	2
30	Mallibhātāya	Appanāchāya	Do. . . .	Do. . . .	2
31	Dēvapa	Kēśava	Hārīta	Rich	1
32	Nṛihari	Śīṅgāya	Do. . . .	Do. . . .	1
33	Lakshṇa	Hegga	Viśṇuvṛiddha	Do. . . .	1
34	Hampapa	Mādhava	Do. . . .	Do. . . .	1
35	Tikapa	Rājā	Vṛisha	Yajus	1
36	Rājā	Jahna	Do. . . .	Do. . . .	1
37	Vallabha	Tippaya	Kauṇḍinya	Do. . . .	1

No.	Name of the donee.	Father's name.	Gōtra.	Vēda.	No. of shares.
28	Lakṣhṇa	Koṁma	Gautama	Yajus	1
29	Gōpa	Nāgārya	Viśvāmitra	Rich	1
40	Mādhava	Allārya	Kauṣika	Yajus	1
41	Vallabha	Ellārya	Do.	Do.	1
42	Do.	Mallārya	Do.	Do.	1
43	Vissapa	Do.	Do.	Do.	1
44	Saptanātha	Līṅgārya	Jāmadagnya-Vatsa	Bahvricha	1
45	Chandrapārya	Yōga	Vāśiṣṭha	Do.	2 1/2
46	Anṇapa	Śiṅgārya	Gōrgya	Yajus	1
47	Tikapa	Ravala	Vṛisha	Do.	1
48	Padma	Viṭṭhala	Śrīvatsa	Do.	1
49	Nīhari		Kauṇḍīnya	Do.	1
50	Kūchirāma		Śālaṅkāyana	Do.	1
51	Mādhava	Heggaṇḍārya	Viṣṇuvardhana	Bahvricha	1 1/2
52	Tippaṇḍārya	Gaṅga	Viśvāmitra	Do.	2
53	Timma	Sūrya	Bhāradvāja	Yajus	1
54	Kēśava	Chittēna	Kauṣika	Rich	1
TOTAL SHARES					82

(Ll. 146 to 148.) Altogether the *ṛittis* are 82, including the share of the gods. Also in words eighty-two *ṛittis*.

(Ll. 149 to 152.) [Here follow the two usual imprecatory verses].

(Ll. 153 to 192.) The boundary of Abhinava-Vijaya-Bukkarāya-samudra is (as follows) :—

One stone set up to the west of the tamarind trees at the south-east corner of Ēḍūru, on the side of the north outlet of the tank; to the east of it, one stone set up to the north of the tamarind tree; in the north-east corner of it, one stone set up to the north of the tamarind tree; east of it, one boulder stone set up with the letters engraved on it; to the east of it, one stone under the tamarind tree which was on the boundary between Ēḍūru and Tālakuṇṭe; one stone set up to the south-west of Tālakuṇṭe; to the east of it, one stone set up to the north of the banyan tree south of Tālakuṇṭe; to the north-east of it, one stone set up at the tamarind tree east of Tālakuṇṭe; to the east of it, one stone (set up) at the Bēl tree in the eastern outlet of the tank; to the east of it, one stone set up below the Tuggīla tree; one rock to the east of it; to the east of it, an inscription engraved on a black stone; to the east of it, one stone set up at the tamarind tree on the boundary between Tālakuṇṭe and Arasāṇḍēyaha[¹]lī; to the south-east of it, one stone set up to the north of the ant-hill¹

¹ *Uṭṭa* is the same as *kutta*, "an ant-hill" according to Dr. Kittel's Kannada-English Dictionary. It is however difficult to account for the form *uṭṭa*.

at the Tāre (*Beleric Myrobalan*) tree on the south bank of the stream and north of Kāṇanahāli[*]i; one stone set up to the east of the rock west of Kāṇanahāli[*]i; an inscription engraved on that rock; to the west of it, one stone set up to the east of the tamarind tree; west of it, one stone set up to the west of the tamarind tree on the road to Tirumale; west of it, one stone set up to the west of a tamarind tree; west of it, one stone set up at the tamarind tree on the boundary of Daṇḍehāli; to the south of it, one stone set up to the west of the wild Mangosteen tree; to the west of it, one stone set up to the east of the waved-leaved fig tree; to the north of it, an inscription caused to be cut on a rock on the road to Tirumale; to the west of it, one stone set up to the south of a tamarind tree; to the west of it, one stone set up at the ant-hill of the banyan tree; to the west of it, an inscription caused to be engraved on the boulder set up to the south of Daṇḍehāli; to the south of it, one stone set up at the ant-hill of the Tuggila tree; to the south of it, one stone set up at the ant-hill of the boulder set up a little beyond to the east of the banyan tree; to the west of it, the boundary is the boundary limit of the fields of Kaṅḡṇiyahāli[*]i.

(L. 193.) Śrī-Triyambaka.

No. 3.—SRIRANGAM PLATES OF MUMMADI NAYAKA : SAKA SAMVAT 1280.

By T. A. GOPINATHA RAO, M.A., TRIPLICANE.

The subjoined inscription is engraved on five copper plates, bound together by a ring, which was already cut when I got them for examination. The ring bore no seal. The plates measure 9" by 2", and the writing is engraved lengthwise on both sides of the plates. There are exactly ten lines on each side, and the plates are numbered with Telugu-Kanarese numerals, marked on the proper right of the ring-hole on the second side of each plate. The rims are neither raised nor shaped thicker, and yet the writing is in an excellent state of preservation.

This set of copper plates belongs to the Raṅganātha-svāmin temple at Srīraṅgam and was kindly lent to me for examination by the trustees of the temple, Messrs. T. Deśikāchārya, B.A., B.L., of the Trichinopoly bar, and K. S. Kuppusāmi Ayyaṅḡar. My thanks are due to these gentlemen for having so obligingly placed this, as also all the other copper plate documents, at my disposal for some time and thus enabling me to take mechanical copies of them.

The alphabet in which the record is written is old Telugu, and the language Sanskrit. The whole is written in 64 verses of various metres. The inscription records that Mummadi Nāyaka, the king of the Teliṅga country, granted to Bhaṭṭa Parāśara, the seventh, the village of Koṭṭāllaparru, which the donee's mother regranted to Śrīraṅganātha-svāmin, the presiding deity of the great Viṣṇu temple at Śrīraṅgam. The genealogy of the donor is given as follows :—



Mummaḍi is said to have married the niece (sister's daughter) of a Kāpaya Nāyaka. His family was known by the name of Mañchikonda, and the ancestors of this family were originally brought down from the Gangetic valley by Mukkaṇṭi. Teliṅga-dēśa, ruled over

by Mummaḍi Nāyaka, was bounded on the north by Kanyākubja, on the south by the Pāṇḍya country, on the east by Kālīṅga and on the west by Mahārāṣṭra. Prince Mummaḍi is described as having conquered the Pāṇāra, the Kōṇa, the Kuravāṭaka, the Cheṅgara and other countries lying on either side of the Godāvarī, and as having made Kōrukōṇḍa his capital. He had two brothers, Śīṅgaya and Gannaya, whom he allowed to rule over the small principalities of Kōṭi and Tāḍipākka. Sovereignty had no attraction for Mummaḍi; but he was obliged to accept the crown for the sake of his father. Mummaḍi is also called Śrīraṅga-varḍḍbana (v. 52), a surname which he perhaps assumed after he became the disciple of Parāśara Bhaṭṭa VII. He became a follower of the latter, when the latter had gone to the Teliṅga-dēśa, and as a *guru-dakṣiṇā* this grant of a village was made.

At present nothing more than what is given in this document is known of Mummaḍi Nāyaka. From the fact that the southern boundary of his kingdom was the Pāṇḍya country we can very well understand that at the time of this record the occupation of the Nellore district by Jaṭā-varman Sundara Pāṇḍya was an accomplished fact. This latter subverted the dynasty of the Chōḷas, overran and captured their country as far north as Nellore, where he had his *cirābhishēka* celebrated.¹ Nothing is known definitely of the chiefs of Pāṇāra,² Cheṅgara, Kuravāṭaka, etc.

The village granted to Parāśara Bhaṭṭa VII was evidently enjoyed by him for some time before he died. His mother, who survived him (v. 48), seems to have thought of allowing the relatives of the deceased to inherit the village; but in the meanwhile she changed her mind and gave it away to the god Raṅganātha, taking Him, as she says, as the greatest of all relatives. Most likely the relatives began to trouble her and perhaps also to question her rights to the property, which must have goaded her on to take the course which she chose.

An inscription found lately at Kōrukōṇḍa itself gives a very interesting account of the death of the seventh Parāśara Bhaṭṭa and his reappearance as a divine being. Incidentally also some facts about his patron and disciple, Mummaḍi Nāyaka, are given in it. Mr. Krishna Sastri summarises the contents of the record thus:—

"Mummaḍi Nāyaka is stated to have been the ruler of Kōrukōṇḍa, which was surrounded by a fort. He was a great conqueror and had subdued the kingdoms of Pāṇāra, Kōṇa, Kuravāṭaka and Bēṅgara A Vaiṣṇava teacher Bhaṭṭari, of whom Mummaḍi was the devoted disciple, told the chief one day that he had reached the last of his human births and, as soon as the existing mortal frame was given up, he would appear in the form of the god Lakṣmi-Nārasimha on the hill at Kōrukōṇḍa. Soon after this revelation the teacher died, and all about his rebirth as the god Nārasimha was apparently forgotten. A dancing-girl of the village, called Lakṣmi-dāśī, saw the teacher in a dream and was told by him of his manifestation on the Parāśara-śaila. The king, being informed of this, was at once reminded of what the teacher had told him and permitted the dancing-girl to build the temple. She wandered about in rags, begging for money, pledged her daughter, earned the amount required, built a temple and consecrated therein Parāśara-Nṛisimha, presenting at the time of the consecration two villages for the maintenance of the worship and offerings."³ Mr. Sastri adds that the verses in the inscription under notice are repeated verbatim in the Kōrukōṇḍa record also. The latter inscription is dated Ś. 1275; this is the date of the consecration of the image of the god Nṛisimha; and therefore the death of the seventh Parāśara Bhaṭṭa would have occurred some time before this date, and this mother would consequently have survived him for at least seven or eight years.

¹ No. 904, p. 145 of the Appendix to Vol. VII of *Ep. Ind.*

² Vājaya, a prince of Pāṇāra, is mentioned in one of the Eastern Chālukya grants published in *South Indian Inscriptions*, Vol. I, p. 64.

³ *Madras Epigraphist's Annual Report* for 1912, para. 68.

Parāśara Bhaṭṭa VII belongs to a very illustrious family of scholars of southern India. Śrīvatsasihna-guru, or Śrīvatsasihna Miśra, as he is generally called, was the first or the founder of the family of Bhaṭṭars of Śrīrangam. He was the first and foremost disciple of Śrī Rāmānuja, the famous founder of the Viśiṣṭādvaita school of philosophy. In all the Śrīvaiṣṇava chronicles and among the Śrīvaiṣṇavas he is better known by the name of Kūrattālvāṇ. He belonged to the Hārita gōtra and Āpastambha Śātra and was of the Yajus śākhā. He was born in the year Saumya, on a Thursday which was Pañchami in the month of Pushya. He was a Vādama by sect and belonged to the village of Kūram near Chingleput. His wife was named Āṇḍāl. The early education of Kūrattālvāṇ was undertaken by his own father; but he finished his studies during his stay with Rāmānuja and under him. He was the chief assistant and the amanuensis of Rāmānuja in the compilation of the Śrībhāṣya. He was of the same gōtra as Rāmānuja.

The Śrīvaiṣṇava Chronicles narrate the persecution of Rāmānuja by the Chōla sovereign, and assert that this king was a bigoted Śaiva and consequently began to persecute the Vaiṣṇavas. It was pointed out to this king that converting the common people by force was not in itself capable of augmenting the numbers to the Śaiva faith, and, if such a great leader as Rāmānuja were to be made to subscribe to the Śaiva faith, his followers would join that sect in a body. Rāmānuja was summoned before the king; Kūrattālvāṇ, apprehending danger to his master, assumed the garb of a *sannyāsin*, proceeded to the royal court, and represented himself as the famous Vaiṣṇava Āchārya. The king then compelled him to sign a declaration that no god was superior to Śiva. Kūrattālvāṇ boldly contradicted him by telling him that "larger than Śiva was Drōṇa," (words which also mean two different measures, of which the latter was the bigger),¹ thus playing upon the double meaning of the words Śiva and Drōṇa. The king, enraged at the behaviour of Kūrattālvāṇ, ordered both his eyes to be put out immediately, and the order was forthwith carried out. So throughout the remaining part of his life he lived a blind man.²

Another important service which he rendered to his master was the conversion of Tiruvaraṅgattamudapār, the hereditary trustee of the Raṅganātha temple at Śrīrangam, to the Śrīvaiṣṇava faith. This neophyte made over the right of management of the temple to Kūrattālvāṇ, who in his turn handed it over to Rāmānuja. Highly pleased with the devotion of his dear disciple, Rāmānuja gave the *pauṛōhītya* of the temple and the right of reading the *Purāṇas* therein to the family of Kūrattālvāṇ.

Kūrattālvāṇ was the author of the *Varadarāja-stava*, *Sundarabāhu-stava*, *Atimānushya-stava*, *Śrīvaikunṭha-stava*, *Śrī-stava*, *Yamakaratnākara* and *Gadyatraya-vyākhyāna*.

Śrīvatsasihna Miśra had two sons, Parāśara Bhaṭṭa and Rāma Miśra.³ Of these the elder was the most distinguished scholar of the day; he was nominated to the pontifical seat by Rāmānuja, and, when he succeeded the latter, he was comparatively a young man. In a short time, however, he was able to convert to his faith a great Vēdāntin named Mādhava and made him his own disciple and successor under the name of Nañjiyar. He is believed by the Śrīvaiṣṇavas to have died at the early age of 28 and without issue; but there are weighty

¹ त्रिवारपरतरं नास्ति. द्रौणमस्ति ततः परम्-

² श्रीवत्सचिन्मिश्रेणैव नमस्तस्मिन्मीमांसे ।

यदुक्तयस्तथैव यानि सङ्गच्छन्ताम् ॥

मीमांसककुलाधीश श्रीवत्सादनुपास्यते ।

अयम् यतीन्द्रमिश्राचार्याय वेदान्तवेदिनाम् ।

³ Some Śrīvaiṣṇava chronicles assert that these were twins.

reasons for assuming that he lived for no less than 60 or 70 years.¹ The education of Parāśara and his brother was entrusted by Rāmānuja to Embār, his own cousin. Bhaṭṭar wrote the *Śrīraṅgarāja-stava*, *Śrīraṅgaratnakōśa*, *Sahasranāma-bhāṣya*, *Kriyādīpa*, *Aṣṭaśloki*, *Chatuśloki*, *Dvayaśloki* and *Tanīśloki*.²

Parāśara Bhaṭṭa, the elder son of Śrīvatsachihna Miśra, says the inscription, had a large number of disciples, of whom Vēdānta-vēdya was the most important. Vēdānta-vēdya is better known to the Śrīvaiṣṇavas as the 'Vēdāntin of the West country' (*mēl-nāṭṭu Vēdānti*). He was defeated in a religious wrangle by Parāśara Bhaṭṭa, whose devout disciple he soon after became, and he assumed holy orders, after which he was known as Nāṇḍiyar, meaning literally 'our jīya,' for he was so addressed by his guru. The name of this *sannyāsin* in his *par-vāraṇa* (that is, before he assumed holy orders) was Mādhava.

As soon as Parāśara Bhaṭṭa and Rāma Miśra were born, the god Raṅganātha commanded their father through the *archaka* (the performer of *pūjā*) to bring the children to His temple and bring them up there. They are therefore believed to be the adopted sons of the god Raṅganātha and his goddess Śrī.³ It is this faith of the Śrīvaiṣṇavas that is recorded in verse 35.

Vāgviṇya Bhaṭṭa was the son of Rāma Miśra,⁴ the brother of Parāśara. He is known to the Śrīvaiṣṇavas as Nāḍuvil Tiruviḍi Pillai Bhaṭṭar ("the Bhaṭṭa of the middle street"). He was the author of *Kṣhamāśhōḍaṣi*, and is hence called also *Kṣhamāśhōḍaṣi Bhaṭṭa*.⁵

¹ It is a well-known fact that Parāśara Bhaṭṭa was born some time before the Chōḷa persecution and the subsequent flight of Rāmānuja to the Hoysala country. I have shown in my History of the Śrīvaiṣṇavas (*Madras Review* for 1905) that Rāmānuja must have lived in the Hoysala kingdom for no less than 20 years, during which period Kūṛattālvān, who was blinded by the Chōḷa king, was living in Śrīraṅgam with his sons. On the return of Rāmānuja to Śrīraṅgam after the demise of the persecuting Chōḷa prince in A.D. 1118 the remaining third part of the *Śrībhāṣya* was finished. After this Rāmānuja lived for ten years; Parāśara succeeded him on the pontifical seat, vanquished the Vēdāntin of the West Country, taught him the Drāviḍa Vēdas, and, after the latter had made sufficient progress in them, ordered him to write the *Onpadiṇḍirappadi vyākhyānam* on the *Tiruvēdymoli*. The *Guruparamparā-prabhācam* of Piṅgalagiya-Jiyar (p. 210) states that Parāśara Bhaṭṭar lived as late as in the reign of Tribhuvanavira-Dēva, that is, Kulōttuṅga-Chōḷa III, who ruled from A.D. 1178 to 1216; and the author of the *Guruparamparā* referred to above was almost a contemporary of the illustrious Bhaṭṭar and is therefore likely to know about what he states in his work. Therefore we may rely on his assertion that the Bhaṭṭar lived at least down to some few years later than A.D. 1178, and therefore was more than 75 years when he died. The majority of the Śrīvaiṣṇava chronicles affirm that Parāśara Bhaṭṭar had no children, which appears to be the fact.

² पुत्रीकृती रङ्गपुरम्बरेश पराशरः कुरकुलप्रदीपः ।

मोचिन्दशिवस्य तु यामुनायमनोरथं पूरितवान् द्वितीयम् ॥

श्रीपराशरमहाय्ये श्रीरङ्गेशपुरोहितः ।

श्रीवत्सादधुन्यश्रीमान् श्रेयसे भिक्षु भूयसे ।

³ रङ्गेशजीतमयललाहितो यतीन्दकारणरसप्रदो ।

महार्थरामावयदशिकोत्तमो भवामि कुराधिपतेस्वरूपो ॥

⁴ पौत्रं श्रीराममिश्रस्य श्रीवत्सादधुन्य नन्दनम् ।

रामसूरिं [भजे] महपराशरवरानुजम् ॥

कुरेशनन्दनं वन्दे व्यासार्थं रङ्गवासिनम् ।

अनुराधे तु वैशाखे जातं श्रीरामसूरिं भजे ।

⁵ श्रीमहावैकुण्ठलक्ष्मणश्रीनिधिं प्रभुम् ।

श्रीरामसूरितनयं मेवै वाम्बिजयं युवम् ॥

कुरनायपुरोः पौत्रं श्रीरामार्थमियं सुतम् ।

वाम्बिजययुवं वन्दे वेदाचमयसंपदम् ॥

His son was Vēdavyāsa *alias* Sudarśana Bhaṭṭa. He studied the *Śrībhāṣya* at Kāñchī under Varadavishṇuvārya, the grandson of Naḍādūr Ālvāṇ (a nephew of Rāmānuja).¹ Varadavishṇu was better known as Naḍādūr-ammāḷ. He was a great exponent of the *Śrībhāṣya*, and his learning drew many earnest students to Kāñchī. One such was Vēdavyāsa Bhaṭṭa. This youth's unostentatious manners, his typical silence and apparent unsociability made him mistaken for a dullard. His colleagues could not perceive that all his thoughts were concentrated on his study and that he found little or no time for idle talk with them. But his teacher knew him very well. One day, when the students were assembled for the usual lecture, Naḍādūr Ammāḷ, who had also come early, would not proceed with his disquisition. He began it only after Vēdavyāsa Bhaṭṭa took his seat in the assembly. With a desire to show the real man to the audience, Ammāḷ feigned forgetfulness in the matter of an explanation which he had given some time back and asked each one of his students about it, but did not succeed in eliciting a reply; when Vēdavyāsa's turn came, he requested his *āchārya* to command him to give the interpretation as given by him (the *āchārya*) on any one particular occasion; for he had heard Ammāḷ twenty-one times. When questioned if he remembered the very language employed by Ammāḷ on those twenty-one occasions, he replied that he did. At the command of Ammāḷ he began to pour forth in the very language in which Ammāḷ had explained that particular point on so many previous occasions. The fellow disciples of Vēdavyāsa were dismayed at this extraordinary performance of the apparent dullard, and began to feel ashamed of themselves. As a matter of fact, this youth committed to memory every word of Ammāḷ, as it fell from his lips, and reduced it to writing the very same evening after the lecture was over. The work that grew in this manner was called the *Śrūta-prakāśikā*, and Sudarśana came to be known thenceforth by the name of Śrūtaprakāśikāchārya.² He was an elder contemporary of Veṅkaṭanāthārya, *alias* Vēdānta-dēśika. When he was very old, the vandalistic march of Malik Kafur swept over Śrīraṅgam, and in the onslaught that took place he perished.³

Sudarśana Bhaṭṭa had two sons, Vēdāchārya Bhaṭṭa and Parāśara Bhaṭṭa.⁴ Before his death Sudarśana Bhaṭṭa entrusted these sons and his valuable work the *Śrūta-prakāśikā* to the care of Vēdānta-dēśika with the request that they might be saved from the Musalman havoc. The latter carried out his promise so faithfully that to-day we owe the existence of this valuable

¹ "Nos. 471a and 505b contain the *Vasanta-tīlaka-bhāṣyam*, a drama by Varadāchārya. This author can be safely identified with the Vaiṣṇava teacher of the same name, who was the son of Dēvarāja of Kāñchī, and to whom the *Guruparamparā-prabhāṣam* attributes the two surnames Ammāḷāchārya and Ghaṭikaṣaṭam-ammāḷ. The first of these two names appears in the form Ambālāchārya in No. 595b, and a corruption of the second name is preserved in the colophon of Dr. R. Mitra's No. 116" . . . "Another drama by Varadāchārya is the *Chōḷa-bhāṣa*." *Rep. on Sans. MSS. in S. India* by Dr. E. Hultzsch, No. I, p. vii of the *Introductio*.

² श्रीवत्साहस्य नत्तारं पीथं रामविपश्चितः ।

व्यासं वाग्जयिनः पुत्रमन्त्राकं तातमाश्रये ।

यतीन्द्रकृतभाष्याद्यां वदन्त्यानेन दमिताः ।

वरं सुदर्शनार्थं तं वन्दे कूरकुलाधिपम् ।

शुभमकाममहायं श्रीरामायण्य पीथकम् ।

शाम्बिजयशूरोः पुत्रं वन्दे सद्गुणसामरम् ।

³ भाष्यप्रकाशिकां तां सङ्कटकाष्ठे सुदर्शनचूरिः ।

प्रादायकं कृतिने मेवे तं वेदभूषिकाशूरिः ।

Vēdāntadēśika-śrībhāṣya-prakāśikā, v. 131.

⁴ श्रीपरामर्शमहायं श्रीवत्साहस्यपीथकम् ।

वेदाचार्यानुजं वन्दे वेदाचार्यस्य नन्दनम् ।

gloss on the *Śrībhāṣya* to Vēdānta-Dēśika. Vēdāchārya Bhaṭṭa was the author of the *Ashṭākṣharadīpikā*, *Rahasyatraya* and *Tanidvayam*. Vēdāchārya's son was Śrīraṅgarāja Bhaṭṭar.¹

The *Periya Tiru-muḍiy-aḍaiem* assigns the following pedigree to the first great Parāśara Bhaṭṭar:—his son was Uddanḍa Bhaṭṭar; his son Parāśara Bhaṭṭar; his son Śrīraṅganātha Bhaṭṭar; his son Bhaṭṭa Parāśara; his son Śrīraṅga Bhaṭṭar; his son Sudarśana Bhaṭṭar; his son Śrīraṅgarāja Bhaṭṭar; his son Sādhu Bhaṭṭar; his son Tiruvēṅkata Bhaṭṭar.²

The grant was made on a Thursday, corresponding to the fifth *tithi* of the bright fortnight of the month of Chaitra, in the Śaka year 1280, computed by the moon (1), the eyes (2), the *nāgas* (8), and *nabhaḥ* (0).

Verses 28 to 33 describe the town of Śrīraṅgam, which is situated in the island formed by the two branches, the Kāvēri and the Kolliḍam, of the river Kāvēri. The image of the god Raṅganātha which is set up in the temple situated in this town is believed to have been originally worshipped by Brahmā and afterwards presented to the ancestors of Ikṣvāku and worshipped by his descendants. On the day of the coronation of the lord Śrī Rāmachandra he made a present of the image of his family god Raṅganātha to his faithful ally and dependant, Vibhishana, the brother of Rāvaṇa. While taking this valuable gift, Vibhishana inadvertently placed it on the ground in the island of Śrīraṅgam, where it stuck fast and could not be removed. It is over this image that the extensive temple of Śrīraṅgam is believed to have been built, and the composer of the *śāsana* alludes in our document to this faith regarding the advent of Raṅganātha to Śrīraṅgam.

"*Pāpiśṭha-Kṣhatrabandhuś cha*," one of the texts quoted in verse 43, occurs in the 17th chapter of the *Vishṇudharmā*. Kṣhatrabandhu was a very wicked king and had committed several sins; but just before his death he unwittingly uttered the three syllabled name, Gōvinda, of Viṣṇu, which virtuous act saved him from eternal perdition. In his *Tirumālai* the Vaiṣṇava saint Tondaradippodiy-ālvār also makes a reference to the story of Kṣhatrabandhu.³

The following are the names of places, etc., that are mentioned in the inscription under discussion:—Himāchala, Bhārata-varsha, the Mahārāṣṭra, Kāliṅga, Pāṇḍya, Kanyākubja and Teliṅga countries; Mañchikōṇḍa; Āndhra-dēśa; the Pāṇḍra, Kōṇa, Kuravāṭa and Ch(or)B(e)ṅgara provinces; the river Godāvart; Kōrukoṇḍa; Kōṭi; Tāḍipākā; the river Kāvēri; Śrīraṅga-purī; Kōṭṭāḷḷaperru in the Pāṇḍra country; Dēva; Villāru; Nāṅgipāṇḍi; Pennuṅkoṇḍa; Charakuvāṭaka; Tāmaravāṭaka; Monambaggu; Peḍḍlikāntaru-cheruvu; Groppuṅgāli and

¹ श्रीराजरमहादेवतनयं विनयीक्यजन् ।

रत्ननाथमुदं वन्दे महत्तायतनं सदा ।

रत्ननाथायतनयं श्रीमहेश्वराग्रम् ।

सततं कुरन्नाथस्य सर्वविद्यानिधिं भजे ।

² In all probability the Bhaṭṭa Parāśara of our document was identical with the Bhaṭṭa Parāśara, the son of Śrīraṅganātha Bhaṭṭa and the grandson of Vēdāchārya Bhaṭṭa; he is also called, in the extract given in footnote 4, the seventh from Kūranātha, that is, Kūratājavān.

³ *Mayita eal-eigaiyul-nāra māgr-eṭatt-aḍaiya pīrāl* ! *Kattirabandam-aṅṅi porāyadī koṇḍa koṇḍā* ! ("Has not Kattirabandha too attained the highest existence, being relieved from the powerful sins that were clustering thickly round him, by the three lettered name?"), *Tirumālai*, verse 4.

Uppungali and the Palēru-agrahāra. The following table gives the identification and situation of a majority of the places enumerated above :—

Name.	Mod. Name.	District.	Taluk.
Kōrukonda	Kōrukonda	Gōdāvari	Rajahmundry.
Kōṭi	Kōṭi	Do.	Do.
Tāḍipāka	Tāllapākam (?)		
Śrīraṅga-puri	Śrīraṅgam	Trichinopoly	Trichinopoly.
Koṭṭāllaparru	Kothalaparru	Kistna	Tannku,
Dēva	Duvva	Do.	Do.
Villūru	Vilturu or Vēḷatūr	Do.	Vinikonda.
Naṅgipūṇḍi	Neggipūḍi	Do.	Tanuku.
Penuṅgonḍa	Penukonda	Do.	Do.
Charakuvāṭaka	Cherukuvāḍa	Do.	Do.
Tāmaravāṭaka	Tāmarāḍa	Do.	Do.
Monambarru	Munamarra	Do.	Do.
Kāvēri river			
The river Vāsishṭha Gōdāvari	The river Gōdāvari or a tributary of it.		
Himāchala	The Himalaya mountains.		
Bhārata-varsha	The ancient name of India.		

TEXT.¹

[Metre of verses 1-2, *Vasantatilaka*; of 3-10, *Upajāti*; of 11, *Indravajrā*; of 12, *Upajāti*; of 13, *Upēndravajrā*; of 14-15, *Upajāti*; of 16, *Upēndravajrā*; of 17, *Vasantatilaka*; of 18-22, *Upajāti*; of 23, *Vamśastha*; of 24, *Upajāti*; of 25, *Śardūlavikrīḍita*; of 26, *Upajāti*; of 27, *Rathoddhata*; of 28-29, *Anuṣṭubh*; of 30, *Vasantatilaka*; of 31-32, *Upajāti*; of 33, *Rathoddhata*; of 34, *Sragdharā*; of 35, *Śardūlavikrīḍita*; of 36-37, *Anuṣṭubh*; of 38, *Śardūlavikrīḍita*; of 39-49, *Anuṣṭubh*; of 50, *Indravajrā*; of 51, *Anuṣṭubh*; of 52, *Giti*; of 53-58, *Anuṣṭubh*; of 59, *Mālinī*; of 60, *Anuṣṭubh*; of 61, *Śalini*; and of 62-63, *Anuṣṭubh*.]

First Plate: First Side.

- 1 श्रीरंगराजाय नमः ॥ यां द्यूतकेलिविजितात् दयितात् मृद्घीतामिंदीकक्षा-
मितर-
- 2 दंतपदे निवेष्ट । प्रेम्णा प्रसादयति पुचमुमेकदंतं सा चा-

- 3 यतां गजमुखः स च तौ शिवौ च ॥[१*] श्वेतः शुभं दिशतु शशदसौ
वराहः पातालसङ्घनि तमोगहने रहो यः [१*]
4 [श्री]सुक्कमंनधृतिरुहहनीसवात् प्राक्^१ दंतेन किंचिददुनोदधरं धरायाः ॥[२*]
तदाख्ययैव प्रथितेव कल्पे
5 मन्वंतरे सप्तम आगतेस्मिन् । बहुष्वतीतेषु चतुर्युगेषु कलिं विदुः संप्रति
वर्तमानं ॥[३*] हिमा-
6 बलादालवणोदमेतत् खंडं भुवो भारतवर्षमाहुः । तत्रापि चैतत्^२ भरतस्य
खंडं चर^३-
7 ति यत्रात्रमवर्णधर्माः ।[४*] पञ्चापुरस्तादपि यस्य देशौ स्यातौ महा-
राष्ट्रकलिंगसंज्ञौ ।(१)
8 अवागुदक् पांड्यककन्यकुक्षौ देशस्य तत्रास्ति तिलिंगनामा ।[५*] तदी-
श्वरः केशमिनायकोभूदभूतपूर्वा-
9 हु^४तवाहुसारः । वृत्तानि यद्वर्तनदर्पणेच्छे रात्रामलक्ष्यंत पुरातनानां ।[६*]
मुक्कंटीनामा नृप-
10 सार्वभौमो गंगातटांतात्किल यस्य पूर्वो । पुरा तिलिंगान् प्रति मंचि-
कोडावानाययन्

First Plate : Second Side.

- 11 नायकवंशमुख्यौ ।[७*] ताभ्यां विनिर्मापितमात्मनाम्ना पुरं महच्च प्रवि-
तेंधदेशे ।(१) तदुत्तमं विभ्रति मं-^५
12 चिकोडगोचं सगर्वा भुवि यस्य वज्राः^६ ।[८*] तस्मिन्नतीते^७ तनयस्तदीयो
गुणैः प्रतीतो गणपाभि-
13 धानः ।(१) भुजंगमाधीश्वरविश्रमाय भारं पृथिव्या विभरावभूव ॥[९*] देवो
नृपेस्मिन्सति युक्तवर्षी चेवा-
14 ख्यभूवन् फलवत्तराणि । न श्वापदेभ्योप्यटवीषु शंका मलिम्लुचेभ्यः किमु-
ताड्यगा-
15 नां ।[१०*] तस्मात्समुद्रादिव शीतरश्मिः कुनाभिधानः कुलकेतुरासीत् ।
आरोप्य सिंहा-
16 सनमात्मजं स्वमैद्रं स सिंहासनमाकरोह ।[११*] धीरो वदान्यो विनयोप-

^१ Read प्राग्दतेन.

^२ The anuvāsa begins the next line.

^३ The anuvāsa of mamekai begins the next line.

^४ Read तस्मिन्.

^५ Read शीतरसः.

^६ Read हु.

^७ Read वज्राः.



32
 34
 36
 38
 40

42
 44
 46
 48
 50

52
 54
 56
 58
 60

- 17 पञ्च[*] प्राज्ञः प्रतापी सुलभप्रसा[द]: । स्थिरोभिगम्यो बलवानष्टथो
नवोपि सोभू-
18 त्वरधूम्भधर्षः ।[। १२*] चिरं बलात्कारक[द]त्विताभ्यां पराक्षुखीभ्यां पुष-
यांतरेभ्यः ।(।)
19 गुणी गुणैरेव वशंवदाभ्यां स्वयं हतो यो वसुधारमाभ्या ।[। १३*]
तदात्मजो मुंम-
20 डिनायको[स्ति] प्राज्ञस्त्वमगो बलपौरुषाभ्यां । पुत्री पिताभूत् स्ववशेन येन
वीरेण वीरप्रस-

Second Plate : First Side.

- 21 वा च माता ।[। १४*] कन्या स्वसुः कापयनायकेंद्र[*] स्त्रीरत्नभूतामुपदाय^१
तस्मै । प्रतीतरूपान्वयपौरुषा-
22 य परार्थमात्मानममन्यत स्वं ।[। १५*] स संमतो मुंमडिरुत्तमानामिरं-
मदो वैरिनरा[धि]पा-
23 नां । त्रियं पितृशासनयंचणेन बलादनिहंनपि^२ चान्वमंस्त ।[। १६*]
पानारकोनकुरवाटकचेंगरादीन्
24 गोदावरोमुभयतीयमुपांतदेशान् । जित्वा वनाचलजलस्त्रलदुग्धैरम्या^३-
25 नेकः प्रशास्ति चिरमप्रतिशासनं सः ।[। १७*] चेमंकरा ये वसतां
जनानां पश्यव्या-
26 शोयवसाभिरामाः । पुंसां वणिज्वाक्यपाशुपात्मान्यत्यर्थमाश्वक-
27 रणानि यत्र ।[। १८*] येष्वप्रयासोऽयम[द्वा*]फलानि चेत्तत्र शालीक्षुव-
शीचिता-
28 नि । कडंकरीया अपि नव यत्र कृतः प्रसंगस्तु भलिस्तुवानां ।[। १९*]
येषु प्रतिग्राममबंध्यपूगास्त्रनागवल्लीसह-
29 काररंभाः । आरामभागास्तुवते वसुनि पक्षैटकावध्वसुसिध्वकूपाः^४ ।[। २०*]
तदीशितुर्द्वारवतीव विष्णोरस्ति प्र-
30 शस्ता भुवि राजधानी । या कोरुकीडा व्यपदिश्यतेभ्रेरायैः पुराविद्विषदश-
शैला ।[। २१*] वकास्ति सालः प-

Second Plate : Second Side.

- 31 रितः पुरो यां पृथ्वी विशालामिव चक्रवाहः । हस्त्यश्वयोषापुरुषादि-
कायास्त्रद्रवसृष्टेरिव गु-

^१ Read दु.

^२ Read दनिच्छत्रपि.

^३ Read ज.

^४ Read मुपदाय.

^५ Read स्त्रलदुग्धै.

^६ Read वदसुसिध्व.

- 32 सिकोशः ।[२२*] सृदंगधोरैर्मदहस्तिर्बृंहतेस्तुरंगहेयैः करणोपशोभिभिः ।
सुरक्तगीतैरपि वं-
33 दिमंगकैर्नृपत्रियो नर्तनशालिकेव या ।[२३*] पुरे च कोट्यां पुरि ताडि-
पाकेप्यात्मातुजौ शिंगयगन्धयाख्यौ । शा-
34 खानगयोर्हभयोर्निधाय वीरस्य तां रक्षति राजधानीं ॥[२४*] संनत्वा
निजमंगसुत्तम-
35 मलंकृत्य युतेन युती सत्येनाननमार्जवेन हृदयं त्यागेन हस्तावुभौ । वीरः कू-
36 न्धमुंमडिचितिपतिर्दत्तांगभूषस्य तामाकल्पं समवेक्षते नवमसावं-
37 तयशोदर्पणं ।[२५*] बहिः पतंगोपलशीतलस्य गूढप्रतापस्य मनीग-
तिज्ञाः । त-
38 स्तोध्वनं^१ व्यालमिव चितीया विलंघितुं शासनमुद्दिजंते ॥[२६*] अ[र्य]सि-
धिमधिगम्य नोतिमान्काम-
39 मध्यनुसरन् यथोचितं । स चिवर्गसमवृत्तिरास्तिको धर्ममार्जयति धर्मतत्ववित्
॥[२७*] शोमतो सुष-
40 मा भाति रंगनामनि धामनि । कावेरीमुभयो पुष्पामंतरानंतशायिनी
॥[२८*] पुरा तत्परमं ब्रह्म [ब्रह्म*]-

Third Plate : First Side.

- 41 [शो] गृहदेवतं । तदनंतरमिच्छाकोस्तपसच फलायितं ।[२९*] अथ विश्व-
निदानमायताक्षं प्रथमा-
42 नं युतिमस्तकैरश्वैः । [द्र]मिडामितवागधेयमासीत्कमलालालितपादपद्मवं
तत् ।[३०*] पाका-
43 वदातैः फणिवलिपवैस्त(स)वर्णचूर्णैः[*] क्रसुकैस्तसारैः । नवैरुपस्थो^२वसपुष्प-
माल्यैश्चायं
44 च सायंतनमालिकाभिः ।[३१*] लवंगतकीलकजातिकेशकस्तूरिकैलागवसार-
45 मुख्यैः । सुवस्तुभिष्कांकवकु^३कुमादीर्या भोगिनामैहिकभोगभूमिः ।[३२*]
46 या चतुर्गुणकलाभिरैदवो मंडलो जयति निर्भरा सती । सूरिवर्गमपव-
47 र्गतत्परं स्यतेपि च , पुराणपूकवात् ।[३३*] तस्यां श्रीरंगपुर्यामधिधरणि-
जनत्रा-

^१ The anusvara of वंदि begins the next line.

^२ Read °सिद्धि°.

^३ Read स्त्री.

^४ Read °स्रीपद्म°.

^५ Read °मा°.

^६ Read °वसुमीराहव°.

- 48 तरलैकहेतोराविभूतस्य विष्णोरनवधियग्रसोनन्यसामान्यकृत्यं पौरोहित्यं, भजन्
यो ह-
49 रितकुलमणिवैदवेदांतविज्ञो नास्मा श्रीवत्सचिह्नो गुरुरभवदध्वंसिधि'व्यावता-
50 रः ।[३४*] तत्पुत्रो भुवि दत्तपुत्रविभवं श्रीश्रीशयोः प्राप्तवान् श्री-
भट्टपरशरो गुरुर-

Third Plate : Second Side.

- 51 भूयत्पादसंसेवनात् । स्वेपां श्रीचरणंबुजं श्रितवतां शिष्यप्रशिष्यादयो
विष्णोस्त-
52 त्परममं पदं विध(द)धते वेदांतवेद्यादिकाः ।[३५*] तदादि समपुरुषं कुलं
श्रीशंशसंभवं^१
53 । इति ख्यातं हि तत्पुत्रो विद्वान् भट्टपरशरः ।[३६*] स वेदाचार्यभट्टा-
र्यप्रमुखैर्वाधवैरभा-
54 त् । परस्परैकद्वयैर्वेदो वेदैरिवापरैः ।[३७*] तदंशंबुधिसंभवः कुवल्या-
55 मोदो कलानां निधिर्भूदेवास्तदायकीभ्युदयवान् स्वान्तस्वकृष्णा-
56 कृतिः । नित्यं विष्णुपदाश्रितोखिलतमस्तापापहंताप्यहो श्रीमद्-
57 ट्टपरशरो गुरुरभूत्तत्वेव दोषाकरः ।[३८*] कावेरीलहरीवातनोतश्रीतलश्रीक-
58 रैः । सित्तः[*] श्रीरंगभोगेषु सक्तस्त्रीखासिकां भजन् ।[३९*] दय-
मानमना[*] श्रीशो देशानंधान् स र-
59 क्षितं । तं पराशरभट्टार्यमनैषोदात्मशक्तिकं ।[४०*] निसर्गतस्त्रिवर्गः[*]
स्यादनित्याद्यगुणान्वितः । सत्याद्यु-
60 पायास्त्रापाया इतिनिश्चयसप्रदं ।[४१*] तच्चान्नयंत तं धन्या यत्पदस्त्वै-

Fourth Plate : First Side.

- 61 भवात् । स्वयमाचार्यकं प्राप्य दिग्भ्यां कीर्तिमतानिषुः ।[४२*] पापिष्ठः चच-
बंधुषेत्यादिवाक्य-
62 तश्चूते^२ । तस्य पादाश्रिता भूत्वा भूपाः प्रादुरनेकशः ।[४३*] ग्रामा-
रामो-
63 वरारक्षाभरणाद्यात्मना सह । स मुंमडिमहीशोपि तमिमं गुरुमाश्रयन् ।
[४४*] को-

^१ Read दि.

^२ Read चूते;

^३ The answer of चूते begins the next line.

- 64 शङ्खपङ्क्तिनामानं ग्राममाचार्यदक्षिणां । श्रीपराशरभट्टाय प्रादात् स्व-
 65 गुरवे सुधीः ।[४५*] स पराशरभट्टार्यो जननीदैवतो भवन् । रंजी-
 शाय कुलेशाय प्रा-
 66 दादासीन्महर्षिपदाः ।[४६*] तस्य माता जगन्माता नाम्ना सर्वगुणे-
 रपि । न केवलं शरीर-
 67 स जनन्यप्यात्मनो हि सा ।[४६*] समाप्य सप्तमे तस्मिन्नवतारप्रयो-
 जनं । श्रीपरा-
 68 शरभट्टार्ये श्रीशभो गोपयोगिनि ।[४८*] स्वजनानाम्प्रदानानि स्वविभूतेर्विधि-
 त्तया । आदौ सर्ववि-
 69 धी बंधू रंगशायीति निश्चयात् ।[४८*] ऐश्वर्यभोगैर्युतमष्टसंख्यैश्चर्वसहाराम-
 70 ष्टहोर्वराभिः । श्रीरंगराजाय तु सा व्यातारीत् कोटशङ्खपङ्क्तिमयहारं ॥
 [५०*] [शक]वर्षे न-

Fourth Plate : Second Side.

- 71 भोनागनेचेदुगणिते शुभे । चैत्रमासि शुचौ पक्षे पंचम्यां गुरुवासरे ।[५१*]
 सप्तमभष्टप-
 72 राशरजननी श्रीरंगवर्धनाद्याप्तं । मुंमडिनायकनाम्नोयं ग्रामं रंगशायि-
 73 ने प्रादात् ।[५२*] एष्यत्भूप्रत्ययार्धे तस्य लक्षणमुच्यते । अविदूरस्थ
 वासिष्ठ-
 74 गोदावर्यास्तु पश्चिमः ।[५३*] कोटशङ्खपङ्क्तिनामायं ग्रामः पानारभूमि-
 [ग]ः ।
 75 तस्याष्टदिग्गतग्रामसंनिवेशो निरूप्यते ।[५४*] देवाख्यः पूर्वदिग्भा-
 76 गे कोणे दूरादसंटकः । विष्णुर्दक्षिणः कोणे मारदेर्न-
 77 गिपुंडि च ।[५५*] पश्चिमे पेनुकोडाख्यः कोणे चळीकुवाडकः ।
 उत्तरे मीन-
 78 बर्हि स्वात्कीणे तामरवाडकः ।[५६*] स्वात्कीकुंतुचेळु मर्हिराम्नेयसी-
 सतः । [मो]-
 79 पुंगुवायुपुंगुगालिच बर्हिर्दक्षिणकीर्णतः ।[५७*] श्रीशहायव्यसीमानं पेम्गो-
 डचेव-
 80 कीर्णकः ।(१) शेषाखेदविशेषा हि सीमानः ।[५८*] अष्टदर्शनाः ।[५८*]
 सर्वेष्वेवप्रमाणं चेद्व्यु-

* Read 'शङ्खपङ्क्ति'.

* Read 'स'.

* Read 'पङ्क्ति'.

* Read 'शङ्ख'.

* Read 'भूप्रत्ययार्धे'.

[illegible]

72
74
76
78
80

106.

72
74
76
78
80

92
 94
 96
 98

Fifth Plate : First Side.

- 81 त्तराशीतिस्वारिकाः । [। ५८*] इति सुविदितपाक्रेणहारस्य लक्ष्मीचिति-
निजपतये प्रच्छपितस्याम्-
82 सिध्वे ।¹ विदधतु विभविष्यद्भूमिपाशासनं त्रीचितिघनकरणायै काल-
83 माचंद्रतारं ॥[५९ ॥*] सर्वदेशदशाकालेष्वव्याहतपराक्रमा । रामानुजार्य-
दिव्यज्ञा वर्त्तता-
84 मभिवर्धतां ॥[६० ॥*]
85 सामान्योयं धर्मसेतुवृणां काले काले पालनिष्यो भवध्मिः² सर्वानि-
86 तान्माविनः पाञ्चिवेद्राभूयो भूयो याचिते³ रामचंद्रः ।[६१ ॥*] स्व-
87 दत्तादिगुणं⁴ पुण्यं परदत्तानुपालनं । परदत्तापहारेण स्वदत्तं निष्यलं⁵
88 भवेत् ।[६२ ॥*] एकैव भगिनो लोके सर्वेषामेव भूभुजां । न भोग्या
न करयाद्या विप्रदत्ता वसुं[ध]-
89 रा ॥[६३ ॥*]

ABSTRACT OF CONTENTS.

Verse 1. Invocation to Śiva, Pārvatī, Gaṇeśa and the Moon.

V. 2. Invocation to Śveta-Varāha, the third incarnation of Viṣṇu.

V. 3. States that the present age is known as the Kali Yuga.

V. 4. States that the portion of the earth stretching from the Himālayas to the southern ocean is called the Bhārata-varaha.

V. 5. Gives the boundaries of the Teliṅga-dēśa situated in the Bhārata-varaha, as follows:—On its north is the kingdom of Kanyakubja, on the south the Pāṇḍya country and on the west the Mahārāṣṭra.

V. 6. The Teliṅga country was once ruled over by a king named Kēśami Nāyaka.

V. 7. His two ancestors, who belonged to a family known as the Mañchikonḍa family, were originally brought down to the Teliṅga country from the Gangetic valley by a king named Mukkaṇṭi.

V. 8. These two founded the city of Mañchikonḍa after their names, and their descendants were also known as of the Mañchikonḍa gōtra.

Vv. 9-10. On the death of Kēśami Nāyaka his son Gaṇapa ascended the throne.

Vv. 11-13. Gaṇapa was succeeded by Kūna.

V. 14. Mummadi Nāyaka was the son of Kūna.

V. 15. He married the daughter of the sister of Kāpaya Nāyaka.

¹ Read 'सिध्वे'.

² Read पाञ्चिवेद्राभूयो.

³ Read निष्यलं.

⁴ Read व.

⁵ Read द्वाचिते.

⁶ Read पाञ्चनीवी भवति:

⁷ Read 'द्विगुणं'.

V. 16. Though personally unwilling to assume the burden of his kingdom, he did so in deference to the wishes of his father.

Vv. 17-20. He conquered the countries of Pānāra, Kōna, Kuravāṭa, Cheṅgara and others lying on either bank of the river Gōdāvarī. He ruled over his vast kingdom for a long time, and under him the people were in a very prosperous condition.

V. 21. His capital was Kōrukonda.

Vv. 22-23. Description of the capital town.

V. 24. King Mummaḍi allowed his younger brothers Śiṅgaya and Gannaya to govern the principalities of Kōṭipura and Tāḍipāka respectively.

Vv. 25-27. Praises of king Mummaḍi. He seems to have had many vassals under him.

Vv. 28-33. Here the narrative turns from Mummaḍi to the island of Śrīraṅgam and the deity presiding over its temple, namely the god Raṅganātha.

V. 34. Begins with the genealogy of the donee, Parāśara Bhaṭṭa. His ancestor Śrīvatsachihna Miśra was born in the Hārīta gōtra and was a very learned man and held the *paurohītya* in the temple of Raṅganātha.

V. 35. His son was Bhaṭṭa Parāśara, and he had many disciples, of whom the most illustrious was Vēdānta-vēdya.

V. 36. His son was also called Bhaṭṭa Parāśara.

V. 37. One of the illustrious relatives of Bhaṭṭa Parāśara was Vēdāchārya Bhaṭṭa (that is, the brother of the first Parāśara Bhaṭṭa).

V. 38. In the family of Parāśara Bhaṭṭa was born a learned and pious *guru*, also named Bhaṭṭa Parāśara.

Vv. 39-42. This person went on a tour to the Āndhra country, where many learned Brāhmaṇas became his disciples.

Vv. 43-45. Here several kings gave him rich presents such as gardens, wet lands, jewels and precious stones. King Mummaḍi Nāyaka also presented him with the village of Kōṭṭāḷlaparru.

Vv. 46-50. This *achārya*, having finished the mission of his human existence, went to enjoy the company of Viṣṇu (i.e. died). His mother Jaganmātā wanted to give away the property to her relatives; but, thinking that Śrīraṅga-nātha was her truest and nearest relative, made a gift of the village of Kōṭṭāḷlaparru to that god, with all her other belongings, such as gardens, houses, etc.

V. 51. This gift was made on a Thursday, the fifth *tithi* of the bright fortnight of the month Chaitra in the Śaka year 1280, expressed by *nabhaḥ* (zero), *nāga* (the mountains), *nētra* (the eyes) and *iṇḍu* (the moon).

Vv. 52-58½. The boundaries and other descriptions of the village of Kōṭṭāḷlaparru are given as follows:—

The village is situated in the Pānāra country to the west of the Vāsishṭha Gōdāvarī. It is bounded on the north by Monambarru village, on the east by the village of Dēva, on the south by Viltūru, on the south-west by Nāṅgipūṇḍi and on the north-west by the village of Charukuvāḍaka.

Vv. 59½-63½. The usual admonitory verses.

No. 4.—THE PORUMAMILLA TANK INSCRIPTION OF BHASKARA BHAVADURA : SAKA 1291.

By Dr. V. S. Suktankar, Ph.D.; Poona.



The position of the inscribed stones on the tank-bund.

Inked estampages of the subjoined inscription, which commemorates the construction of a tank, were prepared by the Madras Epigraphical Department in 1903, and it forms No. 91 of the Epigraphist's collection for the year 1902-3. It was briefly reviewed in the Annual Report on Epigraphy for 1903, and it has also received a short notice in an article by the late Mr. Venkayya entitled: *Irrigation in Southern India in ancient times*.¹ The record is incised on two slabs, one smaller than the other, set up in front of the ruined Bhairava temple at Porumāmilla in the Badvel Taluk of the Cuddapah District, situated in 15° 1' N. and 79° E. The latter district being very dry, cultivation is in general only possible with the help of artificial storing of water. The irrigation tank at Porumāmilla is, according to the District Manual, one of the largest in the Taluk. The inscription, apart from its historical importance, presents various other points of interest, not the least important of which is the light it sheds on the tank-building activity in ancient India.

As regards orthography, the inscription follows the same system which is to be observed in other inscriptions from the Telugu and Kanarese Districts. A superfluous anusvāra is inserted (1) before a nasal+consonant, as in *pumya* ll. 13, 46; also in ll. 19, 36, 89; (2) before a +consonant, as in *Vijayāmhvaya* ll. 34, 35; also in ll. 57, 65; (3) before *nn* as in *vijayōnnatāḥ* l. 36; (4) before *rm* as in *karma* l. 82. We find also the doubling of a consonant after an anusvāra in *chamcha* l. 18. As in other inscriptions, we notice the mixing up of the two forms of visarga-sandhi, as in *taḥṣaṣmya* in l. 23; also in ll. 29, 83, etc.; and the writing of *tth* for *tt* in *ṛththana* l. 100, and of *jhjh* for *jhh* in *ṣāyḍjhjhita* l. 12. Other examples of

¹ See the Director-General's Annual for 1903-4, Part II., pp. 202 ff. — A resumé of the contents of the inscription is included in the new edition of the *Cuddapah District Gazetteer*.

incorrect orthography are the following : l. 113 *ru* for *ri* ; l. 39 *ri* for *ru* ; confusion of the sibilants *ś* and *s* in ll. 20, 22, 29, 37, 52, 54 and 95 ; *ṇ* for *ṇṇ* in ll. 66 and 83 ; confusion of *ḍ* and *ḍh* in ll. 51, 104 and 109 : sporadic adscript of *y* to an initial vowel as in *yēṭad* (for *ēṭad*) l. 21, *yēk-aiva* (for *ēk-aiva*) l. 105. The aspirates are sometimes distinguished from similarly shaped non-aspirates by means of a short vertical stroke added below the letters, as in the modern Telugu alphabet. There is inconsequence in the doubling of consonants after *r* : cf. ll. 7, 10, etc. on the one hand, and ll. 6, 16, etc. on the other. Rough *r* (doubled) is used once in the nomen proprium *Dēvarājya* (l. 109). It remains to be remarked that the letters are incised between equidistant parallel lines running along the breadth of the slabs.—It is necessary to add a few words on the language of the inscription. Excepting the benedictory words at the beginning of the record and a few phrases employed further on to introduce some of the stanzas, the whole of the inscription is in verse. The language is extremely meagre Sanskrit, and the verses are devoid of poetic embellishment. The writer is indeed guilty of the gravest mistakes of grammar and syntax, most of which are noticed in the foot-notes to the text and translation. To mention just two of them here : in l. 37 *ḍiśi pūrṇa pratishṭhitāḥ* is used for *ḍiśi pūrṇasyāṁ pratishṭhitāḥ* ; and the first sentence of v. 16 the *verbum actionis* is omitted.—In respect of lexicography the following uncommon words and expressions deserve notice : *kr̥ti* (ll. 29, 39) = " composition " ; *taḍāka-mātrikā* (l. 47) = " tank-nourished ", on the analogy of *nadi-mātrikā*, etc. ; *bhramā-jala-gaṭi* (ll. 69, 90) = " sluice " (?) ; *madhya-kārma* (l. 73) = " elevated ground in the middle " (?) ; *bhū-vara* (l. 79) = " king " ; *gāṅgāya* (l. 111) = " gold ".

The object of the record is, as remarked above, to commemorate the construction of the tank at Poramāṁḷla by king Bhāskara alias Bhavadūra, son of Bukka I. (v. 49). The following analysis gives a synopsis of the contents of the record : The grant commences with invocatory and introductory verses (vv. 1-10) : the succeeding stanzas give the genealogy of the donor, Bhāskara Bhavadūra (ll. 11-22) : the next few verses recount the merit attaching to the building of a tank (23-27) : then are given the details of tank construction and the specification of the site of the tank, date of its construction, etc. (28-45) : then the usual imprecatory and benedictory stanzas (46-49) : and lastly, the specification of the *adhikārī* of the tank, and the composer of the record (59-62). The only new facts in the history of the First Vijaya-nagara Dynasty¹ with which the inscription furnishes us are the following : (1) Bhāskara alias Bhavadūra (a name which is not known from any other inscription) was the son of Bukka I., and thus the brother of Harihara II. Bhāskara was placed in charge of the eastern provinces—which he ruled from the " top of the sublime Udaya-giri " (in the Nellore District) ; (2) Bukka I. had four brothers, viz. Harihara, Kampana, Mārpa and Muddapa ; and (3) Anantarāja was one of the ministers of Bukka I.—The *adhikārī* of the tank was Dēvarājya, son of the minister (probably of Bhāskara) Kumāragiri-Nātha (v. 50).—The writer, who was rewarded with a gift of land, was the poet Liṅgaya-Māchanāryya (i.e. Māchana, son of Liṅgaya) of the family of the Kaṭṭas, resident of Nāṁda-pura (v. 51). On completion of the tank lands under it were handed over to a number of Brāhmaṇas (v. 45).

The question of the construction of the tank is shrouded in some obscurity on account of the unintelligibility of the termini used in the description of the tank.² It would be, therefore, as well to start with the facts regarding the tank as it now stands. I have been able to gather the following information through the kind courtesy of Mr. Banerji, the Collector of Cuddapah,

¹ A succinct and connected account of the facts in the history of this dynasty, gleaned from stone and copper-plate records, is furnished by Rao Sahib Krishna Sastri in his paper entitled " The First Vijayanagara Dynasty ; its Viceroys and Ministers." (See the *Director-General's Annual* for 1907-8, Part II., pp. 235 ff.)

² To Rao Sahib Krishna Sastri I am indebted for the explanation of several of the technical expressions.

whom I had addressed on the subject.¹ The tank, which is situated about two miles (and as the inscription also tells us) to the east of the village called Porumāmilla, is elongated in shape, being some 7 miles long and $2\frac{1}{2}$ miles broad. The bund consists of four natural hills connected by three short earthen dams, rivetted with Cuddapah slabs. The western flank thus consists of practically the range of hills which runs north and south between Porumāmilla and Badvel. The total length of the artificial bund is about 4,500 ft.; the total length including the hills is about 14,000 ft. At the deepest section the bund is about 12 ft. wide at the top and 150 ft. at the bottom, and about 33 ft. deep. The tank has two sources of supply, one natural and the other artificial. The latter was constructed about 20 years ago. The natural feeder is a stream called the Maldāvi river.—The reservoir is provided with four sluices, two of which have been repaired in recent times and provided with screw-gear, and there are five weirs. This is the actual condition of the tank at present.

From the inscription we learn that in the twelfth century of the Christian era tank-building was looked upon as one of the seven meritorious acts which a man ought to perform during his lifetime. The tank at Porumāmilla was called Anantarāja-sāgara. It is also stated that for two years 1,000 labourers were working daily on the tank and the dam; and 100 carts were engaged in getting stones for walls which formed a part of the masonry work. The dam was 5,000 *rēkhā-danḍas* long, including the hills, 8 *rēkhā-danḍas* wide, and 7 high. Besides, the author gives us the twelve *sūkhanas* of the Porumāmilla tank, and six *dāshas* of tanks in general. Much of this latter is clothed in very obscure language. Nevertheless with the help of the description of the tank given in the previous paragraph we are able to get a fairly clear notion of what the author wishes to convey.² In the *chatur-bhramā-jala-gatī* we have a reference to the four sluices; and in the range of hills forming the western flank of the tank we must look for an explanation of remarkable phrase *tadyōga-khamḍō giriḥ*. Again, as the Maldāvi river ends at the tank, the *triyōjana* must needs refer to its length from the source to the point at which it enters the tank.—One fact which may be gleaned from the measurements of the tank preserved in the record is of no small significance. Knowing as we do the dimensions of the bund, in terms of the *rēkhā-danḍas* as well as in feet, we are in a position to compute the equivalent of this standard of linear measurement current in the Telugu District in the 14th century. For this purpose it would be safest to compare the values for the height of the bund, which, I imagine, would offer the least variation. In the above-mentioned Report of the Collector, 33 ft. is quoted as the height at the deepest section of the bund. Taking, now, 20 ft. as the minimum height for the bund of any large tank of that size, the average height of the bund in feet works out to be $(20+33) \div 2 = 53/2$ ft. This must roughly correspond to the 7 *rēkhā-danḍas* of the inscription. The equation will be $53/2 = 7$, and this gives us roughly $1\frac{1}{4}$ yard as the equivalent of the *rēkhā-danḍa*, which, by the way, corresponds approximately to the distance from the tip of the shoulder of one arm to the tip of the middle finger of the other arm, measured along the chest, for an average man. I mention the latter fact, as it is well known that in primitive times a standardised (but locally varying) value of the lengths of portions of the human body served as units of length; cf. the Indian measures *anguli*, *hasta*, *danḍa*, and the European foot.³

One other feature of this record deserves mention here. Early in the beginning of the inscription (vv. 1-3) we find enumerated the characteristics of an edict (*śāsana-lakṣaṇa*), which include hints on composition and the significance of the metrical foot (*gana*) with

¹ Some time ago, when I visited the site of the tank, I took the opportunity of verifying and correcting the statements in this report. Some few fresh observations which I made on the spot have also been embodied in the succeeding remarks.

² See notes 6-8 on p. 108 and 1-2 on p. 109.

³ Expressed by the chronogram *śāśa-namdy-śāśy-śā*, and in numerical symbols.

which a *sāsana* commences (v. 2). The latter is a curious specimen of superstition: the *gana* ma (— — —), when standing at the beginning of a *sāsana*, secures bliss; na (○○○) in the same position secures wealth, etc. Further we learn that in a faultless verse the *visarga* should stand at the end of the complete stanza and not at the end of the first half (v. 3)!

The inscription is dated on the 14th of the bright half of the month of Kārttika, in the cyclic year Saumya, corresponding to Śaka 1291 (expired) and Kaliyuga 4470. There is some doubt as to the week-day. The syllables *guru* in l. 58, which evidently introduce the name of the week-day, are clear enough; and the following letters must be read as *pushya*, as the vertical stroke between the aksharas *ru* and *pu* is nothing but an accidental depression in the stone. In that case it would seem that the week-day was Thursday, and the *nakshatra* Pushya. But Dewan Bahadur Swamikannu Pillai, whom I had addressed on the subject, informs me that the *tithi* ended on Monday, the 15th October, A.D. 1389, at about 7 *ghaṭikā* after mean sunrise; and the *nakshatra* for that day was Āśvinī, which came to an end about 47 *ghaṭikā* after mean sunrise.

For purposes of orientation the localities Śrī-parvata (i.e. Śrī-sailam), Ahōbala, Siddha-vaṭa, Udaya-giri and Porumāmilla are mentioned. Of these only Siddha-vaṭa needs to be specially noticed here. Its denomination in the inscription is *deśaka*, i.e. subdivision of a country: therefore the name could well be, I think, linked with the modern *Taluk Siddha-vaṭam* in the Cuddapah District, the boundary of which is not far removed from the site of the tank.

A reference to Hēmādri's *Dānakhaṇḍa* (which is undoubtedly what is meant by *Hēmādri-kṛtī* in l. 39) shows that that work enjoyed the reputation of an authority in the Telugu country at the beginning of the 14th century of the Christian era.

TEXT.¹

[Metres: v. 1, *Anuṣṭubh* (Śloka); v. 2, *Śārdūlavikṛīḍita*; vv. 3-4, *Anuṣṭubh* (Śloka); vv. 5-7, *Śārdūlavikṛīḍita*; v. 8, *Mandākrāntā*; vv. 9-10, *Anuṣṭubh* (Śloka); v. 11, *Śārdūlavikṛīḍita*; vv. 12-13, *Anuṣṭubh* (Śloka); v. 14, *Upajāti*; vv. 15-36, *Anuṣṭubh* (Śloka); vv. 37-38, *Śārdūlavikṛīḍita*; vv. 39-40, *Upajāti*; vv. 41-43, *Anuṣṭubh* (Śloka); 44, *Śārdūlavikṛīḍita*; v. 45, *Anuṣṭubh* (Śloka); vv. 46-47, *Śalinī*; vv. 48-50, *Anuṣṭubh* (Śloka); v. 51, *Śārdūlavikṛīḍita*; v. 52, *Anuṣṭubh* (Śloka).]

First stone.

- 1 अवि[धम]स्तु ।।[] गुरु[भ्यो] नमः ।।[] पुष्टिम[द्भ्यो] गणपतिभ्यो नमः ।।*
- 2 शा[स]नल[क्षणम्]॥ श्रीवीजमादौ वक्तव्यं प्रण[वि]ष्टु च पंचसु । [रु]त्व[द्भि]द[द]-
- 3 गुरुदे[षु] च [क]टा[ज्ञान] 'विवर्जयेत् ॥[१॥] मो भूमिस्त्रिगुरु[शु]भं व[ह]ल[घु]-
नोमौ वि[ध]-
- 4 [त्ते] घनं [यो] वार्यादिलघुष्व हेम दिनकृत् मध्ये² गुरु[जो] रुजं ।।()³

¹ From the original stone and a set of inked stampages.

² At the top of the inscription are engraved from left to right figures of Viṣṇuśvara with his vehicle, the mouse, the Liṅgam, the Sun and the Moon.

³ Read रुजं.

⁴ The syllable न was inserted later and engraved above the line in the original.

⁵ Read रुजम्.


⁶ Here an empty space in the original showing traces of letters scored out.

- 5 [रो]ग्निर्मध्यलघुर्भयं लघुयुगप्रा[क्ख]मोर[:*] चयं खं तंतिल-
 6 घुरीशतां कृतिसुखे भोज[३*]शमादौगुरुः ॥२॥ अविस्मर्ग[त]पूर्वार्ध-
 7 मसमस्तपदादिकं । विसर्ग[३]स्वरं^१ र[म्यं] शास[न]श्लोकलक्षणं ॥३॥
 [श्रुतिस्मृ]-
 8 तिपुराणेतिहासागमविशारदः [१*] देशकालविसेष[ज]^२[:*] श्रमवाक [शा]सनः^३
 वदेत् ॥४॥
 9 श्रीस्त्रीभाव्यकरी सदा विजगतां भूयात् कृपारूपिणी हेरंबस्वचराचरा-
 10 ल[क]जगत्संदोहसंदर्भितं [१*] धाता पद्म[स]मुद्भवोपि मनसै[विदं] सु[वर्ना]ज्व-^४
 11 लं ब्रह्मांडं जलमंडलस्तमसृजत्^५ यस्याः प्रसादो(+)व्रतेः ॥५॥ वाराहा-
 12 कृतिरच्युतस्त्रिभुवनं पायादपायो[क्ति]तं । दंष्ट्रायेण महीं [—*] जलनिधो
 13 मग्नां समुष्ट्व^६ यः [१*] तत्रैकत्र निधाय पु(-)ष्टमनुलं पद्मा[क]र-
 स्था[प]ना-
 14 त् । तादृक् सम्यगभावतः^७ तुल्यितं यिना[हु]तं स्वीकृतं ॥६॥ [स]व्या-
 15 सव्यविलोच[ने] विजगतां वृष्टीयधीपोष[के] फाले वारिपिता [स]खा
 ध[न]पतिः]
 16 श्रीरत्नगर्भा रयः [१*] यस्य श्रीगिरिरालयः स कृपया [हे]माचल[:] कामुकः
 17 पायादः शिवतातिरात्रितजनानंदैकसंदायकः ॥७॥ स[म]ही[पा]वयव-
 18 विलसत्कृपिणी^{१०} मेरुमूर्धा^{११} चंच[त्*]चीरोदधिवरकुचा भूषि[ता] रो[ह]णा-
 द्यैः] [१*]
 19 ^{१२}राजत्राकरसुवसना संततं पातु युष्मान् द्वा[दि(+)]न्य[व]जाकरविलसिता पू-
 20 ^{१३}नसस्या धरित्री ॥८॥ पुत्रः कृतिस्तटाक्ष निधा[नं] ^{१४}सि[व]मन्दिरं [१*] वन
 विप्राग्रहा-
 21 रथ ^{१५}सतसंतानमुत्तमं ॥९॥ ^{१६}येतदादिक(+)]सत्पु[ण]कर्ता भास्करभू[प]
 ति[:] [१*]
 22 भवदूराभिधानश्च तस्य वंशं वदाम्यहं ॥१०॥ [जी]रोद[प्र]भवशशी विधुसु-
 23 त[:]स्त्रीम्यस्तदीयान्वये । संजातो च पुरुषवाच नहुष[:]स्तस्माद् य-
 24 यातिर्नृपः [१*] तत्पुत्री यदुरत्न याद[वकु]क्षौ नीलांबर[:*] श्रीहरिः वं-

^१ Read °शेखरं.^२ Read नं.^३ Add नद्वा° after महीं.^४ Read °लसद्रूपिणी.^५ Read वं सस्या.^६ Read एत°.^७ Read बुति°.^८ Read °वर्णाज्व.^९ Read समुष्ट्व.^{१०} Read चय°.^{११} Read शिव°.^{१२} Read °विशेष°.^{१३} Read °लसत्.^{१४} Read °वतसु°.^{१५} Read राजद्वार°.^{१६} Read सप्त°.

- 25 . से¹ तस्य कलौ² [—*] समजनि श्रीसंगमञ्जाप[तिः] ॥११॥ स सं[ग]ममहीपालः
 26 कृत्वा हरिहरार्चनं [1*] लब्धवान् तद्वसा[दे]न पु[त्रं] हरिहरं विभुं ॥१२॥
 27 आपूर्वपद्मिमांभीधिसधदेशाधिनायका[ः] [1*] पादसेवापरास्तस्य सोमसू-
 28 र्यान्वयाधिकाः³ ॥१३॥ तत्सोदरी वैरिचृपालकंपनादाशीत्क्षितौ⁴ कंभ[न]भूमिपा-
 29 लः । तस्यानुजसुखरभूमिभुक् ततो लक्ष्मीपति[र्व्यु]क्क[न]रेंद्रसेखरः⁵ ॥१४॥
 30 भ्रातरौ बुक्कभूपत्य जातौ मारपमुद्[पौ] । एवं पंच सुपुत्रास्ते पांड-
 31 वांशाः कलौ युगे ॥१५॥ पांडवानां पुरा दौत्यं [सा]रथ्यं भक्तवत्सलः [1*] [वा]-
 32 सुदेवो नंतमूर्तिस्तेषां च सचिवोभवत् ॥१६॥ अनंतराजसाचिव्यादक्षि-
 33 लं धरणीतलं [1*] भुंज(—)न् बुक्कमहीपालो जा[तदे]वेंद्रवैभवः । [1*] [१]७॥ (1)
 34 सदाराधनसंतुष्टश्रीविरूपाक्षसन्निधौ [1] तुंगभद्रातटे तस्य नगरं वि-
 35 जया(—)ह्वयं ॥१८॥ पुत्रसंख्या पुरा लोके शशविंदोस्ति (sic) तत्कथा [1*]
 असंख्या बुक्क-
 36 भूपालनंदना विजयो(—)यताः ॥१९॥ तेन बुक्कचृपालेन तेषु पुत्रेषु भास्करः[1]
 37 सा(—)स्त्रान्यविभवोत्तुंगो दिसि⁶ पू[र्वे] प्रतिष्ठितः ॥२०॥ स चोदयगिरीद्राघं
 38 भुंज(—)न् निष्कं[ट]कां महीं [1*] कुवलयानंद[क]री भास्करोपि द्विजप्रियः
 [॥२१॥*]
 39 हेमाद्रिकृतिमा[गं]ण कुर्व(—)न् दानान्यनेकयः [1*] जलदानप्रसंगेन शृतवान्
 40 फलमुत्तमं ॥२२॥ आपो वा इदमुं सर्वमित्याख्यायप्रमाण-
 41 तः [1*] जलादेवाद्यसंभूतिरक्षं ब्रह्मेति च श्रुतिः⁷ ॥२३॥ चरा-
 42 चरजगद्बीजं जलमेव न संशयः[1*] किं पुनर्वह्नु[नी]त्तेन जलाधिक्यं
 43 वदाम्यहं ॥२४॥ गंगाधरी हरस्त्रीपि विष्णुरंभोधिमं[दि]रः [1*] ब्रह्मा जल-
 44 असंभूतस्तस्मात्सर्वाधिकं जलं ॥२५॥ प्रपा कूपच वापी च कुल्या पद्मा-
 45 करस्तथा [1*] उत्तरोत्तरतस्तेषां कीटिकोद्याधिकं फलं ॥२६॥ चराचर-
 46 जगद्रक्षा य[त्त]टाकांबुना भुवि [1*] तस्य पु(—)ण्यफलं बहुमशक्तः क-
 47 मलासनः ॥२७॥ इत्युत्तमफलं शृत्वा भवदूरमहीपति [1*] तटा-
 48 कमावकासुर्वी धर्मात्मा कर्तुमुद्यतः ॥२८॥ तत्क्रमं[॥]
 49 श्रीपर्वतमहापु(—)ण्यक्षेत्रदक्षिणभूस्थ[लि] [1*] अहोबलास्थती-
 50 [र्व]स्थ पूर्वतो योजनद्वये ॥२९॥ श्रीसिंहवटनायस्य सौम्य[स्य] कि-
 51 ल देगके [1*] स्वस्योदयगिरीद्रस्य पश्चिमे योजनध्वये¹⁰ ॥३०॥ वि[ल]स-

¹ Read से.² Read कलौ.³ Read युगे.⁴ Read ह्वये.⁵ Add पुत्रे after कलौ.⁶ Read सेखरः.⁷ Read श्रुतिः.⁸ Read चिपा.⁹ Read दिसि.¹⁰ Read युला.



30
32
34
36
38
40
42
44
46
48
50
52
54
56
58
60
62
64

- 52 त्योरुमामि[क्*]कपट्टणप्रान्दिसि स्थिर¹ [1*] तटाकोद्योगकालस्य क्रमं
 53 वक्ष्यामि शासने ॥३१॥ धातोः परार्धकाले च कल्पे श्वेतवराहके [1*]
 [वि]व-
 54 'श्वते मनौ तत्र चाष्टविंशतिमे युग ॥३२॥ दिव्ये 'तद्[श]भागे च
 55 कलौ प्रथमपादके [1*] चतुस्रहस्रस[—*]युक्तचतुश्शतस[स]-
 56 मति । गतेषु मानुषाब्देषु [1*]४४७०॥ भूनंदाक्षेकसंख्य[या]
 57 ॥३३॥१२८१॥ वक्त्रेषु शक[स्वे]वं² सौम्याब्दे कार्तिका(—)३-
 58 ये ॥३४॥ मासे शुक्लचतुर्दश्यां 'गुरु[पुष्य]दिने शुभे [1*]
 59 लब्धे कर्कटके चैव शुभे ग्रहसुवीचिते ॥३५॥ निर्मित[स्व] तटा-
 60 कस्य द्वादशांगा[नि] शा[स्]वतः [1*] वक्ष्यामि भाविभूपानासु-
 61 एकाराय शासने ॥३६॥ धर्माक्षो धनवान् सुखो स्थिरय[शो]द्रव्याभि-
 62 लाषी नृपः पाथशास्त्रविदग्रजश्च दृढमृत्तंशोभिता चोर्व[रा] [1*]
 63 माधुर्यावुवहचियोजननदी तद्योगखंडो गिरि(ः)स्येतु-
 64 स्तत्र विनिर्मितो 'धनसिलाभित्वल्लदीर्घस्थिरः ॥३७॥

Second stone.

- 65 ॥ 'शृंगौ वा(—)श्चाफलस्थिरापरिद्ध-
 66 तौ 'विस्तीर्ननिष्कोदरं रुक्मायाम³-
 67 दूषत्स्वनिच निकटत्वेवं फला-
 68 व्यं समं [1*] चद्रिस्वानदृढभ्रमा-
 69 जलगतिस्तत्कर्ममर्त्यव्रजयेद्क्¹⁰-
 70 द्वादशसाधनैश्च सुलभ[1*] सेष्ठः¹¹
 71 स्तटाको भुवि ॥३८॥ सेतोय जालं
 72 जलमूपरीर्वी हिराजसंधा¹²
 73 वध मध्यक्ष्म [1*] चष्पावु-
 74 भूविस्तरमभूमिस्तोया-
 75 धिक् चात्र हि दीपवत्कं ॥३९॥ दी-
 76 [वि]र्विहीनो 'गुणराशिगोभितो [छ]-

¹ Read 'प्रि स्थित.² Read 'स्वते.³ Read तद्देव.⁴ Read 'इष्टेवं.⁵ The vertical stroke in the facsimile between ह and पु appears to be due to an accidental depression in the stone at that point.⁶ Read धनसिला.⁷ शृंगौ wrongly masculine.⁸ Read विस्तीर्ण.⁹ Read दूरव्रजयाम.¹⁰ Read 'दृक्.¹¹ Read सेष्ठ.¹² Read probably so.¹³ Read 'राशि.

- 77 नंतराजाख्यजगत्प्रसिद्धः [1*] मा-
 78 धुर्यनीरोयमनंतसाग-
 79 र(ः)सुस्थापितो भास्करभूवर-
 80 ण ॥४०॥ तटाकसेतुकाराय दि-
 81 ने चैकसहस्रकं [1*] [भ]माभित्तिः¹
 82 लाक(ः)र्मशकटानां शतं तया
 83 ॥४१॥ वर्षद्वयेन सपूर्ण(ः)स्तटाक-
 84 चोत्तमोत्तमः [1*] धनधान्यव्यय-
 85 स्यात् संख्या नैव तु विद्यते ॥४१॥
 86 सेतोरुभ्यतविस्तारदीर्घमानमि-
 87 होष्यते [1*] रेखादंडप्रमा[णि]न गि[रि]-
 88 सेतुसमायुतं ॥४२॥ रेखादंडस-
 89 हस्रपंचकलसदीर्घ्यं सप्तोन्नतः स्ते²
 90 तुस्तत्र चतुर्भ्रमाजलगतिः³ तद्विस्तार-
 91 चाष्टकं [1*] विप्रेयेश्वरविष्णुभैरवमहा-
 92 दुर्गाभिसंरचितः क्षेत्रं भूरिसम-
 93 स्तकालफलदं साराममत्युत्तमं ॥४४॥
 94 [दे]वब्राह्मणद्वयं दत्तं क्षेत्रं य-
 95 धेप्सितं [1*] योदृग्भूदानपुष्टेन तटाकस्ते⁴
 96 खरीकृतः ॥४५॥ यद्वत्सेतुर्धनियो⁵
 97 न चान्वेर्भूपांभोधेर्मसेतुस्तथैव [1*]
 98 तस्मादस्मदर्मरक्षार्थमुत्थां याचि या-
 99 चे पार्थिवान् भा[स्क]रोचं ॥४६॥(1) प्राक्तनप्रा-
 100 र्थनाश्लोकाः [1*] सामान्योया¹⁰ [ध]र्मसेतुर्नृपा¹¹
 101 काले काले पालनीयो भवद्भिः [1*] सर्वानितान्
 102 भाविनः पार्थिवेन्द्रान् भूयो भूयो या-
 103 चते रामचंद्रः ॥४७॥ दानपालनयोर्ध-
 104 धे ¹²यानास्तेयोनुपालनं [1*] दानादिद्रव्यमा-
 105 प्रीति पालनादच्युतं पदं ॥४८॥ ¹³यैकेव

¹ Read °मिहि-² Read °देव्यं व सदीर्घमिधे-³ Read °दृष्टं-⁴ Read °भूयो-⁵ Read °यैकेव-⁶ Read °पुष्टं-⁷ Read °मिहि-⁸ Read °नृपा-⁹ Read °यै-¹⁰ Read °वृत्तिविस्तारद्वयं-¹¹ Read °दृष्टं-¹² Read °यनीयो-¹³ Read °यानास्तेवी-

- 106 भगिनी लोके सर्व्वधामेव भूभुजा [१०] न भो-
 107 म्या न करवा(+)द्वा विप्रदत्ता वसुंधरा ॥४८॥
 108 कुमारगिरिना(+)या]स्त्रप्रधानतनयसु-
 109 धी[:] [१*] अधिकारी तटाकस्व देवा ॐ जाभिधानकः ॥५०॥
 110 विद्यास्थानचतु[ई]शप्रदनिजाचार्या-
 111 य कोटिक्रमात् गांगयं वरतंतवै र-
 112 घृष्टपात् लब्धा ददौ दक्षिणं [१*] कौलस्तकुल-
 113 [जे]न नंदपुर[वि]प्रा[ये]न रु [ग्वे]दिना श्रीमति-
 114 (+)गयमाचनार्यकविना प्रोक्तं [श]भं शास-
 115 नं ॥५१॥ शालिवीजफला खारी कणभू-
 116 मिस्तु खारिका [१*] प्रददौ भास्करस्त[स्त्री] धा]-
 117 रापूर्व्वकमादरात् ॥५२॥

TRANSLATION.

(L. 1) May there be freedom from obstacles! Salutation to the preceptors! Salutation to the (various forms of) Gapa-patis⁷ who have Pushti (for their wives)!

(L. 2) The characteristics (*lakṣaṇa*) of an edict (are as follows):—

(V. 1) Out of the five⁸ mystic syllables (*praṇava*) the sacred *bija*⁹ (syllable) should be uttered first. One should avoid (the use of the letters) *cha*, *ka*, *ṣa*, *ha* in the *ṛitu* (6th), *adri* (7th), 10th, and *rudra* (11th) (syllables).

(V. 2) At the beginning of a composition (the *gāṇa*) *ma*, consisting of three long (syllables and representing) the Earth, brings bliss; *na* with many (i.e. all) short (syllables, which represents) THAT,¹⁰ (brings) wealth; and *ya*, with the first (syllable) short (and representing) Water, (brings) gold; *ja* with the middle (syllable) long, (representing) the Sun, (brings) disease; *ra* with the middle (syllable) short, (representing) fire, (brings) fear; *sa* with two short (syllables) in the beginning, (representing) Wind, (brings) destruction; *ta* with a short (syllable) at the end, (representing) Space, (brings) lordship; (and) *bha* with a long (syllable) at the beginning, (representing) the Moon, (brings) happiness.

(V. 3) Not having a *visarga* at the end of the first half; absence of compounded words at the beginning; and having a *visarga* (at the end as) *śākhara*: (these are) the best characteristics of an edict-stanza.¹¹

⁷ Read "पति".

⁸ Read "देव".

⁹ Read "कामादे".

¹⁰ Read "पाद".

¹¹ Read "श".

...

⁸ Read "देव चत्वे". Note the hiatus! In the original an *i*-sign is also added to *ru*.

⁷ The number of Gapa-patis is variously given by different authors. Cf. Bhaṣadarkar, *Vaiṣṇavism, Śaivism*, etc. (*Grundriss d. indo-arischen Philologie*, Band III, Heft 6, pp. 149 f.).

⁸ The dictionaries mention only one *praṇava*, namely, the syllable *Om*.

⁹ It is the mystic letter forming the essential part of the *mantra* of any deity (Apte's Dictionary).

¹⁰ The Earth, Water, Sun, etc. mentioned in this verse are the eight forms of the *Aṣṭamūrti* Śiva; and seven of these agree with those enumerated by Kālidāsa in the introductory verse of the *Śakuntalā*, namely, the five *maṇḍāśāśas*, the Sun and the Moon; consequently the remaining one, which is referred to under *na-gāṇa* with the pronoun *asau*, must be the sacrificing priest *Āṣṭri*.

¹¹ Needless to say, the author himself does not follow the rules of versification laid down here.

(V. 12) This king Saṅgama, having worshipped the gods Hari and Hara, obtained by their grace a son, king Harihara.

(V. 13) The supreme lords of the Middle Country¹ (*Madhya-dēśa*) extending from the eastern to the western ocean, viz. the celebrated (kings) of the Solar and Lunar races, were occupied in doing "foot-salutation" to him.

(V. 14) From his causing hostile kings to tremble his uterine brother was (known) in the world (as) king Kaṁpana. After him his younger brother Bukka, the crest-jewel among kings, the husband of Lakshmi, was the enjoyer of the Earth, who was perfectly constant (to him).

(V. 15) (Then) were born Mārāpa and Muddapa, two brothers of king Bukka. And these five virtuous sons were incarnations of the Pāṇḍavas in the age of Kali.

(V. 16) Vāsudēva, who loves his worshippers and (who had acted) in former times (as) the messenger (and) the charioteer of the Pāṇḍavas, (having countless incarnations), became also the minister of these in the form of Ananta.²

(V. 17) Through having Anantārāja for his minister king Bukka ruled over the whole surface of the earth and acquired the glory of Dēvēndra.

(V. 18) His city, Vijaya by name, (was situated) on the bank of the Tuṅga-bhadra near (the temple of) the blessed Virūpāksha (Śiva), well propitiated on account of steady adoration.

(V. 19) Formerly the number of the sons of Śaśabindu (was very great) in the world. That is but a story! (?) The countless sons of king Bukka were exalted through triumph.³

(V. 20) Out of these sons king Bukka had placed Bhāskara, exalted through the glory of independent sovereignty, in the eastern direction (of his empire).

(V. 21) And he, ruling from the top of the sublime Udaya-giri⁴ the earth freed from the thorns (of enemies), though Bhāskara, (i.e. the Sun, is still) the delighter of the Earth and beloved of the Brāhmaṇas.⁵

(V. 22) Making charities in various ways in keeping with the treatise of Hēmadri,⁶ he heard that the merit attaching to the gift of water was the greatest of all.

(V. 23) On the authority of the Vēdas: "Verily all this is water!"⁷ And the Śruti says that: "From water alone is produced Food; (and) Food is Brahman!"

(V. 24) There can be no doubt (that) Water alone is the seed of the world of movables and immovables. Why speak more? I shall describe the superiority of water (as follows):—

¹ As the early Vijayanagar kings had no claim to sovereignty in any part of India north of the Vindhya, Madhyadēśa cannot have its usual significance, but must refer to the country lying between the eastern and the western ocean, namely, the Dekkan plateau.

² One must supply a verb like *krīṇōti* in the first half of the verse.

³ The construction of the first half of the verse is not quite clear to me. In Ch. 65 of the Drōṇa-parvaṇ of the *Mahābhārata*, we are told that Śaśabindu had 10,000 wives, on each of whom he begat 1,000 sons. These, it is stated, he gave away to the Brāhmaṇas in the Atvamāṇa sacrifice which he performed. The "countless sons" of Bukka are his meritorious acts like the *sapta-santāna*s mentioned in v. 9.

⁴ This must refer to the fortification on the top of the Udaya-giri hill. Even now U. is an exceedingly strong hill-fortress.

⁵ The pun on the words *bhūmalaya* ('night-lotus' and 'earth') and *deja* ('Brāhmaṇa and Moon') is a very common example of the Virūdhābhāsa.

⁶ Namely, the Dāna-khaṇḍa. Hēmadri was the minister of the two Yādava kings Mahādēva (1260-71) and Rāmachandra (1273-1310). See Bhandarkar, *Early History of the Dekkan*, pp. 88 f.

⁷ The phrase *apō cā*, etc. is a part of the *mantra* with which water is purified. *Idaguh* is the word *idam* as it is pronounced by the Yajurvedins in the recitation of Vedic texts.

(V. 25) Even that (great) Śiva is the bearer of the Gaṅgā; Viṣṇu has the ocean for his abode; Brahmā is sprung from the water-born (lotus). Hence Water is superior to everything (else).

(V. 26) A shed for distributing water (*prapā*), a well and a reservoir, a canal and a lotus-tank: the merit of (constructing) them is millions and millions (of times) higher in succession.

(V. 27) As the water of a tank serves to nurture both movable and immovable creation on (this) earth, even the lotus-seated (Brahmā) is unable to recount the fruit of merit (attaching) to it.

(V. 28) Having thus heard the supreme reward, king Bhavadūra, the pious soul, commenced to make the earth tank-nourished (*taṭāka-mātrikā*).¹

(L. 48) Its procedure (was as follows):

(Vv. 29-31) It (i.e. the tank) is situated in the country to the south of Śrīparvata (Śrīśaila), the great sacred place of pilgrimage; two *yōjanas*² to the east of the sacred place (*tīrtha*) called Ahōbala; in the division of the gentle blessed Siddhavaṭa-nātha; two *yōjanas* to the west of his (capital) Udaya-giri; and to the east of the flourishing city of Porumāmilla. I shall (now) describe in this edict the sequence of the period of construction of the tank:—

(Vv. 32-35) ³In the second half of the creator's life-time, in the Śveta-varāha Kalpa, in (the age of) the Vaivasvata Manu, and in the 28th Yuga,—in that divine part of the country—in the first quarter of Kali, after the lapse of four thousand, four hundred and seventy—(in figures) 4470—years of mortals, and also after the (lapse) of Śaka years measured by the number of the earth (1), the Nandās (9), the eyes (2), and one (1)—(in figures) 1291—in the (cyclic) year Saumya, in the month called Kārttika, on the fourteenth (day) of the bright half, on the auspicious day of Guru combined with Pushya, when there was Karkāṭaka lagna, under the influence of well-chosen auspicious planets,—

(V. 36) Of the tank constructed (at the above specified time and place) according to (the requirements of) the *Śāstra* I shall in this edict describe the twelve constituents (*aṅga*)⁴ for the benefit of future kings:

(V. 37) (i) a king endowed with righteousness, rich, happy (and) desirous of (acquiring) the permanent wealth of fame, (ii) and Brāhmaṇa learned in Hydrology (*pāṭha-sāstra*), (iii) and ground adorned with hard clay, (iv) a river conveying sweet water (and) three *yōjanas* distant (from its source⁵), (v) the hill parts of which are in contact with it, (i.e. the tank),⁶ (vi) between these (portions of the hill) a dam (built) of a compact-stone wall, not too long (but) firm, (vii) two extremes (*śrīṅga*) (pointing) away from fruit(-giving) land (*phala-sthira*) outside,⁷ (viii) the bed extensive and deep, (ix) and a quarry containing straight and long stones, (x) the neighbouring fields, rich in fruit (and) level, (xi) a water course (i.e. the sluices) having strong eddies (*bhramā*) on account of the position of the mountain (*adri-sthāna*),⁸ (xii) a gang of men (skilled in the art of) its construction,—with these twelve essentials an excellent tank is easily attainable on (this) earth.

¹ With *taṭāka-mātrikā* cf. the terms *dēsa-mātrikā* and *nadi-mātrikā* in a similar sense.

² Taking a *yōjana* to be equal to 2 miles, this distance is only approximately correct.

³ Construe: *dhātōḥ parārthakālā... dieṣṭ taddāta-bhāgē nirmīṭṭaya taṭākaṅga dōḍatāṅgāni cakṣyāmi*.

⁴ These *aṅgas* are later on called *vādhānas* (l. 70 of the text) and are no doubt identical with the latter.

⁵ See above, p. 99.

⁶ This must obviously refer to the range of hills which is utilised to form a part of the dam.

⁷ I.e. below the tank.

⁸ This may be taken to be a clumsy description of the fact that at the egress the water is led over a stony bed along a tortuous line, so that it issues whirling round with great force, forming strong eddies.

(V. 39) While (i) water oozing (?) from the dam, (ii) saline soil, (iii) (situation) at the boundary of two kingdoms,¹ (iv) elevation (*kūrma*) in the middle (of the tank) bed,² (v) scanty supply of water and extensive stretch of land (to be irrigated), (vi) and scanty ground and excess of water : (these are) the six faults in this (connection).

(V. 40) Devoid of faults and adorned with a multitude of good qualities, renowned in the world by the name *Anantaraṣa*, this endless ocean, of which the water is sweet, was founded by king Bhāskara.

(V. 41) (There were) one thousand labourers (working) at the tank and dam every day, and a hundred carts (were employed) for the masonry work of the sluice and wall (*bhramābhitti*).

(V. 42) And this most excellent tank was completed in two years. There is, to be sure, no limit at all to the expenditure of money and grain in this (connection).

(V. 43) The measurements in terms of *rēkhā-damḍas*³ of the height, the width, and the length of the dam together with (the portion of) the hill (included in the) dam, are here given :

(V. 44) The dam, having eddying waterduces (i.e. sluices)⁴ (and) protected by Vighnēśa, (Gaṇa-pati), Īśvara) (Śiva), Viṣṇu, Bhairava, and the great Durgā, is one which has the enormous length of five thousand *rēkhā-damḍas*, height of seven and its width eight.⁵ And the land (is) excellent and yields plentiful crops in all seasons and contains groves.

(V. 45) This land was liberally given for the gratification of gods and Brāhmaṇas. Through the merit of this gift of land the tank was made to be an ornament (of tanks).

(V. 46) Just as the dam of a reservoir should not be injured, so likewise the *dharma*-dam of the ocean of kings. Therefore I, Bhāskara, repeatedly request the kings on earth to protect my charity.

(L. 99 f.) These are the ancient *śloka*s of entreaty :

[Then follow three of the customary verses.]

(V. 50) The Officer-in-charge (*adhikārin*) of this tank is the clever son of the minister called Kumāragiri-nātha, Dēvarāja by name.

(V. 51) Having obtained from king Raghu gold by the crore, Kautsa gave (it as) *dakṣiṇā* to his preceptor, Varatantu, who had bestowed on him the fourteen branches of knowledge. By a descendant of him (*scil.* Kautsa)⁶ the illustrious Liṅgaya-Māchanāryya,⁷ of Nandapura, best of Brāhmaṇas and a follower of the R̥gveda, the auspicious edict was composed.

(V. 52) (One) *khāri* (of land) producing paddy and (one) *khāri* of black-soil land,—(these) were out of regard given to him by Bhāskara, preceded by a libation (of water).

¹ Perhaps as, in this case, the position of the tank might lead to unpleasant consequences during a conflict between the neighbouring kingdoms.

² The bed ought to form a complete valley.

³ A standard of linear measurement roughly equal to 1½ yard. See p. 99.

⁴ For *īkramā-jala-gatī* see note 8 on p. 108.

⁵ The pronoun *tad* in *tad-vistara* cannot be taken to refer to the noun immediately preceding, but must refer to the *śloka*s of which the dimensions are being given. See l. 88 of the text.

⁶ The sense is that the poet belonged to the Kautsa *gotra*. There is, however, a confusion in the mind of the poet between Kautsa the patriarch, and Kautsa the pupil of Varatantu alluded to in the *Raghu-vaṃśa*, Canto 5, vv. 1 ff.

⁷ I.e. Māchana, son of Liṅgaya.

No. 5.—HARĀHA INSCRIPTION OF THE REIGN OF ISANAVARMAN: [VIKRAMA SAMVAT] 611.

By PANDIT HIRANANDA ŚĀSTRĪ, M.A., M.O.L., LUCKNOW.

This inscription was brought to my notice in March 1915. The stone slab on which it is written was found, I am told, some time ago at a village near Harāhā in the Bārā Bankī district in the estate of the Rājā of Harāhā. A Thākūr of that locality took possession of it and, as has very often been the case with similar documents, used it for grinding spices. Some local Pandit reported the matter to Thākūr Prithvīpāl Singh of Sārajpur, who wrote to Rājā Raghu Rāj Bahādur Singh of Harāhā and got hold of it. For some time it lay in the office of the "Lucknow Advocate," where it was shown to me by Mr. S. P. Sanyal, Rai Sahib, the Managing Editor of the Journal. The Hon'ble Mr. R. Burn, I.C.S., the Chief Secretary to the United Provinces Government, at my suggestion, has secured it for the Lucknow Museum, where it has now been deposited as a present from the said Rājā of Harāhā.

It is incised with great care and neatness on a smooth slab of sandstone, which measures about 2' 2½" by 1' 4½". There are 22 lines of writing in it, cut in the characters of the northern class of Indian alphabets, resembling the Gupta script of about the 6th century A.D. The language used in the epigraph is Sanskrit verse throughout. Excepting a few slight injuries here and there, the inscription is in a very good state of preservation.

As to the orthography a few points are noticeable in the record. The writer has duplicated the symbol for *k*, when it is conjoined with *ra*; e.g., *-chakkra-* in l. 9. Consonants following the symbol for *r* are very often doubled as in *dhātur-Mmaru-* in l. 10. The rules of Sandhi are at times disregarded, as in *badhnamāiva*, l. 9, instead of *badhnamnaiva*. We find *agh* in place of *ah* in l. 2 and *āh* in l. 13. Such a tendency to pronounce the aspirate *h* combined with a nasal like the aspirated guttural media is rather common in the north-west of India, where the word *siṃha* forming part of proper names is generally written and pronounced as *siagh*. In l. 15 *dhritā* is written for *dhritā*.

Two marks of punctuation are to be noticed in the inscription. One is a short horizontal stroke, which stands mostly for *ardhaviśrama* (half-stop), and the other is a double perpendicular line which indicates the completion of a stanza, or *pūrṇaviśrama*, i.e., full-stop.

The composer of the inscription does not appear to have been a poet of a very high order or a Kavi par excellence. The tautological expressions which are to be met with in different places are too glaring for a real poet. But the prosody seems to be all right, and in v. 9 the exigencies of the metre have even caused the author to use a wrong form of a word, writing *hriyā* for *hriyā*, which would have offended against the scansion.

The author of the eulogy appears to be rich in vocabulary, though perhaps he did not hesitate to put in Prakrit words, the use of which will be instanced by the word *-āgara-* in place of Sanskrit *ākara*¹ in l. 11, unless we take *ga* to be a simple mistake for *ka*.

The object of the inscription is to record that in the year 611, Śūryavarman, the accomplished son of the Maukhari king, Īśanavarman, while hunting, saw a small dilapidated

¹ *Āgara* (Sanskrit *ākara*) means a collection or mine. Cf. 'Sab gam kī āgar dhiyā, nāh bin be ādi,' a proverbial saying equivalent to "great braggars, little doers" (lit., you are a perfect mine of good qualities, my child, you only want a nose).

The word *akṣhiṇas* in line 8, which may be taken for *akṣhiṇas* or *akṣhiṇas*, may have been a Prakrit form of *krṣhā*, 'to fret' (from Sansk. *kradā*) or *krṣhā*, 'to beat mercilessly.'

Śiva temple and had it rebuilt, making it much higher¹ than it was originally and white like the moon, and that he gave it the name of *Kṣhēmēśvara* (i.e., the Lord of bliss).

The name of *Sūryavarman* is new to the list of *Maukhari* princes known up to this time. Whether he was the heir or had any claims to the throne, our inscription does not say. From the description, however, which is given in ll. 17-19 it clearly follows that he was an accomplished son of *Īśānavarman*. According to the *Aśtgaṇa* copper seal² inscription, which makes no mention of *Sūryavarman*, *Īśānavarman* was succeeded by *Śarvavarman*. The coins of both of these rulers, namely, *Īśānavarman* and *Śarvavarman*, are known to us.³ But no coin bearing the name of *Sūryavarman* has yet come to light. The reading of the names *Sūryavarman* and *Śarvavarman* is indisputable; for the lettering is clear both in the inscriptions and the coins. Therefore *Sūryavarman* must have predeceased his father, if he was not one of the *rāja-kumāras* or princes junior to the heir-apparent. Or could he have been a rival of *Śarvavarman*?

This inscription does not supply any geographical data, and it is impossible to say what part or parts of the country the rulers whom it describes held or governed. But it gives them the distinctive epithet of *Mukhara*, which in Sanskrit is used in different meanings. Why they were so called is not known with certainty. But according to *Kaiyaṣa* and also *Vāmana*, the two famous expositors of *Pāṇini*'s system of grammar, who flourished probably about the 13th and the 7th century A.D. respectively, the term is a patronymic signifying the descendants of *Mukhara*, who must have been the *ādipurūṣa* or the first to bring his family into prominence and thereby caused it to be known after his name. Whether *Mukhara* was a proper or an attributive name, we have no means of ascertaining. But it will not be unreasonable to assume that it was a surname and that the man was so called for his being a 'leader' or for his fighting in the forefront of the armies which he led into action, as it is such characteristics only which would go to make a man the founder of a line. That *Mukhara* was a personage of such a distinction is evidenced by *Bāṇa*, who in the following statement clearly places him at the head of a family.

"Soon *Gambhīra*, a wise *Brāhmaṇa* attached to the king, said to *Grahavarman*, 'My son, by obtaining you *Rājyaśrī* has at length united the two brilliant lines of *Pushpabhūti* and *Mukhara*, whose worth, like that of the Sun and Moon houses, is sung by all the world to the gratification of wise men's ears.'"⁴

As *Pushpabhūti* was an ancestor of *Harṣa*, the well-known king of *Sthāpaviśvara*, the *Mukhara* in all probability was ancestor of *Grahavarman*, the ruler of *Kanyakubja*. He is not indeed mentioned in the inscriptions that have yet come to light; but possibly it is because of his being a remote ancestor.

The author of the *prafastī* appears to connect this dynasty with the Solar race. He says that the *Mukharas* or *Maukharis* were the descendants of the hundred sons whom *Aśvapati* obtained from *Vaiṣvata*, or the seventh *Manu*, who is supposed to be born of the Sun and to preside over the present age. The name *Aśvapati* is applied to many individuals, of whom the king of *Madra* and father of *Sāvitrī*, the well-known heroine of an episode of the *Mahābhārata*, is very familiar. If that was the person whom the author of the composition had in view, the *Mukharas*, according to the tradition which was evidently current at the time when it was written, must have originally belonged to the north-western part of India, where *Varāhamihira* has located the *Madras*.⁵

¹ This is inferred from the pun on the word *śaśāṇaśatam-akūṭi* in the 20th stanza.

² Fleet, *Corp. Inscr. Ind.*, Vol. III, pp. 219 ff.

³ Mr. B. Burn, *Jour. E. A. S.*, 1906, pp. 483 ff.

⁴ Cowell and Thomas, translation of the *Harṣacharita*, p. 125.

⁵ *Bṛhat-saṃhitā*, 14, 22.

That the family of the Maukharis is a very ancient one is proved, as Dr. Fleet¹ has already pointed out, by the legend *Mākhaliṣam* written in Mauryan Brāhmī characters on a clay seal which was secured by General Cunningham at Gayā. Evidently this is a Prakrit equivalent of the Sanskrit word *Maukharīṣam*, which is a derivative of *Mukhara* and signifies "of the Maukharis." From the scholia² referred to above it would appear that the term was possibly known to Pāṇini and also to Patañjali. That the Maukharis were potent rulers in the sixth and seventh centuries is evidenced by several inscriptions that have already been published. The same inference can be drawn from the accounts found in the work of Bāṇa, the well-known author of the *Harshacharita*, the historical romance of the 7th century A.D. The high esteem they commanded about the time of Harsha can be estimated from the manner in which Bāṇa speaks of them. While praising Avantivarman, the brother-in-law of Harsha, he says,³ "at the head of all royal houses stand the Mukharas, worshipped like Śiva's foot-print by all the world." This would go to indicate that these princes were not upstarts, but of good descent. That they were enterprising rulers would be seen not only from their description given in the commencement of our inscription, but from the fact that there was more than one branch of the family. The Maukharis, for instance, of the Barābar Hill cave inscription, as is clear from the line of descent given, were different from those of the Aśirgaṇḥ copper seal and of the present inscription. This surmise is supported by the references which have already been noticed.

As has already been remarked, the historical identity of the founder of the dynasty is not known. But the epigraphs that have so far come to light, while giving the line of descent, start with Harivarman. From Harivarman to Īśānavarman it runs as follows:—

The Mahārāja Harivarman, his son from Bhāṭṭārikā Dēvi Jayasvāminī⁴ the Mahārāja Ādityavarman; his son from Bhāṭṭārikā Dēvi Harshaguptā the Mahārāja Īśvaravarman; his son, begotten on the Bhāṭṭārikā Dēvi Upaguptā, was the Mahārājādhirāja Īśānavarman.

Beyond giving ordinary praises of the first three princes, namely, Harivarman, who is said to have had the surname Jvālāmukha, Ādityavarman and Īśvaravarman, our inscription does not speak of any historical event which might have taken place in their reigns. Coming to Īśānavarman, however, it alludes to some of his exploits which appear to be historical. They are three, namely, first his conquest over the "Lord of the Āndhras with their troops of elephants," secondly, his routing the Śūlikas "possessed of an innumerable cavalry," and thirdly, his "driving away or victory over the Gauḍas." The first of these is evidently mentioned in the Jaunpur stone inscription, which has been attributed to Īśvaravarman, and which mentions the Āndhras in the latter portion,⁵ but which is incomplete.⁶

Śūlika appears to be a new name, and I am not aware of any other epigraphic reference to it. Possibly it is identical with the Śaulika of the *Bṛhatsaṃhitā*⁷ and the *Mārkaṇḍēyapurāṇa*⁸ and is to be located in the south-east along with Kāliṅga, Vīdarbha, Chēdi, etc. Unfortunately none of the hostile kings is named in this record; otherwise it would have been very valuable for chronological purposes.⁹

¹ *Corp. Ins. Ind.*, Vol. III, p. 14.

² The Scholiasts give only three illustrations, *Pansikā*, *Bhānsikā* and *Maukharyā*, under the aphorism (Pāṇ. IV. 1. 79) which explains the formation of the words in the *śāsa* suffix.

³ *Loc. cit.*, p. 127.

⁴ The names of the queens are given in the Aśirgaṇḥ copper seal inscription, but omitted in this epigraph.

⁵ See Fleet, *Corp. Ins. Ind.*, No. 51, p. 229.

⁶ On this account it will be perhaps more appropriate to ascribe that inscription of Jaunpur to Īśānavarman and not to Īśvaravarman, as has been done by Dr. Fleet.

⁷ XIV, 8.

⁸ LV.

⁹ Dr. Fleet's remarks on the Jaunpur inscription, *loc. cit.*, No. 51, p. 229.

By far the most noteworthy point in this inscription is the date. I believe this is the only dated record of the Maukhari kings that has yet come to light. The year is thus given in words in v. 21: During the year of six hundred autumns increased by eleven,¹ when Īśānavarman, who vanquished his foes, was the lord of the earth. The era to which this year belongs has not been specified, but the use of the term *śaradā* will indicate that it is identical with the Mālava, or Vikrama, era which as the late Professor Kielhorn elucidated long ago, began in autumn (*śarad*).² Different questions connected with the origin, name and use of his reckoning have been fully dealt with by other scholars, and it will be superfluous to discuss them here. The corresponding date of the Christian era is 554.

Īśānavarman, as has just been said, was ruling in the year 611. As he was a contemporary of Kumāragupta of Magadha, with whom, according to the Aṣṣad inscription,³ he was at war, and, as according to the Aśirgaṇḍ copper seal inscription he was the father of Śarvavarman, this record will go to fix the time of these rulers as well with great certainty. But this date of Īśānavarman calls for some remark. No dated record of his rule being available, scholars had to make conjectures regarding his date. Cunningham, for instance, gave circa A.D. 560 and Dr. Hoernle A.D. 564. Mr. V. Smith⁴ wanted to move it back and bring it to A.D. 502. But now the new epigraph has removed all doubts and established the date, and we can re-examine the dates on his coins as well as those on the coins of his son and successor, namely, Śarvavarman, that have been brought to light. The Hon'ble Mr. Burn has summarized their dates as follows:—

(1) Īśānavarman: 54 (Cunningham, *Coins of Med. India*, ii, 12, and V. A. Smith in *Jour. Beng. As. Soc.*, 1894, p. 193); 55 (Cunn. *Arch. Surv. Rep.*, IX, p. 27, where the name is read as Śāntivarman).

(2) Śarvavarman: 58 (V. A. Smith, l.c.); 234 and 23.

(3) Avantivarman: 57, 71, and 250.

Assuming that a new Maukhari era commenced about 500 A.D., he converted these dates into the following years of the Christian era:—

Īśānavarman 553.

Śarvavarman 553, 54 or 55, 557.

Avantivarman 556, 569, 570.

He further observed that the dates of Śarvavarman and Avantivarman overlapped and that it was possible to read 67 instead of 57 on the latter's coins.

In this connection I think the following observations will not be out of place. Avantivarman is known to us from the *Harshacharita* as the father of Grahavarman, the brother-in-law of Harsha and the husband of Rājyāśrī, who met his death at the hands of a king of Māliwa about 605 A.D. From the Dēśa-Baraṇṣī inscription of Jivitagupta II it would appear that he was the son and successor of Śarvavarman Maukhari.⁵ This synchronism will bring Śarvavarman and Avantivarman to about 560 and 580, respectively, giving an average of some 20 years to each of them, and make 67 as the more probable reading of the date of Avantivarman. But

¹ The dictionary gives 'redundant' as one of the meanings of *atirikta*. This would suggest that 11 is to be deducted from 600. But no instance is known to me where the word is used in this way.

² *Ind. Ant.*, Vol. XX, pp. 407 ff.

³ *Corp. Inscr. Ind.*, Vol. III, No. 42.

⁴ History and coinage of the Gupta period, *Jour. Beng. As. Soc.*, 1894, p. 195.

⁵ *J. R. A. S.*, 1906, p. 847.

⁶ The genealogy given in the footnote No. 3, page xi, of the translation of the *Harshacharita* by Cowell and Thomas cannot hold good as regards Śasthitavarman, the contemporary of Aḍitya-śena, who flourished about A.D. 647. (V. A. Smith, *Early History of India*, 3rd edition, p. 315.)

how to explain the dates on the coins of Śarvavarman and Īśānavarman? According to our epigraph the latter was ruling during the rainy season of the (Vikrama) year 611, i.e., the years 235 and 554 of the Gupta and Christian eras, respectively. That the dates on the coins which are expressed in hundreds and odd numbers belong to the Gupta era is also undoubted. How could then Śarvavarman issue coins in his own name when his father was alive and ruling the country? Obviously, therefore, there is some error in the reading of the dates on the coins, and the year of Śarvavarman is to be moved on. Cunningham noticed¹ one coin of Īsanavarman which is dated in the year 257. If he read the date correctly, Śarvavarman will have to be placed about the last quarter of that century, i.e., the 6th century of the Christian era.

Besides these dates in the Gupta era a few other dates, read on the coins of these Maukhari kings and on those of Tōramāpa, have formed the subject of considerable discussion. But, as the date of Īśānavarman has now been indisputably settled, we cannot help accepting one of the two alternatives pointed out by Mr. Burn²; otherwise the dating of the coins of the Hūṇa rulers in the years of one and the same reckoning cannot be explained:—"Either the date on Tōramāpa's coins is in a different era from that of the Maukharis or else this Tōramāpa is not the father of Mihirakula." Besides there is another point. The Aphaṣṭ inscription alluded to above says that the Maukharis threw aloft in battle the troops of the Hūṇas, in order to trample them to death. This being the case, it looks very unlikely that the Maukharis would use an era of their enemy.

The dates on the coins of these kings appear to be doubtful; and until some better specimens are available for comparison, I do not like to hazard a conjecture. But it is not unreasonable to assume that, as Mr. Burn has already said, the Maukharis used a new era on some of their coins. The time of its commencement and the name of its originator are not known. But, if any of the Maukharis was the founder, I think it was Īśānavarman who had the highest claims to that honour; for, as we learn from the Aśirgaṇḍ seal inscription, of all the rulers of this line known to history he is the first to be styled *Mahārājadhīrāja*. But in that case the probability will be that he took a date before his reign began, as a reign of 54 years, though not impossible, is not probable.

Our inscription sheds much light on another important question:—Where was the Vikrama era used in earlier times? Kielhorn said that the earliest known dates from V. 428 to 898 were all from eastern Rājputānā, chiefly from that part of eastern Rājputānā which borders on, or is included in, Mālava. He further said that, if we were to judge by the dates collected, the era spread first towards the north-east, to Kanauj and to Gwālior and Bundēlkhāṇḍ, and afterwards towards the south-east and south to Mālava proper and Aṇhilvāḍ (including Kathiavāḍ), and in the tracts situated to the north of the Jumṇā and the Gauges very late dates of the era were seen. These statements are therefore to be modified, as the locality where the inscription was found lies in the Bārā Bankī district, which is beyond the limits of eastern Rājputānā, that is, in a tract lying outside Mālava. I cannot say for certain that it was found *in situ*; but from the very nature of it one can safely surmise that it was. Although it is a solitary instance, yet, assuming that this record belonged to the spot where it was first discovered, one can reasonably say that the Mālava or Vikrama era was used as early as the middle of the 6th century A.D. in the very heart of Oudh towards the north-east across the Ganges and the Gōmati (Gumti), far away from the place of its origin.

The *prastāvi* (v. 23) was composed by one Raviśānti, the son of Kumāraśānti, who was a resident of a place called Garggarakṣa, and was engraved by one Mihiravarman. The

¹ *Arch. Surv. Rep.*, Vol. XIII, p. 81. He does not say if it is the same coin which he published in his *Coins of Med. India*, II, 12, or *Arch. Surv. Rep.*, Vol. IX p. 27.

² *J. R. A. S.*, 1906 p. 848.

66

68

70

72

74

76

78

80

82

84

86

88

90

92

94

96

66

68

70

72

74

76

78

80

82

84

86

88

90

92

94

96

96 96
 98 98
 100 100
 102 102
 104 104
 106 106
 108 108
 110 110
 112 112
 114 114
 116 116

identity of none of these persons is known, and we are unable to identify the locality of Garggarākāṭa.¹ It is not impossible that the reading intended was Garggarākōṭa, a name with which we may compare the Gōmatikōṭṭaka of the Dēo-Baranpār inscription of Jivitagupta II.² In the term Garggarā one will at once recognize the name Ghāgrā, so called because of its rattling noise. Possibly it was a fort somewhere on the bank of the Ghāgrā, one of the chief tributaries of the Ganges.

TEXT.³

[Metres: vv. 1, 2, 4, 8, 10, 11, 12, 13, 14, 16, 17, 18, and 19, *Sārdulavikrīḍitaḥ*; v. 3, *Gāthā*; v. 5, *Upajāti*; v. 6, *Indravajrā*; v. 7, *Mālinī*; vv. 9 and 12, *Sragdharā*; v. 15, *Drutavilāmbitaḥ*; vv. 21 and 23, *Anuṣṭubh (Śloka)*.]

- 1 लोकाविष्कृतिसंक्षयस्थितिकृतां यः कारणं वेधसाम्
ध्वस्तध्वान्तचयाः परास्तरजसो ध्यायन्ति यं योगिनः ।
यस्याहंस्थितयोषितोपि हृदये नास्यायि धतोभुवा
भूतात्मा क्षिपुरान्तकः स
- 2 जयति ज्येष्ठः प्रसूतिर्भवः ॥[१*]
आशोणां फणिनः फणोपलक्ष्वा सैर्ह्य⁴ वसानं त्वचं
शुभ्रां लोचनजग्मना कपिशयज्ञासा कपालावलीम् [१*]
तन्वीं ध्वान्तनुदं स्रगाकृतिभृतो विभ्रत्कलां मौलिना
दिश्यादन्ध-
- 3 कविद्विषः स्फुरदङ्घ्रि स्वेयः पदं वो वपुः ॥[२*]
सुतशतं लेभे नृपोऽपतिर्वैवस्वताद्यहुणोदितम् ।
तत्प्रसूता दुरितवृत्तिरुधो मुखराः क्षितीशाः क्षतारयः ॥[३*]
तेष्वादौ हरिवर्मापोवनिभुजो भूतिर्भु-
- 4 वो भूतये (१)
रुद्राशेषदिगन्तरालयशसा रुग्णारिसंपक्षिषा ।
सङ्ग्रामे हुतभुक्त्रभाकपिशितं वक्त्रं समीक्षारिभि-
र्यो भीतेः⁵ प्रणतस्ततश्च भुवने ज्वालासुखाख्यां गतः ॥[४*]
लोकस्थितोनां स्थितये स्वि-
- 5 तस्य मनोरिवाचारविवेकमार्गं ।
जगाद्द्विरे यस्य जगन्ति रम्याः सत्कीर्त्तयः कीर्त्तयितव्यमान्नः ॥[५*]
तस्मात्प्रयोधेरिव शीतरश्मिरादित्यवर्मा नृपतिर्वैभूव ।
वर्णाश्रमाचारविधिप्रणीतेर्यं प्राप्य

¹ *Ind. Ant.*, Vol. XX, p. 402.

² From the stone.

³ Read नीते.

⁴ *Corp. Inscr. Ind.*, Vol. III, No. 46.

⁵ Read सैर्ह्य.

6

साफल्मियाय धाता ॥[६*]

इतभुजि मखमध्यासङ्गिनि ध्वान्तनीलम्
विर्यति पवनजन्मभ्रान्तिविचेपभूयः ।
सुखरयति समन्तादुत्पतद्भूमजालम्
शिखिकुलसुखमेवाशङ्कितं यस्य

7

प्रसङ्गम् ॥[७*]

तेनापीश्वरवर्माणः क्षितिपतेः चक्षप्रभावाप्तये (1)
जन्माकारि कृतात्मनः कृतगणेष्वहृतवृक्षद्विषः ।
यस्योत्खातकलिस्त्रभावचरितस्याचारमार्गं नृपा
यत्नेनापि ययाति-

8

तुल्ययशसो नान्वेगुगन्तुं जमाः ॥[८*]

नीत्या शौर्यं विशालं सुहृदमकुठिनेनोमेच्छाङ्गुलिन¹ (1)
त्यागं पात्रेण वित्तप्रभवमपि हृया² यौवनं संयमेन [1*]
वाचं सत्येन चेष्टां श्रुतिपथविधिना प्रथये-

9

शोत्तमर्हिम्

यो बध्ननेव³ खेदं व्रजति कस्मिंयध्वान्तमग्नेपि लोके ॥[९*]
यस्येन्यास्त्रनिशं यथाविधि हृतव्योतिर्वलज्जम्भना (1)
मेनाञ्जनभङ्गमेचकरुचा दिक्कलवालि तते ।
आयाता नव-

10

वारिभारविनमग्नेघावली प्रावृडि-

त्युन्मादोहतचेतसः शिखिगणा वाचालतामाययुः ॥[१०*]
तस्मात्सूर्य इवोदयाद्विशिरसो धातुर्भूत्त्वानिव
क्षीरोदादिव तर्जितेन्दुकिरणः कान्तप्रभः कौस्तुभः [1*]

11

भूतानामुदपद्यत स्थितिकरः स्थेष्ठं महिम्नः पदम्
राजराजकमण्डलास्वरशशी श्रीशानवर्मा नृपः ॥[११*]
लोकानामुपकारिणारिकुमुदव्यालुप्तकान्तिन्दिया (1)
मिचास्याम्बुरुहागरद्युतिज्जता⁴ भूरि-

¹ Possibly erroneous for 'मकुटिलेनीचमीर्षीकुलिन'.

² Mistake instead of 'हृया', which would offend against the metre.

³ Read वप्रप्रेष.

⁴ Read 'वराकार'.

12

(1) प्रतापखिया ।

येनाच्छादितसत्यं कलियुगध्वान्तावमग्नश्च-
क्षूर्येषेव समुद्यता कृतमिदं भूयः प्रवृत्तक्रियम् ॥[१२*]
जित्वाग्नाधिपतिं सहस्रगणितवेधाचरद्वारणम्
व्यावृत्तानियुताति-

13

संख्यतुरगान्धु रणे शूलिकाम्¹ [1*]

कृत्वा चायतिमौचित्यलभुवी² गौडान्सुद्रात्रया-
नध्यासिष्ट नतक्षितीश्चरणः सिद्धासनं³ यो जिती ॥[१३*]
प्रस्थानेषु बलात्वाभिगमनक्षोभस्फुटद्गतल-

14

प्रोद्भूतस्थगितार्कमण्डलश्चा दिग्वापिना रेणुना ।
यस्यामूढदिनादिमध्यविरतौ लोकेन्धकारीकृते (1)
व्यक्तिं नाडिकयैव यान्ति जयिनो यामास्त्रियामास्त्रिव ॥[१४*]
प्रविशती कलिमारुतघटिता

15

क्षितिरलक्ष्यरसातलवारिधौ ।

गुणशतैरवबध्य समन्ततः

स्फुटितनौरिव येन बलाद्धिता⁴ ॥[१५*]

ज्याघातव्रणरुटिकर्कश्रुजा व्याकृष्टशार्ङ्गच्युता-
न्यस्यावाप्य पतन्निणो रणमखे प्राणानमुच्च-

16

न्दिषः ।

यस्मिन्शासति च क्षितिं क्षितिपतौ जातेन भूयस्त्रयो (1)
तेन ध्वस्तकलिप्रवृत्तिमिरः श्रोसूर्यवर्माजनि ॥ [१६*]
यो बालिन्दुसकान्ति कृत्स्नभुवनप्रेयो दधद्यौवनम्
शान्तः शास्त्रविचारणा-

17

क्षितमनाः पारङ्गलानाङ्गतः ।

लक्ष्मीकोर्त्तिसरस्वतीप्रभृतयो यं स्पर्धयेवाश्रिता
लोके कामितकामिभावरसिकः कान्ताजनो भूयसा ॥ [१७*]
सदृत्तेन बलात्कलेरवनतितावप्रवृद्धात्मनो⁵
वाणे-

¹ Read शूलिकान्.² Read सिद्धासनं.³ Read 'रवनतिताव', or 'रवनत' वापं.⁴ Read 'मौचित्य'.⁵ Read बलाद्धिता.

- 18 स्तावदवस्थितं स्मृतिभुवः कान्ताशरीरक्षती (i)
 लक्ष्म्या तावदकाण्डभङ्गजभयं त्यक्तम्यरापात्रयम् [1*]
 यावन्नाविरकारि यस्य जनताकान्तं वपुर्व्वधसा ॥ [१८*]
 लक्ष्म्यः शत्रुभुवः कुचपद्मभयाविशम्भम्-
- 19 श्लोचना(i)
 येनाकाञ्च भुजेन विस्फुरदसिञ्चोतिःकलासङ्गिना ।
 कान्ता मन्मथिनेव कामितविदा गाढं निपीड्योरसा (i)
 प्रायेणान्यमनुष्यसंशयकृतं भावं परित्वाजिता ॥ [१९*]
 तेनानतोन्नतिकृता
- 20 मृगयागतेन
 दृष्ट्वाद्यमन्त्रकभिदो भवनं विशोर्षम् [1*]
 स्वेच्छासमुन्नतमकारि ललाप्त भूमेः
 चेमेश्वरप्रयितनाम शशाङ्कशुभम् । [२०*]
 एकादशातिरिक्तेषु षट् शतितविदिषि ।
 शतेषु शरदां
- 21 पत्नी भुवः श्रीमानवर्षाणि ॥ [२१*]
 यस्मिन्कालेस्त्वुवाचा नवगवलङ्घ्यः प्रान्तलम्बेन्द्रचापा-
 स्तान्वन्त्याशावितानं स्फुरदुत्तडितः सान्द्रधीरं कथन्तः ।
 वाताश्च वान्ति श्रीमानवकुलमचयानममूर्त्तिं
- 22 धनाना-
 स्तस्मिन्मुक्ताम्बुमेवद्युति भवनमदो निर्मितं शूलपाणेः ॥ [२२*]
 कुमारशान्तेः पुत्रेण गर्भराकटवासिना ।
 नृपानुरागात्पूर्व्वयमकारि रक्विशान्तिता ॥ [२३*]
 उत्कीर्णा मिहिरवर्षाणा

TRANSLATION.

(V. 1.) Victorious is Bhava (i.e. Śiva), the source of bliss; the destroyer of the demon Tripura; the soul of all being; in whose heart the mindborn (Cupid) did not find room, though a woman (i.e. Pārvatī) forms one half of his body; whom the ascetics, who have suppressed their passions and destroyed the multitude of darkness (of ignorance), contemplate, and who is the cause of the gods that bring about the manifestation, the destruction and the maintenance of the universe.

(V. 2.) May the body of the Enemy of Andhaka (i.e. Śiva) grant you an eternal abode—the body of Śiva which has sparkling serpents on it; bears on the forehead the slender streak of the Moon, which dispels darkness; renders the shining row of skulls brown by the lustre proceeding from his eyes; and wears the skin of a lion reddened on account of the brilliance of the jewels on the hood of serpents.

(V. 3.) The **Mukhara** princes, who have vanquished their foes and checked the course of evil, are the descendants of the hundred sons whom king **Aśvapati** got from **Vaivasvata** (**Manu**) and who were conspicuous on account of their excellences.

(V. 4.) Among them king **Harivarman** was first born for the welfare of the earth, who became known by the name of **Jvālāmukha** (or, flame-faced), as he was honoured by the foes who were struck with terror when they saw his face red on account of the lustre of fire (i.e. anger) at the time of battle and as his splendour destroyed the wealth of the enemy and his fame pervaded the intervals of all the quarters;

(V. 5.) Whose name was worthy of fame and whose lovely excellent fame filled the worlds, while he remained, for the perpetuation of the moral laws in the world, on the path of virtue and discrimination like **Maun**.

(V. 6.) Like the Moon from the ocean king, **Ādityavarman** was born from him. Getting him, the Creator obtained, as it were, the full result of his laying down the regulations of right conduct for the four castes and stages of life.

(V. 7.) When fire was kindled during his sacrificial performances, the volume of smoke black like pitch darkness, rising on all sides and increased through the tossing and whirling produced by the wind in the sky, made the crowds of peacocks noisy, as they mistook it for a large cloud.

(V. 8.) For the obtainment of martial glory he caused the birth of **Īśvaravarman**, the king whose soul was pure and who invoked **Indra** in many a sacrifice. In the pursuit of virtue other kings in their efforts failed to equal him, whose pious conduct had uprooted the character of the **Kali Age** and who possessed the glory of **Yayāti**.

(V. 9.) Qualifying his high bravery with political wisdom, his friendship by honesty, his lofty ambition by his noble descent, his liberality by fit recipients, his might of wealth by modesty, his youth by self-restraint, his speech by truthfulness, his manner of life by the injunctions of the *Śruti*, and his high prosperity by humility, he never felt tired in the world, though it was immersed in the darkness of the **Iron Age**.

(V. 10.) At whose sacrifices, when the round of the quarters was overlaid with the smoke which arose from the fire kindled constantly in accordance with the canons and which was darkly blue like streaks of collyrium, the multitude of peacocks became noisy, their minds becoming maddened; for they thought that the rainy season, having a line of clouds bending low because of the weight of the fresh water, had set in.

(V. 11.) As the Sun (rises) from the top of the **Udaya** mountain, as **Indra** is born from the Creator, as the beautiful **Kaustubha** jewel, which excels the moon in splendour, came out of the **Milk Ocean**, the illustrious king **Īśanavarman** was born from him, the most firm abode of greatness, maintainer of stability amongst the beings, a resplendent moon in the sky of the circle of princes.

(V. 12.) By whom, as by the rising Sun, the world, which was sunk in the darkness of the **Kali Age**, where the paths of virtue were consequently obscured, was again set to work, he being a benefactor of the world, eclipsing the lustre of water-lilies in the form of the foes, illuminating the collection of lotus-like faces of his friends, and being possessed of abundant majestic splendour;

(V. 13.) Who, being victorious and having princes bending at his feet, occupied the throne after conquering the lord of the Āndhras, who had thousands of threefold rutting elephants, after vanquishing in battle the Śūlikas, who had an army of countless galloping horses, and after causing the Gaṇḍas, living on the seashore, in future to remain within their proper realm ;

(V. 14.) The victorious one, whose watches can only be determined by means of the water-clock,¹ as if it were at night, the world being encompassed in darkness and bewildered as to the beginning, the middle or the end of the day on account of the dust which rises from the earth rent asunder by the agitation caused by the marches of his ocean-like armies on their expeditions, screens the lustre of the orbit of the sun, and pervades the quarters ;

(V. 15.) By whom the earth was forcibly upheld like a broken boat, after fastening it on all sides by hundredfold virtues (or, strings), when it was sinking below the invisible ocean of the nether regions, being shaken by the storms of Kali ;

(V. 16.) Whose foes on the sacrifice-like battle-field gave up the ghost, when hit by (lit. having got) his arrows loosed from the bow fully bent by his arms, which were hardened owing to the growth of the wounds caused by the blows of the bowstring. When this king was ruling the earth, the three Vēdas were, so to speak, born afresh. Of him the illustrious Sūryavarman was born, who dispelled the darkness which originated in the advent of the Iron Age ;

(V. 17.) Who, possessing youth that was dear to the entire world, like the new moon, being calm and devoted to the study of the Śāstras, attained the highest proficiency in fine arts ; to whom Wealth, Fame, Learning and other [Muses] resorted, as if in emulation. Loving women are in the world highly devoted to a beloved lover.

(V. 18.) So long virtuous conduct had to bow down before the full grown Kali, so long the arrows of Cupid were capable of troubling the bodies of the fair sex, and so long did the goddess of wealth give up taking refuge with others, whereby she had to fear sudden breakdowns, as the Creator did not bring forth his body, pleasing to mankind.

(V. 19.) Who dragged forth by means of his arm, which was surrounded by the lustre of his sparkling sword, the Riches of hostile lands, whose eyes trembled for fear of seizure of the breasts, forcibly pressed them to his bosom, as a lover (would press) his sweethearts whose mind he knew, and caused them mostly to give up the thought of going to other men.

(V. 20.) By him, who raised those who were submissive (or low), an old and dilapidated temple of the slayer of Andhaka (Śiva) was seen while hunting, and it was raised at his wish and made an ornament of the earth, resplendent like the moon and known by the name of Kāśmēśvara (the Lord of Bliss) ;

(V. 21.) When six hundred autumns had become increased by eleven, while the illustrious Īśānavarman, who had crushed his enemies, was the lord of the earth,

(V. 22.) That temple of the Trident-wielder (Śiva), shining like an empty cloud, was (re)constructed at the time when the clouds, having the lustre of the wild buffalo and having rain-bows stuck to their borders, stretch a canopy over the quarters, with shining and extensive lightnings, thundering deep, and when the winds blow on all sides, shaking the Nīpa (*Nauclea Cadamba*) trees with their branches bent low on account of the multitude of new flowers.

(V. 23.) Raviśānti, the son of Kumāraśānti and resident of Garggarākṣa, composed the preceding [*praiśasti*] out of regard for the king.

It was engraved by Mibiravarman.

¹ See Dr. Fleet, *J. R. A. S.*, 1915, pp. 213 ff.

No. 6.—BHANDAK PLATES OF KRISHNARAJA I.: SAKA 634.

By V. S. SUKTHANKAR, Ph.D.; POONA.

The copper-plates which bear the subjoined inscription of the Rāshtrakūṭa king Krishnarāja I. were discovered at Bhāṇḍak, *Tahsil* Warḍā, in the Chāṇḍā District of the Central Provinces. They were forwarded for examination by the Commissioner for the Nāgpur Division, through Dr. D. B. Spooner, to the Assistant Archaeological Superintendent for Epigraphy, Southern Circle. I am now editing them from the original plates as well as a set of impressions kindly placed at my disposal by the latter.

The plates are three in number, each measuring roughly $10\frac{1}{2}$ by $6\frac{1}{2}$ ins., and weigh 340 tolas. The margins are folded over and beaten down, so as to serve as rims. The grant is engraved on the inner side of the first and the third plates, and on both sides of the second. The plates are pierced by a circular hole, $\frac{3}{4}$ in. in diameter, in order to receive the ring and seal, which are, however, missing.—The engraving is deep, but not neat. The letters, which are uncouth in shape, vary in size from $\frac{3}{4}$ to $\frac{1}{4}$ in. The letters *cha*, *pa* and *ya* have been most indifferently incised and are consequently difficult to distinguish from each other; so also the letters *va* (*ba*) and *dha*. The ligature *nta* is often so carelessly written as to be indistinguishable from *tta*. Some letters, again, sporadically show quite strange forms, as, for example, *su* in *rājasu* at the beginning of line 4, *śa* in *śarvarishu*, l. 3, *lā* in *balāna*, l. 28, etc.—The characters belong to the northern class of alphabets, and, like those of the Multai plates¹ of the Rāshtrakūṭa Nanda-rāja Yuddhāsura, represent the last phase of the acute-angled variety.² The medial *u* is marked by a short stroke slanting upwards, attached to the *mātrikā* at its right lower end; sporadically by a curve opening to the left, as, for instance, in the *śu* of *śuchī*, l. 3. The sign for the medial *ē* is a short vertical stroke appended to the top of the *mātrikā* on the left; and, only very rarely, by a stroke above the *mātrikā*. The central bar of *ja* slants downwards, but is not vertical; the lowest bar does not form a double curve, but merely slants downwards towards the right and only sporadically ends in a small notch. Those corners of the letters *kha*, *ga* and *śa*, which later develop into loops or triangles, are in our inscription marked by small projections or notches.³ The verticals on the right of the letters are short and project but little below the remaining portion of the signs.⁴ These palaeographic characteristics are sufficient to establish the archaic character of the script and to prove that the plates belong actually to the period to which they refer themselves, viz. the third quarter of the eighth century of the Christian era.⁵ Our record contains specimens of initial *ā* in l. 2; initial *ī* in ll. 3, 8; initial *u* in l. 37; initial *ē* in l. 53; a cursive form of *ka* in ll. 5, 12, 23, etc.; and the following ligatures, *śa*

¹ Bühler, *Indische Palaeographie*, Tafel IV, Col. XX.² Bühler, *op. cit.*, p. 50.³ E.g. *kha* in *mukhō*, l. 2, *mukhī*, l. 4; *ga* in *gōttra*, l. 8, *vāga*, l. 10; *śa* in *pradāsati*, l. 11, *śikharāṇī*, l. 13, etc.⁴ In the *yā* of *yān-āyān* (l. 31) we have an instance where the vertical stroke is altogether wanting.⁵ The Sāmāṅgaḍ grant of Dantidurga (ed. Fleet, *Ind. Ant.*, Vol. XI, pp. 110 ff.) and the Alās grant of Yava-rāja Gōvinda (II.) (ed. D. B. Bhandarkar, *Ep. Ind.*, Vol. VI, pp. 208 ff.) are two Rāshtrakūṭa records which bear the dates Śaka 675 and 692, i.e. are dated earlier by 19 and 2 years respectively than the grant which is the subject of this article. The palaeographic differences between these three grants are worthy of consideration. The alphabet of Gōvinda's grant is wholly different from that of our record. The script is entirely Dravidian in character; the letters are round in appearance, and are akin to those of the grants of the later Chālukyas of Bādāmi, the immediate predecessors of the Rāshtrakūṭas. The difference is clearly a local one and is perfectly consistent with the geographical limits over which the southern alphabet was current. Such is not, however, the case with the other inscription. The alphabet of the Sāmāṅgaḍ grant belongs to the same category as that of our grant, and represents an archaic variety of the Nāgari. The difference lies, however, in its showing just those peculiarities which characterise the script of an epoch some decades later than that to which it refers itself. The regular sign for the medial *ē* in this grant is a curved stroke on the top of the letter, while the short vertical stroke on the left appears only occasionally as representing this letter. The right-hand portion of *gā*, *pa* and *śa* shows the development of long verticals on the right of these signs. The letters *kā*, *ga* and *śa* show distinct

l. 9, *aga* l. 36, *nighri* l. 17, *ncha* l. 6, *nda* l. 2, *ndya* l. 27, *kaha* and *kahmā* l. 14, *jāa* l. 8, *lpha* l. 16, *shēva* l. 4; and lastly final *t* (?) in l. 33.—As regards orthography, the only points worthy of notice are the following: (1) the use of *gha* for *ha* in *rājasighaḥ*, l. 4 (cf. also l. 23); (2) no distinction is made between *b* and *v*; (3) no rule is followed with regard to the use of *anuvāra* in the middle of a *pāda*; (4) wrong conversion of the *anuvāra* into *n* before a sibilant in *likhīḥ-āna*, l. 14; (5) once the use of *da* for *dha* in *dadatā*, l. 5; (6) the use of the vowel *ri* for *ri* in *tripishṭapa* (for *trivishṭapa*), l. 7.—The grant commences with a symbol representing *Om*. Then follows the stanza *su vō-vyād-vēdhasā dhāma*, etc., which stands at the beginning of, I think, all the early Rāshtrakūṭa records. The rest of the composition is also in Sanskrit: the *prastāvi*, the benedictory and imprecatory stanzas being in verse, the grant proper in prose. Most of the verses of this record are repeated with slight verbal differences in one or other of the following grants: the Sāmāṅgaḍ grant of Dantidurga,¹ the Alās plates of Gōvinda II,² the Paithap³ and the Kāvī⁴ grants of Gōvinda III. Of these it approaches closest to the first mentioned, viz. the Sāmāṅgaḍ grant. The four verses 5, 9, 21 and 22 I have not been able to trace anywhere else. In recounting the exploits of Dantidurga all the early Rāshtrakūṭa grants repeat the two well-known verses, *Kāñchitā*⁵ and *sabhrūvibhāṅga*, etc.⁶ Our grant has instead only one stanza, made up of the two half-verses belonging to the two stanzas, a deficiency which, I should imagine, is merely due to the negligence of the scribe. In other respects the execution is satisfactory. And with the help of this text we are placed in a position to correct the extremely corrupt text of the Sāmāṅgaḍ grant with respect to those verses which it has in common with our grant and which do not occur elsewhere.

The grant, as already remarked, is a record of the Rāshtrakūṭa king Kṛishṇa-rāja I. and is of particular importance, being the first record of the king to be discovered so far.⁷ Another grant which refers itself to the reign of Kṛishṇa I. is the Alās grant of his son Gōvinda II, while yet a *yuvārāja*; it was issued in Śaka 692, that is, two years previous to our record.⁸ The genealogy of the Rāshtrakūṭas given in the present grant commences with Gōvinda I., as in all other early grants of this dynasty, excepting the unfinished inscription from the Daśavatāra temple at Ellora⁹; and the details regarding his successors Kakka-rāja and Indra-rāja accord well with what we know of them from other records. Here again, as in the Sāmāṅgaḍ grant, the queen of Indra-rāja is described as being a Chālukyan princess, tracing her descent from the Lunar race on her mother's side. But from the new record we gather some more information about her, which in the mangled version of the Sāmāṅgaḍ grant was distorted beyond recognition. The defective *anushṭubh* half-verse,

Śrīmad-yuvati-gaṇānām sādhetuām-āpa nā(nā) padaḥ |

of the Sāmāṅgaḍ grant, stands for some original like

Śrīmad-Bhavanā nāma sādhetuām-upamāpadaḥ

which I translate with: 'Śrīmad Bhava-gaṇā by name, the (very) standard of comparison

developments of loops, where our record has only straight projections or notches. The middle bar of *ja* approximates more to the vertical, and the lower portion forms a distinct double curve. These facts are clear indications of a later palmographic epoch and raise suspicions against the *bona fides* of the grant. For this and other reasons I am inclined to entertain the gravest doubts regarding the authenticity of the Sāmāṅgaḍ grant. But, as I intend dealing with the question at length in a separate article devoted to the subject, I do not wish to enter into details here.

¹ *JBBRAS.*, Vol. II, pp. 371 ff.; ed. Fleet, *Ind. Ant.*, Vol. XI, pp. 110 ff., and Plates.

² *Ep. Ind.*, Vol. VI, pp. 208 ff., and Plate.

³ *Ibid.*, Vol. III, pp. 105 ff., and Plate.

⁴ *Ind. Ant.*, Vol. V, pp. 144 ff.

⁵ The Kāvī grant, vv. 8, 9; the Sāmāṅgaḍ, vv. 18, 17 (in the reverse order!); the Alās, vv. 5, 6; the Paithap, ll. 11-14.

⁶ Since writing these lines I have come to know of the recent discovery of another record of Kṛishṇa-rāja, viz. the Talegaon (Poona District) plates dated in the year Śaka 690, vide *Progress Report of the Archaeological Survey of India, Western Circle, 1913*, p. 64. [The inscription is published in *Ep. Ind.*, Vol. XIII, pp. 275-282.—F. W. T.]

⁷ Ed. D. B. Bhandarkar, *Ep. Ind.*, Vol. VI, pp. 203 ff.

⁸ Edited by Bhagvanlal Indraji, No. 10 (p. 91) of the separate pamphlets of the *Arch. Survey of West India*

among virtuous and chaste women.' The name of the queen was therefore Bhavaganā. Dr. Fleet translates the corresponding half-verse of the Sāmāṅgaḍ grant as follows : 'She attained the position of honourable young women who are faithful wives.' On comparing my translation with that of Dr. Fleet there will be no doubt as to which reading is to be preferred. Coming to Kṛishṇa himself, in addition to his *birudas* Śubhatuṅga and Akālavārsha, which we know from other inscriptions as well, he appears to have also assumed the title Śrī-pralaya-mahā-varāha. Besides these three *birudas* this record contains no further historical information about him, and it would therefore appear that it was issued in the early part of his reign : at any rate, before the event of the construction of the Ellora temple, which event is described with such pomp and ceremony in a later record of this dynasty.¹

With regard to the charge brought against Kṛishṇa by Dr. Fleet² that he 'had uprooted his relative Dantidurga, who had resorted to evil ways and appropriated the kingdom for the benefit of his family,' I hope this record of Kṛishṇa-rāja himself will have the last word to say and that too in a decided negative. The weak points of Dr. Fleet's theory have already been pointed out with sufficient clearness and force by Mr. Devadatta R. Bhandarkar recently in his article on the Alās plates of Gōvinda II.³ It is here sufficient to point out that Dantidurga was no licentious weakling, but a very powerful and, probably, also a popular king. In fact, he was the first king of his dynasty to assume the title of *Rājādhirāja-Paramāśvara*, or, to quote the words of Dr. Fleet himself, 'he was the real founder of the dynasty.'⁴ In our grant, just as in the Sāmāṅgaḍ grant, he is called the 'sun to the lotus (which was) his family'; both these records lay stress on his devotion to his mother in unmistakable terms. It is, therefore, preposterous to identify the relative of Kṛishṇa 'who had taken to evil ways' with the founder of the dynasty, Dantidurga, who had merited the epithet *sva-kul-ambhoja-bhāskara*. Besides, were Kṛishṇa really guilty of the murder, it is inconceivable that he should have tolerated the eulogy showered upon the murdered uncle in a grant of his own and coolly added that he ascended the throne after the victim of the assassination had gone to heaven!

The formal part of the grant records that the king, being encamped at Nāndī-pura-dvāri, granted on the occasion of a *samkrānti*, at the request of one Madana, the village of Nāgapa-puri to the Bhaṭṭāraka of the temple of Āditya in the town of Udumvara-manti. The concluding verse gives the name of the writer as Vāmana-[nā]ga.

The grant is dated in the Śaka year 694 expired on the third day of the dark half of Āshāḍha, which was, as remarked above, a *Samkrānti*. Dewan Bahadur Swamikannu Pillai, who kindly examined for me the details of the date, informs me that the *tithi* mentioned in our record ended on the 23rd June (Tuesday) A.D. 772, at about one *ghaṭikā* after sunrise; the day was also the first day of the solar month Karkāṭaka by the Tamil rule. The Karkāṭaka *Samkrānti* fell on June 22nd (i.e. on the previous day) at a little before midnight. We are therefore led to assume that in the present case the first day of the civil month was called *Samkrānti*, though the astronomical *Samkrānti* fell on the previous day, a supposition which is countenanced by the practice actually followed in Southern India in certain well-known instances.

TEXT.⁵

[Metres: - v. 1, *Anuṣṭubh* (Śloka); vv. 2-7, *Vasantatilakā*; v. 8, *Anuṣṭubh* (Śloka); v. 9, *Indravajrā*; vv. 10-16, *Anuṣṭubh* (Śloka); v. 17, *Vasantatilakā*; v. 18, *Sārdulavīṭṭita*; vv. 19-24, *Āryā*; vv. 25-26, *Anuṣṭubh* (Śloka); v. 27, defective *Āryā*.]

1 श्री [१] स बोध्यादेवसा धाम यन्नाभिकमलं कृतं [१] हरच यस्य
कान्तेन्दुकलया

¹ R. G. Bhandarkar, *Early History of the Deccan* (Bombay Gazetteer, Vol. I, Part II), p. 196.

² *Kanarese Dynasties*, p. 391.

³ *Ep. Ind.*, Vol. VI, p. 209.

⁴ *Kanarese Dynasties*, p. 389.

⁵ From the original plates and a set of impressions.

⁶ Represented by a symbol.

- 2 कमलंकृतं ॥[१॥*] आसी[द*] द्विपत्तिमिरमुद्यतमण्डलायो ध्वस्तवयवमिमुखो
 3 रण[श]र्वरीषु [१*] भूपः शुचिर्विधुरिवासदिग'त्तकीर्त्तिर्गोविन्दराज इति रा-
 4 ज[सु] राजसिघः^१ ॥[२॥*] दृष्ट्वा च[मू]रमिमुखो[ः*] सुभटादृ(१)हासा [उजा]मितं
 5 सपदि येन रणेपु नित्यं । द[ष्टा]धुरेण^२ द[द]ता भुक्ति[ः*] ललाटे
 खरभं^३
 6 कुलं च हृदयश्च निजश्च गर्व[ः*] ॥[३॥*] तस्यात्मजो जगति वि
 श्रुतदीर्घकी-
 7 त्तिरात्तात्तिहारिविक्रमधामधारी^४ । 'भूपस्तुपिष्टपन्टपानुक्तः
 8 कृतज्ञ[ः*] श्रीकन्नराज इति गोक्षमणिर्वर्भव^५ ॥[४॥*] नास्तेव यस्य र-
 9 मणाद्विवर्त्तिनीना[ः*] रीमाश्चवेपथुश्रुतामरिसुन्दरीणा[ः*] [१*] अ-
 10 [सु]णि^६ वाहुवलयानि मनांसि सद्यः संज्ञा[स]वेगविधुराणि सम[ः*] निपे-
 11 तुः ॥[५॥*] यस्मि[म्]शासति महीश्वरपे द्विजाना[ः*] वीतानधूमनिचयैः
 परिक-
 12 ११वराणि [१*] स[ः*]ध्यासु सौधशिखराणि विलोक्य केकाः कुर्वन्ति
 वैशम्यशिखिनो
 13 जलदागमोक्ताः ॥[६॥*] तस्य प्रभिसकरट्युतदानदन्तिदन्तप्रहारवचि-
 14 रोल्लिखितान्सपीठः^७ । क्षापः चितौ चपितयसुरभू[त्]नूनः सद्राद्वकूट-

Second Plate ; First Side.

- 15 (४)कनकद्विरिवेन्द्रराजः^८ ॥[७॥*] तस्य द्विजजनाग्रान्तग्रान्तिवाचनवारि-
 16 या [१*] प्रत्यहं^९ दुर्लभदन्तेन जनच[र]ति मन्दिरे ॥[८॥*] सेवासमा-
 यातवृद्धः^{१०}
 17 शरैन्द्रहन्दाभिवन्द्य[त्ति]युगस्य^{११} यस्य [१*] अश्वानवज्ञैस्त्रिजगत्प्रवीणैः^{१२} स[ः*]
 18 १२गोच्यते श्री[ः*] १३स्वजनैरजसं ॥[९॥*] पूरिताया शशिर्वस्तध्वान्तज्यो-
 तस्तेव भासतः[ः*] [१*]
 19 राज्ञो सोमान्वया तस्य पिष्टतश्च शुलुक्वजः^{१४} ॥[१०॥*] श्रीमद्वगणा नाम सा-

^१ Read 'दिनल'

^२ Read 'धरेण दधता,

^३ Read 'भूपस्त्रिविष्ट'

^४ Read 'वाहु'

^५ Read 'काद्विरि'. The i-sign of द्वि is appended to the symbol for दृ

^६ Read 'युक्त'

^७ Read 'वध्या'. The i-sign in द्वि seems to be appended to the symbol for दृ.

^८ See note 6 on p. 127,

^९ Read 'जा.

^{१०} Read 'विष्ट'.

^{११} Read 'वृद्ध'. Note 'वृद्ध' masculine!

^{१२} Read 'वर्भव'.

^{१३} Read 'वराणि'.

^{१४} Read 'वृद्ध'.

^{१५} Read 'वृद्ध'.

^{१६} Read 'वृद्ध'.

^{१७} Read 'वृद्ध'.

^१ Read 'सुभटाहासा'.

^२ Read 'हारिविक्रि'.

^३ Read 'शुचि'.

^४ Read 'तासि'.

^५ Read 'सजने'.

30
 32
 34
 36
 38
 40
 42

44
46
48
50
52
54
56

44
46
48
50
52
54
56

- 20 [ध्वो]नामुपमापदं [१*] रक्षणाद्गरणात्कोकं या चकार निरापदं ।[१११*]
सु(स)नयन्त-
- 21 नयं तस्यां स लेभे भूभृदुत्तमः ।(१) 'नीतावर्धमिवाग्ने[ष]जानता-^१
- 22 प्रार्थितायति [११२*] अष्टतेजाः^२[स्व]धामौघः(ः)प्रसाधितदिग[न्त]रं [१*] ओ-
- 23 दन्तिदुर्गराजस्य[—] स्वकुला[भो]जभास्करं ।[११३*] अस्त्राजो^३ रणसिंघस्य^४
वि-
- 24 अस्ता वैरिवारणाः स्वलज्जास्तम्भमुन्मूल्य ज्ञायन्ते कापि [नो] गताः[१*]
।[११४*] [सा]ज्ञा-
- 25 लकानि दुर्गाणि हृदयैः सह विद्विषाम्य[त]न्ति यत्प्रतापेयकोपाहु-^५
- 26 रसमुद्गरे ।[११५*] 'मःतुभक्तिः[१*] प्रतिग्रामं ग्रामलचचतुष्टये [१*]
ददत्वा भू[प्रदा]-
- 27 नानि यस्य भाषा प्रकाशिता ॥[११६*] कांचीशकेरलनराधिपचोलपाण्य-
ओह-
- 28 ध्वज्वटविभेदविधानदत्तं [१*] यो वल्लभं सपदि दण्डव[लि]न^६ जित्वा
रा[जा]-
- Second Plate ; Second Side.*
- 29 धिराजपरमेष्ठरतामवाप ॥[१७*] आसेतोर्विपुलोपलावलिलसत्तो-
लो-
- 30 भिन्नेलावलादाप्रात्येककल[—]*कितामलशिलाजाला[त्तु]धाराचलादापूर्वाप-
- 31 रवारिराग्निपुल्लिगप्रान्तप्रसिद्धावधेः[१*] येनेयं जगती स्वविक्रमवलेनैकात-
- 32 पञ्चोक्तता ॥[१८*] तस्मिन्निदं प्रयाते वल्लभराजे चतुप्रजावाधः^७ [१*]
ओक्तकरा-
- 33 जस्रुतुमंहीपतिः कृष्णराजोभूत् ।[१९*] यस्य स्वभुजपराक्रमनिःशेषोत्सारि-
- 34 तारिदिक्कनं [१*] कृष्णस्वैवाकृष्णं चरितं श्रीकृष्णराजस्य ॥[२०*] विषमेषु
विषमशो-
- 35 लो यस्त्वागमहानिधिर्दरिद्रेषु [१*] कान्तासु वल्लभतरः ख्यातः प्रणतेषु श-
- 36 भतुङ्गः ॥[२१*] सुहृदि धनं रिपुषु शरा^८ युवतिजने काममशरणे शर-
- 37 णं [१*] यः सन्ततमभिवर्धयन्नकालवर्षां भुवि ख्यातः ।[२२*] छल-
घितम-
- 38 "यादे कलिजलधौ व्याकुला निमज्जन्ती [१*] "येनोद्धृता धरत्री^९ श्रीलक्ष्म-
महावरा-

^१ See note 1 on p. 128.^४ Read 'जौ.^५ Read 'नातु'.^६ Read 'शरा'.^७ Read 'रिपी.^२ Read 'जगता-^३ Read 'इस.^४ Read 'वर्ध'.^५ Read 'वादे.^६ Read 'तज'.^७ Read 'तापीय'.^८ Read 'वाध'.^९ Read 'येनी'.

- 39 हेष ।[१२३॥*] तेनेदमनिलविद्युच्चलमवलीक्य जीवितमसारं [१*]
चित्तिदानप-
40 रमपुण्यः प्रवर्त्तितो 'ब्रह्मदायोय[+*] ॥[२४॥*] स च परमभट्टारक-
महाराजाधिरा-
41 जपरमेश्वरश्रीमदकालवर्षश्रीपृथिवीवल्लभनरेन्द्रदेवः सर्वानिव रा-
42 दृपतिविषयपतिभोगपतिप्रभृतोश्चमाज्ञापयत्यस्तु वः 'सम्बिदितं
43 यथा मया मातापिन्नोरात्मनश्च पुण्ययशोभिहृदये । शकनृप-

Third Plate.

- 44 कालातीतसम्बत्सरशतषष्ठे^१ चतुर्नवत्युत्तरे 'चा]न्दीपुरद्वारीस-
45 मावासके आषाढवद्वृत्तीयायां स[+*]क्रान्तौ [म]दन(वि)विज्ञापनया
46 उदुम्बरमन्तिपत्तने कारितादित्यायतनभट्टारकाय उदुम्बरम-
47 न्तिपूर्वती गव्यूतमात्रे णगणपुरिनामग्रामो दत्तः बलि(ः)च[रु]-
48 नेवेद्यपूजाखण्डस्फुटितस[+*]स्कारनिमित्तं । तस्य चाघाटनानि लि-^२
49 ख्यन्ते[१*] पूर्वतः [१]^३ नागामाग्रामः [॥*] दक्षिणतः[१*] उम्बरग्रामः [॥*]
पश्चिम-
50 तः[१*] अन्तरैग्रामः [॥*] उत्तरतः[१*] कपिहो ग्रामः[१*] एवं चतुराघा-
51 टविश्वः पूर्वप्रदत्तदेवमाह्वयवर्ज्यः [१*] तथापरं उम्बरमन्ति-
52 लसीमायां देवतडाकस्थोत्तरतः राजशितडाके^४ पश्चिमतो नदी [१*]
53 एवं नियर्त्तनशत[+*] ।[१*] 'वहृभिर्वसुधा मुक्ता राजभिः[+*] 'शकरादिभि
[ः] * य-
54 ख यस्य यदा भूमिस्तस्य तस्य तदा [॥हृ]र्लं ॥[२५॥*] स्वदत्तां पर[द]-
त्ताम्वा^५ यी
55 हरैत वसुधरां । षष्टिं वर्षसहस्राणि विष्टाया^६ जायते [क]मिः ॥[२६॥*]
शासन-
56 मकालवर्षस्यादेशाल्श्रीमता^७ लगर्हण(?) [१*] 'परहितकृपातुवध्या लिखितं
श्रीवामन[ना]ने[न]^८ ॥[२७॥*]

TRANSLATION.

Om.

(Verse I.) May he (soil. Vishnu), the lotus on whose navel Brahmā has made (his) dwelling, protect you; and Hara (i.e. Śiva), whose forehead is adorned by the beautiful moon-crescent.

^१ Read ब्रह्म°.^२ Read संवि°.^३ Read 'सवि°.^४ Read नान्दी°.^५ Read 'वहृ°.^६ The u-sign (medial) is appended to the symbol for वि.^७ Correct, perhaps, to नागामो वा°.^८ Read 'कस्य.^९ Read 'वहृ°.^{१०} Read सगरा°.^{११} Read फलं.^{१२} Read 'सी वा.^{१३} Read विष्टायां.^{१४} Read 'श्रीमता.^{१५} Read 'कृपातुवध्या°.^{१६} The last quarter of this Āṅgā is defective

(V. 2.) There was a king called Gōvinda-rāja [I.], a royal lion among kings, whose fame reached to the ends of the regions, (and who) pure (of conduct), lifting (his) scimitar (and) facing (them), destroyed his enemies in battles, just as the lustrous Moon, whose glory (i.e. radiance) penetrates to the ends of the regions raising the tip of (his) orb (above the horizon and sending his rays) straight forward, dispels at night the darkness.

(V. 3.) Invariably, when he saw on the battlefield the armies (of the enemies) confronting him, ringing with the loud laughter of warriors, forthwith he, biting (his) lip (and) knitting (his) brow, elevated (his) sword, (his) family, (his) heart and (his) pride.¹

(V. 4.) His son, the glorious Kakka-rāja [I.], was the gem of the (Rāshtrakūṭa) race, a king who was grateful (for services rendered), whose extensive glory was famed throughout the world, who stilled the sufferings of the distressed, (and) possessed the valour and the majesty of the lion, (thus) resembling (Indra), the king of heaven.²

(V. 5.) ³At the mere (sound of the) name of him fell straightway from the wives of his enemies, retreating from the laps of (their) lovers with (their) hair standing on end and trembling, (the following three things :) tears, armlets and also (their) minds, which were deranged by the impetuosity of their fright.

(V. 6.) While this king was governing the earth, the tame peacocks, eager for the advent of clouds, used to break out into cries (of delight), when they in the evenings caught sight of the turrets of his palaces, which were completely gray with the mass of smoke from the oblations of the twice-born (i.e. Brāhmaṇas).

(V. 7.) His son was Indra-rāja, as it were the Mount Mēru of the noble Rāshtrakūṭas, a prince whose expansive shoulders were bright though being scratched through the blows from the tusks of elephants from whose split temples trickled down ichor, and who had destroyed (his) enemies on earth.

(V. 8.) Every day people walked about in (his) palace ankle-deep through the water (sprinkled during) unceasing recitals of śānti-texts⁴ by Brāhmaṇas.

(V. 9.) ⁵The wealth of him, whose pair of feet were worshipped by a large crowd of princes who came to do homage (to him), was perpetually shared by virtuous men⁶ with unclouded countenances.⁷

(Vv. 10, 11.) His queen, who had fulfilled (all) desires (of others);—who was pure like the lustrous moonlight (which), filling (all) regions, destroys darkness;—who was by her mother's side descended from the Moon⁸ and on her father's side from the Chulukyās (Chālukyās), called the glorious Bhavagaṇē⁹—was the standard of comparison among virtuous and chaste women : she freed the world from misery by protecting and maintaining (the needy).

¹ Better perhaps to take *garva* in the sense of *gurutā*—'dignity', 'importance'.

² All the attributes apply to Indra as well. In his case, however, *hari-vikrama-dādma-dhārī* is to be understood in the sense, 'one who supports the place (covered by) the strides of Hari (i.e. Vishnu)', referring to the form of the latter striding over the heavens in three paces. None of the earlier interpretations of this verse take into account this *śiṣha*.

³ This verse is not found in any other Rāshtrakūṭa record.

⁴ These are recited for the averting of evil and the pacification of various deities.

⁵ This verse does not occur in any other Rāshtrakūṭa record.

⁶ *Tri-jagat-pravīṇaḥ* does not convey any sense to my mind, and appears to be a mistake of the scribe who wrote off *tri-jagat* in place of something less familiar. Read perhaps *tri-gaṇa-pravīṇaḥ* and translate : 'by those versed in the triad of duties (viz. *dharma*, *artha* and *kāma*)'.

⁷ I.e. without being made to feel the subservience. ⁸ The Rāshtrakūṭas were themselves also *Sōma-vamśīn*.

⁹ The corresponding verse of the *Sāmāṅga* grant contains a *varietas lectionis* in the first half-verse. See above, p. 122.

(V. 12.) He, the best of kings, begat a righteous son from her like unto material well-being (*artha*) from prudence (*nīti*), (a son who was, as it were) the future prosperity (*āyati*) prayed for by the whole of mankind.¹

(V. 13.) (*him*) who was known as the illustrious king Dantidurga, the sun to the lotus (*that was*) his family, who illuminated the spaces between the regions by the flood of his effulgence, the lustre of which was palpable.

(V. 14.) In the battles with this lion of the martial field the affrighted elephants (*which were his*) enemies, having pulled up by the root the posts (*namely, their*) shame,² have absconded, no one knows where.

(V. 15.) Before the bursting forth of the 'sprouts' of his prowess and (*his*) fierce anger the turreted fortresses of (*his*) enemies fall down along with their hearts.

(V. 16.) His devotion to (*his*) mother was demonstrated by (*the fact of his*) mother's making (*charitable*) donations of land in every village in (*his kingdom of*) four hundred thousand villages.

(V. 17.) Having in no time conquered Vallabha,³ who was (*even*) able to inflict crushing defeats on the lord of Kāñchi, the king of Kērala, the Chōla, the Pāṇḍya Śrī-Haraha and Vajra by the prowess of his arm (*or arms*), he acquired the state of the 'Supreme King of Kings' and 'Supreme Lord.'⁴

(V. 18.) Through the power of his valour he brought under one (*royal*) umbrella this earth from the Sēta, where the coast-mountain has tossing waves flashing along the live of its large rocks, up to the Snowy Mountain (Himālaya), where the masses of spotless rocks are stained by the snow,⁵ as far as the boundary line beautified by stretches of the sandy shores of the eastern and western oceans.

(V. 19.) When that Vallabha-rāja⁶ had gone to heaven, Krishna-rāja, the son of the illustrious Kakka-rāja who relieved the sufferings of (*his*) subjects,⁷ became king.

(V. 20.) The career of that glorious Krishna-rāja, during which the circle of his enemies was completely swept away by the prowess of his own arm, was as stainless as that of Krishna (Vāsudēva),—

(V. 21.) ⁸who is famed to be of fierce disposition towards the fierce, a mighty repository of generosity towards the poor, most dear to women, and towards the prostrate Most-Highly-Gracious (Śubha-tuṅga),—

(V. 22.) who, constantly showering wealth on friends, arrows on enemies, love on young damsels, protection on the helpless, was famed in the world as the Untimely-Showerer⁹ (Akala-varsha),—

¹ This half-verse occurs also in the Sāmāṅga grant. In the *editio princeps* appearing in the *JBBRAS*, this line was read as *nitāraśmīdāśha jagataḥ pālītyati* [h]; but the editor of the inscription did not translate the phrase *nitāraśmī*. Dr. Fleet in his article on the same grant, some time later (*Ind. Ant.*, Vol. XI, p. 112), after examining the plates, corrected the reading to *nitāradāśha* (or *tāśha*), etc., but followed the example of his predecessor in not translating the awkward phrase. The correct reading is evidently supplied by our plates. For the meaning of *āyati*, cf. *Kirātārjunīya* 2, 14: *raḥayaty āpad-upātām āyatiḥ*.

² Dr. Fleet's correction of *salajjā* of his text to *salajjāḥ* is obviously wrong, as his translation does not give a good sense.

³ i.e. the Chālukyan king Kirtivarman II. See Fleet's *Kan. Dyn.*, p. 391.

⁴ See above, p. 122.

⁵ For the idea implied by the word *kalashkita* cf. Kālidāsa's *Kumāra-saṃbhāra*, Canto 1, v.

⁶ A *biruda* of the Western Chālukyan kings, probably adopted by the Rāshtrakūṭas as their successors.

⁷ Bühler's reading *kṛita-prajāśāśha* and translation, 'who did not oppress his subjects' (*Ind. Ant.*, Vol. XII, pp. 182, 187), are both unsatisfactory. Why should he oppress them? As no impression is appended to his article, it is not possible to decide if the reading is not a mislection. *Kāśata-prajāśāśha* corresponds exactly to the phrase *artti-artti-kāśha* in a previous verse, and does not in the least presuppose that his predecessors had oppressed their subjects. [In the Talegaon Plates (*supra*, Vol. XIII, p. 279) Dr. Konow read *kṛita-prajāśāśha*. Perhaps we should here understand *prajāśāśha* as *prajāśāśha*.—F. W. T.]

⁸ This and the following two verses do not occur in any other Rāshtrakūṭa record.

⁹ To be understood in the sense: "raining in season and out of season."

(V. 23.) by which glorious Great-Deluge-Boar (*Pralaya-mahā-varāha*) was rescued the frightened Earth, which was sinking in the Kali ocean, which had overpassed (*its*) boundary.

(V. 24.) He, seeing (*that*) life, which is unsteady like the wind and the lightning, is without substance, established this *brahmadāya*, which is particularly meritorious on account of (*its being*) a gift of land.

(L. 40.) And this *Parama-bhaṭṭāraka Mahārāj-ādhirāja Param-ēvara*, the illustrious *Akāla-varsha*, the Lord of Prosperity and the Earth (*Śrī-prithivī-vallabha*), King of Kings (*Narēndra-dēva*) commands all the governors of kingdoms (*rāshṭra*), governors of districts (*vishaya*), governors of divisions (*bhōga*) and others (as follows) :

(L. 42.) Be it known unto you that,—Six hundred and ninety-four years of the Saka era having elapsed, on (the occasion of) an eclipse, on the third (day) of the dark half of *Āshāḍha*, while encamping¹ at *Nāndī-pura-dvāri*,—in order to increase the religious merit and the glory of (Our) parents and of Ourselves, the village of *Nagaṇa-puri*, (*situated*) at a distance of a *gavyūti*² to the east of *Udumvara-manti*, has been given by Us at the request of *Madana* to the *Bhaṭṭāraka* of the temple of *Āditya* erected in the town of *Udumvara-manti* for the (performance of) *bali*, *charu*, *naivedya*, worship and (repairs of) dilapidations.

(L. 48.) Its boundaries are noted (as under) :

to the east the village *Nāgāma* ;
to the south the village *Umvara* ;
to the west the village *Antarai* ;
to the north the village *Kapiddha*,—

thus determined by (*its*) four boundaries, excepting former gifts to gods and *Brāhmaṇas*; and also the river along the boundary of *Umvara-manti* to the north of the *Dēva-taḍāka* (and) to the west of the *Rājīni-taḍāka*. Thus altogether one hundred *nivartṭanas*.

(V. 25, 26.)

[Two of the customary verses.]

(V. 27.) (*This*) edict was written at the order of *Akāla-varsha* by the illustrious *Vamana-[nā]ga* of benevolent and compassionate nature. . . .

Note by Rai Bahadur Hiralal, Extra Assistant Commissioner, Jubbulpore, C. P.

First of all I take *Udumvaramanti* to be identical with *Umravati*. *Umravati* means the town of *Umar* (*Ficus Glomerata*), the same as the *Udumvara* of the Sanskrit. That the pronunciation and spelling continue to be *Umaravati* in the vernacular will be seen from a cutting of a Marathi-English paper herewith enclosed. Exactly to the east of *Amraoti* at a distance of about 60 miles there is a village named *Antaragaon* in the *Wardha Tahsil* of the *Wardha District*, to the west of which and contiguous to it is another village *Umaragaon*. I take these to be identical with *Antaragrāma* and *Umvaragrāma* of the inscription. *Nagaṇapuri*, the subject of the grant, is not traceable nor *Nāgāma* and *Kapiddhagrāma*, which bounded it on its east and north. The *Umvaragrāma* was to the south of *Nagaṇapuri* and *Antaragrāma* to its west. If there is no mistake in interpreting the record, I should suppose that the villages have, for some reason or other, changed their sites, causing a confusion in the directions of their original positions.

The donor's camp was at *Nandipuradvāri* and I take this to be *Nandora*, 9 miles south of *Antaragaon*.

The villages in the vicinity of *Antaragaon* and *Umaragaon* are *Jherai*, *Borkhedi*, *Chargaon*, *Pipalasenda*, *Wargaon*, *Echora*, *Kamthi*, *Hirora* and *Giroli*, most of them named after trees, as *Kapiddhagrāma* and *Nāgāmāgrāma* appear to be, and apparently the last two have disappeared, giving place to names derived from trees which later on abounded in the place where *Kapiddha* and *Nāgāma* were situated.

¹ *Samāśrānti* can only refer to a dwelling-place, and the preceding word ending in *pura* evidently supports the idea of encampment. Nevertheless, the position of this word expressing locality right in the middle of others expressing time, is a little curious. ² A *gavyūti* is equal to 4,000 *daṇḍas* or two *krōśas* (Monier Williams).

Since some four villages give the clue for identification, we may take it that Nagapuri was situated somewhere at $20^{\circ} 51' N.$ and $78^{\circ} 44' E.$

No. 7.—THE ARA INSCRIPTION OF KANISHKA II: THE YEAR 41.

By STEN KONOW.

This inscription was discovered in an ancient well in a nala known as Āra, two miles from Bāgnilāb, and was presented to the Lahore Museum by Dr. M. A. (now Sir Aurel) Stein. Mr. R. D. Banerji, to whom we owe this information, did not mention where Bāgnilāb is situated. Dr. Fleet therefore made inquiries through Dr. Spooner, and "it would seem that the place is the Chah Bagh Nilab of maps, about ten miles south-south-west from Attock, and apparently on the south bank of the Indus at a part where the river, having made a sharp bend about eight miles below Attock, runs to the west for some ten miles: the latitude and longitude appear to be $53^{\circ} 46'$ and $72^{\circ} 12'.$ "

According to Mr. Banerji, "the inscription is on a small piece of stone, measuring 2 ft. 8 ins. by 9 ins., and consists of six lines. The surface of the stone is extremely rough and uneven. The mason has not taken the trouble of planing the surface."

The inscription was first edited by Mr. Banerji,¹ and then by Professor Lüders.² Some valuable critical remarks were made by Dr. Fleet.³ The inscription is of considerable interest, and, at the instance of Dr. Fleet, I have therefore asked Mr. H. Hargreaves, Superintendent of the Archaeological Survey in the Panjab, to examine the stone closely. This he has very kindly done, and sent me a series of valuable remarks by his assistant Mr. Y. R. Gupta, together with new estampages and some photographs. I have given a preliminary report of the results obtained from these new materials in a paper on the Indo-Scythians,⁴ and I now publish the inscription with a plate prepared from the new estampages.

The characters are Kharoṣṭhī of the Kushana period. With regard to individual letters we may note that the *e-mātrā* has been added at the bottom of the *akshara* in *devaputra*, l. 1, and in every initial *e*. The same is the case in the damaged letter at the end of l. 3, which Professor Lüders reads *pe*, but which I read *de*. The *jha* of *Vajheska*, l. 2, seems to be quite certain. The compound letter which I read *shk* with Professor Lüders has been transliterated *shp* by Mr. Banerji and Dr. Fleet and Mr. Gupta agrees with them. I think, however, that we must read *shk*. In the first place, as pointed out by Professor Lüders, the compound *shk* has exactly the same shape in the Zeda inscription. It is quite true that it is different in *Kanishka*, l. 2, and no doubt every record should, as pointed out by Dr. Fleet, primarily be judged separately on its own merits. This does not, however, imply that we should not take other facts than the mere shape of the individual letters into consideration. It is a well-known fact that the masons who executed the inscriptions were not always or even usually literate persons. We know from an inscription published by Mr. Pargiter⁵ that it was often done in such a way that the inscription was first drawn up with ink, and then executed by the engraver or the mason. This procedure partly accounts for the fact that the same letter often takes different shapes in the same inscription. As pointed out by Professor Lüders, the

¹ *Ind. Ant.*, 1908, pp. 58 ff.

² *Sitzungsberichte der K. Preuss. Akademie der Wissenschaften*, 1912, pp. 824 ff., translated *Ind. Ant.*, 1913, pp. 112 ff.

³ *JRAS.*, 1913, pp. 97 ff.

⁴ *Sitzungsberichte der K. Preuss. Akademie der Wissenschaften*, 1916, pp. 787 ff.

⁵ *Archaeological Survey of India, Annual Report*, 1910-11, pp. 73 ff.

analogy from other Kushāṇa names such as Kanishka, Vāsiṣka, and Huvishka strongly favours the reading *Vajṣhka*. Finally, the compound *shp* does not occur in any other known Kharoṣṭhī inscription.

The name *Kanishka* has been written with a cerebral *ṣ* by Mr. Banerji. In order to justify my reading *Kanishka*, it will be necessary to go into details.

It is a well-known fact that two different *n*-s are used in Kharoṣṭhī, one with a bent head, which the late Professor Bühler treated as the regular sign of the cerebral *ṣ*, and another consisting of a broken line with a curvature at the head, which he transliterated *na*. I have shown¹ that the two signs are regularly distinguished in this way in the Central Asian Kharoṣṭhī manuscript of the *Dhammapada*, and that we can there lay down the rule that every single *n* between vowels became cerebral, while every initial *n* and every double *n* between vowels was dental. This is the same state of things which prevails in a series of modern vernaculars, and it should be noted that the cerebral pronunciation of a single intervocalic *n* is strongly rendered in Sindhi and other north-western tongues. We may safely infer that such was the case in the ancient speech of North-Western India, more especially if we bear in mind that the dialect of the *Dhammapada* manuscript certainly is a North-Western Indian form of speech. We would then naturally expect to find at least distinct traces of a similar distribution of the two *n*-sounds in Kharoṣṭhī inscriptions. Nobody will, of course, think of judging these records after the exigencies of Sanskrit grammar. If we now examine the more important ones from this point of view, and assume, for the sake of argument, that the two signs are distinguished in the same way as in the Kharoṣṭhī manuscript of the *Dhammapada*, we will find that the following is the state of things:

In the Taxila vase inscription of Sihla and Siharachhita only *ṣ* occurs, and always between vowels. The same is the case in the Muchai inscription of Sam. 61.

The Taxila plate of Patika has initial *n* in *nama*, *nagare*, *navakarmika*, and single *n* between vowels in *utarena*, *Sakamunisa*, *Rohinimitrena*. On the other hand, we find against the rule *sarvabudhana* and *mahadanapati*, where it is perhaps possible to think of the influence of Sanskrit.

The Mahaban, Paja, Kaldarra, Panjtār and apparently also the Takht-i-Bāhi inscriptions only have *ṣ*, and always between vowels. On the Mathurā lion capital, on the other hand, we only find dental *na*. The Taxila inscription of Sam. 136 uses *ṣ* throughout, even when the *n* is initial. It will be seen that this is in accordance with the practice in the old Prakrits, and in both cases it is possible that we have here to do with an attempt at generalizing such features as were not clearly understood. At least I have grave misgivings about the use of a cerebral initial *ṣ* in the Prakrits.

I am unable to make any statement with regard to the Dewal inscription of Sam. 200 and the Skārah Dhērī inscription of Sam. 399, though the latter certainly in some cases writes *ṣ* between vowels.

The Loriān Tangai inscription of Sam. 318 has only *ṣ* and always between vowels, while no *n* occurs in the Hashtnagar image inscription of Sam. 384.

If we turn to the inscriptions of the Kanishka group, we have first the Sue Vihar inscription of Sam. 11, which is throughout under the influence of Sanskrit. Here the only instance of a cerebral *ṣ* is in *viharavamini*.

The interpretation of the Zeda inscription is too uncertain to allow any inference. There are however some certain instances of *n* between vowels.

In the Māpikīāla inscription of Sam. 18 we regularly find *n* in *navakarmigena* and *ṣ* in *kaneshkasa*, *gushona*, *dadanayago*, *vespasiena*, *kujachiena*, *Buritena*, *viharakarafaena*, *samvopa*,

¹ *Zeitschrift für Indische und Iranische Philologie*, p. 88.

parivareṇa, eṭeṇa and *Budhileṇa*. Against the rule is *ṇaṇa*, where however the reading as well as the interpretation are extremely doubtful, and further *apanage, taena, kuṭalamulena* and *sachha[?] sana*. I do not think that these few exceptions in any way invalidate the rule, at least if we bear in mind what has been said about the way in which old inscriptions were engraved. The two short Kharoṣṭhī records from Māpikiāla published by Mr. Pargiter¹ have no instance of the dental *ṇ*, and the cerebral *ṇ* only occurs, in accordance with the general rule, between vowels.

The Shakardarra inscription of Sam. 40 has *ṇ* in *nikame* and always *ṇ* between vowels.

In the Āra inscription *ṇ* only occurs between vowels and is always cerebral with the exception of the dental *ṇ* in *Kanishkasa*.

The Wardak vase inscription of Sam. 51 is of the same kind as the Taxila inscription of Sam. 136, *ṇ* being used throughout, even when it is initial.

The Ohind inscription of Sam. 61, on the other hand, uses only *ṇ*.

N is always cerebral and occurs only between vowels in the Lahore Museum inscription of Sam. 68, the Jhaoli copper plate inscription, and some minor records, such as the inscriptions on the Lahore image No. 206, the Chārsada pedestal, the Swāt Buddha statuette of Buddhāmītra and Buddhānāhita, and the Swāt bas-relief of Simhamītra. In the Pālāṭu Dhēri pedestal inscription, on the other hand, we find *ṇ* alone used, and, so far as I can judge, that is also the case in the inscriptions in the Kanishka stūpa, though I am not certain about the word which Dr. Spooner reads as *nasakarmī*.

It will be seen that the most serious exception to the rule is the inscription on the Mathurā capital, and I think that even this exception can be satisfactorily explained. I hope to have shown² that the old language of the Śakas and the Kushāṇas was of the same kind as the old Iranian tongue spoken in ancient Khotan, and here the cerebral *ṇ* occurs only as a secondary development of an old dental *ṇ* combined with some other consonant. It is therefore quite natural that the Śakas who engraved the Mathurā inscription were influenced by the phonetic features of their own language. The form *Kanishka* in the Āra inscription must be explained in the same way. This name is certainly not Indian, but was coined in accordance with the rules of the old language of the Kushāṇas. Its *ṇ* must therefore originally have been dental, and, if it is often written as a cerebral in Indian records, that is due to the influence of the Indian dialect adopted by the Kushāṇas.

I think we have to infer from a consideration of the entire material at our disposal that the old Aryan language which is used in the Kharoṣṭhī inscriptions did in fact distinguish the dental and the cerebral *ṇ* in the same way as the Kharoṣṭhī manuscript of the *Dhammapada*. Though we have no certain instances of a doubled *ṇ* between vowels, we can safely assume that every initial *ṇ* and every compound *ṇ* between vowels was dental, while every single *ṇ* between vowels became cerebralised. The few exceptions can be explained through the phonetic tendencies of the Indo-Scythians themselves, through the influence of Sanskrit, and through the ignorance of the masons and sometimes also of the scribes. At all events, I think I am justified in transliterating the two letters in accordance with Professor Bühler's table and the state of things in the *Dhammapada* manuscript.

The reading and interpretation of the inscription still present many difficulties, and it will be necessary to make some additional remarks.

In l. 1 the only crux is the last word, which Mr. Banerji reads *paṭhadarasa*, Professor Lüders *kaśarasa*, while Dr. Fleet remarks that the only certain *akṣara* of the whole word is the last one. Mr. Gupte states that the reading *kaśarasa* seems to be the right one. The first

¹ *Ep. Ind.*, Vol. XII, pp. 299 f.

² *Sitzungsberichte*, 1916, pp. 787 ff.

akshara is not, he says, on a line with the others and is small. Its upper part is a little damaged. The letters *sa* and *ra* can be read on the stone, but have not come out in the impressions. I may add that some photographs which I owe to the kindness of Mr. Hargreaves corroborate Mr. Gupte's statement.

Dr. Fleet has drawn attention to the fact that after *kaīsarasa* there is space for two more syllables. He says, "Lines 2 to 5 all end exactly one below the other.¹ We have no reason for thinking that the writer of the record would not run out line 1 to just the same measure. We can also see distinct indications that the writer did, in fact, put in two more syllables here, and so did make all the lines of equal length." I have asked Mr. Hargreaves to pay especial attention to this point, and he declares positively that, after a careful examination of the stone, he can find no traces of any letter after the *sa*. Mr. Gupte is of the same opinion and adds : "The estampages lead us astray owing to the roughness of the stone. Something looks like *ma*, and then comes a line which at first sight may be mistaken for a damaged *ta* or *ra*. Certainly there is sufficient room for two letters. But they were not cut, perhaps owing to the roughness of the material. After careful inspection the delusion about the letters vanishes. The supposed *ma* of the estampages looks too small and is much above the ordinary level of the line, and, if we examine the stone itself, we feel sure that it cannot be a letter. The ruggedness of the stone itself is responsible for the deception." It seems to me that we must accept this definite statement, and we have to admit that the title *kaīsarasa* was indeed used by Kanishka II. Nor can there be any doubt that we have here the imperial title of the Roman emperors.

In l. 2 the reading *sambatśaraē* is certain. As pointed out by Professor Lüders, we similarly find *sambatśaraye* in the Patika inscription and *sambatśaraye* in the Mahabhan inscription. Dr. Thomas has² further found *sambatśaraē* in the Takht-i-Bāhi inscription, and also in the Paja record³ we must read *sambatśaraē*, and the Sas Vihar inscription evidently has *sambatśaraē*. We find the same *ts* in this word in the Kharoṣṭhi records. No. XV 155 (*sambatśaraē 20 1 mahānuvā maharaya Jitroga(?) Mayiri devaputrasa mase 2 divase 10 4 1 iśa chhūṇami*), XV 166 (*sambatśaraē 10 1 mahānuvā maharaya Jitroga(?) Māiri devaputrasa mase 2 divase 4 4 iśa chhūṇami*) and XV 2 (*sambatśaraē 10 mahānuvā maharaya Jitroga(?) Vashmana devaputrasa mase 4 1 1 divase 10 iśa chh[u]ṇami*) from Niya.⁴ I think the combination *ts* represents an unsuccessful attempt at writing the word correctly. The pronunciation was no doubt *chh*. The *ḍ* in the Takht-i-Bāhi and Āra inscriptions agrees with the phonetic treatment of such compounds in the Kharoṣṭhi manuscript of the *Dhammapada*.⁵

The reading of the date *ekachaparisaē sam 20 20 1 Jeṭṭhasa masasa di 20 40 1 iśe divasa chhūṇami* is according to Mr. Gupte almost certain. Only he thinks that the final vowel of *ekachaparisaē* is *i* and not *e*, and I follow him in reading so.

I have already remarked that I read the last word of l. 3 *khade* and not *khane*. Compare *kuvo khadao* in the Shakardarra and *kue karite* in the Paja inscription. In the Zeda inscription I would likewise read *khade kue muraḍasa marjhakasa Kanishkasa rajami*. The forms with *e* I think are nominatives.⁶

The second word of l. 4 was read *Dashaverana* by Professor Lüders. Mr. Gupte says the reading is very uncertain, especially the first letter. It seems to me, however, that the *da* is almost certain. The second *akshara* is probably *sha*, but might also be *ṣa*. The third cannot, I think, be *ve*. I think I can distinctly read *fa*, and in one of the photographs there is a clear *o-mātrā* at the bottom, as will be seen from the reproduction of the *akshara* on the margin. The fourth *akshara* may be *te* or *re*, and I think *te* is more likely than *re*, because the lower perpendicular is slightly curved; compare the

¹ He seems to have overlooked the damaged final *akshara* of l. 3 and perhaps an *akshara* at the end of l. 4.

² *JRAS.*, 1913, p. 636.

³ Cf. Stein, *Ancient Khotan*, Vol. II, Pl. XCIV, XCV, CIV.

⁴ Cf. *Sitzungsberichte*, 1916, p. 806.

⁵ *Ind. Ant.*, 1908, p. 65.

⁶ Cf. *Festschrift Windisch*, p. 91.

ta in matara in the same line. I therefore read *Dashafoteṣa*.¹ So far as I can see, an instrumental is exactly what we would expect in this place.

The following word or words are certainly, as Professor Lüders thinks, *Poshapuria putraṇa*. It follows however from the reading *Dashafoteṣa* that this can only be a mistake for *Poshapuria putreṇa*. Professor Lüders thinks that *putra* here means "member of," "belonging to." The frequent mention of the father's name in similar records, however, in my opinion makes it more likely that *Poshapuria* is the genitive of the name of Dashafota's father. Now we know² that several Saka names ended in *i*, the regular termination of the nominative singular in the old Iranian language of Khotan, and these names in Kharoṣṭhi inscriptions commonly form their genitive in *ia* or *ya*; compare *Ayasia* on the Mathurā lion capital; *Indafria* in the Taxila inscription of Sam. 136; *Datia* in the Kaldarra inscription of Sam. 113; *Kavītia* on the Mānikāla bronze enket and *Karagulya* in the Wardak vase inscription. I therefore read *Poshapuriaputr[e]ṇa*, "by the son of Poshapuri."

The last word of l. 4 was read *puya* by Professor Lüders, and Mr. Gupte thinks he can see *pupha* or *puka*. The last *akṣhara* does not look like a *ya*, because the left leg has been prolonged upwards. Still I think we must read *puya*, because this word is necessary in the context. I think I can see traces of a letter after *ya*, which would then come exactly underneath the *de* of *kḥāde*, and I read *puyae*.

The first word of l. 5 is according to Mr. Gupte certainly *atmaṇasa*: the stroke on the right hand side of the first *akṣhara* visible in the plate is due to the roughness of the stone.

The fifth line is quite uncertain. The first word is perhaps *jaṭiṣṭu*, though none of the *akṣharas* is certain. The next I read with Lüders *hitae* though the first *akṣhara* does not look like *hi*, but might be *i*. Perhaps *sthitae* is intended. The third word has been read *ima* by Professor Lüders and *hima* by Mr. Banerji. The first *akṣhara* consists of two curves facing the left and separated by a horizontal stroke. Underneath there is moreover an incomplete circle, which might represent an *anusvāra*; compare (*ma*)*ham(tasa)* in the Patika inscription. The following *akṣhara* is certainly *mo*. In my Indo-Scythian contributions I proposed to read *dhaimochala*, which might mean "religious expenditure." The horizontal cross-bar is however so pronounced that I think we must read *imo*. *Imo* is used as the accusative sing. of *ayam* in the Mathurā Lion Capital, and in the Prakrits the base *ima* is also used in the neuter. The next two *akṣharas* are *chala*. I am inclined to separate *cha*, "and," and *la*, which I take to be an abbreviation of *loka*, a lakh. The following sign is the numeral 1, and thereafter I would read *khipam[i] dhamada[ṇa]*. The sign which I now agree with Messrs. Banerji and Lüders in reading *khi* I formerly thought to be the numeral 100, which had a similar form in a hand-copy of the Taxila record of Sam. 136 which I owe to the kindness of Sir John Marshall. After having seen the published fac-simile plates of that record, however, I do not think this explanation possible. The *pa* of *khipami* can also be read *ya*, compare *puya[e]*, l. 4, and it was read so by Professor Lüders. It is however almost identical with the *pa* in *saputrasa*, l. 3. The *i* of *mi* is very indistinct, though, I think that I can see it.

If this reading is correct, it will be necessary to translate *khipami* "I throw in," "I expend"; compare the meaning of *khip* in *nikhēpa*. I would accordingly translate: "and I expend this (or, here) one lakh as a religious gift." We may compare the Panjtār record, where I would propose to read *Sak 1 100 20 1 1 Śravanasa masasa di pradhame* (or, *prathame*) *1 maharayasa Gushanasa rajami Kasnasa pracha[deṣo] Moike Urumuṣa-putre karavide divathale tatra cha (?) me dana mita* (or perhaps *kḥita*) *taṇka 1 1*, "in the year 123, on the first day of the month Śravana, during the reign of the Mahārāja, the Gushapa,

¹ In my paper in the *Sitzungsberichte*, I have compared the Scythian name *Spargaphotes*, Thomas, *JRAS*, 1906, pp. 205 and 209.

² Cf. Lüders, *Sitzungsberichte*, 1913, pp. 419 ff.; Kenow, *ibidem*, 1916, p. 708.

a Śiva temple (?) was caused to be constructed in the eastern quarter of Kasu by Moika, the son of Urumuja. And there two *tanikas* were measured (or, expended) by me as a gift." Here we have a similar addition about a money gift and the same change of the person of the subject.

I give this explanation with great diffidence, but I cannot suggest a better one.

The inscription is dated on the 25th day of the month *Jetha* (*Jyēshṭha*) in the year 41, during the reign of the *mahārāja*, the *rājātirāja*, the *devaputra*, the *kāśara* Kanishka, the son of Vajheshka. Mr. Banerji was of opinion that the Kanishka of the Āra inscription is the famous Kushaṇa, of whom we already possess a number of inscriptions. I agree with Professor Lüders and Dr. Fleet that that cannot be the case. Professor Lüders thinks that Vajheshka, the father of this second Kanishka, is the same Kushaṇa king who is elsewhere called Vāsishka, and that the year 41 must be one of the Kanishka era. After Vāsishka's death he accordingly assumes that the kingdom was divided, Kanishka II ruling in the north, while Huvishka held sway in India proper. Later on, however, Huvishka also became master in the north. Dr. Fleet, on the other hand, thinks that Vāsishka and Vajheshka, or, as he prefers to read, Vajheshpa, were two different persons, and that Kanishka II should be placed after Huvishka and Vāsudēva. He thinks that there was a revival of the line of Kanishka I some time after Vāsudēva, and that the Māpikīla and the Āra records bear testimony to this revival. If I understand him right, these inscriptions would consequently be dated in another era and not in the one instituted by Kanishka. The chief difficulty, from Dr. Fleet's point of view, seems to rest with the fact that it is hardly conceivable how the title *kāśara* could have been adopted in India in the year 41 of the Kanishka era, supposing, as Dr. Fleet does, that this era is identical with the Vikrama era. I cannot see, however, how it is possible to maintain this latter view any longer after the results of Sir John Marshall's excavations at Taxila. It supposes that the Kanishka group preceded the Kadphises kings, and in that case it would be impossible to understand the fact that the strata of the Kadphises kings always lie at a deeper level than those of Kanishka and his successors.

If we admit that the Kanishka era is different from the Vikrama one, we have to choose between two possibilities. Either Kanishka established the Śaka era, as Professor Oldenberg and others maintain,¹ or his era starts from a point which has still to be settled. For the elucidation of this question it may prove of interest to examine how the oldest Kharoṣṭhī and Brāhmī inscriptions are dated.

I first turn to the Kharoṣṭhī records, and primarily to those which I would think are dated in the same era as the Taxila plate of Patika. I agree with Dr. Thomas² in thinking that this era must have been of Śaka institution.

1. Taxila inscription of Patika: *Samvatsaraye aṭhasatatiṃśas 20 20 20 10 4 4 Mahārājasa mahāntasa Mogasa Pa[nemasa] masasa divase pañcama 41*, "in the seventy-eighth year, 78, (during the reign) of the Mahārāja the great Moga, on the fifth, 5., day of the month Panema."

Muchai inscription: *vashe ekasitimaś 20 20 20 20 1*, "in the eighty-first year, 81."

3. Mahaban inscription: *sa[m]vatsaraye 1 100 2*, "in the year 102."

4. Takhi-i-Bāhi inscription: *maharajasa Gudufarasa vasha 20 4 1 1 sambatsarase ittiatiṃśas 1 100 1 1 1 Vetakhasa masasa divase prathame di 1*, "in the 26th year of Mahārāja Gudufara, in the hundred and third year, 103, on the first day, d. 1., of the month Vaiśākha."³

¹ Cf. Thomas, *JRAS.*, 1914, p. 990.

² *JRAS.*, 1913, p. 637.

³ The usual reading is *divase pañcama 5*, where the figure 5 is the numeral symbol of the Brāhmī.

5. Paja inscription : *saṁvatsāre ekadate [śa*]timae 1 100 10 1 Śravanasa masasa di[va]se pañchadate 10 4 1*, "in the one-hundred-and-eleventh year, 111, on the fifteenth, 15., day of the month Śrāvāṇa."

6. Kaldarra inscription : *vasha 1 100 10 1 1 1 Śravanasa 20*, "year 113, the 20. of Śrāvāṇa."

7. Panjtār inscription : *Sam 1 100 20 1 1 Śravanasa masasa di pradhame* (or, perhaps, *prathame*) *1 maharajasa Gushanasa rajami*, "anno 122, on the first, 1., day of the month Śrāvāṇa, during the reign of the Mahārāja the Gushaṇa."

8. Taxila inscription of the Khushaṇa king : *Sam 1 100 20 10 4 1 1 ayasa Ashadasa divase 10 4 1*, "anno 136, on the 15. day of the first month Āshāḍha."

9. Dewal inscription : *Sam 2 100 Vesakhasa masasa divase aṣṭhame 4 4*, "anno 200, on the eight, 8., day of the month Vaiśākha."

10. Loriyān Tangai image inscription : *Sa 3 100 10 4 4 Proṭhavadasa di 20 4 3*, "anno 318, on the 27. day of Prōṣṭhapada."

11. Hashtnagar image inscription : *Sam 3 100 20 20 20 20 4 Proṭhavadasa masasa divasammi pañchami 4 1*, "anno 384, on the fifth, 5., day of Prōṣṭhapada."

12. Skarah Dhērī image inscription : *vasha ekupañchādāsatimae Ashadasa masasa di 10*, "in the three-hundred-and-ninety-ninth year, on the 10. day of the month Āshāḍha."

Then follow the records of the Kanishka group :

13. Sue Viḥar' inscription : *Maharajasya rajatirajasya devaputrasya Kanishkasya savatsāre ekadate 10 1 Daisikasya masasya divase aṣṭhame di 20 4 4*, "in the eleventh, 11., year of the Mahārāja, the Rajatirāja, the Dēvaputra Kanishka, on the twenty-eighth day, d. 28., of the month Daisika."

14. Zeda inscription : *Sam 10 1 Ashadasa masasa di 20 Utaraphaguna (?)*, "anno 11, on the 20. day of the month Āshāḍha, in Uttaraphāḡunī."

15. Brass box lid inscription : (JRAS., XX, Pl. 1-3) : *Sam 10 4 4 sasthehi 10*, "anno 18, after 10 days" The remainder of this inscription has not been made out. The last word before the date is perhaps *Kanishka*.

16. Mānikīālā inscription : *Sam 10 4 4 etra purvae maharajasa Kaneshkasa Kartiyasa masa divase 20*, "anno 18, on the 20. day of the month Kārttika, at the said date, (during the reign) of the Mahārāja Kanishka." I think this is the correct translation, though I admit that the order of words is irregular. That is however also the case in the Zeda inscription, where we find *muraḍasa marjhakasa Kanishkasa* not only after *ite chhūnamī*, but even after the words *khade kue*. Besides I do not think that the construction of *Kaneshkasa* with *Gushanavatasamvardhaka* is free from objection. In Sanskrit it would hardly be possible to form such a compound *śāpēkshatvā*, because it is not at all *gamaka*.

17. Hidda inscription¹ : *Sambattaras aṭṭharisatihi(tii) 20 4 4 mass Apelas sasthehi dafaki 10*, "in the twenty-eighth, 28., year, in the month Apelaiois, when ten, 10, (days) had passed."

18. Shakardarra inscription : *Sam 20 20 Proṭhavadasa masasa divase vitami di 20*, "anno 40, on the twentieth day, d. 20, of the month Prōṣṭhapada."

19. Āra inscription : *maharajasa rajatirajasa devaputrassa kaisarasa Vajreshkaputrassa Kanishkasa sambattaras ekachoparisai sam 20 20 1 Jephasa masasa di 20 4 1*, "in the forty-first year, anno 41, (during the reign) of the Mahārāja Rajatirāja Dēvaputra, the Kaisar, the son of Vajreshka, Kanishka, on the 25. day of the month Jyāishṭha."

¹ See Thomas, *Jo. R. Asiat. Soc.*, 1915, pp. 91 ff.

20. Wardak vase inscription: *Sam 20 20 10 1 masya Arthamesiya sasthehi 10 4 1*, anno 51, after 15 (days) of the month Arthamesi had passed."¹

21. Ohind inscription: *Sam 20 20 20 1 Chetrasa mahasa divasa ahami*, "anno 61, on the eighth day of the month Chaitra."

22. Lahore Museum inscription of Sam 68: *Sam 20 20 20 4 4 Proshavatasa masasa divasa shodase 10 4 1 1*, "anno 68, on the sixteenth, 16., day of the month Proshthapada."

23. Jhaoli copper plate: *savatsa . . . ma di 10*, "in the . . . th year, on the 10. day."

It will be seen that a common way of dating runs through all these inscriptions. First the year is given and afterwards usually the name and the day of the month. In four cases, Nos. 1, 13, 17 and 20, the month is not an Indian, but a Macedonian one. In the oldest dated inscription from India proper, the Beasagar epigraph, the month is not mentioned. We read only (Lüders, *List*, No. 669) *raño Kāśiputasa Bhāgabhadrasa trātārasa vasēna chatudasēna rājēna vadhamānasa*, "of the king Kāśiputra Bhāgabhadra, the Saviour, increasing with the fourteenth year in his reign," i.e. only the regnal year of the king is mentioned. Similarly in the Pabhsā inscription of Udāka (Lüders, No. 904) we read [*Udākasa*] *dasamē savacharē*, "in the tenth year of Udāka." We shall have to reckon with the possibility that the use of eras and the mention of the name of the month was not an old Indian institution, but brought into the country by the Indo-Scythian invaders.

Let us now turn to such Kushana inscriptions as were intended not for the frontier districts, but for India proper. The materials are now conveniently put together in Professor Lüders' *List*. I disregard inscriptions where the name of the king is not mentioned, or where the date is too damaged to yield any certain result:

No. 925: *Mahārājasya Kāṇishkasya sam 3 hē 3 di 20 2*, "(during the reign) of the Mahārāja Kāṇishka, anno 3, the 3. (month of) winter, the 22. day."

No. 18: *Dēvaputrasya Ka[ni]shkasya sa[m] 5 hē 1 di 1*, "(during the reign) of the Dēvaputra Kāṇishka, anno 5, the 1. (month of) winter, the 1. day."

No. 21: *Mahārājasya rājātirā[ja*]sya dēvaputrasya Shāhi Kāṇishkasya sam 7 hē 1 di 10 5*, "(during the reign) of the Mahārāja Rājātirāja Dēvaputra Shāhi Kāṇishka, anno 7, the 1. (month of) winter, the 15. day."

No. 22: *Mahārājasya Kāṇishkasya rājyasamvatsarē navamē [9 vāsa] māsē pratha 1 divasē 5*, "in the ninth, 9., year of the reign of the Mahārāja Kāṇishka, in the first, 1., month of the Rains, on the 5. day."

No. 23: *Mahārājasya dēva[putrasya] Kāṇishkasya savatsarē [10] gri 2 di 9*, "(during the reign) of the Mahārāja Dēvaputra Kāṇishka, in the 10. year, in the 2. (month of) summer, on the 9. day."

No. 149a: *Mahārājasya r[ā]jāt[ī]rājasya dēva[pu]trasya Shāhēr-Vāśishkasya rājyasamvatsarē [cha]turviṃśē 20 4 gr[ī]śhmāmāsē chaturthē 4 divasē trīmśē 30*, "in the twenty-fourth, 24., year of the reign of the Mahārāja Rājātirāja Dēvaputra Shāhi Vāśishka, in the fourth, 4., month of summer, on the thirtieth, 30., day."

No. 181: . . . *sya rājātirājasya [dēva]putrasya Shāhi Vāsishkasya sam 20 8 hē 1 di 5*, "in the 28. year (during the reign) of the [Mahārā]ja Rājātirāja Dēvaputra Shāhi Vāsishka, in the 1. (month of) winter, on the 5. day."

No. 33: . . . *[Vā]s[ī]shkasya rājyasamvatsarē 20 8 hē manta 3 di . . .*, "in the 28. year of the reign of . . . Vāśishka, in the 3. (month of) winter, on the . . . day."

¹ Cf. my edition of this record *Sitzungsberichte*, 1916, pp. 307 ff.

No. 35: *Mu . . . ra . . . sya dēva[pu]trasya [Hu]kshasya ēkunatt[sa] . . .*, "in the twenty-ninth [year] of the *Ma[hā]ra[ja] Dēvaputra Huksha*."

No. 13a: . . . *Huvishkasya saṁ 30 1 di 20*, "in the 31. year (during the reign) of *Huvishka* . . . on the 20. day."

No. 38: *Maharajasya dēvaputrasya Huv[is]hkasya saṁ 30 3 gri 1 di 8*, "in the 33. year (during the reign) of the *Mahārāja Dēvaputra Huvishka*, in the 1. (month of) summer, on the 8. day."

No. 151a: *Maharajasya dēvaputrasya Huvishkasya saṁ 30 5 hēmata . . .*, "in the 35. year (during the reign) of the *Mahārāja Dēvaputra Huvishka*, (in the . . . month of) winter . . ."

No. 41: *[Ma]h[ā]r[aj]asya dēvaputrasya Huvishkasya saṁ 30 8 hē 3 di 10 1*, "in the 38. year (during the reign) of the *Mahārāja Dēvaputra Huvishka*, in the 3. (month of) winter, on the 11. day."

No. 149b: *Maharajasya rajatirajasya Huvishkasya savatsara chatarita 40 hēmatamāsē 2 divasē 20 3*, "in the fortieth, 40., year (during the reign) of the *Mahārāja Rajatirāja Huvishka*, in the 2. month of winter, on the 23. day."

No. 43: *[Mahārā]jasya Huvishkasya dēvaputrasya sa 40 5 va 3 di 10 5*, "in the 45. year (during the reign) of the *Mahārāja Dēvaputra Huvishka*, in the 3. (month of) the Rains, on the 15. day."

No. 45a: *Mahārā]jasya Huvishkasya savachara 40 8 va 2 di 10 7*, "in the 48. year (during the reign) of the *Mahārāja Huvishka*, in the 2. (month of) the Rains, on the 17. day."

No. 46: *Mahārā]jasya Huvishkasya sa 40 8 hē 4 di 5*, "in the 48. year (during the reign) of the *Mahārāja Huvishka*, in the 4. (month of) winter, on the 5. day."

No. 51: *Mahārā]jasya dēvaputrasya Huvishkasya rajyasam 50 hē 3 di [2]*, "in the 50. year of the reign of the *Mahārāja Dēvaputra Huvishka*, in the 3. (month of) winter on the 2. day."

No. 42: *Sarasatama[r] . . . maharajasya Huvishkasya savas[is]rē aṣṭapana gri[s]yamasa 8 divasa 2*, "in the fifty-eighth year (during the reign) of the *Sarasatama (?) Mahārāja Huvishka*, in the 3. month of summer, on the 2. day."

No. 56: *Ma[hā]r[aj]asya r[aj]atirajasya dēvaputrasya Huvashkasya saṁ 60 hēmatamāsē 4 di 10*, "in the 60. year, (during the reign) of the *Mahārāja Rajatirāja Dēvaputra Huvashka*, in the 4. month of winter, on the 10. day."

No. 60: *Mahārā]jasya r[aj] sya dēvaputrasya Vāsu . . . savatsarē 70 4 varsham[ā]sē prathamē divasē trisē 30*, "in the 74. year (during the reign) of the *Mahārāja Rajatirāja Dēvaputra Vāsu(dēva)*, in the first month of the rains, on the thirtieth, 30., day."

No. 66: *Maharajasya Vāsudēvasya saṁ 80 hapa va 1 di 10 2*, "in the 80. year (during the reign) of the *Mahārāja Vāsudēva*, in the 1. (month of) the Rains, on the 12. day."

No. 68: *Mahārā]jasya Vāsudēvasya saṁ 80 3 gri 2 di 10 6*, "in the 83. year (during the reign) of the *Mahārāja Vāsudēva*, in the 2. (month of) summer, on the 16. day."

No. 69a: *Mahārā]jasya rajatirajasya dēvaputrasya Shāhi-Vāsudēvasya rajyasam[ā]vatsarē 80 4 grihmatamāsē doi 2 di 5*, "in the 84. year of the reign of the *Mahārāja Rajatirāja Dēvaputra Shāhi Vāsudēva*, in the second, 2., month of summer, on the 5. day."

No. 72: *Mahārā]jasya rajatirajasya Shāhi-Vāsudēvasya saṁ 80 7 hē 2 di 30*, "in the 87. year (during the reign) of the *Mahārāja Rajatirāja Shāhi Vāsudēva*, in the 2. (month of) winter, on the 30. day."

No. 76: *Rajā Vāsudēvasya savatsarē 90 8 varshamāsē 4 divasa 10 1*, "in the 98. year (during the reign) of *Rajā Vāsudēva*, in the 4. month of the Rains, on the 11. day."

It will be seen that we have here to do with a different way of dating. The name of the month is not given. Instead the season is mentioned and the number of the month within the season. If we bear in mind that all these inscriptions are written in the Brāhmi alphabet, which we might style the national Indian script, and that they were all issued in India proper, it becomes likely that this change in expressing the dates is due to the influence of national Indian methods.

So far as I can see, we possess two other ancient inscriptions which immediately present themselves for comparison, viz.

No. 949 : *Maharajasya Trikamatasya sa 60 4 gri 3 di 5*, "in the 64. year (during the reign) of the *Mahārāja Trikamata*, in the 3. (month of) summer, on the 5. day," and,

No. 59 : *Sv[ā]misa mahākshatrapasa Śōḍāsa savatsarē 70 2 hēmantamāsē 2 divasē 9*, "in the 72. year (during the reign) of *Svāmin Mahākshatrapa Śōḍāsa*, in the 2. month of winter, on the 9. day."

Of these I have not sufficient materials for judging about the Bōdh Gayā record No. 949.¹ The Śōḍāsa inscription, which hails from Mathurā, like most of the Brāhmi inscriptions of the Kushanas, is, to judge from paleography, certainly older than them.

We do not know for certain in which era the Śōḍāsa inscription of Sam. 72 is dated. I do not think it possible that it can be the same as in the Taxila plate of Sam. 78. I think that Patika, who issued that record, is identical with the Mahākshatrapa Padika of the Mathurā lion capital, which mentions Śūḍasa, i.e. Śōḍāsa, as Kshatrapa. In the Taxila plate Patika is not even Kshatrapa. Dr. Fleet² thinks that we have to do with two different Patikas; but I cannot agree with him, because I do not think it possible that the Taxila plate is as late as the Śōḍāsa inscription. Paleographically I think we must place it before the Takht-i-Bāhi record, and I should certainly think that it must go back to about the last years before or the very first years after the birth of Christ. The Śōḍāsa record is found on a sculptured stone-slab, and Sir John Marshall some time ago informed me that he thinks it impossible to relegate the sculpture to an earlier date than the 1st century A.D.³ I therefore think it necessary to assume that the Śōḍāsa inscription is dated in the Vikrama era. Moreover, so far as I can see, we have a distinct indication that the dating according to three seasons, each comprising four months, was later on considered as a characteristic feature of the Vikrama era. It is well known that in the oldest inscriptions which give a name to this era it is designated as a Mālava reckoning. In two of the most ancient instances of its use, in the Mandasor inscription of the time of Naravarman and in the Mandasor inscription of the time of Kumāragupta I, the season is expressly mentioned. Moreover, we have three inscriptions where the era is designated as *kṛita*. In the Bijayagaḍh inscription of Vishnupardhana⁴ we read : *kṛitēshu chaṭvāṁśhu varshaśatēshu-aṣṭāvīnāśhu 400 20 8 Phālgunābahulasya pañchadaśīyām*, "after four hundred and twenty-eight, 428, *kṛita*-years, on the fifteenth of the dark fortnight of Phālguna"; the Mandasor inscription of the time of Naravarman⁵ has : *īrīr-Mūlavaraganāmāntē prastātē kṛitasamjñātē ākashashṭyadhikē prāptē samāsatachatuṣṭayē prāvṛik(i)-kālē śubhē prāptē . . . m[ā]ṣ[ā]ghā prāpittē . . . dinē Aśvōjāsuklasya pañchamyām*, "when the auspicious year four hundred increased by sixty-one, used in the illustrious Mālava gaṇa and named *kṛita*, had arrived, when the glorious rainy season had arrived, while the clouds were dancing, on the fifteenth day of the bright fortnight of Aśvōja"; and finally, the Gaṅgdhār inscription of the

¹ To judge from the remarks by Dr. Bloch, *Jo. Beng. As. Soc.*, Vol. LXVII, P. I., p. 282, it is perhaps dated in the Kanishka era.

² *JRAS.*, 1913, p. 1001.

³ *Gupta Inscr.*, p. 253.

⁴ Cf. *JRAS.*, 1914, p. 985.

⁵ *Ep. Ind.*, Vol. XII, p. 320.

time of Viśvavarman¹ has : *yātēshu chatu[r]ēshu kritēshu satēshu sausaishvāśītasōttarapa-dēshu²-iha vatsarēshu sukṛē trayōdaśadinē . . . Kārttikasya māsasya*, "when four hundred and eighty (?) *kṛita* years had elapsed, on the bright thirteenth day of the month Kārttika."

It is quite plain from these instances that the years of the Vikrama-Mālava era were at an early date characterised as *kṛita*. Sir R. Bhandarkar³ is inclined to explain this designation in such a way that the era "was invented by the people or astronomers for the purpose of reckoning years and was consequently originally known as *kṛita*, which means 'made.' " Dr. Fleet⁴ reminds us of the fact that the Vikrama era was never an astronomical era and suggests that there may be some connection between the designation *kṛita* and *Ki-li-to*, the name of a race which according to Hsün-tsang seized the sovereignty in Kashmir after the death of Kanishka; and Mahāmāhōpādhyāya Paṇḍit Haraprasād Śāstri⁵ says that *kṛita* was the name of the first year of a cycle of years which was used in Vedic periods, though he admits that only in two of the three cases it is possible to divide the number of years, after the subtraction of one, by four. So far as I can see there is a much simpler explanation of the designation *kṛita*. It should be remembered that the years, and not the era, are so called. Now *kṛita* is the best throw in the play of dice, when the number of points is divisible by four.⁶ At the ritual play on the occasion of the Agnyādheya, the father and the son who take twelve *akṣhas* each win. I think this explains the designation of the old Vikrama-Mālava year as *kṛita*. It was divided into three seasons, each comprising four months.

It is evident that this arrangement of the year is no new invention of the establishers of the Vikrama era. It is simply an adaptation of the old Sāvana year with the three *chāturmāsya*s, and we are quite justified in assuming that this was the old national Indian arrangement.

A slightly different subdivision of the year is found in a number of ancient Brāhmi inscriptions, most of which hail from the Dekhan and Southern India. In the first place we have the inscriptions of the Āndhras (Lüders, Nos. 987, 1001, 1021 (?), 1024, 1100, 1105, 1106, 1107, 1120, 1122, 1123, 1124, 1125, 1126, 1146, 1147, 1186, 1195). It will be sufficient here to take one example, all the inscriptions being dated according to the same principle. The Kārṣ inscription of the 7th year of Puṣumāvi has : *rājā Vāsīṣṭhīputasa sāmī-Siri-P[uṣumāvi] savachharē satamē 7 [g]imhapakhē pachamē 5 dīcasē pathamē 1*, "(during the reign) of the Rājan, the son of Vāsīṣṭhi, Svāmin śri-Puṣumāvi, in the seventh, 7., year, in the fifth, 5., fortnight of summer, on the first, 1., day." It will be seen that we have here a slightly different method, the *pakhās*, fortnights, of the season and not the months being given. This same method is used by the Abhira Īśvarasēna (Lüders, No. 1137); by the Svāmin Virasēna (Lüders, No. 684a); by the Mahārāja Bhimasēna (Lüders, No. 906); by the Rājan Aśvaghōsha (Lüders, No. 922); by the Mahārāja Jayavarman (Lüders, No. 1328); by the Ikshvākus (Lüders, Nos. 1202, 1203 and 1204); and by the Pallavas (Lüders, Nos. 1196, 1200, 1205). It was evidently the prevailing one in the south.

The dating in the ancient inscriptions of the Western Kshatrapas, who certainly used the Śaka era, presents quite a different picture. To take an example, the Junāgaḍh rock inscription of Rudradāman (Lüders, No. 965) is dated : *rājā mahākshatrapasya gurubhīr-ābhyastanāmno Rudradāmanō varhē drisaptitāmē 70 2 Mārggaśīrsha-bahula-prat[īpadi]*, "(during the reign) of the Rājan Mahākshatrapa Rudradāman, whose name was repeated by the venerable, in the seventy-second, 72., year, on the first day of the dark half of Mārggaśīrsha." In this way all the

¹ *Gupta Inscr.*, p. 75.

² *Ind. Ant.*, 1913, p. 183.

³ *Ep. Ind.*, Vol. XII, p. 319.

⁴ Cf. Lüders, *Das Würfelspiel*, Berlin, 1907, especially pp. 51 ff.

⁵ Dr. Fleet suggested *sausaishvāśītasōttara*.

⁶ *J.R.A.S.*, 1913, pp. 996 and 998.

Kashatrapa inscriptions (Lüders, Nos. 962, 963, 964a, 965, 966, 967, 1133, 1135), and also the record of the Śālaṅkāyana Vijayadēvavarman (Lüders, No. 1194) are dated. The Nahapāna record, No. 1174, gives an incomplete date (*vasā* 40 6).

It will be seen that we have here again the name of the month, as in the Kharōṣṭhī records, with the addition of the *pakṣa*. If we bear in mind that the Western Kashatrapas were certainly Śakas or Yüē-chi, it becomes likely that the Śaka era which they used in their inscriptions was a direct imitation of the reckoning used by their cousins in the North-West, the additional mentioning of the *pakṣa* being perhaps a concession to the custom in the part of the country where they ruled.

From the whole state of things I think we must draw certain conclusions.

The oldest Kharōṣṭhī inscriptions were dated in an era, of unknown origin, which was most probably based on foreign models. Kanishka and his successors used a different era, but, in their Kharōṣṭhī inscriptions, recorded the dates in the same way as their predecessors, giving the name of the month and the day within the month.

A new era, known as the Śaka era, which was based on the same principles, but added the *pakṣa*, was later on established in Kathiawar and Central India.

The northern Kashatrapa Śōdāsa used a different method, which apparently represents the ancient Indian way of dating, with mention of the season, the number of the month within the season, and the day of the month. The same way of dating seems to have been considered as characteristic of the old Vikrama-Malava era, and Kanishka and his successors adopted it in their Brāhmī records.

Now paleographical and iconographical considerations point to a date in the first century A.D. for Śōdāsa and also place him earlier than Kanishka and the Western Kashatrapas.

I think we are forced to the conclusion that Śōdāsa dated his inscription in the Vikrama era, and that the method of dating used in that reckoning was adopted by Kanishka and his successors in such records as were destined for India proper, because it was the national north-Indian way of dating. Finally, it becomes impossible to maintain that Kanishka was the founder of the Śaka era and used it in his inscriptions, because then it becomes unintelligible why he should have changed the way of expressing the dates. I am still of opinion that the Śaka era was established by Vima-Kadphises. I have given my reasons in my Indo-Scythian contributions in the publications of the Berlin Academy for 1916 and I shall resume them below in my edition of Taxila inscription of Sam. 136.

We must therefore look to other indications in order to fix the starting point of the Kanishka era. Professor Lüders has drawn attention to M. Chavannes' statement¹ that the name Po-t'iao of the Ta Yüē-chi king who sent an embassy to China in A.D. 229 may be a rendering of the name Vāsudēva. If this should prove to be the case, the initial point of the Kanishka era cannot be earlier than A.D. 130 or later than A.D. 168. The Āra inscription would accordingly fall between A.D. 171 and 209, provided that it is dated in the Kanishka era; and I think we have no reason for doubting that, if we admit that Kanishka cannot be the founder of the Vikrama era.

Now Dr. Fleet² maintains that the use of the Roman imperial title "Kaisar" would not be possible at such a late date. He says: "The name Caesar, as an appellation of the head of the Roman state, started with Julius Caesar, to whom it belonged by birth. It was assumed, on adoption, by his grand-nephew and successor Octavianus, better known as Augustus from the title which was given to him by the Roman senate and people in B.C. 27. It was

¹ *T'oung Pao*, II, 7, p. 489.

J.E.A.S., 1913, pp. 104 f.

transmitted by Augustus, together with his own title, to his successors. And undoubtedly it was a very leading designation, along with Augustus and Imperator, of all the Roman emperors down to a certain time, and was probably the particular appellation by which they were most generally known and spoken of in popular usage in the western parts of the empire, though we may doubt whether the same was the case in the eastern parts. But there was an important change in the time of Hadrian (A.D. 117-38). He dropped the name *Cæsar* as a title of the emperor, and gave to it the application which it continued to bear after his time: namely, he transferred it to the second person in the state, the intended successor to the throne. And, though he did not make a *Cæsar* till A.D. 136, when he adopted and appointed L. Aelius Verus, his coins show that he abandoned the use of the title by himself in A.D. 125. Thus, from A.D. 125 the name *Cæsar* was no longer a title of the emperors, but had only a subordinate value We are thus confronted by the position that the name *Cæsar* was taken up by a Kushan king as an imperial title in imitation of the Roman emperors when it had ceased to be a title of those emperors themselves. And this is sufficient in itself, I think, to upset Professor Lüders' application of the Kushan record."


I have consulted an eminent classical epigraphist, Professor E. Ziebarth, about this question. He informs me that all Roman emperors, with the exception of Vitellius (15-69 A.D.), used the title *Cæsar*. After Hadrian the use of the title was no more allowed to every prince but only to the emperor himself and his successor and co-regent. The title is used in inscriptions, in Europe and in Asia, at all times, and it is impossible to draw any chronological conclusions.

It is therefore quite allowable to assume that the Roman title could be adopted by an Indian ruler as late as A.D. 170. The Romans were repeatedly victorious in their wars in Mesopotamia and against the Parthians during the latter half of the second century; and there is nothing unlikely in the supposition that an Indian ruler in the North-Western Frontier districts should have adopted the Roman imperial title at that time. But soon the Roman power began to melt away in Asia; and there is nothing extraordinary in the fact that the title was not used in India any more.

In support of Professor Lüders' dating I have¹ drawn attention to the traditional tales about Khotan handed down by the Tibetans. We learn from them that "the king Kanika and the king of Guzan and king Vijayakirti, lord of Li (Khotan) and others, having led an army into India and overthrown the city of Soked (Sākēta), king Vijayakirti, obtaining many *śāstras*, then bestowed them in that stūpa of Phru-ño." This can only mean that the Khotan king Vijayakirti joined the Kushana king Kanishka in an expedition against Sākēta. I have compared this traditional account with the statement made by Tāranātha and in the Chinese biography of Aśvaghōsha, according to which the Yüeh-chi king attacked Magadha in order to get hold of Aśvaghōsha, Sākēta being one of the towns which tradition mentions as the home of that saint. Vijayakirti would accordingly be a contemporary of Kanishka. Now Vijayakirti was the successor of Vijayasinha, whose queen helped to propagate Buddhism in Kashgar. Professor Franke has shown² that the introduction of Buddhism in Kashgar apparently took place about A.D. 120. Vijayakirti must accordingly have ascended the throne after that date, and he may roughly be assigned to the middle of the second century A.D. I have proved³ that the Tibetan traditional tales about Khotan are at least in part based on fact and that they should not be disregarded as fictitious.

It is in my opinion a remarkable fact that both the Chinese remark about Po-t'iao and Tibetan tradition lead to the same conclusion, that Kanishka I belongs to the middle of the second century A.D. More definite information may reasonably be expected from excavations.

¹ *Sitzungsberichte*, 1910, p. 820. ² *Sitzungsberichte*, 1903, p. 740. ³ *JRAS.*, 1914, pp. 339 ff.



The Āra inscription would accordingly belong to the last quarter of the second century A.D.; and with regard to the king Kanishka mentioned in it I do not think we can get beyond the suggestions made by Professor Lüders that he was a son of Vāsishka and probably a grandson of Kanishka I.

Dr. Fleet has objected that, even if we read *Vajheshka* and not *Vajheshpa* in the Āra inscription, the names *Vajheshka* and *Vāsishka* cannot easily be identified, nothing justifying us in assuming that *jh* and *s* are two different renderings of one and the same sound. He admits that *jh* can represent the voiced *s*-sound which is usually in phonetical works designated by *s*, but he does not seem to know any analogy to the rendering of such a *s* through *s*. I think however that we have a good analogy in another word which is used in Śaka and Kushana records, viz. in the title *kusulaa* in the Mathurā lion capital, *kusuluka* in the Patika plate, which is undoubtedly the same as the title *kujula*, *κωζουλο* used by Kadphises I. I agree with Professor Hultsch¹ that this is a Turkish word, though I do not identify it with *gūjlā*, "strong," but with *gūzel*, "beautiful."² At all events the different writing, with *s* and *jh*, forms an almost exact parallel to the writings *s* and *jh* in the name of the successor of Kanishka I.

Kanishka II can only have held sway over a part of the Kushana empire and only during a short period. If we admit that the Māpikiāla inscription belongs to the reign of Kanishka I, we have dates for him between Sam. 3 and 18, for Vāsishka between Sam. 24-28, for Huviska between Sam. 29-60, and for Vāsudēva between Sam. 74-98. Kanishka II may, as supposed by Professor Lüders, have assumed sovereignty after Vāsishka's demise in the North-West. Later on however Huviska seems to have conquered the North-West as well.

TEXT.

- 1 Mahārājasa rajatirajasa devaputrāsa [ka]i[sā]rasa
- 2 Vajheshka-putrāsa Kanishkasa sambatśarāsa ekachapar[i]-
- 3 [sai] sam 20 20 1 Jeṭhāsa masasa di [20 4 1] i[sē] divasa-ohhupami
kha[d]e
- 4 [kupe] Dashafotēsa Poshapurīa putr[e*]ṇa matarapitarāsa puya[e]
- 5 atmapāsa sabharyā[sā sa]putrāsa aṇugrabarīthāsa sarva[sapa]ṇa
- 6 jatish[u] [hi]tāsa imo cha la 1 khipami [dhamada][ṇa*]

TRANSLATION.

(During the reign) of the *Mahārāja*, *Rājatirāja*, *Dēvapura*, *Kāśara* Kanishka, the son of Vajheshka, in the forty-first year, anno 41, on the 25th day of the month Jyāishṭha, at this day-date a well was dug by Dashafota, the son of Poshapuri, in honour of his mother and father, in order to confer benefit on himself together with his wife and his son, for the welfare of all beings in the (various) births. And here I throw in one Lakh as a religious gift.

No. 8.—SANJAN PLATES OF BUDDHAVARASA.

BY STEN KONOW.

These plates have already been published by Mr. A. M. T. Jackson,¹ who remarks that they were found "by Hasanji Kelia, a cultivator of Sanjān in the Umbargaon pētha of the Dāhānu Talukā of the Thānā district." I now edit the grant from impressions kindly prepared by Mr. H. Cousens.

There are altogether two plates, measuring $9\frac{1}{2}'' \times 8\frac{1}{2}''$. According to Mr. Jackson, "they have raised rims, and are pierced with two holes for the connecting rings, of which the left-hand one, bearing a heavy copper seal with the figure of a lion walking to the left, still remains intact." The beginning and the lower corners of the first and the lower left-hand corner of the second plate have been damaged. In other respects the plates are in a fair state of preservation. The first plate contains twenty and the second nineteen lines, and the letters can mostly be read with certainty. The first line is much effaced and cannot be made out with certainty.

The characters belong to the southern class and might well belong to the latter half of the seventh century. Sometimes, however, quite peculiar forms occur. Compare *ra* in *-rāpam*, l. 2; *la* in *śrīmatām*, l. 2; *-lira-*, l. 7; *-Daśaratha-*, l. 7; *-nīśiśa-*, l. 12; *va* in *varō*, l. 5; *eva* in *-Mānava-*, l. 2, etc. *Da* has a loop at the bottom; compare *-paundarika-*, l. 6; *bāhudamḍa*, l. 10; *Sādhava-*, ll. 22, 27, 34; *Lavanīvaundēna*, l. 22; *Kaṇḍaḍi-*, l. 24; *Viyāḍi-*, l. 24. The cerebral *ga* usually takes the form illustrated in Bühler's Table VII, column 21, numbers I-III. The form given as number IV, however, occurs twice in *-kalyāṇaparamparāpām*, l. 4. The dental *na* has a loop. Both the *ā* and the *ai* mātrās are attached to the right-hand bar of *pa* in *-pautra-*, l. 29; *Pausha-*, l. 33, while the *ai* strokes are attached to the left-hand bar in *-paundarika-*, l. 6; *-prapautra-*, l. 29. A peculiar interest attaches to the sign for *la*. There are, as a matter of fact, two different forms of this sign, compare *sakala-*, l. 2, and *varāha-lamchhanam*, l. 5. On comparing the signs, it will be seen that the former corresponds to the *la* given under Nos. VI-IX in column 34 of Bühler's Table VII, while the latter corresponds to the first numbers of the same column, and still more closely to the most common *la* in Gupta inscriptions. These two different forms of *la* are used side by side in several inscriptions from the time of the Guptas onwards, and usually there does not seem to be any difference made between them. In the Sanjān plates, however, they seem to be differentiated according to a distinct principle. The former occurs in *sakala-*, l. 2; *Chalukyānām*, l. 5; *-tula-*, l. 6; *-pālana-*, l. 10; *-sajalajalodharapaṭalavyōmatāla-*, ll. 10 f.; *-dhavalavimala-*, l. 11; *Chalukyākula-*, l. 15; *-pālana-*, l. 16; *-vipula-*, l. 16; *kulālī*, l. 17; *-kula-*, ll. 18, 23; *-Uddhavalī-*, l. 24; *talaeriksham*, l. 25; *-kāliṇa-*, l. 29; *-Vilachchhēa*, l. 31; *balī-*, l. 31; *phalam*, l. 35; *-nupālana-*, l. 39, and further in *-Kōkkullī-* (?), l. 13, and *-Kaleivana-*, l. 29. The latter occurs in *lōcha-*, l. 1; *-kalyāṇa-*, l. 4; *varāha-lamchhanam*, l. 5; *-labdha-*, ll. 8, 15; *-vallabha-*, ll. 9, 13; *Malla-*, l. 22; *Lavanīvaundēna*, l. 22, and further in *-Palakēśi-*, l. 9; *Sagula-*, ll. 21, 31, 34; *Varasigilēna*, l. 23. If we compare all these instances, it will be seen that one form of *l* is regularly used for a single uncompounded *l* between vowels, while the other form occurs when *l* is initial or combined with another consonant. There are, as will be seen, some exceptions to this rule. The intervocalic form is also used in *-Kōkkullī-*, l. 13, and *-Kaleivana-*, l. 29, and the initial form in *Palakēśi-*, l. 9; *Sagula-*, ll. 21, 31, 34; *Varasigilēna*, l. 23. It will be seen that all the exceptions occur in names, which cannot, of course, be viewed in the same way as ordinary words. The reading *-Kōkkullī-*, l. 13, is moreover quite uncertain. It can also be read *Kōkkulī* or perhaps even *Kōkkulī*. It is impossible to decide whether the *ō* is long

¹ *Journal Bomb. Ac. Soc.*, Vol. IX, pp. 40 and ff.

or short. At all events the name must be compared with the Eastern Chālukya *Kokkili*,¹ the Telugu-Chōḍa *Kōkili*,² the Chola *Kōkili*,³ etc. The correct form seems to be a cerebral *l*, single or doubled. The name is certainly Dravidian. The same is probably the case with *-Kalcivana*-, l. 29. *Palakēsi* is likewise in its first part a Dravidian name; compare Kanarese *puli*, tiger, where it is of interest that the *l* of this word is dental and not cerebral. Also the remaining names are most likely of a similar kind. At all events, it seems quite certain that in ordinary words the two forms of *la* are correctly distinguished as mentioned above.

Now it is a curious fact that we find exactly the same state of affairs in some other inscriptions, viz. the spurious plates of Dharasēna II of Valabhi, dated Śaka 400, and the spurious Gurjara grants of Śaka 400, 415, and 417.⁴ Here also there are some few exceptions. In the Bombay Museum Plates of Dharasēna II⁵ we find the sign which usually denotes an initial or a doubled *l* written in the name *Giriviligrāmaḥ*, l. 20, while the intervocalic form is used in *lagna* in *trīṇāgralagna*-, l. 27. In the Umetā grant of Dadda⁶ we find *jivalōkaḥ*, l. 12, and *trīṇāgralagna*-, Pl. II, l. 9, with the intervocalic, and the name *Gilaka*-, Pl. II, l. 15, with the initial *l*. In the Bagumrā grant⁷ we find the same words *jivalōkaḥ*, l. 11; *trīṇāgralagna*-, l. 25, with the intervocalic, and the name *Ushilathana*, l. 18, with the initial form. The Ilāo plates⁸ likewise have *jivalōkaḥ*, l. 10, and *trīṇāgralagna*-, l. 21, with the intervocalic, and the name *Akulēvara*-, l. 14, with the initial form of *la*.

It will be seen that the exceptions are everywhere of the same kind. In the first place, we find some standing terms in which the *l* has been treated as intervocalic, though it is the initial of the second part of a compound word. There is nothing extraordinary in this. We know from the history of the Prakrits in India that compound words were often treated as one word and suffered such phonetic changes as resulted from the word-Sandhi. It is also of interest to note that the exceptional use of intervocalic *l* in these inscriptions always recurs in the same words, an additional proof that all these forged records proceeded from the same source. The remaining exceptions to the rule, where the initial form is used when a single *l* occurs between vowels, are all found in proper names, just as was the case in the Sanjān plates.

The necessary inference from this state of things is that at the time when these plates were engraved the sound of *l* differed according to its use. When it was initial or formed a compound consonant, it had a sound other than when it was used as a single consonant between vowels.

Now it is a well-known fact that a corresponding state of affairs is found in a number of Indo-Aryan vernaculars of the present day, such as Marāṭhi, Rājasthāni and Gujarātī. As I have shown elsewhere,⁹ every old initial *l* and such *l*'s as are derived from old compound consonants in Marāṭhi, and, I may add, in other languages of the same kind, remain dental, while on the other hand every old single uncompound *l* between vowels becomes cerebralised. I have also drawn attention to the fact that this is an ancient feature of certain Indo-Aryan vernaculars. In the so-called Pāisāchi dialects, which belong to the oldest Prakrits, it was already fully developed.¹⁰ According to the oldest Indian tradition the old Pāisāchi was spoken somewhere in the neighbourhood of the Vindhyas,¹¹ and we have no information that the same

¹ *Ep. Ind.*, Vol. V, p. 128; Vol. IX, pp. 51, 133.

² *Ep. Ind.*, Vol. V, p. 123 n.

³ *Ep. Ind.*, Vol. IX, p. 89 n. 1, and so forth.

⁴ Kielhorn, *Inscriptions of Northern India*, Nos. 346-349.

⁵ *Ind. Ant.*, Vol. X, pp. 277 ff.

⁶ *Ind. Ant.*, Vol. VII, pp. 61 ff.

⁷ *Ind. Ant.*, Vol. XVII, pp. 199 ff.

⁸ *Ind. Ant.*, Vol. XIII, pp. 115 ff.

⁹ *J.R.A.S.*, 1902, pp. 417 ff.

¹⁰ Cf. Pischel, *Grammatik der Prakritsprachen*, para. 260.

¹¹ Cf. Konow, *ZDMG.*, Vol. LXIV, pp. 95 ff. I cannot find that my arguments have been weakened by Grierson, *ibidem*, Vol. LXVI, pp. 49 ff.

state of things prevailed in other old vernaculars. The use of two different *l*-sounds in a series of modern Indo-Aryan tongues, however, shows that it must at some period have spread over a wider area; and it would be of interest if we could find out when this new state of things had become established in the different places. It is not, however, possible to arrive at certain results.

There cannot, so far as I see, be any doubt that the use of two different signs for *l* in some Indian inscriptions, of which the one represents an old initial or doubled *l*, the other an old single *l* between vowels, can only be explained in the light of the modern vernaculars just referred to, the more so because these inscriptions hail from territories in which at the present day Marāṭhī and Gujarātī are spoken. But the difficulty is to decide when these grants were engraved.

With regard to the spurious Valabhi and Gurjara grants it is as yet impossible to arrive at certainty. We may state with confidence that they are later than the Kaira plates of Dadda II Prasāntariga (A.D. 628 and 633), from which the writer's name Rēva or Rēvāditya has probably been taken. The Sanjān plates, on the other hand, purport to have been issued during the reign of the Western Chalukya Vikramāditya I, on the occasion of an eclipse of the sun on the new moon day of Pausa. Now we know¹ "that Vikramāditya I commenced to reign between some time in September A.D. 654 and July A.D. 655," and his son Vinayāditya must have ascended the throne about A.D. 680. I have consulted Professor Jacobi about the eclipses of the sun which were visible in Western India during this period, and he has kindly informed me that the only one that suits the case is the one that occurred on the 7th December A.D. 671. Of the other eclipses which, according to the Pārnimānta system, might come into consideration, viz. those of the 18th December A.D. 670, the 25th November A.D. 672 and the 27th November A.D. 680, the first and the last were not visible in India, and the eclipse of A.D. 672 was too unimportant. Professor Kielhorn has shown² that in early times the Pārnimānta system was in use in Southern India. The intended date would accordingly be the 7th December A.D. 671. And it would be possible to date the spurious Gurjara grants about the same time. It is in this connection of interest that the name of the writer of the Sanjān grant is Rēvagana; compare Rēva, Rēvāditya of the Gurjara grants. As we shall see, however, there are so many indications showing that the Sanjān plates are not genuine, that their date cannot be relied on. On the other hand I see no reason for assigning them to a much later date, and we may provisionally state that the cerebralisation of an uncompound intervocalic *l* in the Western Marāṭhā country can be dated back to about A.D. 700.

The orthography of the Sanjān grant is rather careless. Thus we find *am* for *ā* in -bhayamnēka-, l. 15: *i* for *a* in -ānviyaḥ-, l. 29: *i* for *ī* in mahipati-, l. 11; mahipālana-, l. 16; -samakālinaḥ, l. 29: *ā* for *u* in -Pālakāśi-, l. 9: *ri* for *ri* in kriy-, l. 32: *ē* for *a* in -bhayamnēka-, l. 15: *kt* for *tt* in dakta-, ll. 5, 21, 27, 36, 38; -kiñchiktula-, l. 6: *ga* for *sa* in -garira-, l. 7: *na* for *ṇa* in -Harinā-, l. 4; Anubārāmōna-, l. 21; -pratiharēna-, l. 24: *n* for *nn* in Mātridina-, l. 23: *pu* for *hu* in -Nupusha-, l. 7: *bhi* for *dhi* in rājābhīrāja-, l. 13: *ya* for *vya* in pitriyō-, l. 14: *sa* for *sha* in -ābhikṣitānā-, l. 3. A consonant after an *r* is doubled in kṛttikēya-, l. 4; -Arjjuna-, l. 12; -karkkaś-, l. 12; sarva-, ll. 18, 19; nivarṭta-, l. 20; pārvvāna-, l. 25; -maryyada-, l. 26; sarvādānaḥ, l. 27; -ārka-, l. 28; -chaturvōdasya-, l. 31; -kriyōtsarppanāritham-, l. 32; udakātisarggōṇa-, l. 34; bahubhīṣṭ-evasudhā-, l. 34; bhāmiharttā-, l. 38; pārvva-, l. 38, but not in -Arjuna-, l. 12, -chāturdanta-, l. 15, and, of course, not in -Harsha-, l. 8. Letters and syllables have not rarely been omitted. Compare yāva for yāvat, l. 25; yatnā for yatnād, l. 38; -nīśēsha- for -nīṣēsha-, l. 12; Dvādaśagrāmyā for Dvādaśagrāmyā, l. 19; -ādhikāri for -ādhikāriṣaḥ, l. 18, and perhaps Madanaṁgātrayaḥ for śrīmāḍ-Anaṁgātrayaḥ, l. 17. A superfluous

¹ Ep. Ind., Vol. IX, p. 102.

² Ep. Ind., Vol. IX, p. 102.

anusvāra occurs in -rāmshīra-, l. 18; -samudhīh-, ll. 25, 26; -anēkam-, l. 30, and a superfluous visarga in -ādhipatīh-, l. 8; -ōgrah-, l. 8; -satah-, l. 9; -ānciyah-, l. 29; -Hiranyakēśīh-, l. 30; -bahubhīh-, l. 34; -bhūmīh-, l. 35, while the visarga has been wrongly omitted in *samāsādita*, l. 5; -pratāpa, l. 8; -bāhudaṁḍa, l. 10; -rāja, l. 17.

The rules of Sandhi are constantly violated. Thus we find visarga instead of *s* in -parikarāh-, l. 27; visarga instead of *s* in *mahārājah*, ll. 9, 14; and visarga before sonants in -yāgah yat-, l. 6; -bhōgikah nēkakulapradhānīh Mātri-, l. 23; *nadhāyirah Rēva*-, l. 31. On the other hand, we find *ō* before surds in -vijayō, l. 15; *Mahindārāmō*, l. 21; *parivāhō*, l. 26; -vāpakō, l. 27. When two vowels follow each other, they are sometimes wrongly combined; thus, -bhīshanaṭur- instead of *bhīshana ātur*-, l. 12. In other cases an *m* is inserted as a kind of Sandhi-consonant.¹ Compare *dakṣhina*=*m*=*iva* *bāhudaṁḍa*, l. 10; -*śhadhī*=*m*=*iva* *tushṭikarō*=*m*=*Arjuna*=*m*=*iva*-, l. 12; -*chandramā*=*m*=*iva*, l. 16; -*Hiranyakēśi*(h)=*m*=*anēka*-, l. 30; *sahasrēṇa*=*m*=*asva*-, l. 37. Other instances of wrong Sandhi are -*vinashṭam* *ava*-, l. 6; -*nyāyēna* *achātābhaṭapravēśyah ā*-, l. 28.

The language is Sanskrit. There are however several mistakes. The nominatives in *ō* of *a*-bases where no sonant follows; forms such as *sīmasy-āpi*, l. 23, perhaps -*chaturvēdaya*-, l. 31, and the use of the genitive instead of the dative in l. 31, and so forth, make it probable that the person who drafted the plates was more familiar with Prakrit than with Sanskrit. A form such as *Mahindārāmō*, l. 21, is pure Prakrit, and the form *mātarā* instead of *mātri* in *saptamātarābhīkṣitānā*, l. 3, is in accordance with the rule in Hēmachandra's Prakrit grammar III, 46, that the Sanskrit word *mātri* becomes *mātarā* if it denotes a deity, *mātarā* being a Sanskritised form of this *mātarā*. Also the use of two different *l*'s points in the same direction. That the grant was drafted by a person who was not very well versed in Sanskrit is also shown by the use of parenthetical sentences in l. 4 (*bhagavā-pratyakṣa-Harīnā tushṭēna varō dakṣhā samāsādita*[h²] *pratyayō varāhalaṁchhanam cha*), l. 3 (*kṛitachātāmēdha-rājāsūya-paunḍarikayāgāh yat-kīṣhiktu(t-ku)laduritam tad-vinashṭam . . . dhanushmatā*) and so forth. Note also -*Rāmadēva-tat-pratimānam-iva*, l. 7; -*ānudhyatā*, ll. 10, 17; -*yadō*, ll. 11, 16, and so on.

Such occurrences cannot fail to throw some doubt on the genuineness of the plates. And other considerations lead to the same result.

I have already mentioned that the seal shows the figure of a lion. Now the Western Chalukyas used the boar crest,² and this is in accordance with l. 5 of the Sanjān grant. The invocation of the Varāha-incarnation of Vishnu at the head of many Chalukya grants should, no doubt, be seen in connection with the use of this crest. It speaks strongly against the genuineness of the present grant that this stanza has been so much changed.

On the other hand, it cannot be urged against the genuineness of the plates that the grantor Buddhavarasa is not known from other sources; for a Mahāsāmanta Buddhavarasa of the Śalukika family is known from the Tōrkhēḍ grant of Śaka 735.³ This Buddhavarasa was in possession of an estate known as the Siharakhi Twelve, which Dr. Fleet has identified with the present Serkhi, near Baroda, at 73° 8' E. and 22° 21' N. This place is not too far removed from Sanjān to make it unlikely that he was a descendant of the Buddhavarasa of the Sanjān plates, and the name of his family Śalukika can hardly be anything else than Chalukya. The later Buddhavarasa was a feudatory of the Rāshtrakūṭa king Govinda III; and nothing prevents us from supposing that members of the old imperial Chalukya family, after its overthrow by the Rāshtrakūṭa's, served under the new rulers. I am thus inclined to think that the older

¹ Cf. Kielhorn, *Ep. Ind.*, Vol. IX, p. 268 and n. 3.

² Cf. Fleet, *Gazetteer of the Bombay Presidency*, Vol. I, Part II, p. 299 n. 4.

Ep. Ind., Vol. III, pp. 53 ff.

Buddhavarasa is no fiction. This however does not affect the argument regarding the genuineness of the Sanjān plates. If we suppose, as I think we must, that they were drawn up at all events not long after the date they mention, it would be natural for the forger to insert real names and not fictitious ones.

Buddhavarasa states that he was the younger brother of Palakēśin II, and styles himself *rājan*. Now we know that there was about the same time another Chalukya who held sway in the same part of the country, viz. the Gujarāt Chalukya Śrīyāśraya Śīlāditya, of whom we possess two grants, dated in A.D. 669 and 691 respectively. The former has been edited by Professor Hultzsch¹ and contains the information that the grantor, the *yuvārāja* Śrīyāśraya Śīlāditya, was the son of Dharāśraya Jayasinhavarman, the younger brother of Vikramāditya I. About Dharāśraya we only learn that his "power had been increased by his elder brother." Śrīyāśraya was residing at Navasārikā, the present Nausāri, where the plates were found. The latter grant, which comes from Surat, was published by Bhagvānlāl Indrājī.² Professor Hultzsch has shown that Śrīyāśraya Śīlāditya must have held sway over a province that included Navasārikā. The villages granted by him were Āsattigrāma, Kārmapōya, Ōsumbhālā and Allāraka. Of these Āsattigrāma is the present Astgām, seven miles east-south-east- $\frac{1}{2}$ -south from Nausāri; Kārmapōya is the present Kamrōj, 72° 2' E. and 21° 18' N.; Ōsumbhālā is the present Umbhel, 73° 1' E. and 21° 11' N., and Allāraka the present Alurā, 73° 5' E. and 21° 12' N. There is accordingly no objection to assuming that another Chalukya prince at the same time ruled over a province in the present Thānā District.

In such circumstances I think we are justified in making use of the historical information contained in the Sanjān grant, and even the attribution of the name *Kōkkulī* to Vikramāditya I may very well be justified, if we remember that the name *Kōkkilī* recurs in the genealogy of the Eastern Chālukyas.

The genealogy of the Western Chālukyas, as given in the grant, carries us back to the *Paramēśvara* Satyāśraya Pulakēśin [II] Prithivivallabha, who had conquered Harsha-Dāva, the king of Northern India (Uttarāpatha). His son was Prithivivallabha, the *Rājādhirāja* *Paramēśvara* Jayasīri Kōkkulī Vikramāditya, the *Mahārāja*; and the younger brother of his father was the *Rājā*, the *Paramamāhēśvara* Madanamāśraya (or, *śrīmad-Anamāśraya*), the glorious Buddhavarasa, by whom the present grant purports to have been issued. He claims to have conquered the terrible four-tusked elephants of the lord of the *gana* of the Achhatyana or Natyana. I do not know what to make out of this name.

We further learn that Buddhavarasa, being in good health, while residing in Pinuka, on the occasion of an eclipse of the sun on the new moon day of Pausha, during the reign of Vikramāditya I, grants to Sagulasvāmin Dīkshita, the son of the Chaturvēdin Rōva, a resident of Kalvivāna, of the Hārīti *gōtra*, the Taittirīya *śākhā*, proficient in the various *śāstras* of the Hiraṇyakēśina, Mahindārāma and Ambārāma in the twelve-village-district (*Dvādaśagrāmī*) in Avaranta (*Aparānta*), at the sea-shore, and further the plots of Sēdīva and Malla, the Lavānivaṇḍa and Varasigila. The name of the village to which these plots belonged has been lost. We may however perhaps supply the name Mātridīnnagrāma from l. 23. To the north and west it was bounded by the sea. To the east some localities are mentioned, which I cannot identify, viz. Viyaḍi, Uddhavāli (or Uddhavālikā), Kanakōcharā (or Nakōcharā), Taṭāyikā, and the eastern boundary, the Vyāghrataṭāka.

Mr. Jackson has identified Pinuka with the present Pen, the chief town of the *Tāluka* of the same name in the Kolaba District, situated at 18° 44' N. and 73° 6' E., and Kalvivāna with

¹ *Ep. Ind.*, Vol. VIII, pp. 229 ff.


² *Verhandlungen des VII. Internationalen Orientalisten-Congresses*, Wien, 1883, Ariische Section, pp. 311 ff.

- 15 chhatyana¹-gaṇa-yati-bhayaṁnōka-chā[t]urdanta-gaja-ghaṭ-āṭṭpa-labdha-vijayo² Cha-
lukya-kula-
- 16 [na]rapa[ti]nā[m] gagana]-chandramā-m-iva mahi-pālana³-sita-vipula-prakhyāta-
yaśō⁴ mātā-pitṛi-
- 17 pād-ānudhyā[tā] parama-māhōśvarō Madanamgāśrayaḥ⁵ śri-Buddhavarasa-rāja[h*]
kuśali
- 18 [sarvvaṇ-eva vishayapa]ti-rā(m)shṭra-grāmakūṭa-kala-maha[t*]tar-ādihikāri[paḥ*]
samanubōdhaya-
- 19 [ty-astu sarvva]-vi[ditam yathā] mayā sāgara-taṭō Dvā[da*]śa-grāmyā⁶
Avaranta-visha[y-ā-]
- 20 mā⁷ uttara-diśā daśa niva[rta]nā[ni]⁷

Second Plate.

- 21 [pramāṇōna] Mahindārāmō sthāvaram Ambārāmōna⁸ vibhūshita[m] daktam⁹
[Sagula-dikshita]-
- 22 sy-ārāmasya dakshīpa-diśā Sēdiva-kahō[tram] Malla-kahō[tram] cha saha
Lavani[vau]ṇḍōna Varasigi-
- 23 lēna sahitaṁ simasy-āpī krama-pramāṇam dvādaśa-bhōgikāiḥ¹⁰ nōka-kula-pra-
dhānaiḥ Mātrīdina-grāma-
- 24 kōṭēna cha Kañchadi-pratihārēna¹¹ sahitaṁ amku 30 Viyaḍi-Uddhavāli-Kanakō-
charā-Taṭṭyikā-pū-
- 25 rrvēṇa bāp-āntarēṇa gatā yāva[t*] tala-vṛikshaṁ 5 śhā¹² pūrvvēṇa sa(m)n-
dhīḥ¹³ Vyāghra-taṭākam tasya cha pari-
- 26 vāho 30 śhā dakshīpa-diśā sima-sa(m)ndhīḥ pāschima-diśā uttara-diśā cha
mahōdadhī-maryyādā 30
- 27 śhaḥ sa sima-parikaraḥ chatur-ādghūṭana-viśuddhaḥ¹⁴ Sēdiva-vāpako¹⁵ sarvv-
ādānam daktam¹⁶ viśiṣṭō-[prā]-
- 28 tibh[ō]dikā-parihīnō-bhyaṁtarasiddhīḥ¹⁷ bhūmicchhidra-nyāyēna a-[chā]ṭa-bhaṭa-
pravēśya(h) ā-chandr-ārka-
- 29 samakālina[h]¹⁸ putra-pautra-prapautr-ānviya(h)-kram-ōpabhōgyaḥ śri-Kalvivana-
vāstavya-Hārīti-

¹ Perhaps *Notyana*- and read -gaṇapati-bhayaṁnōka.² Read *mahi*.³ Read -vijayata.⁴ Read -yaśō.⁵ Read perhaps -paramamāhāśrayaḥ śrīmad-Anamgāśrayaḥ.⁶ There would be just room for sufficient syllables to read -ataḥpāti-Mātrīdinagrāmā.⁷ There does not seem to have been any writing in the remaining part of l. 20.⁸ Read *ga*.⁹ Read *daktam*.¹⁰ Read -kaśīra-nāka-kulapradhānair-Mātrīdina-.¹¹ Read *ga*.¹² I am not quite certain about the reading 5 and I do not know what to make out of śhā.¹³ Read *sandhīr*.¹⁴ Read -karaṭ-chatur-ādghūṭa-viśuddhaḥ.¹⁵ Read -vāpakaḥ.¹⁶ Read *daktō viśiṣṭi-prā*.¹⁷ Read -parihīno- and -siddhyā.¹⁸ Read -kālinaḥ putra-pautra-prapautr-ānviya-.



[illegible]

- 30 sagōtra-Tōttiri-sākhā-Hiranyakṣīḥ-m-anēka¹- śāstra - pāramgata - pradhāna - pratham-
ōttama-nagara-
- 31 Vilachchhē nadhāyirah² Rēva-chaturvēdasya putrāya Sagulasvāmi-dikshitasya bali-
charu-
- 32 [vai]śvadēv-āgnihōtrāya³-kriy-ōtaarppan-ārtham mātāpitrōr-ātmanas-cha puṇya-yaśō-
bhi-
- 33 [v]ridhdhayō Pauṣha-māsasya amāvāsyām āditya-graha[ṇē]⁴ Pinuka-nagara-
sthitēna śri-Buddhavarasē-
- 34 na s[v*]a-hastēna⁵ ndak-ātisarggōṇa Sagula-dikshitasya ta[t*] Sōdiva-kshētram ||
Bahubhi(h)r-vvasu-
- 35 dhā bhuktā rājabbhiḥ Sagar-ādibhiḥ [i*] yasya yasya yadā bhūmi(h)s-tasya
tasya tadā phalam [||*]
- 36 Sva-daktām⁶ para-daktām cha yō harōta vasundharā[m*] shashṭid-varsha-
sahasrāṇi⁷ viśhṭāyā[m]
- 37 [ja]yatō kṛimih || Taṭākānām sahasrēṇa-m-aśvamēdha-śatēna cha [i*] gavām
koṭi-pradānēna
- 38 [bh]ūmi-hartā na śudhyati [||] Pūrvva-daktā⁸ dvijātibhyō yatnā[d*] raksha
Yudhishtira [i*] mahi[m*] mah[1]-
- 39 ma[tām śrē]shṭha dānāch-chhrōyō-nupālanaḥ || Likhitaḥ Rēvagaṇēna ||

TRANSLATION.

(Line 1) Hail, Prosperity. Ever victorious is the boar shape (of Viṣṇu), which has a body of the colour of bees, which has terrible eyes, red at the corners . . . which is bent . . .

(Ll. 2-9) [In the lineage] of the glorious Chalukyas, who belong to the Mānavya gōtra, which is praised by the whole world; the Hārti-people; who have been anointed by the seven (divine) mothers; who meditate on the feet of the illustrious Mahāsēna (Kārttikēya); who through the protection of Kārttikēya have obtained continuous prosperity—by the divine Hari, who, being pleased, showed himself before their eyes, a boon was granted and fame and the boar crest were obtained—, (there was) the supreme lord, the devout worshipper of Mahēśvara (?), Satyāsraya, the illustrious Pulakēśin [II] Prithivīvallabha, the Mahārāja,—the Aśvamēdha, Rājāsuya and Paundarika sacrifices were performed, whatever evil there was in the family, was annihilated, head and body were cleansed and purified through Avabhṛitha baths by him who was an archer comparable as it were to the following, viz. Nṛiga, Nahusha, Dhundhumāra, Daśaratha and Rāmadēva—, who had acquired vigorous power through his victory over the lord of Uttarāpatha, the illustrious Harshadēva,—

(Ll. 9-14) His son was Prithivīvallabha, the sovereign king, the supreme lord, the victorious and glorious Kokkulli Vikramāditya [I], the great king, who meditated on his

¹ Read -Taittirīya-sākhā-Hiranyakṣī-anēka-.

² Read nicāsinō? I take Vilachcha to be the name of a town.

³ Read -āgnihōtr-ādī-kriy-.

⁴ Read -māsary-āmāvāsyām-āditya-.

⁵ Read -hastēna-ndak-.

⁶ Read sva-dat'tām para-dattām. There is a superfluous hook at the right-hand side of pa.

⁷ Read shashṭim varsha-.

⁸ Read -dattām.

[father's] feet, who, like his right arm-staff, was capable of protecting the earth; whose fame was spotless and white, like the rays of the autumnal moon risen in the skies; from which the mass of water-filled clouds has disappeared; who was terrible in his utterly violent effort of warding off the war elephants of (hostile) kings; who was causing satisfaction like a medicinal herb given to a sick person; who was victorious in every battle like Arjuna,—

(Ll. 14-19) His father's brother, the younger brother of Satyāsraya, who rejoiced in showing reverence to gods and Brāhmanas; who has obtained victory over the multitude of four-tusked elephants of the lord of the Aṅgharāya (?) gosa; who, like a moon in the sky of the lords of the Chalukya family, has acquired white, wide-spread, and well-known fame through protecting the earth; who meditates on the feet of his mother and father, the devout worshipper of Mahēśvara, Madanaṅgāsraya (or, the illustrious Anaṅgāsraya), the illustrious Buddhavarṇa, the rājan, being in good health, instructs all the heads of districts, the heads of provinces and villages, the tribal chiefs and officials:

(Ll. 19-23) Be it known to everybody, that the estate Mahindārāma, adorned with the Ambārāma (or, a mango grove), on the sea-shore of the Dvādasa-grāmi (Twelve-village district), in the village . . . within the Avaranta-vishaya, on the northern side, ten *niartanas* in extent, [this] being given by the . . . and further, on the southern side of Sāguli Dikṣita's grove, the Sēdiva-field and the Malla-field, together with Lavanivaṇḍa and combined with Nāmaṅgila.

(Ll. 23-26) And the measure of steps of the [borderline (mada) by the (bhaghu)] of the Twelve-(district), the heads of several families, and the [headman of Mātridima village] together with the door-keeper Kañchadi is in figures 30. They went to the east of Viyadi, Uddhavalī, Kanakōchāra and Tajāyika, in the distance of an arrow shot, up to the palmyra tree, five (?) *sha*.² To the east the limit is the Tiger-tank (Vyāghra-taṭaka), and its waterline measures 30 *sha*. To the south the limit is the boundary (of the village). To the west and to the north the sea-shore, 30 *sha*.

(Ll. 27-34) This is the surrounding limit, and defined as to its four abutments, the Sēdiva field has been given, with all taxes, free from *vishti-prātibhādika*, with all the spaces within, according to the maxim of *bhūmichchhidra*, not to be entered by petty officials³ and soldiers, for as long a time as moon and sun (endure), to be enjoyed in succession by sons, grandsons, and great-grandsons, to the inhabitant of the illustrious Kalivāna, of the Harā-hoṭa, the Dattivāra, the foremost of those who are prominent in the various *śāstra* of the Mātridima, the son of the *śāstrin* Rava, who lives in the foremost excellent town Vilachhita, to Sāguli Svastī Dikṣita, for the performance of *śraṇa*, *śraṇa*, *śraṇa*, and (other rites) for the increase of the merit and fame of his mother and father and of himself, on the new-moon-day of Pausā, on the occasion of an eclipse of the sun by the *śraṇa* of Buddhavarṇa, staying in the town of Pinuka, with his own hand, with libations of water; and to Sāguli Dikṣita this Sēdiva field (has been given) . . .

(Ll. 34-39) Four of the customary verses . . .
(Ll. 31) Written by Rāvagaṇa.

(Ll. 3-14) His son was . . . the great king, who mediated on his . . .

¹ See *Ep. Ind.*, Vol. IX, p. 273 and n. 6.

² I do not know what is meant with *sha*, perhaps *śāstrin*, of Kanthya, p. 107.

³ Ch. *Ep. Ind.*, Vol. IX, p. 284 n. 10, and p. 296; Vol. XI, p. 176, and Lalla Dikṣita's Commentary on the *Mricchakatika* (ed. Godabole, Bombay, 1896), p. 223: *śāstrin* *śāstrin* *śāstrin*.

⁴ I am extremely doubtful about the interpretation of this part of the grant, and a name such as Vilachhita does not seem to be likely.

⁵ There is a suspicious book at the right-hand side of the . . .

The subjoined Prakrit record incised in the reign of the Andhra king Sri-Pulumāvi, King of the Satavahana (family), was discovered by Mr. T. Rajarao, Kanare Assistant in the Office of the Assistant Archaeological Superintendent for Epigraphy, Southern Circle, during his tour of inspection in the Adoni Taluk of the Bellary District, Madras Presidency. The estampages were prepared under the direct supervision of Rao Sahib H. Krishna Sastri and kindly placed at my disposal by him for publication. I am indebted to him also for many valuable suggestions in the matter both of decipherment and of interpretation of the record.

The inscription is engraved on the eastern face of a large natural boulder of reddish granite, known to the villagers as Jangli Gunda (Jungle Stone). The inscribed rock, which is nearly buried in the soil, lies midway between the villages Myakadoni and Chinna Kadaburu at a distance of about eight miles due N. from the Taluk Head-quarters. The surface of the boulder has peeled off at various places, sometimes right up to the depth to which the letters were incised. The written surface, consisting of four lines of the inscription, covers an area of 8 by 5, and the height of the average letter is 2½". The engraving, though bold and neatly executed, is not very deep; indeed the "ducts" of the letters are so shallow that a superficial examination of the rock discloses hardly any traces of the record. It is worth noting that the words are separated from each other by small gaps, a circumstance which greatly facilitates the deciphering of the record. The fourth and last line of the inscription is considerably shorter than the rest, and commences much further to the right than these. The closest inspection of the rock did not disclose any distinct trace of letters in the gap at the beginning, caused by the shortness of this line.

The alphabet resembles that of the Jagrayapeta inscription of Parisadata¹ on Chāṇakī. The characters are the hooks with which the elongated verticals of the letters ka and cū terminate as well as the pedantic semi-circular arc used as the sign for the medial i. The signified medial ā and ē show a tendency to droop downwards at their free ends. In spite of this similarity with the characters of the Jagrayapeta record, there could be, as far as I can see, no objection on palaeographic grounds to their being assigned to an epoch earlier than the third century, to which the Jagrayapeta inscription is hesitatingly ascribed by Bühler. *Indische Palaeographie*, p. 45.

The number of epigraphic records belonging to the Satavahana Dynasty, which had succeeded in holding away over a large part of southern India for an unusually prolonged period, is remarkably small. In the Madras Presidency, besides the one I am now editing, there are only two inscriptions which refer themselves directly to the reign of a Satavahana king, and these are both records from the Krishna district, one of them being certainly a private record. So is the inscription under consideration a private record: it registers the construction of a tank.

The inscription is composed of 11 lines, which are arranged in a single column. The first line is a title, and the following lines contain the text of the inscription. The inscription is written in a script which is very similar to the one found in the Jagrayapeta inscription. The characters are the hooks with which the elongated verticals of the letters ka and cū terminate as well as the pedantic semi-circular arc used as the sign for the medial i. The signified medial ā and ē show a tendency to droop downwards at their free ends. In spite of this similarity with the characters of the Jagrayapeta record, there could be, as far as I can see, no objection on palaeographic grounds to their being assigned to an epoch earlier than the third century, to which the Jagrayapeta inscription is hesitatingly ascribed by Bühler. *Indische Palaeographie*, p. 45.

¹ Bühler, *Indische Palaeographie*, p. 45, and Tafel III, Col. XVII, XVIII.

See also his remarks in the *Arch. Surv. of Southern India*, Vol. I, p. XII. Excepting the tendency of horizontal lines which are unconnected at one end to curve downwards, there is no difference between the alphabet of our record and those which are figured in Table III, Col. X-XIII of Bühler's *Typla*, which would justify its being assigned to a later palaeographic epoch. The curving downwards of the horizontal lines is, in my opinion, as much an ornamental variation as the hooks at the ends of elongated verticals, which are to be observed as early as in an inscription of Satākapi I. (Col. X), which Bühler himself assigns to 1-2 century A.D. With the semi-circular arc representing medial i of *gi* and *ei* in an inscription of Pulumāvi (Col. XI); *ai*, *ai* and *ai* in an inscription of Satākapi I. (Col. X); *ti* (twice) and *dai* in those of Ushavādāta (Col. VII, VIII) and others much earlier.

² See Lüders, *List of Brāhmī Inscriptions*, Nos. 1249, 1340.

of a tank by a certain householder (*gahapati*). The only other designation besides Puḷumāvi which the king receives here is Raño Sātavahanānam, 'of the King of the Sātavahana.' One notices here the absence of the metronymic with which the names of the Sātavahana kings are as a rule accompanied, such as Gotamīputa and others.¹ Worthy of note also is the use of the family name Sātavahana, a term of comparatively rare occurrence in inscriptions.²

With the scanty information we have in our record about this Puḷumāvi an identification is precarious. There are in fact at least four kings with the name Puḷumāvi (or its variants) known to history; and the chronology of this dynasty is far from being satisfactorily settled. Mr. Vincent A. Smith,³ working upon the Puranic material supplied by Pargiter, gives us tentatively the following dates for the various Puḷumāvis:—

1. Puḷumāvi (I.), the fifteenth king of the dynasty, ruled some time before A.D. 50.
2. Puḷumāvi (II.), Vāsīthiputa, came to the throne about A.D. 135, and ruled for something like 28 years.
3. Puḷumāvi (III.), came to the throne about A.D. 163, and ruled for something like 7 years.
4. Puḷumāvi (IV.), came to the throne about A.D. 218, and ruled for something like 7 years.

For purposes of identification the Puranic king Puḷumāvi (I.), of whom we know next to nothing, may be rejected on palaeographic grounds. Further, if the lengths of reigns allotted to these kings in the list supplied by Mr. Vincent A. Smith happen to be correct, then the last two Puḷumāvis will also have to be rejected, as they are stated to have ruled only seven years each, while our inscription is dated in the eighth regnal year of the king. From this point of view the Puḷumāvi of our inscription will have to be identified with Vāsīthiputa sāmī-Siri-Puḷumāvi (II.), the [Σίρα]πτολεμαίος of Ptolemy.⁴ A large number of records dated in the reign of this king have in recent years come to light. The year of his accession to the throne is, as remarked above, put down roughly at A.D. 135. Assuming a plurality of kings with the name Puḷumāvi, there is no other criterion in the inscription for identifying him further.

It was mentioned above that the object of the inscription was to record the sinking of a reservoir (*taḷāka*). There is, however, no reservoir or tank to be seen in the neighbourhood, to which the record may apply. But it may be remarked that the soil in the vicinity of the inscribed rock is alluvial, consisting of sand and finely powdered dust; so that the adjoining land might well at one time have formed the bed of a tank.

Among the localities mentioned in this record Sātavahani-hara is particularly interesting, as it occurs once again in the Hira-Haḍagalli copper-plate inscription⁵ of the Pallava king Śivaakandavarman in the slightly altered form of Sātāhani-raṭṭha. I am not aware that the names of places mentioned in this grant of the Pallava king have been satisfactorily identified, so that the situation of Sātāhani-raṭṭha has been, as far as I know, a matter of conjecture. The inscribed boulder bearing the present record is, however, a sure landmark, as far as the situation of the locality is concerned. If, now, the find-place of the grant, Hira-Haḍagalli, which is also situated in the Bellary District, be supposed to be not far removed from the subject of that grant, which is described as being located in the Sātāhani-raṭṭha, then the territorial


¹ See Rapson, *Catalogue of the coins of the Andhra Dynasty*, etc. (London, 1908), p. cxxxix.


² See Rapson, *op. cit.*, Index V, s. e. Sātavahana.

³ *Early History of India*, 3rd Edition (1914), pp. 216 ff.

⁴ Rapson, *op. cit.*, p. xxxix.

⁵ *Ep. Ind.*, Vol. I, pp. 2 ff.





division Sātavahani-Sātāhani must have comprised a good portion of the modern Bellary District. The relation in which the *mahāsēnāpati* and the *gumika* stand to the *janapada* and the *gāma* which appear along with their names, is not explicitly mentioned. But, considering the position of these persons, one might hazard the guess that these military officers were feudal lords of the lands, holding them in the form of *jāgirs*.

In conclusion, it may be remarked that the site of the inscribed rock is an important landmark, fixing definitely a point south of the Kṛishṇā to which the sway of the Sātavahanas extended.

TEXT.¹

- 1 ²[Si]dha[m] [||*] Raño Sātavahanānam S[i]ri-Puḷum[ā]visa sava 8 hēma 2
diva 1
2 [masa]³ mahāsēnāpat[i]sa Khaṇḍa[nā]kasa janapādē⁴ S[ā]tavahani-hārē
3 . mikasa⁵ Kumāradatasa gāmō Vēpurakē vathavēna gahapatikēna [Koin]tānam⁶
[Saimbē]na
taḷakam khānitam [||*]

TRANSLATION.

Success! On the first day of the first (fortnight of) the second month of Winter⁷ in the eighth year (of the reign) of Siri-Puḷumāvi, King of the Sātavahana (family), the reservoir was sunk by the householder (gahapatika) . . . resident in the village (of) Vēpuraka, belonging to the Captain (gumika) Kumāradata (Kumāradatta), in the country (janapada) of Sātavahani-hāra,⁸ belonging to the Great General (mahāsēnāpati) Khaṇḍanāka⁹ (Skandanāga).

¹ From the stone and a set of impressions.

² Traces of the bracketed syllable are visible on the stone.

³ The consonant signs are almost certain; the vowel signs are all but obliterated, as at this point the rock has peeled off almost to the depth to which the letters were incised. Perhaps, we have to read *masi*, making with the foregoing numerical symbol 1 the word *paṭhamasi*.

⁴ Read *janapadē*.

⁵ We have probably to restore *gumikasa* (from Skt. *gaulmika*, 'captain'), which would accord well with the *mahāsēnāpatias* of the preceding line.

⁶ This and the following word must, in my opinion, contain the specification of the *gahapatika*; the first (*gen. plu.*) is most probably a tribal name, and the second (*inst. sing.*) is the personal name. The reading of the first *akṣaras* of the names must however be looked upon as problematic.

⁷ This is the season commencing with the dark fortnight of the month of Kārttika.

⁸ This is a clear case of the use of the word *hāra* in the sense of 'kingdom or district.' See Lüders, *List of Brāhmī Inscriptions*, Appendix, Index of miscellaneous terms s.v. *ghāra*.—In the Hira-Haḍagalli copper-plates (Lüders' List, No. 1200) this territorial division receives the designation *raṭṭha* (*rāṣṭra*). Thus *hāra* must correspond to *raṭṭha*.

⁹ Cf. the personal name Khaṇḍanāga-sātaka occurring in a Buddhist inscription at Kapāri (Lüders' List, No. 1021).

No. 10.—THE NAIHATI GRANT OF VALLALA-SENA, THE 11TH YEAR

By R. D. BAKER, M.A., INDIAN MUSEUM, CALCUTTA.

The plate on which this grant is incised was discovered by some coolies, while digging some waste land, between the villages of Naihati and Sitahati in the Katwa subdivision of the Burdwan district of Bengal, belonging to Babu Baidyanath Chatterji, Zamindar of Sitahati, in January 1911. The piece of waste land on which the grant was discovered is called by the local people *Nai rājār bhūṭa*, "The ruins of Nai Raja's place." A copper cup, *tanra-kanda*, a vessel still in common use for divine worship in Bengal, was discovered at the same time. Subsequent excavations at the same place yielded some more utensils of worship:—

(1) A copper censer on two legs, one of which is peculiarly curved. Such censers are very often represented on the pedestals of images of the Pala period (800-1200 A.D.). This form is no longer used in Bengal. Dr. J. Ph. Vogel, when Officiating Director-General of Archaeology, found similar utensils for use in the Tiruchendur Temple of Vaidyanātha, Trichinopoly district, Madras. The censer had a movable cover, which has now disappeared and of which the hinge only remains. It measures 7" in length and 4½" in height.

(2-5) Four small stands or cups, most probably intended to hold *pāni-saṅkhas*, or conch-shells. No. 2 measures 2½" in height, and the diameter of the top is 1½". No. 3 measures 2½" in height, and the diameter of the top is 1½". No. 4 measures 2" in height, and the diameter of the top is 1½". No. 5 measures 1½" in height, and the diameter of the top is 1½".

(6-8) One elaborately curved and two plainly curved small conch-shells, used during *pūjā*. They are called *pāni-saṅkhas* and are not used for blowing. They are filled with water, and waved before the deity at the time of *Āratika*.

(9-12) Four irregular pieces of oxidized zinc.

The nature of the finds indicates that the piece of waste land where the grant and the other objects were discovered is the site of an ancient temple. Local people say that some images made of gold, or covered with gold leaf, were found at the same place. Mr. Tīrak Chandra Roy, M.A., when Subdivisional Officer of Katwa, interrogated the agent of the Zamindar of Sitahati, who denied all knowledge of them. Subsequent inquiries did not lead to the discovery of any such images, and Mr. Roy is inclined to regard the rumours as baseless.

Immediately after the discovery a reading of the record with excellent photographs was published by Mr. Roy in the *Journal of the Bangiya Sahitya Parishad*. A revised reading of the text was then published by Mr. Akshaya Kumāra Maitreya, B.L. of Raishahi, in the Bengali monthly journal "*Sahitya*." Prof. Rādhāgovinda Basak, of the Raishahi College, published a Bengali translation of this record in the same journal. Subsequently Dr. D. B. Spooner, B.A., Ph.D., F.A.S.B., Superintendent, Archaeological Survey, Eastern Circle, undertook to edit this grant for the *Epigraphia Indica*, and prepared a version of the text and a translation. But he was unable to finish this task on account of pressure of work, and his discovery of the Maurya ruins of Pataliputra diverted his attention, and in 1915 he permitted me to take up the work. Dr. Spooner's version of the text and his translation of it have been largely used in this article.

¹ Cunningham's *Maṣṣōḍhi*, pl. xxviii.

² *Bangiya Sahitya Parishad Patrikā*, Vol. XVII, pp. 231-45.

³ *Sahitya*, Vol. XXII (B. S. 1318), pp. 6-19-27.

⁴ *Ibid*, pp. 575-85.

The record is incised on a single plate of copper, measuring $13\frac{1}{2}''$ by $15''$. A seal is attached to the top: like the seals of the other grants of the Sēna kings, it does not contain the name of the sovereign. It consists of a seated image of the ten-armed Śiva, known as Sadā-śiva. In the Edilpar grant of Kṣaya-sēna the seal is expressly called *Sadāśiva-mudrā*.¹ The record bears sixty-four lines of writing, thirty-two on the first side and thirty-two on the second. The average length of the letters is $\frac{1}{16}''$. The engraving has been neatly and carefully done, and on the whole the record is free from mistakes. The characters of the grant show the well-developed Bengali alphabet of the 12th century A.D., the beginning of which is to be seen in the Deopara inscription of Vijaya-sēna, the father of Vallāla-sēna. Among vowels the initial forms of *i*, *ri*, *li*, *ai* and *au* do not occur. Only *i* retains its old form and does not even approach the Bengali form. *a*, *ē* and *ō* show complete forms. *u* and *ā* have intermediate forms, and in these two cases the modern curved top strokes only are wanting. Among consonants *ka*, *na*, *chha*, *ta*, *da*, *pa*, *pha*, *bha*, *va*, *sa* and *ha* retain intermediate or transitional forms. The other letters of the alphabet show complete Bengali forms. The *anuvāra* still retains its old form, and the *anuvāsikā* is used in two or three instances, e.g. *anyānt=cha* (l. 35), *kshētra-karānt=cha* (l. 36). Final forms of *ta*, *na* and *ma* are used in many cases, and the doubling of consonants with a subscript or superscript *r* is optional. The language of the record is Sanskrit. With the exception of *om om namaḥ Śivāya* at the beginning of the first line, the first twenty-eight lines contain in verse the genealogy of the Sēna kings from the moon to Vallāla-sēna.

The first verse contains an invocation to Śiva in the form *Ardhaṇṛīśvara*. The second is devoted to the praise of the Moon-God, in whose lineage the Sēnas were born. The third verse contains the important statement that the forefathers of Sāmanta-sēna ornamented the Rādhā country, proud of its fame for the maintenance of legal behaviour (*śad=śchāra*), with unheard-of glory. Verses 4-13 contain the usual genealogy of the Sēna kings. Fresh information is available in verse 7, where it is stated that Vijaya-sēna defeated a king named Sāhasāṅka. It is difficult to identify this Sāhasāṅka. According to my view of the chronology of the Sēna kings the year 1119-20 A.D., which is the initial year of Lakshmaṇa-sēna's era, must also be the first year of the reign of Lakshmaṇa-sēna: therefore, according to this view, the death of Vallāla-sēna occurred in 1118-19 A.D. Vijaya-sēna, the father of Vallāla-sēna, must therefore be placed in the last decades of the 11th century A.D.² This is the earliest possible date for Vijaya-sēna. According to the other view, Vallāla-sēna died in 1168-69 A.D.,³ and Vijaya-sēna reigned during the earlier decades of the 12th century A.D. Even if we accept the earlier date, it does not make it possible to identify this Sāhasāṅka. The only possible prince with whom it is possible to identify him is Śālivāhana, also called Sāhasāṅka, Nīlāṅka-malla, Maṭamaṭa-siṃha and Kari-varsha, who is known from the Chamba grant of his son Sōmavarman-dēva (p. 7) and who, according to the late Dr. Kielhorn, lived "about the middle of the 11th century A.D."⁴ In Southern India the only prince who is called Sāhasāṅka in an Epigraphic record is the Rāshtrakūṭa Govinda IV,⁵ who cannot be taken to be a contemporary of Vijaya-sēna. Another Sāhasāṅka is Sindhu-rāja, the Paramāra chief of Dhārū, the brother of Vākpati-rāja II and father of Bhōja-dēva, according to the *Narasahasāṅka-charita* of Padma-gupta. But he also belongs to the last decades of the 10th century or the first two of the 11th. It may be said that Sāhasāṅka is a synonym of Vikramāṅka or Vikramāditya. Even if we accept that, the difficulties of identification do not diminish. In North-

¹ *Journal and Proceedings of the Asiatic Society of Bengal* (New Series), Vol. X, pp. 99 and 104.

² *Memoirs*, A. S. B., Vol. V, pp. 103-07.

³ *Ep. Ind.*, Vol. VIII, Synchronistic table for Northern India, col. 7.

⁴ *Ibid.*, Vol. V, App., p. 81, note 6.

⁵ *Ep. Ind.*, Vol. VII, p. 36.

ern India Gāṅgēya-dēva is perhaps the only prince whose surname was Vikramāditya;¹ but, as he was dead before 1042 A.D.,² he cannot be said to have been the contemporary of Vijaya-sēna. The only possible person in Southern India is Vikramāditya VI of Kalyāṇi, the founder of the Chālukya-Vikrama era, who ascended the throne in 1076 A.D.³ We have not as yet come across the name Sāhasāṅka as a surname of this Vikramāditya, nor have we heard of his campaigns in Northern India. So the only possibility is the Chamba prince. In the troubled times when the last remnants of the Gurjara-Pratihāra empire in Kānyakubja or Pratihāra were being destroyed and when Chandra-dēva was trying to found the Gāhaḍavāla kingdom, Vijaya-sēna of Bengal may have come in contact with Sālivāhana somewhere in Northern India. Further information is to be found in verse 10, where it is stated that the principal queen of Vijaya-sēna was Vilāsa-dēvi. Vallāla-sēna was the son of Vijaya-sēna by Vilāsa-dēvi. Verse 14 states that the land granted as the *dakṣhiṇā* of the gift of the golden horse (*hēma-dēva-dāna*) on the occasion of a solar eclipse by the mother of the king was recorded by Vallāla-sēna on a copper-plate and given to the learned Ōvāsu, i.e. Ōvāsudēva-śarman.

The inscription records the grant of the village of Vallahitṭhā, with habitable (*vāstu*), cultivable (*nāla*), and waste (*khūla*) lands, measuring seven *bhū-pāṭakas*, nine *droṇas*, one *āḍhaka*, forty *unnānas* and three *kakas*, measured by the *nala* called *Vṛishabha-śaṅkara*; with an annual income of five hundred *Kapardāka-purāṇas*, in *Svalpa-dakṣhiṇa-vīthī*, of the Northern Rādhā *maṇḍala*, of the Varddhamaṇa *bhukti*. This is the first mention in an ancient inscription of a *maṇḍala* named Northern Rādhā and of a *bhukti* named Varddhamaṇa. The Varddhamaṇa *bhukti* is mentioned in a new grant of Lakshmaṇa-sēna, discovered by Bābā Amālya Charaṇa Ghōṣha. The village of Vallahitṭhā was granted by Vallāla-sēna as the *dakṣhiṇā* of the golden-horse gift made by Vilāsa-dēvi, the mother of the king, on the banks of the Ganges, on the occasion of a solar eclipse (*Sāryyōparāgē*), to the *āchārya*, the illustrious Ōvāsu-dēva-śarman, son of Lakshmidhara-dēva-śarman, the grandson of Bhadrēśvara-dēva-śarman, and the great-grandson of Varāha-dēva-śarman, of the Bharadvāja *gōtra*, whose *pravaras* were Bharadvāja, *Āngiras* and *Bṛihaspati*, and who was a student of the Kauthumi *śākhā* of the *Sāma-vēda*. The name of the donee presents some difficulties. In verse 14 he is simply referred to as the learned Vāsu (*Vāsu-vidushā*);⁴ but in the prose portion, where his lineage is mentioned, his name is written "Āchārya-Śrī-Ōvāsudēva-śarmanāḥ," which may also be read as "Śrī 3 Vāsudēva-śarmanāḥ" meaning the "thrice illustrious Vāsudēva-śarman." But in l. 63, in the verse which mentions the *dātaka* of the grant, the name occurs as "Ōvāsu" or "3 Vāsu," where we cannot take the first letter to be a numeral, because, if we do so, we shall be at a loss to explain it, as the syllable *Śrī* is absent before it. It is therefore better to take the name as Ōvāsu-dēva-śarman. The *dātaka* of the grant was the minister of peace and war (*Sāndhivigrahika*) Hari-ghōṣha, and it was issued from the victorious camp at Vikrama-pura on the 18th day of Vaiśākha of the 11th year of the king's reign.

The boundaries of the village granted are as follows :—

It was situated to the north of the river Siṅgaṭiā, which lay to the north of the *Sāsana* of Khāṇḍayillā, to the north-west of the river Siṅgaṭiā, which lay to the north of the *Sāsana* of Nāḍiōhā, to the west of the river Siṅgaṭiā, which lay to the west of the *Sāsana* of Amvayillā, to the south of the southern boundary-wall (*Simālī*) of Kuḍumvamā, to the south of the boundary-wall on the west of Kuḍumvamā which runs to the west (*paṭchima-gaṭi*), to the west of the southern cattle track (*gōpatha*) on the south of the Āuhāgaḍḍiā, to the south of the boundary-wall which issues from the northern cattle track of Āuhāgaḍḍiā, runs to the west and

¹ *Ep. Ind.*, Vol. VIII, App. 1, p. 16.

² *Ibid.*, Vol. VIII, App. II, p. 7.

³ *Ep. Ind.*, Vol. II, pp. 299-302.

⁴ This has to be corrected into *adit-aveśam*.

reaches to the northern boundary-wall of Surakonāgaddiā, to the east of the eastern boundary-wall of Nāḍḍinā, to the east of half of the cattle track to the east of the Śāsana of Jalasōthi and to the east of half of the cattle track to the east of the Śāsana of Mōlādandī, (which runs) up to the (river of) Sīngatīā. The village granted, Vallahitṭhā, still exists in the Murshidabad district of Bengal, where it is now called Valutiya. This identification and the identification of some of the boundary villages have been made by Mr. Tārak Chandra Roy, M.A., Deputy Collector, when Subdivisional Officer of Katwa. Mr. Roy succeeded in identifying the following villages mentioned in the grant :—

- (1) Jalasōthi, a village still existing under the same name in the Murshidabad district of Bengal.
- (2) Mōlādandī, a village now called Murandi in the Burdwan district of Bengal.
- (3) Khāṇḍayillā, a village called Khāruliā at the present time, which is situated in the Burdwan district of Bengal.

I edit the grant from the original plate.

TEXT.

[Metres: vv. 1, 2, *Śārdūlavikrīḍita*; v. 3, *Mandākrāntā*; v. 4, *Sragdharā*; v. 5, *Āryā*; v. 6, *Sragdharā*; v. 7, *Vasantatilaka*; v. 8, *Śārdūlavikrīḍita*; vv. 9, 10, 11, 12, *Vasantatilaka*; v. 13, *Śārdūlavikrīḍita*; v. 14, *Śikharinī*.]

- 1 Om¹ om namaḥ Śivāya || Sandhyā-tāṇḍava-samvidhāna-vilasa-nāndi-ninād-ormm-
bhīr-nnirmmaryāda-ra-
- 2 -s-ārṇavā dīśata vaḥ śrōyō-rddha-nārisvaraḥ | yasy-ārddhe lalit-āṅga-hāra-
valanair-arddhā cha bhīm-ō-
- 3 -dbhaṭair-nnāty-ārambha-rayair-ijayaty-abhinaya-dvaidh-ānurodha-śramaḥ || (1*)
Harsh-ōchchhāla-pariplavō nidhir-apāṁ
- 4 trailokya-viraḥ smarō nistandrāḥ kumudākarā mṛigadrīṣō viśrānta-mānādhayaḥ |
yasminn-abhyuditiḥ
- 5 chakōra-nagar-ābhogē subhikṣh-otsavaḥ sa Śrīkaṇṭha-śrōmaṇir-vvijayatō devas-
tamt-vallabhāḥ || (2*) Vamśō
- 6 tasy-ābhyudayini sadāchāra-charyā-nirūḍhi-prauḍhām Rāḍhām-akalita-charair-bhā-
shayantō śubhāvaiḥ | Śaśva-
- 7 -d-viśv-ābhaya-vitorāṇa-sthūla-lakṣhyā-valakṣaḥ kirtty-ullolaiḥ snapita-viyatō
jajñirō rājaputrāḥ || (3*) Tashām-vam-
- 8 -śō mahaujāḥ pratibhaṭa-pṛitan-āmbhōdhi-kalpānta-sarāḥ kirtti-joyōm-ōjjvala-śrīḥ
priya-kumuda-van-ollā-
- 9 -sa-lilā-mṛigāṅkaḥ | āśid-ājanma-rakta-praṇayi-gaṇa-manō-rāj-a-siddhi-pratishṭhā-śrī-
-śailaḥ satyaśīlō nī-
- 10 rupadhi-karṇā-dhāma Sāmanta-sēnaḥ || (4*) Tasmād-ajani Vṛisha-dhvaja-charaṇ-
āmva(mba)ja-shatpado gaṇ-ābharaṇaḥ |
- 11 Hēmanta-sēna-dēvō vairi-sarāḥ-pralaya-hēmantaḥ || (5*) Lakṣmī-mēh-ārtta-dugdh-
āmva(mba)dhi-valana-ṛaya-śraddhaya¹ Mā-
- 12 -dhavēna pratyāvṛitta-pravāh-ōchchhalita-suradhunī-śaṅkayā Śaṅkarēṇa | hamsa-
-śrēṇī-vilāsa-ōjjvalita-
- 13 -nija-pad-āhamyūnā viśvadhātrā sutrām-ārāma-simā-viharaṇa-lalitāḥ kirttayō
yasya drīṣṭāḥ || (6*) Ta-
- 14 -smād-abhūd-akhila-pā(r)ttkiva-chakravartī nirvyāja-vikrama-tiraskṛita-Sahasāṅkaḥ |
dik-pāla-chakra-pu-

¹ Expressed by a symbol.

- 15 -ta-bhōdana-gita-kirtitā prithvipatir-Vvijaya-sēna-pada-prakāśaḥ || (7°) Bhāmyanti-
nām-vauśotē yad-ari-mṛi-
- 16 -ga-driśāḥ hāra-mukta-phalāni chechinu-ākṛipāni¹ bhūman nayana-jala-milat-
kajjalair-llāñchhitāni | yatnāch=chi-
- 17 nvanti darbha-kāṭa-charaṇa-tal-āṣṭig-vilīptāni guñjā-śrag-bhūṣhā-ramya-rāmā-stana-
kalāśa-ghan-āślēṣha-lolāḥ
- 18 pulindāḥ || (8°) Pratyādiśann-avinayam prativēśma rājā vabhrāma kārmmuka-
dharah kila Kārttaviryah | aśy-ā-
- 19 -bhishēka-vidhi-mantra-padair-mṛitir-ārōpitō vinaya-varmani jīva-lōkah || (9°)
Padmālay-ōva dayi-
- 20 -tā Parushōttamasya Gaur-iva vāla-rajani-kara-śēkharasya | aśya pradhāna-mahishī
jagad-iśvara-
- 21 -śya sūddhānta-manli-manir-āsa Vilāsa-dēvi || (10°) Ēśhā sutam su-tapasām
su-kṛitair-asūta Vallāla-sēnam-a-
- 22 -tulan gunā-gauraveṇa | adhyāsta yāḥ pītur-anantaram-ēka-virah simhāsan-ādri-
śikharāḥ nara-dēva-
- 23 -simhah || (11°) Yasy-āri-rāja-sisavaḥ śavar-ālayēṣhu vālair-alika-nara-nātha-padē
śhishiktāḥ | driptāḥ pramōda-
- 24 -taral-śkhanayā jananyā nīśrasya vatsalatayā sa-bhayan nishiddhāḥ || (12°)
Kṛitāḥ prāṇa-trina-vyayōna rabha-
- 25 -sād-ālingya vidyādhari-ākālpam viharanti nandana-van-ābhōgēṣhu saṁsaptakāḥ |
Iti-ālōchya nṛipaiḥ
- 26 amara-praṇayit-ābhikāḥ śritāḥ syar-vvadhū-nētr-ēndivara-tōrap-āvali-mayō yasy-
āsi-dhārā-pathah || (13°)
- 27 Dadānā sauvarṇam turagam-uparāgē (s)mva(mba)ra-manēr=yad-aśy-ōdasrākṣhīd-
ahani janani śāsana-padam |
- 28 nṛipa-tāmr-ōtkirṇam tad-ayam-aditō² Vāsu-vidushē satām dāny-ōttāpa-prasamana-
phal-ākāḷajaladāḥ || (14°)
- 29 Sa khalu śrī-Vikramapura-samāvāsita śrīmaj-jayaśandhāvārāt | Mahārājādhirāja-
śrī-Vijaya-
- 30 -sēna-dēva-pādānudyāta-paramēśvara-paramamāhēśvara-paramabhaṭṭāraka-mahārāj-ādhi-
rāja-śrī-
- 31 -mad-Vallāla-sēna-dēvah kuśali samupagatāślēṣha-rāja-rājanyaka-rājñi-rācaka-
rājaputtra-rājā-
- 32 -mātya - purōhita - mahādharmmadhyakṣha - mahāsāndhivigrahika - mahāsēnāpati-
mahāmudrādhikṛita-

Second Side.

- 33 antaraṅga-vṛiṣaduparika-mahākaṣapaṭalika-mahāpratthāra-mahābhōgika - mahāpi[1]japati-
mahā-
- 34 -ganastha-daussādhika-chaurōddharanika-mad-vala-hasty-aśva-gō-mahish-āj-āvik-ādi-vyap-
ritaka-gaulmi-
- 35 -ka-daṇḍapāsika-daṇḍanāyaka-vishayapaty-ādin anyāms-cha sakala-rāja-pād-
ōpajivinō śdhyakṣha-pra-
- 36 -chār-ōktān ih-ākṛittitān chaṭṭa-bhaṭṭa-jāṭṭyān janapadān kaṣētrakarāmś-cha
vrā(brā)hmaṇān vrā(brā)hma-

¹ Read *kripāni.

² Read *adit-an.

[illegible]

- 37 -pottarān yath-ārham mācayati vō(bō)dhayati samādisati cha | matam-astu
bhavatām | yathā śrī-Varddhamaṇa-bhukty-antaḥ.
- 38 -pātīny-Uttara-Rādhā-maṇḍalē Svalpa-dakṣhiṇa-vithyām Khapdayillā-śāsan-ottara-
sthita-Siṅgaṭiā-nady-n-
- 39 -ttarataḥ Nāḍichā-śāsan-ottarastha-Siṅgaṭiā-nadi-pāschim-ottarataḥ Amvayillā-
śāsana-pāschima-sthi-
- 40 -ta-Siṅgaṭiā-pāschimataḥ Kuḍumvamā-dakṣhiṇa-simāli-dakṣhiṇataḥ | Kuḍamvamā-
pāschima-pāschima-gati-
- 41 -simāli-dakṣhiṇataḥ | Āhāgaḍḍiā-dakṣhiṇa-gōpatha-dakṣhiṇataḥ tathā Āhāgaḍḍiy-
ottara-gō-
- 42 -patha-niṣṛita-pāschima-gati-Surakōṇagaḍḍiākiy-ottar-āli-paryanta-gata-simāli - dakṣhi-
ṇataḥ Nāḍi-
- 43 -nā-śāsana-pūrvva-simāli-pūrvvataḥ Jalasōthi-śāsana-pūrvva-stha-gōpath-ārdha-
pūrvvataḥ Mōlādandi-śāsana-
- 44 -pūrvva-sthita-Siṅgaṭiā-paryanta-gōpath-ārdha-pūrvvataḥ | Ēvam chatuḥ-sim-
āvachchinnāḥ Vāllahittā-grāmaḥ śrī-
- 45 -Vṛishabha-śāṅkara-nalēna sa-vāstu-nāla-khilāḍibhiḥ kākā-tray-ādhika-chatvāriṇśad-
unmāna-samōta-
- 46 ādhika-nava-droṇ-ottara-sapta-bhū-pāṭak-ātmakāḥ pratyavda(bda)m kapardaka-purāṇa-
pañcha-śat-ōtpattikāḥ
- 47 sa-sāta¹-viṭapaḥ sa-gartt-ōsharaḥ sa-jala-sthalaḥ sa-guvāka-nārikōraḥ sahya-daś-
āparādhāḥ parihri-
- 48 -ta-sarvva-ṇḍaḥ triṇa-pūti²-gōchāra-paryantaḥ a-chaṭa-bhaṭṭa-pravēśaḥ a-kiñchit-
pragrāhyāḥ samasta-rāja-bhō-
- 49 -gya-kara-hiraṇya-pratyāya-sahitaḥ | Varāhadēva-śarmmaṇaḥ prapauttrāya Bha-
drēśvara-dēva-śarmmaṇaḥ pauttrā-
- 50 -ya Lakṣmīdhara-dēva-śarmmaṇaḥ puttrāya Bharadvāja-sagotrāya Bhāradvāj-
āṅgīrasa-vārhaspatya-pravarāya
- 51 Sāmaveda-Kaṭhuma-śākhā-charaṇ-ānushṭhāyīnē āchāryya-śrī-Ōvāsudēva-śarmmaṇē
asmau-mātri-śrī-
- 52 -Vilāsa-dēvibhiḥ sura-saritē sūry-ōparāgē datta-bēm-āśva-mahādānasya dakṣhiṇātvēn-
ōtṛiṣṭaḥ
- 53 mātā-pittrōr-ātmanāś-cha puṇya-yaśōbbhividdhayaś ā-chandr-ārkkam kṣhiti-
sama-kālam yāvat
- 54 bhūmi-chchhīdra-nyāyēna tāmraśāsanikṛitya pradatto śmābhiḥ | ato bhavadbhiḥ
sarvva-ir-ō-
- 55 -v-ānumantavyam | bhāvibhir-api bhū-patibhir-apabaraṇō naraka-pāta-bhayāt pālanē
dharma-gau-
- 56 -ravāt pālanīyam | bhavanti ch-ātra dharm-ānuśāsināḥ ślōkāḥ | Vahubhir-
vrasadhā dattā rājābhi-
- 57 -a-sagar-ādibhiḥ | yasya yasya yadā bhūmis-tasya tasya tadā phalam ||
[15*] Bhūmim yaḥ pratigrihpati yaś-cha bhū-
- 58 -mim prayachchhati | ubhau tau puṇya-karmmaṇau niyataḥ svargga-gāminau ||
[16*] Āspṛṇyanti pitarō va-
- 59 -lgayanti pitāmahāḥ | bhūmi-dātā kulē jātaḥ sa nas-trātā bhaviṣhyati ||
[17*] Shashṭīm varaha-sahasrāṇi svargga
- 60 tiṣṭhāti bhūmi-daḥ | ākṣhēptā ch-ānumantā cha tāny-ēva narakam vrajēt ||
[18*] Sva-dattām para-dattām-vā yō harēta

¹ May also be read *sa-jāṭa*, but *sa-śāṭa* is the reading of other Sēna grants.² May also be *yāti*.

- 61 vasundharām | sa viśṭhāyām kṛmīr-bhātṛvā pitṛibhiḥ saha pachyatē || [19*]
Iti kamala-dal-āmvu(mbu)-vindu-lōlām śriya-
- 62 -m-annohintya manushya-jivitaṁ cha | sakalam-idam-udāhṛitaṁ cha va(bu)-
ddhvā na hi puruṣaiḥ para-kīrttayo vilōpyāḥ || [20*] Jita-
- 63 -nikhila-kahitipālāḥ śrīmad-Vallāsa-sēna-bhūpālāḥ | Ōvāsu-śāsanē-kṛita dūtāṁ
Harighoṣha-sāndhivigrahaikam || [21*]
- 64 Saṁ 11 Vaiśākha-dīnē 16 Śrī ni || Mahāsām Karaṇa ni ||

TRANSLATION.

Om ! Om ! adoration to Śiva.

V. 1. May Arddhanārīśvara (a form of Śiva, half male, half female), in (one) half of whose body, by the trembling caused by the movement of beautiful limbs, and in (the other) half by the force of the beginning of the dance, which was extraordinary as well as terrible, the double labour of acting is successful (or victorious), bestow prosperity on you, making the ocean of delight to overflow by the waves of sound of the Nāndī (a preliminary song of blessing) arising at the beginning of the evening dance of Śiva (*tāṇḍava*).

V. 2. He, the crest-jewel of Śiva (*Śrīkaṇṭha*), the god (who is) the beloved of night (*tamā-vallabha*), is prosperous : on whose rise the receptacle of water (ocean) becomes restless on account of increased joy, the god of love (*Smara*) becomes a hero in the three worlds, multitudes of white water-lilies become sleepless, the deer-eyed ones (ladies) forsake sulking, there is a rejoicing on account of plenty throughout the city of *Chakora* birds.

V. 3. In his rising family were born princes (*rājaputtrāḥ*), ornamenting the *Rājās* country, illustrious on account of excessive practice of good behaviour (*sadāchāra*), with a dignity not felt or seen before, whose principal aim was to grant protection to the universe constantly, who had flooded the sky by the waves of their white fame.

V. 4. In their family was born the truthful (and) mighty *Sāmanta-sēna*, who was a guileless receptacle of pity, who was like the illustrious mountain (*Himālaya*)¹ in making his friends, who were devoted to him for ever, realise the objects of their realms of fancy, who was the moon for the festive blossoming of the water-lilies, i.e. those dear to him, whose royal dignity was made radiant by his fame, which was like moon-light, (and) who was like the Sun at the end of the *Kalpas* (i.e. at the time of the deluge)² to the ocean of troops of his enemies.

V. 5. From him was born *Hēmanta-sēna-Dēva* who was a bee to the lotus-feet of him with the bull-standard (Śiva, whose *vāhana*, or emblem, was the bull), whose qualities were his ornaments, (and) who was like the destructive winter to his pond-like enemies :

V. 6. The masses of whose beautiful fame, which had travelled up to the confines of Indra's garden, were seen by the creator of the Universe (*Vīśva-dhātṛi*) proudly as the line of geese, which by its movement had made his own realm radiant ; by Śaṅkara, with fear, as the returning (and therefore) overflowing stream of the Ganges ; (and) by Mādhava, with belief (i.e. trust or assurance), as the moving ocean of milk attracted by love for (his daughter) Lakṣmī.

V. 7. From him was born the lord of Earth called *Vijaya-sēna*, who was the overlord of all other kings, who had outshone *Sāhasāṅka* (*Vikramāditya*) by his deceitless prowess, whose fame was sung in the cities of the protecting deities of the cardinal points (*Dikpālas*).

V. 8. Torn and scattered on the earth from the necklaces belonging to the deer-eyed ones (i.e. womenkind) of whose (*Vijaya-sēna's*) enemies, as they (the women) wandered in the middle of the forest, the *Palindas*, longing to embrace closely the breasts of their beautiful women ornamented with garlands of *guṣṭā* beads, were carefully collecting the pearls (taking the pearls

¹ This mountain is supposed to contain all sorts of precious things upon which people come unexpectedly.

² At the time of the deluge twelve suns rise and dry up the mass of water.

to be *guñjā* seeds because they were) partly besmeared with the blood from wounds made in the soles of the feet by *darbha* grass, and partly by the collyrium (of the eyes of the ladies) mixed with tears.

V. 9. It is said that king Kārtavīrya went into every house, holding (his) bow in hand, checking unrighteousness; but by the mere *mantra* recited at the time of his (Vijaya-sēna's) coronation all living beings, being freed from affliction, were placed in the path of righteousness.

V. 10. Vilāsa-dēvi was the principal queen (and) the crest-jewel of the ladies' quarter of this lord of the earth, as Padmālayā (*Lakshmi*) was the wife of Purushōttama (*Vishnu*) and Gauri was of him whose crest was the young moon (*Śiva*).

V. 11. She (Vilāsa-dēvi) by the merit acquired by great austerities gave birth to a son (named) Vallāla-sēna, incomparable in virtue and dignity, who, a pre-eminent hero, a lion-like lord of men, ascended the high throne, which was like a mountain peak, after his father.

V. 12. The children of kings who were his enemies, while living in the houses of Śavaras, being crowned in pretence as kings by children (and) become proud, were seen by their mothers, with eyes atremble through joy and with sighing were forbidden through fear due to affection.

V. 13. The *Sahasaptakas* (the well-known heroes of the Mahābhārata), impetuously embracing heavenly damsels purchased at the cost of their lives, which were (held as cheap as) grass, disport themselves in the Nandana forest till the end of the *Kalpas*,—this being considered, the way of his (Vallāla-sēna's) sword, which was like a series of gateways, with blue lotuses consisting of the eyes of heavenly brides, was entered by kings, whose fearlessness was instilled by the god of love (*Smara*).

V. 14. The donative grant (*dāna-pada*) which the mother of this (king) gave (as *dakṣiṇā*) on the occasion of the gift of the golden horse on the day of a solar eclipse this king, who is to the good a cloud out of season for quenching the pains of poverty, gave, engraved on copper, to the learned Ōvāsu.

(Here follow the terms of the grant, the particulars concerning the estate granted, the name, genealogy, etc., of the donee, and the usual admonitory verses.)

NO. 11.—SANGOLI PLATES OF HARI-VARMA: THE 8TH YEAR.

By K. N. DIKSHIT, M.A., POONA.

These copper-plates, three in number, were first handed over to me, and subsequently presented¹ to the Prince of Wales Museum of Western India, Bombay, by Mallappa Īśvarappa Baḷigār, inhabitant of the village of Sangoli or Sangoḷi, on the river Malaprabhā, in the Sampaḡam Tāluk of the Belgaum District,—a place well known in the annals of modern Karnatic history, as the native place of Rāyappa² Nāyak, a rebellious retainer of the Desai of Kittūr, who caused a considerable amount of trouble in 1829 A.D.

The owner is a coppersmith, and that might account for the plates coming into his possession. He says, however, that they are his ancestral property, for the last three or four generations, and he hoped to find in them a record of ancient times, conferring on his ancestors the 'Deśgat' of the country around Bāgalkoṭ in the Bijapur District, from which place he says his grand-father came down and settled at Sangoli. The grant may, therefore, have been brought

¹ It was through the good offices of Mr. G. L. Gajendragadkar, B.A., Mamlatdar, Sampaḡam Tāuka that the owner, after much persuasion, consented to present the plates, which he said he was in the habit of worshipping daily.

² See the ballad describing the rebellion, published in *Ind. Ant.*, Vol. XIV, pp. 393 ff.

from that part of the country; but the present *provenance* is quite in keeping with the known extent of the Kadamba dominions, Halsi or Palāsikā, one of the secondary Kadamba capitals being only 24 miles away from Sangoḷi.

The plates are three in number, rectangular with corners slightly rounded off, flat without raised rims, of uniform thickness and equal dimensions, each being $8\frac{1}{2}''$ long $\times$ $2\frac{1}{2}''$ broad. Through a hole in each plate, $1\frac{1}{2}''$ in diameter, passes a heavy ring, $2\frac{1}{2}''$ in diameter. There is no emblem on the ring. Of the first and last plates only one side, of the middle one both sides, are inscribed. All the inscribed sides contain five lines each, except the reverse side of the middle plate, which contains six.—The letters are engraved with sufficient care, and are deep enough, except in places, where they are completely lost. They do not, however, show through the reverse. The average length of each letter is $\frac{1}{4}''$. The plates together with the ring weigh about $2\frac{1}{2}$ lbs.

The alphabet closely agrees with that of all the other Kadamba grants, and is thus regular for the period and locality to which the grant refers itself. Comparing particularly with the other¹ two grants of Hari-varman, from Halsi, I find that the alphabets are identical in all the three grants, except the letters *ga*, *ta* and *sa*, which show a distinct loop at the bottom in the Halsi grant issued in the fifth year of the reign, which proves that both forms were in vogue at the period. Of individual *akṣaras* from the present grant the form of *a* in line 1 is noteworthy owing to the loop; also the form of *ka* in l. 9, which has instead of a complete vertical line an oblique stroke up to the horizontal line and below it the vertical line as usual from the centre downwards. This form of *ka* has its origin in the late Kadamba period, and it continues to early Chalukya times.

The language is Sanskrit, the whole grant being in prose, except the first benedictory stanza and the usual verses at the end. The attributes employed to describe the Kadamba kings in general and Hari-varman in particular are such as are found in other Kadamba grants, except *Parama-māhēśvara*, which is worthy of note. The epithet *Śrī-nīlambānām* in l. 4 is introduced before *Kadambānām* merely to serve the purpose of alliteration, as other phrases² are introduced in so many other Kadamba grants. Another attempt at alliteration may be traced in the final obeisance to the three Brahmanical deities, i.e., *Namō Hṛī-Hara-Hiranyagarbhābhyaḥ* l. 21.

As regards orthography, we find the doubling of the preceding consonant before *ya*, as in *anuddhyānā*³ l. 2, *evāddhyāya* l. 3, and before *ra*, as in *sa-gōttre*⁴ l. 12, *sa-gōttrāya* ll. 14, 15. But, on the other hand, we find *sa-gōtrānām* l. 3, *sa-gōtrābhyaḥ* ll. 10-13, *sa-gōtrāya* l. 15. The consonant following *ra* is often doubled, as in *Śambhur-vva*⁵ l. 1, *charchchā* l. 3, *kīrttiḥ* l. 6, *Hari-varmmā* l. 7, *pravarddha*⁶ l. 8, *Atharvva* l. 9, *dharma-karmma* l. 9, *śarmma* ll. 10-15, *-paharttā* l. 17, *Bahubhīr-vva*⁷ l. 18; but not in *Dharma*⁸ l. 5, *Garga* l. 12, *śarma* ll. 12, 14. The use of the class nasal is preferred to that of an *anusvāra* in the body of a word, while the latter is retained at the end of a word, the only exceptions being *viśvāśān-ja*⁹, *jagatām-patīḥ* l. 1, *sa-pāntīyan-Te*¹⁰, *Tēdāva-grāman-datta* l. 16, and *uktān-cha* l. 18. The final *Visarga* is as often as not changed into the following sibilant; e.g. *anidhanas=Śambhu*¹¹ l. 1, *dikshitaiśruta* l. 6, *Māhēśvaraś-Śrī*¹² l. 7, *Yasaiśarmma* l. 13, *rājābhīś-Saga*¹³ l. 18; but *rājaḥ sakala* l. 6, *bhyaḥ va-dharmma* l. 9, *bhyaḥ Śiva* l. 10, *bhyaḥ Śravishtā* l. 13. The *Jihvāmāltya* is not used; the *Upadhāntya* is used twice; e.g. *-kīrttiḥ prajā* l. 6, *-paraḥ parama* l. 7. The *Sandhi*

¹ *Ind. Ant.*, Vol. VI, pp. 29 and 31.

² Cf. the following expressions, occurring in juxta-position with *Kadambānām*; viz., *sad-dharma-sad-ambānām*, *Ind. Ant.*, Vol. VI, p. 26; VII, 35; *āśritāmbānām* [*Epi. Carma.*, Vol. VIII, p. 12]; *āśrita-jan-āmbānām* [*Ind. Ant.*, Vol. VII, p. 83]; *prajā-sādharan-āmbānām* [*Ind. Ant.*, Vol. VI, p. 23]; *ādī-kūla-rājarekhī-śimbānām* [*Ind. Ant.*, Vol. VII, p. 33]; *vīrudha-pratibimbānām* [*Ind. Ant.*, Vol. VII, p. 37].

rules are often violated; e.g. -*nām anēka* l. 4, -*saṃvatsarē āvra°* l. 8, -*vriddhaye Atharva-* l. 9, -*Sarmabhyaḥ Garga-* l. 12, -*gōtrēbhyaḥ Vishnu-* l. 12, -*bhyaḥ Yaśa-* l. 13, -*bhyaḥ Chaūliya-* l. 14. The wrong class nasal is used in *Vaikuntha-* l. 11, which ought to be *Vaikunṭha-*. The word *Chaūliya*, l. 14, perhaps stands for *chaūliya*.

The plates record a grant by king Hari-varman of the early Kadamba dynasty of Vaijayanti. Since the publication of the Halsi¹ and Devagere² grants, which were the first to come to light, our knowledge of the dynasty has vastly improved, owing to the publication of seven³ more copper-plate grants, and two⁴ stone inscriptions, all from Mysore territory; so that now we are in possession of a genuine account of the origin, as well as a fairly certain genealogy for the family, thanks to the excellent paper⁵ by Dr. Kielhorn on the Tālagunda pillar inscription. From the earliest known grants Dr. Fleet was led to believe that the Kadambas were followers of Jainism;⁶ but all the records from Mysore since brought to light show that not only did they worship Brahmanical deities, and highly respect the Brahmins, but they were themselves linear descendants of a Brāhmaṇa. The more probable conclusion is that the Kadambas were very tolerant in religion, favouring with donations, now one sect, now another. On careful examination of all the published records we find that from Kākutṣtha-varman down to Hari-varman every king granted donations to Jaina ascetics, as well as to Brāhmaṇas.

The grant was issued from Vaijayanti, the modern Banavāsi in the Sirsi Taluka of the North Kanara District. The donees were 23 Brāhmaṇas of 8 different *gōtras*, all well versed in the *Atharva-vēda*. Some of the *gōtra* names are very unusual, e.g. Kaimbala, Kālāśa, Śrāviṣṭha, Valandata, Chaūliya. The fact may also be noted that there are very few Brāhmaṇas belonging to the *Atharva-vēda* at present in the Deccan, and Bombay Karnatic. The village granted was Tēdāva, of which no particulars are given, and which cannot be identified.

The date is given as the New Moon day (*Amāvāsyā*) of the month Āśvina, during the eighth regnal year of Hari-varman. This in itself would have given us no more data for fixing the chronology than the other Kadamba inscriptions supply; but the further specification of the date as *Vishupā*, no doubt, helps to some extent in doing so. Let us see how we can make use of this clue.

It is admitted on all hands that the Kadamba rule in the Deccan was displaced by the Chalukyan, some time before 570 A.D., and that Hari-varman, who must have been one of the last Kadamba princes, if not the very last, cannot be placed earlier than about the end of the first half of the sixth century A.D. On this hypothesis I began to calculate whether the *Amāvāsyā* in the month of Āśvina coincided with *Vishupā* or *Tulā-Samkrānti* (autumnal equinox) during any year about the same period. On consulting Diwān Bahādur L. D. Swāmikannu Pillai of Madras, I found that during the whole of the sixth century A.D. there were only three years in which the above astronomical phenomenon occurred; viz., during A.D. 507, 526 and 545. The first of these years is out of the question, as being too early for Hari-varman. Of the other two I think the year 545 is more probable than the year 526, as in the former case we should not have to leave a large gap unaccounted for, between the periods of Kadamba and Chalukya ascendancy. However, it is not unlikely that the year was 526. The date of the present grant must therefore be either Tuesday, the 22nd September 526 A.D., or Thursday, the 21st September 545 A.D.

¹ *Ind. Ant.*, Vol. VI, pp. 22-32.

² *Ind. Ant.*, Vol. VII, pp. 33-38.

³ *Ep. Ind.*, Vol. VI, pp. 14, 18; *Ep. Ind.*, Vol. VIII, p. 146; *Epi. Carna.*, Vol. IV, p. 138; Vol. V, p. 594; Vol. VI, p. 91; Vol. VIII, p. 12.

⁴ *Ep. Ind.*, Vol. VIII, p. 24; *Epi. Carna.*, Vol. VIII, p. 167.

⁵ *Ep. Ind.*, Vol. VIII, pp. 24 ff.

⁶ *Ind. Ant.*, Vol. VI, p. 22.

These conclusions admit of an independent corroboration. Dr. Fleet has recently published an article,¹ in which he states that the Pennkonḍa copper-plate grant of the Western Gaṅga Mādhava II. is perhaps the first genuine record of the Gaṅgas, which he would assign on palaeographic grounds to about 475 A.D. Now, assuming that the same Gaṅga king Mādhava II. was married² to a sister of the Kadamba Mahārāja Kṛishṇa-varman I., we may easily consider Kṛishṇa-varman I. to have lived about 475 A.D. and his elder brother Śānti-varman at a slightly earlier date, say 470 A.D. If we test the accuracy of our assumed dates for the present grant in this light, we find that in one case we leave a space of about [526-470]=56 years or so, and in the other of about [545-470]=75 years or so, to be bridged over by three generations, as Hari-varman was the great-grandson of Śānti-varman, grandson of Mṛigśa-varman and son of Ravi-varman. The assumption, involving a gap of about 75 years for the three generations, is the more probable, as the average period for a generation is in India calculated to be 25 years. So 545 A.D. is the most probable date for our record. The date of accession for Hari-varman, on this assumption, would be 538 A.D.

The accompanying plates have been prepared from impressions taken for me by the office of the Superintendent, Archaeological Survey, Western Circle, Poona.

TEXT.³

[Metres: vv. 1-3, Anuṣṭubh Śloka.]

First plate.

- 1 Jayati dhruva-bāl-āṇḍa-jaṭā-makṣa-maṇḍanaḥ⁴ [I] anādy-anidhanaś-Sambhur-
vī[ś]vāśā[ḥ]-jaga[tā]m-[patih] [|| *]
- 2 *Vijaya-Vaijayantyaś Svāmi-Mahāśēna-māṭṛi-gaṇ-ānuddhyān-ābhishiktānā[m]
- 3 Mānavya-sa-gotrāṇām Hārīti-putrāṇām pratikṛita-svādhyāya-charachā-
- 4 pārāṇām Śrī-nitambānām Kadambānām anēka-janmānta[r-o]
- 5 pachita-vi[pu]la-p[u]ṇya-akandha-yaśasā[m] sākshā[d iva] Dharma-

Second plate; First side.

- 6 rājāḥ sakala-di[g-an]tar-ōdit-āmala-kirttiḥ-prajā-rakṣaṇa-dīkṣitaś-śrūta-vinaya-
- 7 pavitrīta-śarīrō dvijāti-śuśrūṣhā-parah-parama-Māheśvaraś-Śrī-Harivarmmaś
- 8 pravarddhamāna-rājya-śaṣṭama-samvatsarē Āśvayuj-āmāvāsyāyām viśhupē
- 9 sva-kul-ābhivṛddhaye Atharvva-vēda-pāragōbhyah sva-dharmma-karmma-niratōbhyah
- 10 Kaimbala-sa-gotrōbhyah Śiva-śarmma-Prajāpati-śarmma-Dhātṛi-śarmma-Nan[d]i-śarmma-
Dharmma-

Second plate; Second side.

- 11 [śarm]mabhyah Kālāśa-sa-gotrōbhyah Vaikunthaś-śarmma-Vasu-śarmma-Nāga-
śa[r]mma-[Ma*]pdaśa-śarmmabhyah

¹ *Journal of the Royal Asiatic Society*, July 1915, pp. 471 ff.

² No less than four copper-plate grants mention this relation between the Gaṅgas and Kadambas; and, though the records are held to be spurious, there is no reason why the alleged alliance should be considered fictitious. The identity of Kṛishṇa-varman can be established from the fact that he is said in all the records which refer to him to have performed the celebrated Āśva-mūḍha sacrifice (vide *List of Southern Inscriptions*, *Ep. Ind.*, Vol. VII, Nos. 112-115).

³ From the original plates and a set of impressions.

⁴ Read *mukṣa*; cf. *Jed. Ant.*, Vol. VI, p. 86; Vol. VII, p. 86; *Ep. Carna.*, Vol. IV, p. 136; perhaps the word was more common then in the form *mukṣa* than as *mukṣa*.

⁵ The word *Siddham* is written in the margin opposite l. 2.

⁶ Read *Vaidyaśa-*

iii.

[illegible]

11

ॐ नमो भगवते वासुदेवाय ॥ १ ॥
 नमो भगवते वासुदेवाय ॥ २ ॥
 नमो भगवते वासुदेवाय ॥ ३ ॥
 नमो भगवते वासुदेवाय ॥ ४ ॥
 नमो भगवते वासुदेवाय ॥ ५ ॥
 नमो भगवते वासुदेवाय ॥ ६ ॥
 नमो भगवते वासुदेवाय ॥ ७ ॥
 नमो भगवते वासुदेवाय ॥ ८ ॥
 नमो भगवते वासुदेवाय ॥ ९ ॥
 नमो भगवते वासुदेवाय ॥ १० ॥

ॐ नमो भगवते वासुदेवाय ॥
 श्रीकृष्णाय नमः ॥
 कुरु मे भक्त्यै ॥
 नमः ॥

[illegible]

- 12 Garga-sa-gōtrēbhyah Vishṇu-śarmma-Prajāpati-śarmma-Pitṛi-śarmabhyah Ko(Kau)tsa-
sa-gōtrēbh[ya]h
13 Kumāra-śarmma-Tvaṣṭṛi-śarmma-Skanda-śarmma-Varuṇa-śarmabhyah Śrāviah[tha]-
sa-gōtrēbhyah Yaśas-śarmma-[Ā]-
14 yya-śarmma-Paśupati-śarmma-Mitra-śarmabhyah Chaūliya-sa-gōtrāya Vana-śarma[nē]
15 Valandata-sa-gōtrāya Prajāpati-śarmma[nē] Kāśyapa-gōtrāya Kumāra-śarmma[nē]
16 a-āṣṭādaśa-pravibhāgam sa-dakṣiṇam sa-pāṇiyan-Tēdāva-grāman-dattavān [i*]

Third plate.

- 17 Yō=ay-āpa[hart]t[ā] sa pañcha-mahā-pātaka-samyuktō bhavati [i] Rakshi[tā]
cha p]uṣya-phala-
18 bhāg-bhavati [i*] uktañ=cha [i*] Bahubhir-vvasudhā bhuktā rājabbis-Sagarā-
dibhiḥ [i*] yasya ya[aya]
19 yadā bhūmis-tasya tasya tadā phalaṁ [i] Sva-dattām para-dattām vā yō
harēta [vasu]-
20 ndharām [i*] shashṭi-varsha-sahasrāpi narakē pachyatō tu saḥ [i] Siddhir-
astu [i*]
21 [Namō] Ha[r]i-Ha[ra-Hi]raṇya-gabbhābhyah¹ [i*] Svasti prajābhyah² [i*]

TRANSLATION.

(L. 1) Victorious is (*the god*) Śambhu, lord of all the worlds, on whom the crescent-shaped (lit. young) moon is a steadfast ornament crowning his matted hair, and who has neither beginning nor end.

(ll. 2-5) Success! In the victorious (*city of*) **Vaijayanti**, (*in the family*) of the **Kadambas**, who were consecrated in meditation upon the Lord Kārttikēya and the host of (*his*) mothers; who belong to the **Mānavya gōtra** (*lineage*) and are descendants of Hāriti; who studied³ the requital (of good and evil) as their sacred text and were well-versed in that; who are the (*very*) hips⁴ of the goddess of wealth, and who are famed to have stored immense religious merit throughout a succession of former births,

(ll. 5-7) the illustrious **Hari-varman**,—who is Lord Dharma⁵ incarnate, as it were, whose unspotted fame has pervaded all the different quarters, who has been initiated into (*the vow of*) protecting the subjects, whose body has been sanctified by means of learning (*combined*) with modesty, who is intent on the service of the Brāhmaṇas (lit. *twice-born*), and who is a great devotee of the mighty god (i.e. Śiva)—

(l. 8) in the eighth year of his flourishing reign, on the New Moon day of Āṣvina on the (autumnal) equinox

(ll. 9-16) gave, for the prosperity of his dynasty, the village of Tēdāva, with all its eighteen subdivisions, along with water and (*money as*) *Dakṣiṇā*, to (*the following Brāhmaṇas*), who have thoroughly mastered the *Ātharva-vēda*, and who are devoted to their religious duties and rites, by name Śiva, Prajāpati, Dhātṛi, Nandi, and Dharmma of the **Kaimbala gōtra**; **Vaiṣṇu**, **Vasu**, **Nāga**, and **Maṇḍapa** of the **Kālāsa gōtra**; **Vishṇu**, **Prajāpati** and **Pitṛi** of the **Garga gōtra**; **Kumāra**, **Tvaṣṭṛi**, **Skanda**, and **Varuṇa** of the **Kotsa gōtra**; **Yaśas**, **Āyya**, **Paśupati** and **Mitra** of the **Śrāvishṭha gōtra**; **Vana** of the **Chaūliya gōtra**, **Prajāpati** of the **Valandata gōtra**, and **Kumāra** of the **Kāśyapa gōtra**.

¹ Read *garbhābhyah*.

² Read *prajābhyah*.

³ I follow Dr. Kielhorn in translating the difficult phrase *pratikṛta* (*Ep. Ind.*, Vol. VI, p. 17).

⁴ The meaning is that the Kadambas constituted the very bulk of the goddess of wealth; i.e. they were very rich.

⁵ The god of righteousness, viz. Yama; or Yudhishṭhira, the renowned king.

(Il. 17-20) He who revokes this will have committed the five deadly sins; he who protects will share the fruit (arising) from the religious merit (of the donation); as has been said: 'By many kings, Sagara and others, has the earth been enjoyed; he who at any time possesses it also gets the fruit. He who deprives (another of) land given by himself or by others will be tormented in hell for sixty thousand years, together with his forefathers. Let there be success!

(I. 21) A bow to (the gods) Hari, Hara, and Brahmā (Hiraṇyagarbha)! Hail to the subjects!

No. 12.—UDAYAMBAKAM GRANT OF KRISHNA-DEVA RAYA : SAKA 1450.

By S. V. VENKATESWARA, M.A., AND S. V. VISWANATHA, M.A., KUMBakonam.

The grant is on three copper-plates bored at the top and secured by a ring, attached to which is the seal, bearing the Vijayanagara emblem of a boar and the figures of the sun and the moon on the upper half, and on the lower half some characters, probably corresponding to *Śrī Venkaṭēśa*, as suggested by Dr. Hultzsch¹ in regard to the seal attached to the Kaniyār plates of Venkaṭa II. The plates, which are in good preservation, belong to the Śaṅkarāchārya of the Conjeeveram maṭha, who very kindly lent them for examination.

The plates measure $8\frac{1}{2}$ in. by 7 in., except in the middle, which is $10\frac{1}{2}$ in. by 7 in. on account of the arch at the top. The ring has a diameter of 1 in., and the seal of $2\frac{1}{2}$ in. The holes through which the ring passes have a circumference of $1\frac{1}{2}$ in. All the plates have raised rims. The writing is legible and runs right across the breadth of the plates, as usual. As in other Vijayanagara plates of the period, the first and third plates are inscribed only on one side, and the middle one on both sides. The plates are ruled. The inscription contains 99 lines in all, and the average height of a line is $\frac{1}{4}$ in.

The language of the inscription is Sanskrit, or Sanskritized Kanarese, as in the *birudas* of the king (Il. 25 to 29). The inscription is in verse, and the usual metres are employed, the *Anuṣṭubh*, the *Śārdūla-vikrīḍita*, *Śragdharā*, etc. Not only is the poetry of a low order, but the rules of metre are transgressed here and there; e.g. in verses 34 and 32 the halves *Chandraśekhara-Sarasvatyāḥ śiṣhyāyāmitatājāś* and *śiṣyāyāmitatājāś cha mahātmanāḥ*, which are out of accord with the *Anuṣṭubh*, the metre of the verses. In many places where the metre is faulty, however, it is due to a mistake of the scribe, e.g. *śriyam iha likṛitya* in verse 28, which should be read *śriyam iha bahalikṛitya*. If in this case the scribe has left out letters in a word, elsewhere he has added superfluous ones, e.g. *jaladhī* in verse 21, *prati* and *nuta* in verse 22.

The characters are Nandināgari, except the signature, or rather the name of the tutelary deity¹ at the bottom, which is written in Kanarese. There are several orthographical peculiarities. There are many instances of a redundant *anuvāra*, especially before conjunct consonants, as in other Vijayanagara plates.—*pūṇnyaiḥ* for *pūnyaiḥ* (l. 7), *amṇyān* for *anyān* (l. 20), *hiraṇya* for *hiranya* (Il. 36, 37). But we have also instances of redundant *visarga* in *śiraśi-chumbi* (l. 1) for *śiraś-chumbi*, *bhuvanaḥ-stūyamāna* for *bhuvana-stūyamāna* (l. 18). In conjunct consonants the former member is often omitted. This error is specially noticeable in connection with the consonants *ta* and *da*. Cf. *mayādēva* for *mayād dēva* (l. 5); *tasy-āṣṭtanaya* for *tasy-āṣṭ tanaya* (l. 6); *udabhātasmānara* for *udabhāt tasmān nara* (l. 11); *bhuja-balātām* for *bhuja-balāt tām* (l. 16); *tadhāma* for *taddhāma* (l. 4); *chatu-simā* for *chatus-simā* (l. 84); *a-gaj-bhātām* for *a-gaj-odbhātām* (l. 4); *nṛisinh-āndrā tasmāt* for *nṛisinh-āndrāt*

tasmāt (l. 22). There is the usual confusion in the writing of the sibilants; cf. *bhabhāsē* for *babhāsē* (l. 17), *bhūyāsē* *erēyāsē* for *bhūyāsē* *śrēyāsē* (l. 54), *śasāsa* for *śasāsa* (l. 27), *chatu-śīmā* for *chatus-sīmā* (l. 84) and *śishya* for *śishya* (4, 86, 87). It is interesting to note that in the Poḍavūr and Kāṭṭapaṭṭa grant¹ of the same king six years earlier we find *śishya* written for *śishya* (l. 82). Thus all three letters *śa*, *sa*, *sha* were used indiscriminately. The influence of the Dravidian languages in the pronunciation of Sanskrit words is clear in *tām̐bra* for *tāmra* in l. 93, and in *varuśa* for *varuśa* in l. 96. Udayambākam, the name of the village granted, is spelt Wudayambākam as the result of the same influence.

The inscription records the grant of Udayambākam, a village near Tirukkalukkupram in the Chingleput district, by Kṛṣṇadēva Rāya of the second Vijayanagara dynasty to Sadāśiva Sarasvatī, the disciple of Chandrasēkhara Sarasvatī of the Śaṅkarāchārya *maṭha* at Conjeeveram.

It is noteworthy that in this grant, and in that of Poḍavūr referred to above, there is no special purpose for which the grant was made, as in the grant of Vijaya-Gaṇḍagōpālā²—which expressly says that it was made 'for the attainment of the highest *dharma*' 'by feeding 108 Brāhmins every day.' The terms of the gift are the same as those given in the other plates of the king. It is curious that, though the gift was made to the Āchāryas of the *maṭha* and their descendants in the apostolic line, it is not made inalienable, as we should have expected; '*Bhōktuṃ dātum chāpi nij-śechchaya*' (v. 41).

The date of the grant is Śaka 1450, the cyclic year Virōdhin, month Vaiśākha, constellation Viśākhā, and *tīthī* Pūrṇimā.

Many of the names of places given in the grant correspond to the names of villages in the district of Chingleput:

'Tirukkalē-kunnarēndāru' is probably the modern Tirukkalukkupram,³ 'the hill of the sacred kites,' which is much resorted to as a place of pilgrimage, or may it be Tirukkāṭṭikkāḍu in the Conjeeveram Taluk?

Kaḷattūr is another name for Oṭṭivākkam, five miles from Chingleput town, and a station on the South Indian Railway.

Maṇappakkam is an insignificant village, 2 miles from Kaḷattūr.

Udayambākam, the object of our grant, is about 4 or 5 miles from Kaḷattūr.

Kshira-nadī is the Sanskrit name of the Pālār river.

Prallayannūr is the modern Palayanūr in the Madurāntakam Sub-District.

Punyapaṭṭu is Punnampattū in the Chingleput Sub-District.

The name of the donee is Sadāśiva Sarasvatī, a pupil of Chandrasēkhara Sarasvatī. Chandrasēkhara and Chandrachūḍa are variant forms of the same name. Further, the name Chandrasēkhara in our grant is probably an engraver's error for Chandrachūḍa. The metre requires the latter form: '*Chandrasēkhara-sarasvatīś śishyāy-āmita-tējasē*' has one syllable more than is allowed by the rules of metre in the *pāda* of an Anuṣṭubh verse. If we read Chandrachūḍa for Chandrasēkhara, there is no such metrical difficulty. If so, the donee Sadāśiva of our grant was a pupil of Chandrachūḍa, the donee in the earlier grant of the same king.⁴ Some time in the interval between the two grants (1521 and 1527 A.D.) Chandrachūḍa must have died, and his disciple Sadāśiva must have succeeded him. Thus we get the names of four successive teachers of the *maṭha*, as mentioned by us in our introduction to the grant of Vira-nṛsiṃha Rāya.⁵ In connection with the latter grant we have

¹ *Ep. Ind.*, Vol. XIII, pp. 122 ff.

² *Ep. Ind.*, Vol. XIII, p. 194.

³ Tirukkalukkupram is in Kaḷattūr-kōṭṭam. See the inscriptions of that place edited in *Ep. Ind.*, Vol. III, No. 38.

⁴ *Ep. Ind.*, Vol. XIII, pp. 122 ff.

⁵ *Ep. Ind.*, Vol. XIV, pp. 231 ff.

also given extracts from the *Gururatanmālāstava*, and have identified the donees of these grants. Our identification of the donees with the *Gurus* of the Śaṅkarāchārya *maṭha* is supported by the epithets used in the grant before us: 'the wearer of holy beads' (*rudrākṣha*), 'whose body is besmeared with holy ashes,' 'one who is above the pairs of opposites,—heat, cold, etc., which give pain,' 'Guru who has the form of Śiva.'

We have already shown elsewhere that Kṛishṇa-dēva Rāya's gifts at holy places are confirmed by inscriptions. His conquest of Kalinga is referred to in various stone inscriptions.¹ His suzerainty over Aṅga and Vaṅga must be regarded, however, as an empty boast. It is possible to understand *Ā-Gaṅgā-hra-Laṅkā*² as referring not to the Ganges river, but to one of the rivers of Berar (Wainganga or Penganga). There is no confirmatory evidence of the Vijayanagara Rāja having extended his arms as far north as the Ganges. Nor is there any evidence of the conquest of the Chēra country by Narasa, father of Kṛishṇa-dēva Rāya. There is an anachronistic reference to an invasion of Kṛishṇa-dēva Rāya in the *Kēraḷōtpatti*, the traditional history of the Malayālam country. But the west coast of South India was practically independent.

The Kanarese *birudas* of the king were mostly borrowed from those of the kings of the first dynasty,³ as also the titles Rājādhirāja and Rāja-paramēśvara.

TEXT.⁴

[Metres: vv. 1-4, 6-8, 12 and 13, 25-27, 29-42, 45-49, *Anuṣṭubh*; vv. 5 and 20, *Sārdūlavikṛīḍita*; vv. 10, 14, 21 and 28, *Sragdharā*; v. 9, *Hāriṇī*; v. 24, *Dōḍhaka*.]

Plate I, Side i.

- 1 श्रीगणाधिपतये नमः । नमस्तुंगशिरः⁵बुविचंद्र-
- 2 चामरचारवे । त्रैलोक्यनगरारंभमूलस्तंभाय भवे⁶ [। 1*] हरिलीलावरा⁷।
- 3 ह्रस्व दंष्ट्रादंडः स पातु वः । हेमाद्रिकलशायत्र धात्री च्छत्रत्रियं दधी [। 2*]
- 4 कल्याणायामस्तु त धाम⁸ प्रबुद्धतिमिरापहं [।] यज्ञजोष्यगजोभूत⁹ हरि-
- 5 णापि च पूज्यते [। 3*] अस्ति चौरमया¹⁰ देवेर्मध्यमानान् महान्बुधेः । नवनी-
- 6 तमिवीरूतमपनीततमो महः [। 4*] तस्मात्तौ तनय¹¹स्तपोभिरतुलैरन्व-

¹ See Madras Epigraphist's Report for 1915, Nos. 18 and 64 of App. C.

² One of the *birudas* of Dēvarāya II in the Satyamaṅgalam plates, edited by Dr. Hultzsch in *Ep. Ind.* Vol. III, pp. 35-41, is *Bhāsā-ātīlāṅghī-bhāpāla-bhajaṅga*, which is a Sanskrit rendering of *Bhāsāga tappasa rāgara gaṅga*. The *birudas* in that grant are mostly the same as in ours:

राजाधिराजलोचनी श्री राजपरमेश्वरः ।

भावातिवद्विष्णुपाशमुज्ज्वलितदीप्तिः ॥

मूढराजवर्णकः परराजभयंकरः ।

हिन्दुराजसुरवाची बन्धिवर्णकः ॥

Dr. Hultzsch translates these passages as follows:—

"He bore the surnames (*birudas*) Rājādhirāja, Rājaparamēśvara, 'the disgracer of kings who break their word,' 'the disgracer of the three kings (of the south),' 'the terror of hostile kings' and 'the sultan (*sarathraja*) among Hindu kings.'"

⁵ From the original.

⁶ Read 'अभवे'.

⁷ Read 'हरि'.

⁸ Read 'मिरदुवि'.

⁹ Read 'हरिलीलावरा'.

¹⁰ Read 'महादेवे'.

¹¹ Read 'तौ'.

¹² Read 'तस्मात्'.

¹³ Read 'तनय'.

7 र्थनामा बुधः पुं^१स्त्वैरस्य पुरुरवा भुजवलैरायुर्हिषां निघ्नतः । तस्या^२
 8 तस्यायुष्^३द्वयोस्य तस्य पक्षो युद्धे ययातिः^४ चितौ स्यात्तस्य तु त्वं^५सुर्वसुनि-
 9 भः श्रीदेवयानीपतेः ।। 5*] तदंशे देवकौजानिर्दिदीपे तिमभूपतिः । यशस्वो
 10 तुलुवेद्रेषु यदोः कृष्ण इवान्वये ।। 6*] ततोभृदुक्कमाजानिरोश्वरक्षितिपाल-
 11 कः । अत्रासमगुणभंशं मौलिरत्नं महीभुजां ।। 7*] सरसादुदभू^६ तस्मा^७ नर-
 12 सावनिपालकः । देवकीनंदना कामो^८ देवकीनंदनादिव ।। 8*] विविधसुक्ततोहा-
 13 मे रामेश्वरप्रमुखे सुडुर्मुदितहृदयः^९ स्याने स्थाने व्यधत्त ययथाविधिः^{१०} । बु-
 14 धपरिवृतो नानादानानि यो भुवि षोडश त्रिभुवनजनोद्भूतं स्फी^{११} यशः^{१२} ।।
 15 पुनरुक्तयथा^{१३}विधिः ।। 9*] कावेरीमायु बध्वा बहलजलभरां यो विलं-
 16 ध्यैव शतनु^{१४} जीवयाहं गृह्येत्वा समिति भुजबला^{१५} तं च राज्यं तदियं^{१६} ।।
 17 कृत्वा श्रीरंगपूर्वं तदपि निजश्रे^{१७} पट्टयं यो बभूव^{१८} कीर्त्तिस्तंभं निखातं
 18 स्त्रिभुवनभुवनःस्तूयमानापदानः^{१९} ।। 10*] चेरं चीलं च पाण्ड्यं तमपि च मधु-
 19 रावत्तंभं मानभूषं वीर्योदधं तुरुष्कं गजपतिनृपतिं चापि जि-
 20 त्वा तदंन्यान् । आगंगातीरलं^{२०} प्रथमचरमभूत्तटांतं नितांतं । स्या-
 21 तः चीनीपतीनां सजमिव शिरसा शासनं यो व्यतानोत् ।। 11*] तिप्पाजीनाग-
 22 लादेव्यो कं^{२१}सन्ध्याश्रीसुमित्रयोः (i) देव्योरिव नृसिंहेंद्रा^{२२} तस्मात्पंक्तिर-
 23 याविव^{२३} ।। 12*] वीरो विनयिनौ रामलक्ष्मणाविव नंदनौ जातौ वीरनृसिं-
 24 हेंद्रकृष्णरायसहीपती ।। 13*] वीरश्रीनारसिंहः स विजयनगरे रत्न-
 25 सिंहा^{२४}सनस्यः । कीर्त्त्या नीत्या निरस्यं नृगनलनहुषानप्यवन्ध्यां^{२५}-
 26 शंन्या^{२६} । आ^{२७}तोरासुमेरोरवनिसुरनुतस्त्वैरमाचोदयाद्रेरापाशां^{२८}त्वा-
 27 चलांतादखिलहृदयमावर्ण्यं राज्यं सशास^{२९} ।। 14*] नानादानान्यकार्षीत्क-
 28 नकसदसि यः श्रीविरुपाक्षस्थाने श्रीकालहस्तो शितुरपि न-
 29 गरे वेंकटाद्रौ च कांच्यां । श्रीशैले शोणशैले महति हरिहरे ऽहोबले
 30 संगमे च श्रीरंगे कुंभघोणे हततमसि महानंदितोर्ध्वे निहत्तौ ।। 15*]
 31 गोकर्णे रामसेतौ [ज]गति तदितरेष्वप्यशेषेषु पुंस्त्वस्थानेष्व-

^१ Read पु.

^२ Read स.

^३ Omit.

^४ Read पुनरुक्तयन्.

^५ Read तदौयं.

^६ Read निखायतिभुवनभवनकायं.

^७ Read नृसिंहेंद्रात्वात्.

^८ Read अप्यवन्ध्यां.

^९ Read या.

^{१०} Omit.

^{११} Read स.

^{१२} Omit *sisarga*.

^{१३} Read शतनु.

^{१४} Read निजश्रे.

^{१५} Read लला.

^{१६} Read पक्षिरथादिव.

^{१७} Read धान्यान्.

^{१८} Read शशास.

^{१९} Read न

^{२०} Read नंदनात्कामो.

^{२१} Read स्फीतं.

^{२२} Read 'बलाच'.

^{२३} Read बभूव.

^{२४} Read देव्योः कौसल्या.

^{२५} Read सिंहा.

^{२६} Read आसे.

Plate II, Side i.

- 32 लब्धनानाविधवहुलमहादानवारिप्रवाहैः । यस्यो-
 33 दंचतुरंगप्रकरखुररजःशुष्यदंभोधिमग्नः आभृत्य-
 34 चक्षिदोत्करकुलिशधरोत्कंठिता कुंठिताभूत् ।[11] 10* ब्रह्मांडं
 35 विश्वचक्रं 'टमुदितमहाभूतकं रत्नचेतुः' सप्तांभो[धौ]शक[ल्प]-
 36 क्षितिरुहलतिके कांचनीं कामधेनुं । स्वर्णज्वायोहिरं-
 37 ण्याश्वरथमपि तुलापूरुषं गोसहस्रं हेमाश्वं हेमगर्भं कन-
 38 ककरिरथं पंचलांगल्यतानीत् ।[1] 17* प्राच्यं प्रशाख निर्विघ्नं रा-
 39 ज्यं द्यामिव शासितुं । तस्मिन्गुणेन विख्याते क्षितेरिन्द्रे दिवं ग-
 40 ते ।[1] 18* ततोप्यवार्यवोर्यश्रीकृष्णरायमहीपतिः । विभर्ति मणिके-
 41 यूरनिर्विशेषं महीं भुजे ।[1] 19* कीर्त्त्या यस्य समंततः प्रसृतया वि-
 42 श्वं रुचैश्च ब्रजेदिव्याशंक्वा पुरा पुरारिरभवतभालेक्षणः¹ प्रा-
 43 यशः । पद्माक्षोपि चतुर्भुजो जनि चतुर्वक्त्रोभवत्यग्रभू काली
 44 खड्गमध्राद्रमा च कमलं वीणां च वाणी करे ।[1] 20* शत्रूणां² वा-
 45 समेते ददत इति कथा किं नु सप्तांबुराशो नानासेनातुरं-
 46 गद्रुटितवसुमतो धूलिकापालिकाभिः । संशोष्य³ स्वैर-
 47 मेतप्रतिनिधिजलधिजलधि⁴ श्रेणिका यो विधत्ते ब्रह्मां-
 48 ङं स्वर्णमेरुप्रमुखनिजमहादानतोयैरमयैः⁵ ।[1] 21* महत्तामर्थिसार्वाः
 49 श्रियमिह सुचिरं भुंजतामित्यवेत्य प्रायः प्रत्यूहहेतोः⁶ स्त
 50 पनरथगतेरालयं देवतानां । तत्तद्भिर्जैवहृत्वापि
 51 च विरुदपदेरंकितांस्तत्र तत्र स्तभां जातप्रतिप्रतिष्ठा-¹⁰
 52 ष्यतनुतनु¹¹ त सुवि यो भूधदभ्रकषाग्रान् ।[1] 22* कांचोद्यो-
 53 शैलशोचल¹² कनकसभावेकटाद्रीद्रमुख्येषावर्त्ताव-
 54 र्त्त्य सर्वेष्वतनुत विधिवत् भूयमे¹³ स्त्रेयशे¹⁴ यः । देवस्थानेषु
 55 तोर्थेष्वपि कनकतुलापूरुषादीनि नानादानान्येवोप-

¹ Read विशोपरकर.² Read नं.³ Read ब्रह्मणा.⁴ Omit one अलधि.⁵ Omit visarga.¹¹ Omit one नुत.¹² Read भूयसे.² Read सप्तमुदित.³ Read शालि.⁴ Omit one अ.⁵ Read मेयैः.¹⁰ Omit one प्रति.¹¹ Read श्रीवाचल.¹² Read सेवसे.

W. GRIGGS & SONS, LTD., PHOTO-LITH.

३२
 ३४
 ३६
 ३८
 ४०
 ४२
 ४४
 ४६
 ४८
 ५०
 ५२
 ५४
 ५६
 ५८
 ६०

W. GRIGGS & SONS, LTD. PHOTO-LITH.

80

92

94

96

98

92

94

96

98

ॐ नमो भगवते वासुदेवाय

[illegible]

1 Read **सुखी** *Read "सुखी" in the new edition.*
 2 Read **सुखी** *Read "सुखी" in the new edition.*
 3 Read **सुखी** *Read "सुखी" in the new edition.*
 4 Read **सुखी** *Read "सुखी" in the new edition.*
 5 Read **सुखी** *Read "सुखी" in the new edition.*
 6 Read **सुखी** *Read "सुखी" in the new edition.*
 7 Read **सुखी** *Read "सुखी" in the new edition.*
 8 Read **सुखी** *Read "सुखी" in the new edition.*
 9 Read **सुखी** *Read "सुखी" in the new edition.*
 10 Omit **सुखी** *Omit "सुखी" in the new edition.*

- 83 तं । कृष्णरायपुरं चेति प्रतिनामसमन्वितं ।[39*] सर्वमान्यं-
 84 चतुशीमासंयुतं¹ च समंततः । निधिनिक्षेपपाषाणाद्यष्टभोग्यैर-
 85 धेतैः ।[40*] विविधेषु फलेयुक्तं सतडाकं समूहं । चाचंद्रतारकं
 86 भोक्तुं दातुं चापि निजच्छेद्या ।[41*] सिध्यप्रशिक्ष्यः स्तच्छिष्यैः² तच्छिष्यैः त-
 87 त उत्तरैः । कृष्णदेवमहारायो माननि³यो मनस्विनां ।[42*] सहिरंश्च-
 88 [प]योधारापूर्वकं दत्तवान्मुदा ॥—॥⁴

Plate III, Side i.

- 89 तदिदमवनोवनिपकविमुतधरापस्य कृष्णरायस्य । शास-
 90 नमुक्कविबैभवनिवहनिदानस्य भूरिदानस्य ।[43*] कृष्णदेवम-
 91 हारायशासनेन सम⁵पतिः । अभाणोत् मदु⁶संदर्भं तदिदं तांम्⁷
 92 शासनं ।[44*] कृष्णदेवमहारायशासनं⁸ मल्लणात्मजः (i) त्वष्टा श्रीवीरणाच-
 93 यो व्यलिखत्तां⁹शासनं ।[45*] दानपालनयोर्मध्ये दानाच्छेयोनुपालनं । दा-
 94 नात्स्वर्गमवाप्नोति पालनादच्युतं पदं ।[46*] स्वदत्ताद्विगुणं¹⁰ पुण्यं परदत्तानुपा-
 95 लनं । परदत्तापहारेण स्वदत्तं निष्फलं भवेत् ।[47*] स्वदत्तां परदत्तां वा
 यो हर-
 96 ति वसुंधरात् । षष्टिर्वर्ष¹¹सहस्राणि विष्टायां जायते क्रिमिः¹² ।[48*] एकैव भगि-
 97 नी लोके सर्वेषामिव भूभुजा । न भोज्या न करग्राह्या विप्रदत्ता वसुंध-
 98 रा ।[49*] सामान्योयं धर्मसेतुः नृपाणां काले काले पालनियो¹³ भवद्भिः (i)
 99 सर्वानेतान् भाविनः पार्थिवेद्रान् भूयो भूयो याचते रामचंद्रः ।[50*]
 श्रीविरुपाक्ष

TRANSLATION.

(ABRIDGED.)

Verses 1-3. The usual benedictory verses in praise of Śambhu, the Varāha incarnation of Hari, and Gaṇeśa.

Verses 4, 5. The descent of the family from the moon.

Verses 6-8. The first historical kings of the dynasty: Timma, Īśvara, and Narasa.

Verse 9. The gifts made by Narasa in Rāṁśvaram and other places.

¹ Read चतुस्त्रोना°.

² Read जी.

³ Read भा.

⁴ शासनेन would be necessary here to suit the meaning, but the metre would be disturbed. शासनेन उभापतिः, which is found in the other grant edited by us, is certainly a better reading.

⁵ Read ताव.

⁶ Read क्रिमिः.

⁷ Read शिष्यप्रशिक्ष्यैः तच्छिष्यैः.

⁸ Shows the verse has only two pādas.

⁹ Read मदु.

¹⁰ Read ताव.

¹¹ Read स्वदत्ताद्वि.

¹² Read पालनयो.

¹³ Read ०११°.

Verses 10, 11. Exploits of Narasa. His capture of Seringapatam, defeat of the Chola, Chēra, Pāṇḍya, and Musalman kings, of the chieftains of Madurā, and the king of Orissa, and his suzerainty over the Dakhan—from Laṅkā to the banks of the Gaṅgā (probably the Pēṅgaṅgā of Central India).

Verses 12, 13. Birth of his sons Vira-nṛsiṃhāndra and Kṛishṇa Rāya.

Verses 14-17. Praises of Vira-nārasimha and his gifts in holy places in South India.

Verse 18. Death of Vira-nārasimha.

Verse 19. Accession of Kṛishṇa Rāya.

Verses 20-22. Praises of Kṛishṇa Rāya.

Verse 23. His gifts.

Verses 24-26. His *birūdas*, such as *Rājādhirāja*, *Vīra-pratāpa*, etc.

Verses 27, 28. His praises.

Verses 29, 30. In the year 1450 of the Śāli-vāhana Śaka era, the year named Virodhin, in the month of Vaiśākha, on the *tīthi* Pūrṇimā, and *nakshatra* Viśākha,

Verse 31. (Is given) on the banks of the Tuṅga-bhadrā, near the temple of Śrī Virūpākha, to the great sage working for salvation, the great saint and anchorite.

Verses 32-33. Whose body is besmeared with holy ashes, who wears a necklace of *radrāksha* beads, who is high-souled and talented, who has practised the eight-fold path of the Yōga who is compassionate to all beings, (but) is (himself) above the pairs of opposites like heat and cold, which only give rise to pain; who is possessed of knowledge and freedom from attachment; who is master of himself.

Verse 34. (To this) Guru, who is Śiva incarnate, Sadā-śiva Sarasvatī, disciple of Chandra-sēkhara Sarasvatī,

Verses 35-43. The village of Udayambākam, otherwise known as Kṛishṇarāya-puram, in Paṇḍa-viṇḍa mahārājya, in Jaya-chōla maṇḍala (Jayam-koṇḍa Chōla maṇḍala), comprising the town of Tirukkaḷu-kunram and the fort of Kalattūr in Veḷimala nāḍu in the *śimā* (district) of Chingleput, on the banks of the Pālār. The boundaries of the village are, Prallayannūr to the west, Maṇappāk to the north, Kalattūr to the east, Puṇya-paṭṭu to the south.

The said village is marked by clearly defined boundaries on its borders.

The grant includes the right of enjoyment of eight kinds of interest in the land, viz. treasures in it, mines, rocks, tanks, gardens, trees, etc.; and the right of possessing it for ever or parting with it at will (by sale to another). The rights over the land are to descend from the donee to his disciples, their disciples, and so on in the apostolic line. The grant was made in a ceremonial way, with water and with gold.

Verses 44, 45. The grant was composed by Sabhāpati and engraved by Virāṇśchārya.

Verses 46-50. The usual admonitory verses.

‘Śrī Virūpākha.’¹

¹ On Virūpākha and the devotion of the Vijayanagar house to Śiva and Nāga worship, see our note in the introduction to the Conjeevaram plates of Kṛishṇa-dēva Rāya (*Ep. Ind.*, Vol. XIII, No. 8).

The meaning of *sādhāra* (ll. 26 and 32) is not clear: it may mean 'with the adjacent grounds' or may be an abbreviation of *sādhārana* (common). *Vaha* (l. 32) is the common highway and *kachchha* (ll. 26 and 28) is a field bordering on a stream.

As regards orthography, it may be noted that *v* is used for *o* throughout and *n* for *a* in some instances: *pungu* (l. 11, twice), *hiranya* (ll. 13 and 24), *saranya* (l. 17) and *grihasti* (l. 30). Dental *s* is used for the palatal in *śādhārana* (l. 12), and *sadrisham* (l. 18) is an example of the converse. Consonants are mostly doubled after *r*, but the necessary doubling is not shown in *prōtārīta* (l. 15), *patatrīnah* (l. 16) and *āchchheta* (l. 35). The doubling of *t* before *r* is seen in *putrū* (ll. 6 and 8), *putrō* (l. 11) and *hitattir* (l. 13), but not everywhere (e.g., *putra* in ll. 5, 6, 7). *n* at the end of a word is not joined generally to the next word (ll. 20, 21, 22, 29). The *ananta* is used for the appropriate nasal in *kāhlikyan*, *gūnagāyān* (l. 11), *lingita* (l. 16), *damgajō* (l. 17), *ghōmto* (l. 23), *likhyantē* (l. 28), *kshātrāntarītan* (l. 29), *bhavanūtu* (l. 1), *chintā* (l. 18), *tamitra* (l. 20); it is wrongly replaced by *m* in *param-bhu* (l. 17) and is redundant in *mānānveaya* (l. 15) and *chintya* (l. 23). Of the class-nasals, *v* is frequently used (ll. 15, 22, etc.), once wrongly for *ā* (*pancha*, l. 26); *ā* occurs in ll. 15 and 19 and once wrongly in *chintā* (l. 18), and *u* in l. 18. Omissions of *visarga* (ll. 4, 5, etc.), its redundant use (ll. 20, 21, 30), and instances of letters (ll. 10, 27, 30, 31) and particles (ll. 23, 18) left out are specified in the footnotes. There are no symbols for *avagraha*, *jihvāmālīya* or *upadhānīya*. The necessary punctuation marks are omitted in some places (ll. 2, 3, etc.), and there are redundant lices (ll. 1, 3, etc.) in others. Other mistakes are pointed out at the proper places.

All the grants recorded in the inscription are in favour of shrines attached to the monastery of Hari-Kishisvara, who originally belonged to Daśapura (l. 12). Under its management were the shrines of Vata-yakshini Dēvi (ll. 12, 33), Indrāditya-dēva or Indrājāḍitya-dēva (ll. 23, 28) and Trailokya-mohana-dēva (l. 33), which were situated at the village of Ghōṭa-varshika, where there was also a temple dedicated to Nityapramudita-dēva (l. 23). Chief among the deities was Indrāditya-dēva, who is spoken of as "the deity" of Ghōṭa-varshika (l. 28), while Trailokya-mohana-dēva is spoken of as "enshrined" within the grounds of Indrāditya-dēva (l. 31). This pre-eminence is borne out by the verses (ll. 1-2) in praise of the sun-gods (Indrāditya-dēva), which precede those (ll. 3-4) extolling Durgā (Vata-yakshini Dēvi), who is the donee proper of the first grant.

The occasion of the grant of a village to Vata-yakshini Dēvi by the king of Mahodaya in Samvat 1003 was used by the authorities of the monastery for the purpose of consolidating on one stone all the grants in favour of one or other of the temples attached to it. Such consolidation of grants belonging to one institution, but issued at different periods, is not rare in Rājputānā. We have an instance of it in the Vāsishtha temple inscriptions at Mount Abu.

The inscription is naturally divided into four parts:—

I. A grant of a village in favour of Vata-yakshini Dēvi, issued by Mahārāja Mahēndra-pāla Dēva II. of Mahodaya (Kannu), dated Samvat 1003, or A.D. 946 (ll. 1-14).

II. A grant of a village, etc., in favour of Indrāditya-dēva by Mādhaḥva, the provincial governor of Ujjain (under the same king), at the request of Chāhamāna Indra-rāja, a feudatory chief, without date (ll. 14-27).

III. A grant of a field in favour of Indrājāḍitya-dēva by Bhartṛ-patta, son of Khōmmāna, dated Samvat 999, or A.D. 942 (ll. 27-31).

IV. Minor grants to different deities by different persons, undated (ll. 31-35).

PART I.

The first grant recorded in the inscription—though it is not the first from a chronological point of view—begins with two benedictory verses invoking the sun-god, followed by two similar verses in praise of the goddess Durgā (ll. 1-4). It is issued from the capital at Mahōdaya and gives the genealogy of the donor as follows:—


1. Mahārāja Dēva-śakti-Dēva, a devotee of Viṣṇu;
2. His son, born of [queen] Bhūyikā-Dēvi, Mahārāja Vatsa-rāja-Dēva, a devotee of Mahēśvata (Śiva);
3. His son, born of [queen] Sundari-Dēvi, Mahārāja Naga-bhaṭa-Dēva, a devotee of Bhagavati (Durgā);
4. His son, born of [queen] Īsaṭa-Dēvi, Mahārāja Rāma-bhadra-Dēva, a devotee of the sun-god;
5. His son, born of [queen] Appā-Dēvi, Mahārāja Bhōja-Dēva, a devotee of Bhagavati;
6. His son, born of [queen] Chandra-bhaṭṭārikā-Dēvi, Mahārāja Mahēndra-pāla (I.), a devotee of Bhagavati;
7. His son, born of [queen] Mahādēvi-Dēvi, Mahārāja Vināyaka-pāla-Dēva, a devotee of the sun-god; and
8. His son, born of [queen] Prasādhana-Dēvi of the Devathāddhi (?) family, Mahārāja Mahēndra-pāla-Dēva (II.), a devotee of Mahēśvara (ll. 5-9).

The last-named king enjoins all and sundry residing in the village of Kharpara-padraka, —in the holding of Tala-varṅika Harishadā, and situated in the vicinity of Ghōṭṭā-varshikā, in the western Pathaka (district) of Daśa-pura,—and the residents of the neighbourhood, that the said village Kharpara-padraka, with all rights belonging thereto, has been bestowed by him, for all time to come, at the request of Dhana-sūra, upon the goddess Vaṭa-yakṣiṇī Dēvi, (whose shrine is) connected with the Maṭha (monastery) of Hari Rishisvara, versed in all the four Vēdas, resident of Daśa-pura, on an auspicious day, after bathing in the Kāhinkī Gaṅgā, for increase of religious merit to the donor's parents (ll. 9-12). The grant is written by Purōhita Trivikrama-nātha, under orders from Jajja-nāga, is dated the fifth day of the dark half of Mārgga (Mārga-śrisha), in the Samvat year 1003 (A.D. 946), and is signed by Śrī Vidagdha, "his own hand" (l. 13).

The name of Mahēndra-pāla (II.), son of Vināyaka-pāla, comes to our knowledge for the first time from this inscription. There seems to be a *double entente* in the word *prasādhana*, in which the writer pays a compliment to the queen-mother, by name Prasādhana-Dēvi, by calling her the 'ornament of the family of her birth' (l. 9). The name of this family Devathāddhi (?) is not quite clear for purposes of identification. Of the names and places mentioned Mahōdaya (Kanaūj) and Daśa-pura (Mandasor), and the names of the kings and queens call for no remark. Kharpara-padraka is the modern village of Kharōṭ, 7 miles south-east of Partābgarh. Ghōṭṭā-varshikā¹ can be identified with Ghōṭārai, 7 miles east of Partābgarh and about 8 miles north-east of Kharōṭ. The Kāhinkī Gaṅgā (the river Kāhinkī) cannot be identified. Jajja-nāga was probably the Dātaka of the grant. Vidagdha appears to be the Governor of the province who issued this grant under his own signature.

¹ The name of this village is spelt as Ghōṭṭā-varshikā (l. 10), Ghōṭṭā-varshika (l. 23) and Ghōṭṭā-varshi (l. 34).

The genealogy of the Pratihāra kings of Mahodaya (Kanauj), in the light of the information available up to the present, would stand thus:—



¹ This date is from a photograph in my possession of an unpublished copper-plate grant from Hānsūt, in the district of Broach (Bombay presidency), issued by the Chāhamāna prince Bhartṛi-vaḍḍha (Bhartṛi-varḍha) II, a feudatory of king Nāgāvalōka.

² From the Jaina *Hari-samāsa Purāṇa* (Bom. Gazetteer, Vol. I, part II, p. 197).

³ The *Prasādhaka-charita* speaks of the death of king Nāgāvalōka of Kānya-kubja, grand-father of Bhōja, as taking place in Vikrama year 890 (A.D. 833-34) (Nirṇayasaṅgṛaha Press ed., p. 177, verses 720-725). The Nāgāvalōka of the *Prasādhaka-charita* can be identified with no other than Nāga-bhāṭa II. of Kanauj, and the date seems to be accurate, as the first known date of Bhōja I. is A.D. 843.


⁴ This date of Rājya-pāla is given by Al-Uthī in his *Tārīkh-i-Yamīn* (Elliot's Hist., Vol. II, p. 45), where he speaks of Bai Jaipāl as the ruler of Kanauj when Sultan Mahmūd of Ghazni invaded it. He was killed the next year (A.D. 1019) by the Chandēla prince Vidyā-dhara, son of Gaṇḍa, and Trilochana-pāla succeeded him.

⁵ The dotted line in the table indicates a successor, not necessarily a son.

Dēva-pāla of Mahōdaya is mentioned in the Stradon inscription (*Ep. Ind. Vol. I. p. 177*) as the son of Kshiti-pāla, which is evidently a synonym of Mahi-pāla; but the same Dēva-pāla is identified by the editor of that inscription with *Haya-pati* Dēva-pāla, son of Hēramba-pāla, from whom Yaśo-varman obtained the celebrated image of Vaiṣṇuṭha, mentioned in that king's Khajurāho inscription. This has led to the identification of Hēramba-pāla, the father of this Dēva-pāla, with Mahi-pāla or Kshiti-pāla, the father of Dēva-pāla of Mahōdaya. The fact that Hēramba and Vināyaka are synonyma lends colour to this view, the result of which is the identification of two kings with two sets of names—

- (1) Mahi-pāla and Kshiti-pāla; and
- (2) Vināyaka-pāla and Hēramba-pāla,

which is accepted by scholars up to the present and is given in the genealogical tree above; but this identification is based on very slender evidence. That Dēva-pāla, son of Hēramba-pāla, who is introduced by the minor title of *Haya-pati* (lord of horses) is the same as Dēva-pāla of Mahōdaya cannot be established on the casual mention of the former in an inscription of a king of a dynasty other than his own. *Haya-pati* was never the accepted title of the Pratihāra kings of Mahōdaya and is not met with in their inscriptions; and there is no ground for assuming that a scion of the paramount dynasty of the Pratihāras was ever known by that appellation. Besides Mahi-pāla and Vināyaka-pāla are known to be two different kings of Mahōdaya with different dates which do not overlap; and there is no reason to justify their identification. If this view is accepted and the identification of Hēramba-pāla with Mahi-pāla set aside, this part of the genealogy would stand thus:



The second grant begins with a panegyric in praise of the Chahamanya family of kings, which is spoken of as having been the source of great pleasure to King Bhoja-Dēva. Then mention is made of Gōvinda-rāja of this dynasty, who fought against many foes; his son Durisabha-rāja and his son Indra-rāja, who built the great temple dedicated to the sun-god (II. 14-19). We learn further that Mādhava was the great feudatory lord, and governor at Ujjayini and Śrīśaṣṭana appointed by Kōkkaṭa, who was the commander-in-chief serving at the feet of Paramōśvara (i.e. Mahendra-pāla II.) was carrying on the affairs of state at Mandapika (II. 19-20).

The aforesaid Mādhava, son of Dāmodara, being great feudatory, great governor and *Chargé d'Affaires*, and having come to Ujjayini on business, bathed at the temple of Maṇa-kāla,

worshipped the god Śiva and meditated on the unreality of life and wealth, bestowed, on the *Mina-samkrānti* day, the village of *Dhārā-padraka*, with all its appurtenances, for repairs to, and maintenance of daily services at, the temple of *Indrāditya-dēva* at *Ghōṇṭā-varshikā*, a place associated with *Nityapramudita-dēva*, at the request of the great feudatory *Indra-rāja*, son of *Durlabha-rāja* of the *Chāhamāna* race. He therefore enjoins all residents of the village and the neighbourhood to observe this order (ll. 20-26). A further endowment of a field by the river-side to the north of the village, irrigated by a Persian wheel, and of five matting screens for the erection of a flower porch is recorded (l. 26). The grant is signed by *Mādhava* and countersigned by the *Vidagdha* (l. 27) of the first grant.

The names of the warlike *Chāhamānas* eulogized in this grant are not known from any other record. It was probably a local dynasty of the *Chāhamānas* which had entered into a subordinate alliance with king *Bhoja-Dēva* I. and helped him in his wars, thus giving the overlord 'great pleasure.' *Indra-rāja* built a temple to the sun-god (*Indrāditya-dēva*) and applied to the governor of *Ujjain*, appointed by his overlord, the king of *Kanauj*, evidently *Mahendra-pāla* II. of the first grant, for an endowment for its upkeep. The grant is not dated; but we find from the third grant that the temple of *Indrāditya-dēva* was existing and was well-known after the name of the builder (l. 28) four years before the date of the first grant. We thus have reason to suppose that the request of the builder to the provincial representative of his overlord to secure a permanent endowment for it must have immediately followed its erection and preceded the gift of *Bhartṛi-paṭṭa* recorded in the grant following. Thus this grant is evidently prior to the third, and is consequently the first, though not by many years, as is evident from the signature of the same governor, *Vidagdha*, affixed to both the grants. The custom of provincial governors countersigning grants issued by subordinate chiefs relating to lands in their (the governors') jurisdiction is borne out by the evidence of the *Unā* plate of the time of *Mahendra-pāla* I. of *Kanauj*, where *Dhūika* countersigned a grant of *Bala-varman*, a feudatory of the king (*Ep. Ind.*, Vol. IX, p. 6).

Maṇḍapikā is *Māṇḍū*, where another officer *Śrī-sarman*, appointed by the king's commander-in-chief, resided. *Dhārā-padraka* is probably *Dharyāvad* (in *Mēwār*), situated near the boundary of the *Partābgarh* State. The matting screens referred to were to be used, evidently, in the periodical festivals in which the throne of the deity is placed in a porch of flowers and leaves temporarily erected over it.

PART III.

This grant records that *Mahārājādhirāja Bhartṛi-paṭṭa*, son of *Khōmmāna*, enjoins his descendants to maintain in perpetuity, and not to interfere with, the enjoyment of the bestowal of a field named *Vavvūlika* (*Babbulika*) by the side of the river *Nandya* in the village of *Palāsa-kūpikā*, made by him upon *Indrarājāditya-dēva* of *Ghōṇṭā-varshi* for increase of merit to himself and his parents (ll. 27-30). The boundaries of the field are defined (ll. 28-29), and a customary verse extolling the donor and the donee follows (ll. 31-32). The date is given as the first day of the bright half of the month of *Śrāvaṇa* in the *Saṃvat* year 999 (A.D. 942).

Bhartṛi-paṭṭa of this inscription is *Bhartṛi-paṭṭa* II., son of *Khōmmāna* III. of *Mēwār*, belonging to the *Guhila* family. Another inscription of his reign is dated *Saṃvat* 1000 (A.D. 943).¹ *Palāsa-kūpikā* is probably the present *Parāsiā*, about 15 miles south of *Mandasor*. The river *Nandya* and the village of *Varāha-palli*, mentioned in the boundaries, cannot be identified at present.

¹ *Ind. Ant.*, Vol. XXXIX, p. 191.

² *Annual Report on the working of the Rajputana Museum, Ajmer, 1914, p. 2.*

PART IV.

This part records minor grants:—

I. The gift of a field named Chhittullaka, in which 10 *Māṣa* of seed could be sown, and which was irrigated by one leather bucket, in favour of Indrāditya-dēva, by Dēva-rāja, son of Chāmunda-rāja (l. 31).

II. The gift of a field, called Umdiyāka, with boundaries defined, in favour of Trailōkya-mōhana-dēva in the grounds of Indrāditya-dēva, by Indra-rāja (ll. 32-33).

III. The [permanent] endowment of one *Palika* [of oil] per oil-mill, five bundles of foliage, 100 garlands of four strings, on the ninth day of the bright half of the month of Chaitra, together with two *palas* of saffron and one [*palā*] of betel-nuts from the trading community in the month of Chaitra, in favour of the Vāṣa-yakshini Dēvi (ll. 33-34).

IV. The gift of Dhaḍivāṣa field, in which 10 *Māṣa* of seed could be sown, and of Mōchoba field, to the north-east of Ghōṣṭa-varshi, requiring 10 *Māṣa* of seed, from persons not mentioned and in favour of deities not specified (l. 34).

Then follows the usual verse extolling the giver of land and condemning the usurper (l. 35), after which the name of the engraver of the inscription is given as Siddhapa, son of [Sa]tya and the date as Samvat 1003 (A.D. 948).

Dēva-rāja, son of Chāmunda-rāja (l. 31), appears to be a scion of the Chāhamāna family mentioned in the second grant, and Indra-rāja (l. 32) is the builder of the temple of the sun (ll. 18-19) himself.

TEXT.

[Metres: v. 1, *Anuṣṭubh* (Śloka); v. 2, *Māṇḍūkāntā*; v. 3, *Sārdalavikrīḍita*; v. 4, *Vasantatilakā*; v. 5, *Sārdalavikrīḍita*; v. 6, *Vasantatilakā*; v. 7, *Anuṣṭubh* (Śloka); v. 8, *Sārdalavikrīḍita*; v. 9, *Vasantatilakā*; v. 10, *Sārdalavikrīḍita* (half); vv. 11 and 12, *Anuṣṭubh* (Śloka).]

L. 1 — — — [m]:

भवतु भवतां भानो भूतये भानवः सदा ॥
प्रातर्बभस्तु रोस्तामाः पवित्राः पञ्चवा इव ॥ [१०]

ब्रह्मादीनां नियमितव्यां [स्तोत्र]पात्रं यदेकं ।

यस्मिन्नेताः पुनरपि दिशो ।

२ — — — [११]

[सूर्याद्या]भ्यं प्रतिदिनमहो ध्यायते यन्मनीन्देः

तेजस्तदो हरतु दुरितं पावनं समसमेः ॥ [१२]

[रुद्रे] विद्वति द्रुतं सुरपते पश्य प्रति प्रसिद्धे ।

विज्ञेये प्रतिपन्नरायि [तः]

From impressions prepared by the writer and from the stone itself.

Read भवतु. One stroke is redundant.
Read ब्रह्मा. This stroke is redundant.

This stroke is redundant.
Read "नीन्दे". This stroke is redundant.

3

[REVERSED]

— — — [शाहे] सति [११]

- १३३ वैकुण्ठे मतिकुण्डतामुपगते [१३] विष्णुपते ०१

- १३४ मायायज्ञो महिषासुरं सुररिपुं देवी दृशा निवृत्तो ॥ १३ ॥

वर्षदयाभ्यसनम्ब^१ तवेदमेव^२ - तीरपुत्रात्- १३५ दुर्धिति नाकगमनाय^३ तममहाशक्ति^४ त्रिपुण्ड्रक ॥

- १३६ [१३] [१३] [१३] [१३] [१३] [१३]

कात्यायिनीति वरदेति च सन्ति कस्याः

- १३७ नामाचराणि परमाणि यथा भवन्तां ॥ १४ ॥

- १३८ श्रीमहोदयसमावासितानिकनौहस्थथरयपत्तिसम्पद-

स्कन्धवारात्-

- १३९ [१४] श्रीमहोदयसमावासितानिकनौहस्थथरयपत्तिसम्पद-

- १४० त्यादातुध्यात श्रीभूयिकादेव्यामुत्पन्न^५ परममहिषरो महाराजश्रीवत्सराज-

देवस्तस्य पुत्रस्तत्पादानुध्यात श्री-

6 [

- १४१ श्रीमहोदयसमावासितानिकनौहस्थथरयपत्तिसम्पद-

भगवतीभक्तो महाराजश्रीनागभटदेवस्तस्य पुत्रस्तत्पादानुध्यातः श्रीमदी-

सटादेव्यामुत्पन्नः परमादित्यभक्तो महाराजश्रीरामभट-

- १४२ [१५] [१५] [१५] [१५] [१५] [१५]

महाराजश्रीभोजदेवस्तस्य पुत्रस्तत्पादानुध्यातः श्रीचन्द्रभट्टारिकादेव्या-

मुत्पन्नः परं

- १४३ ८ भगवतीभक्तो महाराजश्रीमहेन्द्रपालदेवस्तस्य पुत्रस्तत्पादानुध्यातः श्रीमहा-

देवीदेव्यामुत्पन्नः परमादित्यभक्तो महाराजश्रीविनायकपालदेवस्तस्य

पुत्रस्तत्पा-

- १४४ ९ दत्तुध्यातः श्रीदेव[या]^६ [१५] [१५] [१५] [१५] [१५] [१५]

महिषरो महाराजश्रीमहेन्द्रपालदेवः श्रीदशपुरपश्चिमपथके तलवर्गिकहरि-

पडभुज्य-

1. Read शा. (OGI =) ...
 2. Read ...
 3. Read ...
 4. Read ...
 5. Read ...
 6. Read ...
 7. Read ...
 8. Read ...
 9. Read ...
 10. Read ...
 11. Read ...
 12. In most of the grants and seals of the Pratiharas kings of Mahodaya the adverb parama- (or parama-) is persistently used before Bhagavati-Bhaktas in place of the adjective parama—which is used before the names of other deities, and there appears to be no need of correcting it to parama-.
 13. The word is indistinct; it may also be read as देव्याहि, देव्याहि, देव्याहि or देव्याहि.

- 10 मानखर्परपद्रकग्रामे घोषटावर्षिकाप्रत्यासन्ने समुपगतान् सर्वावे¹ यथा-
स्थाननियुक्तान्प्रतिवासिनश्च समाप्तापयत्वस्तु वः² उपरिलिखितग्रामः स्वसी-
मातुषप्रति³
- 11 गोचरपर्यन्तो⁴ सर्वादायसमेत आचन्द्रार्कक्षितिकालं पूर्वदत्तदेवव्र⁵द्वादेय-
वर्जितो मया पित्रोः पुन्या⁶भित्तद्वये का[हि]क्षां गंगायां स्नात्वा
पुन्ये⁷हनि [ध]नशूरप्रार्थनया श्री-
- 12 दशपुरचातुर्वर्ष्यद्वयहरिषे⁸श्वर⁹मठसंव¹⁰ध्यमानश्रीवटयक्षिणोदेव्यै शासनत्वेन प्रति-
पादितः¹⁰ मत्वा भवद्भिः सा¹¹मुनुमन्तव्यो¹² प्रतिवासिजनपदैरप्याज्ञास-¹³
वणविधेयैर्भूत्वा यथा-
- 13 दीयमानभागभोगकरहिरन्या¹⁴दिकभस्योपनेतव्यमिति [१*] श्रीजज्जनागप्रद-
त्तादेशात् । संवत्स¹⁵ १०००¹⁶ १००३ माग्नं यदि ५ [१*] पुरोहित-
चिविक्रमताच्च¹⁷लिखितमिदम् । स्व-
- 14 हस्तोयं श्रीविदग्धस्य ।०।
यो राज्ञामुपरि स्थितः¹⁸ वसुमतीर[चा]यमुत्पादितः¹⁹
येनोच्चैः सुखमासितं क्षितिस्रता श्रीभोजदेवेन च [१*]
यस्माद्दि²⁰भ्यति विद्विषः किमपरं यस्माच्च
- 15 लक्ष्मीवृक्षां²¹
सोयं राजति राजचक्रनिलयः[.] श्रीचाहमानान्वयः²² [॥५*]
गोविन्दराज इति तच्च²³वभूव भूपो ।²⁴
राकाशशाङ्ककिरणोत्करयभकीर्तिः [१*]

¹ Read सर्वनिव.² Read °पुति°.³ Read न.⁴ Read षे.⁵ Read व.⁶ Read च.⁷ Read य.⁸ Read संवत्सरे.⁹ Here *samvatsarō* stands for *samvatsarī* and is followed by *sam* (= 100); but in the copper-plates of other kings of Mahōdaya (*Ind. Ant.*, Vol. XV, pp. 112 and 140; and *Ep. Ind.*, Vol. V, p. 209) *arō* itself represents 100, as it is not followed by the symbol for 100.¹⁰ The symbol *sam* is used to represent 100 and *lri* to denote 10. Thus *sam lri* means 100 × 10 = 1000. In the inscriptions of the 9th and 10th centuries, the symbol for 3 being the same as the numerical figure, it has been purposely omitted with the symbols to avoid the ambiguity of the date in figures being read as 31003. Hence the figure for 3 has been inscribed only at the end.¹¹ Read °पविक्कनमाय°.¹² Read ली.¹³ This stroke is redundant.¹⁴ Read य.¹⁵ Supply संविदितम् or सुविदितम्.¹⁶ Read °पर्वत्तः.¹⁷ Read षा.¹⁸ Read °चयंपीथर° (हरि + चपी°).¹⁹ Read °त इति म°.²⁰ Read ष्यः.²¹ Read षा.²² Read ली.²³ Read षि°.²⁴ Read °नाश्वनः.²⁵ This stroke is redundant.

2
4
6
8
10
12
14
16
18
20
22
24
26
28
30
32
34

येन प्र[च]ण्डभुजदण्डतरण्डकेन ।¹

प्रोता-²

16

रिता समरसागरतो जयत्रीः ॥६*॥

यस्य पोतवृ³हद्भीमभुजपञ्चरमध्वगाः ॥१*॥

विपक्षाः संकुचत्पक्षाः पतविष इवाभवन् ॥७*॥

लि⁴च्यालिङ्गितविषहो हरिरिव क्रोधाग्निदग्धाहितः

17

सर्वे[षां] च शरन्व⁵तामुपगतो भास्त्रजतापोदयः ॥१*॥

श्रीमदुल्लभरा[ज]नामसृपति ।⁶ तस्मादभूदंगजो

वक्रं येन कृतं नचार्थिनि जने वक्रं द्विषीवा[य]ति ॥ ८*॥

तस्मादनेकसमरार्जि-

18

तकीर्त्तिकीशः

चिंतामणिः प्रणयिनां प्रणतो द्विज⁷तेः ॥१*॥

यो योषितां तनुधरोभिनवो मनोभूः

भू⁸षा भुवः समभव[त्सु]त इन्द्र⁹राजः ॥ ९*॥

तेनाकारि हिमाचलेन्द्रशट्य¹⁰ भासां

19

प्रभोर्भासरं

धामेदं ध्वजकिङ्किणीकलमिलत्कोलाहल¹¹लङ्कतं ॥ १०*॥

स्वस्ति श्रीमदुज्जयन्या¹² महासामन्तदण्डनायकश्रीमाधवः ॥ तथा

मण्डपिकायां परमेश्वरपादोपजीविव¹³लाघी¹⁴क-

20

तवीकोकटनियुक्तश्रीशम्भो¹⁵ च व्यापारं कुर्वते¹⁶ इत्यस्मिन् काले वर्त्तमाने

इहैव श्रीमदुज्जयन्यायां¹⁷ कार्याभ्यागततं¹⁸पालमहासामन्तमहादण्डनाय-

कश्रीमाधवेन¹⁹ श्री-

¹ This stroke is redundant.

² Read वृ.

³ Read ष.

⁴ Read कीशधि.

⁵ Read मनोभू.

⁶ Read सद्रं.

⁷ Read विन्वा.

⁸ Read धि.

⁹ Read कुर्वति (or कुर्वते).

¹⁰ Read तव.

² Read वा.

³ Read ल.

⁴ Read लपतिसन्ना. The stroke is redundant.

⁵ Read जा.

⁶ Read न्द्र.

⁷ Read लालं.

⁸ Read व.

⁹ Read शर्कधि च (or शण्यां च).

¹⁰ Read विन्वा.

¹¹ Read न. Correct to माधवः.

- 21 दामोदरसुतेन¹ ।² चाहमानान्वयमहासामन्तश्रीइन्द्रराज³ ।⁴ श्रीदुर्लभराज-
[सुतस्य प्रार्थनयाः⁵ । श्रीविदम्भोगावाप्तये धारापद्रकग्रामे समुपगतान्
सर्वराजपुरुषान् ।⁶ ब्राह्म-⁷
- 22 शोत्तरीयान्⁸ प्रतिनिवासीजनपदीय⁹ वो¹⁰ धयत्यस्तु वस्त्रं विदितं श्रीमहा-
कालदेवाय तने¹¹ सुखात्वा महादेवमभ्यर्च्य¹² श्रीमतीपिचोरामेन च सुपुत्र-
कर्मयशोभिषुवे¹³ ।¹⁴ परलोकादि-¹⁵
- 23 ताय जलचन्द्रचपलजीवितं¹⁶ त¹⁷ ।¹⁸ जलदृष्टनेष्टसंपद¹⁹ समन²⁰ चिन्त्य²¹ ।
[²²] श्रीनित्यप्रसुदितदेवप्रति²³ ।²⁴ धौटावधिकस्थाने श्रीमदिन्द्रा-
दित्यदेवस्य खण्डस्फुटितसमार-²⁵
- 24 चनाय²⁶ वलिचक्रशत्रु²⁷ प्रवर्त्तनाय ।²⁸ ग्रामोयं स्वमीमापयन्तु²⁹ सवचमाला-
[कु]ल³⁰ सकाष्ट³¹ लणगोपचार³² सजलस्थलसमेत³³ ।³⁴ चतुष्कंकट³⁵ विशुद्ध³⁶
भागभोगकरहिरन्या³⁷ दिस्कध-³⁸
- 25 कमा³⁹ णकादिराजभावेस्मृष्टित⁴⁰ उदकपूर्वकेन शासनेन प्रदत्त⁴¹ । मत्वे-
तदम्भइङ्कु⁴² जैरन्यैश्च धर्ममिदमनुपालनीय⁴³ । प्रतिनिवासी⁴⁴ जनपदैश्चात्थ-
वणविधेयमत्वा⁴⁵
- 26 यथा दायमानं च दातव्यं ॥ आगरं⁴⁶ चैतस्मिन्नेव ग्रामे उत्तरतो
[दिग्भा]गे साधारं कच्छ[क]वाम परहटन तु संयुत दत्तं । पुनः
पञ्चमण्डपकिटिकाः पञ्च⁴⁷ शासनेन प्रदत्ताः ॥ सह-

- 1 Correct to सुतः.
2 Read राजस्य.
3 Read वा. The stroke is redundant.
4 Read सि.
5 This stroke is redundant.
6 This stroke is redundant.
7 Read न.
8 Read न. The stroke is redundant.
9 Read व.
10 This stroke is redundant.
11 Read न.
12 Read न.
13 Read न.
14 Read न.
15 Read न.
16 Read न.
17 Read न.
18 Read न.
19 Read न.
20 Read न.
21 Read न.
22 Read न.
23 Read न.
24 Read न.
25 Read न.
26 Read न.
27 Read न.
28 Read न.
29 Read न.
30 Read न.
31 Read न.
32 Read न.
33 Read न.
34 Read न.
35 Read न.
36 Read न.
37 Read न.
38 Read न.
39 Read न.
40 Read न.
41 Read न.
42 Read न.
43 Read न.
44 Read न.
45 Read न.
46 Read न.
47 Read न.

27 स्तोयं श्रीमाधवस्य । स्वहस्तोयं श्रीविदग्धस्य ॥

संवत् ८८८ आवण सुदि-११ श्रीसुसाराजवलिपूर्वमेष्टे महाराजा-
धिराजश्रीमहर्षिपट्टे श्रीश्रीमानसुतः श्रीसुमातपिबोरात्मनव ध-
[१११] ॥

28 श्रीभित्तव्ये घोषावर्षीयेन्द्राजदित्यदेवाय । पलासकूपिकासमे दंजू-
लिको नाम कच्छे । अस्य चाघाटानि लिख्यंते पूर्वस्यां दिशि
स्वर्मापालो दक्षिणस्यां दिशि च पलासकूपिका-

29 चैत्रांतरित वराहपक्षप्रथमवले । पश्चिमस्यां दिशि सोमायां चैत्राणि ।
उत्तरस्यां दिशि नन्दानदीसमीपवर्त्तिनी-घ(?)मेत्ताघाटाने सहायं

वञ्जूलिकी नाम कच्छी अक्षामिः प्रदत्तो मत्वा ॥

30 तुचपौचादिकैरयं च मात्तन्द्राक्षित्युदधिसमकालं पालनी एतदीयरति-

परिपंथना न केनापि कर्त्तव्याः ॥ भूमिः यः प्रतिपद्यति यच्च भूमिः प्रयच्छति ॥

हावेतो पुण्ड्रकभानी नियतो स्वर्गीनां ॥ १११ ॥

31 श्रीदेवराजिन श्रीचामुण्डराजसुतः श्रीमदिन्द्रादित्यदेवस्य कोसवाडे
क्षित्माकचेवं माणिवाप १० शासनन प्रदत्त ॥ श्रीमदिन्द्रा-

दित्यदेवकगत्यां । चै-
32 लोकासीहर्नदेवस्य श्रीमदिन्द्राजिन उडिआकचेवं भाघाटा लिख्यंते
दक्षिणतः साधारवहं पश्चिमतः राजवल्मी उत्तरपुर्वतः वा दक्षिणतः

दित्यस्य चैवं । एवं चतुराघा-

Read (if not मय ११). This syllable is written below the line.

- * मय ११ is also found in some Mewar inscriptions.
- * Supply a verb, e.g. समाश्रयति.
- * This stroke is redundant.
- * Read नाम.
- * Read लिख्यंते (also in line 32).
- * Read चै. The next stroke is redundant.
- * Read घाटे. कः.
- * Read दक्षिणतः.
- * Read दक्षिणतः.
- * Read इतिमावा.
- * Read कच्छीअक्षामिः.
- * Read रयमा.
- * Read कवत्या.
- * Read मि.
- * Read सुतेन.
- * Read वी.
- * Read प्रदत्त इति मय.
- * Read पालनीय ए.
- * Read मय.
- * Read मय.
- * Read मय.
- * Add मय.
- * Read मय.

- 33 टोपलचितं¹ शासनेन प्रदत्तं ॥ श्रीवटयक्षिणी² घाणापलिका १ पञ्च-
मण्डप[पालिका]—५ महानवम्यां चैवे पुष्पचौसरा शत³ १०० वणिवर्मन⁴
कुंकुमपल २ पुग १ चैवे निवे-
- 34 दनीया⁵ ॥ • ॥ धाडिवाहाचेचं माणवाप ६ लौडाभिचय[भोज्ये?]
दातव्य⁶ मास वि ५ घोष्टावर्षिपूर्वोत्तरतः मोचचेचं माणवाप १०
पष्टो⁷वरिष⁸सहस्राणि स्वर्गे ति[ष्ठ]ति
- 35 भूमिदः [१*]
आच्छेता¹¹ चानुमन्ता च¹² तान्येव नरकं [वसेत्] [॥१२*]
[स]त्त्वसुत सिद्धयेन इयं प्रशस्ती उ¹³त्कीर्णमिति¹⁴ ॥ संवत् १००३ [॥*]

No. 14.—LAKSHMESHWAR PILLAR INSCRIPTION OF THE YUVARAJA
VIKRAMADITYA.

By LIONEL D. BARNETT.

The town of Lakshmēshwar is the head-quarters of the Lakshmēshwar *tāluka*, which is an outlying part of the Miraj State within the limits of the Dhārwar District, Bombay. It is situated about thirty-six miles south-east of Dhārwar, and is shown in the Indian Atlas quarter-sheet 41, S. E. (1904), in lat. 15° 8', long. 75° 31'. Its ancient name is found as *Porigere* in the record now published, and elsewhere as *Purigere* and *Puligere*, which forms were Sanskritized as *Purikara* and *Pulikara*: it is still preserved in the name *Huligere-bapa* of a part of the lands of the town (see Vol. XIII above, p. 179). For some facts of the early history of the place the reader may be referred to Vol. XIII above, p. 178. From this town comes the present inscription, which I edit from two ink-impressions and a plain squeeze placed at my disposal by the late Dr. Fleet,¹⁵ which are now in the British Museum.

The inscription is on two faces of a stone pillar which in 1892 was standing at the local *Kachēri*, along with a large number of other inscriptions which had been collected there for safe preservation. The first face, bearing ll. 1-40, has an inscribed area of about 7 ft. 1 in. in height and 1 ft. 2½ in. in width; on the second face, comprising ll. 41-55, the inscribed area is about 3 ft. 6½ in. in height and 1 ft. 2 in. in width. The state of the stone is very bad: ll. 39-48 are wholly illegible, and there are many gaps and doubtful readings elsewhere.

The character is Kanarese, of a type characteristic of the early eighth century. The letters on the first face, which, though somewhat sprawling and irregular, are on the whole graceful and clean-cut, average between ½ in. and 1 in. in height; but on the second face a difference of type is noticeable, which possibly began from l. 41, and is very obvious from l. 46 onwards,

¹ This stroke is redundant.

² Read सं.

³ Read कुकुम°.

⁴ Read निवेदनीयानि.

⁵ Read टि.

⁶ Read वा.

⁷ Read प्रशस्ति°.

¹⁵ The record has been mentioned by Dr. Fleet in his *Dyn. Kan. Distr.* p. 374, No. 10.

⁸ Read श्री.

⁹ Read दधिचर्षेय.

¹⁰ Read पुन.

¹¹ Read च.

¹² Read चर्ष°.

¹³ Read च.

¹⁴ Read °वति.

the letters becoming rader and clumsier, with a height varying from $\frac{3}{4}$ in. to $1\frac{1}{4}$ in. As will be seen below, a new section begins on or about l. 46, and probably it was inscribed by a different hand. The record contains all the test-letters kh, ñ, j, b, and l, and all of them, with the exception of l, are of archaic forms. Examples of kh appear in l. 12, of ñ in ll. 10, 15, of j in ll. 2, 3, etc., of b in l. 8. The l is usually of the ancient type, with the tail prolonged in a curve round it towards the left; but in illā, l. 21, telliga, l. 29, and possibly in the last word of l. 32, we find a cursive form almost identical with the modern Burmese letter. On the whole, then, we may safely ascribe the character to about A.D. 735; and hence we may conclude that the Yuvarāja or Heir-Apparent Vikramāditya mentioned in it as granting the constitution embodied in it to the burgesses of Porigere was no other than Vikramāditya, son of Viṣṇuāditya, of the dynasty of the Western Chalukyas of Bādāmi, who about this time, A.D. 725, was ruling the province as Heir-Apparent, and subsequently, about A.D. 733, succeeded his father as Vikramāditya II.

The language is Kanarese prose, of the oldest dialect known. Typical of it are the following flexions: the accusative in -ān, as in *jivitaṅgaḷān*, l. 10, *poḷāḷān*, l. 24, *viṭṭiyān*, l. 35; the genitive in -ā, as in *Porigereyā*, ll. 2-3, *soṇageyā*, l. 33, *irppattā*, l. 34, *keyyā*, ll. 34-35; the locative in -uḷ, as in *māsaduḷ*, ll. 12, 22; the curious accusative *Vāraṇasivamath*, ll. 50-51, with which we may compare the locatives *Bāraṇāsicaduḷ*, above, Vol. VII, p. 204, and *Vāraṇāsicaduḷ* in *Ind. Ant.*, Vol. XIX, p. 145, l. 13; the verbal forms *kāvodu*, l. 10, *envodu*, l. 21, *apporoge*, l. 13, *koṭṭor*, l. 50, *koḷom*, l. 50, *uḷvār* or *uḷeor*, l. 31, *āḍadu* (imperative?), ll. 6 ff., and *āḷidona*, l. 52. In *āḷke*, l. 12, there seems to be a use of l instead of ḷ. The name *Kupparma*, l. 46, is of a type similar to that of *Uḍayamma* in the Narēndra inscription B, Vol. XII above, p. 321, l. 28. A considerable number of words are of lexical interest, as *ara*, l. 46 (cf. *piriy-araṅge* in the Baṅkāpūr inscription above, Vol. XIII, p. 174); *are-vāḍa*, l. 31; *gutta*, l. 22; *kūḷ*, l. 30; *pāka-daṇḍa*, l. 19 (cf. *kīru-kūḷa*); *rāva*, l. 22; *soṇage*, l. 33; *utsāha* in the sense of "generous gift," "bounty" (cf. the inscription of Vēma Roḍḍi above, Vol. VIII, p. 14, verse 6, l. 13, and the Kaḷas record of Gōvinda IV, l. 5, Vol. XIII above, p. 329), besides some of which the reading is not quite certain.

The purport of the inscription is to record the mutual obligations and rights of the Royal authorities, represented by the Heir-Apparent Vikramāditya, and of the Mahājanas (Brāhmaṇa householders) and burgesses of Lakshmēshwar. The preamble (ll. 1-5) is as follows: "Hail! the social constitution which the Heir-Apparent Vikramāditya has granted to the Mahājanas and the burgesses and the eighteen *prakṛitis*¹ of Porigere (is as follows)." The charter then proceeds to specify the position of the royal officers and their relation to the municipality in the following terms (ll. 5-10): "The king's officers are to protect those of the houses that are untenanted,² the king's gift, the king's proclamation, authoritative testimony of good men (?), constitutional usage, copper-plate edicts, continued enjoyment of (estate) enjoyed . . . the lives of the five *dharma*s."³ Then comes the section defining the duties of the townspeople (ll. 10 ff.).

¹ The "eighteen *prakṛitis*" would naturally seem to denote the eighteen royal ministers, on whom see the *Kaṣṭhīya*, translation, p. 25 and (list) p. 23, *Pañchastotra* (Bombay S. S.), iii, p. 50, ll. 17 ff., *Mahābhārata*, *Sabha-parvan*, v. 38, *Rājatarāṅgiṇī*, l. 120 and iv. 141, *Ind. Ant.*, Vol. XXV, p. 183, and note 82, Kittel's Dictionary, s. v. *aśṭādasa-pradhāna*. But this will not suit the present context, which states that the constitution was granted by Vikramāditya to the *prakṛitis* and others. Hence we must understand *prakṛiti* here to denote the classes of the population. The division of the population into 18 classes is well known: see Kittel, s. v. *aśṭādasa-jāti*, and the Eighteen Samayas mentioned in *Progress Report of Asst. Archaeol. Supt. for Epigraphy, Southern Circle*, 1914-15, p. 106 (which speaks of *padīnāḥ-bhūmi-samayattār*), and *Ep. Carn.* X, l. Kl. No. 70.

² For this suggested translation, and for several others in this paper, I am indebted to Mr. B. Narasimhachar.

³ Mr. Narasimhachar suggests that this refers to the life (*pañcāḥ-prāṇa*) of *dharma* (can it be the life of children and men in the four *āśramas*?).

It begins with the Mahājanas or Brāhman burgesses (ll. 10-23): "This is the municipal constitution for the Mahājanas. A tax that (*every*) occupied house shall pay once every year¹ in the month of Vaiśākha to the governors of the district: each several household for festival expenses (?), the highest households (*paying*) ten *paṇas*, the intermediate households seven *paṇas*, the lower five, the lowest three: all previous usages, viz., *puṭṭige*,² . . . fines for theft and minor delinquencies, (*finer for*) the ten offences,³ likewise what is known as property of childless persons: (*all these*) shall be paid in to the guild there in the month of Kārttika. A *gutta*⁴ shall be paid for (? to) the *rūva* in the month of Māgha." Then after a reference, unfortunately only half legible, to the government of *pāṇḍis* and *seṭṭis* in the town (ll. 23-24), we have⁵ the article on the braziers (ll. 24-29): "For the guild of braziers (*every*) occupied house (*shall pay*) for festival expenses (?), the highest households twenty *palas* . . . the intermediate fifteen, the lower ten, the lowest five; total, one *tole*."⁶ Next to be mentioned are the oilmen; but the articles from this point (l. 29) to l. 35 are very obscure and the reading in many places doubtful. Then come about ten lines which are almost wholly illegible. They cover the bottom of the first face and the top of the second face. On l. 46, the fourth line of the second face, we find a distinct change in the character of the writing; it has become larger, and more coarse and clumsy. Possibly this change may have begun from the first line of the second face (l. 41); but ll. 41-45 are too much defaced to allow of any conclusions of the kind.

Ll. 46-55 record a supplementary endowment: "Also the field granted to (?) the *ara* of the fortunate Kuppama the three-hundred households and the Gāmuḍa of the province, together with the *goḍigar* (?), have granted. He who may appropriate it shall be accounted equal to persons who should destroy Benares, (*or*) persons who should kill a thousand Brāhmanas and a thousand cows."

TEXT.⁶

First face.

- 1 [Ōm?] Svasti śri-Vikramā-
- 2 ditya-yuvarājar Pori-
- 3 geṇeyā mahājanakkum na-
- 4 garakkum padineṭṭum prakritigaḷgum
- 5 koṭṭa āchāra-vyavasthi(sthe) [i*] rāja-
- 6 puruṣar-mmanegaḷoḷ viḍ-illāda-
- 7 du rāja-dattam rāja-ārāvitam saptra-
- 8 me⁸ maryyāde tāmbra-śāsanam bhukt-ā-
- 9 nubbōgam * * ayduṁ dhammadā ji-
- 10 viṇḍaḷān-kāvodu [i*] idu mahājanakke
- 11 nagara-maryyāde mane viḍ-illādadu
- 12 ōr-āḷke orṁme Vaiśākha-māsaduḷ
- 13 dēśādhipatigaḷ-apporḡge kuḍuva
- 14 tere uttamam-appa okkal-mi *¹⁰

¹ Understanding *āḷ* as = the Tamil *āḷa*.

² Probably a kind of measure; or possibly a tax on births.

³ See J. Jolly, *Recht und Sitte*, p. 123 f.

⁴ Mr. Narasimhaśar suggests a connection between this word and *guttiga* (contract or monopoly, or tax thereon).

⁵ Thus the local *tole* (*talā*) contained 50 *palas*. * From the impressions.

⁷ I conclude that the inscription began with the symbol for *ōm*, as there is a space for it, on which the stone is badly worn.



⁸ Read *sat-prame*.

⁹ These two *ākṣaras* are very uncertain. The first looks like *āḷa*, but it might be *cāḷa*; the second is like a *ḍa* with the top curled back towards the left, and is surmounted by the sign for the vowel *i*.

¹⁰ The *mi* is not quite certain, and the next syllable is quite illegible.

Lakshmeshwar inscription of the Yuvaraja Vikramaditya.

First face.



Second face.



- 15 sam pattu paṇavum madhyamam-a[ppa]
 16 okkal ēlum paṇavum kanishṭha(shṭha)r-aydum
 17 kaniyasar mōrum-amtt-appa osage-
 18 utsāhaṅgalge ond-okkal-ondū puttī-
 19 ge ma * chōra-pāka-daṇḍa dās-aparā-
 20 dhaṅga)=appav-ellam pūrvv-āchāraṁ a-
 21 [pu]tra-dhanam-envodu tāne illi s[ē]ṇig[e] KA-
 22 ritika-māsadu]=koḍuvadu guttām rāvanige Mā-
 23 gha-māsadu]=koḍuvadu pāṇḍi-seṭṭi nāl-chhā-¹
 24 siram tirmesagaḍepakko² poḷalāu-āle ka-
 25 ṇchagāra-sēṇige mane viḍ=illādadu utta-
 26 mam-appa okkal-chelade³ irppattu palam
 27 madhyamam padinaydu kanishṭha(shṭha)m pattu kani-
 28 yasam aydum-amtt-appa osage-utsāhaṅga-
 29 lge samūham or-ttole telliga-sēṇige
 30 mane viḍ=illādadu kū]=illādadu tereyum
 31 k[e]y-u]lār⁴ are-vāḍa keyy=illādadu so-
 32 re matt-appa osage-utsāhaṅgalge ilti⁵
 33 vayilamum pettavi⁶ vayilamum soṇageyā
 34 maryyāde irppattā ayi valla ke-
 35 yyā viṭṭiyān=keyi nā * * [g]āra-
 36 sēṇige uttamam a * * * * *
 37 madhyamam sāyira * * * * *
 38 * * sāyira[m] kanishṭha[m] kani[yasam]
 39-40 [illegible]

Second face.

- 41-43 [illegible]
 44 * * ra sēṇige * * *
 45 aras-ā]ke * * * *
 46 svasti ārt-Kupparmed-aram-
 47 ge koṭṭa keyum goḍi-⁷
 48 gar-oḍam mōnu(nā)rvvarum akka-
 49 lum nāl-gāmapḍanum iḷḍa
 50 koṭṭor [||*] Idam koḷvom Vā-
 51 rapasivamam alī-
 52 dona lōkakke sandon=akkum
 53 sāsirvvar-pārvarum sā-
 54 [yira kavī]leyumam ko-
 55 [nda lōkakke sa]n[d]on=akkum [||*]

¹ It is not quite clear whether this letter is meant for cāāḍ or cāḍ; I have decided for the former in accordance with grammatical rule (see Kittel's Grammar, p. 178).

² Most of these seven aksaras are more or less uncertain, and no sense can be obtained from them.

³ Or possibly *esjade*.

⁴ The subscript letter which I read as *lā* is not quite clear; apparently what is meant is *uḷār* or *uḷor*.

⁵ Or possibly *ilti*, with a cursive *l*.

⁶ The *ē* (if that is the right reading) is written above the line, having apparently been omitted by the error of haplography.

⁷ Or possibly *gāḍi*.

No. 15.—CHANDRAVATI PLATES OF CHANDRA-DEVA : V. S. 1150 AND 1156.

By DAYA RAM SAHNI, M.A., RAI SAHIB.

These plates, which are six in number, were found at Chandravati, in the district of Benares, at the same spot on the left bank of the river Ganges as the Chandravati plate of Chandra-dēva of Vikrama-Samvat 1148, published by Dr. Sten Konow.¹ Chandravati, pronounced Chandrauti, is a village situated on the river Ganges in the *pargana* of Katōhir (anc. Kathēhali), a short distance to the east of the metalled road from Benares to Ghāzipur, three miles south of Kaithi and fourteen miles from the district head-quarters. It has long been, and still is, the chief village in the *pargana* of Katōhir. The village is now entered by a ruined gate on the west. Upon the southern wall of this gate is an inscription of Vikrama-Samvat 1797. The village contains two Jaina temples, to which we shall refer later on.

The plates under review were enclosed in a strong box of stone, measuring 3' 1½" × 2½" × 1' 6½" high, provided with a lid of the same material. The box and the lid were transferred to the Lucknow Museum in 1912, where they, as well as the plates, are now preserved. The stone box was exposed to view by the erosion of the river bank. The fact was reported to the Executive Engineer of Benares, who had the box and its contents safely brought over to his office and presented them to the Lucknow Museum at the suggestion of the Director-General of Archaeology in India, who has kindly authorized me to edit them. The transcript published below was prepared in 1912, when, on a personal visit to Chandravati, I made the topographical notes that are subjoined. The same visit enabled me to identify with certainty some of the localities mentioned in the plates.

The plates are well preserved and measure 2' 3" long by 1' 3¼" broad. They are all pierced with a circular hole, 1¼" in diameter, in the middle of the upper part, and were fastened with three copper rings, to the biggest of which was soldered a stout copper seal, bearing the legend Śrīmach-Chandradēva in Nāgarī characters. Above and below the legend are a flying figure of Garuda and a conch-shell in conformity with the Vaishṇava faith of the king who issued the plates. These are engraved on one side only. The characters are Nāgarī. The height of the letters averages ⅜". The language is Sanskrit throughout, the historical portions being in prose, the rest in verse.

In respect of orthography and spelling the following points may be noted. No distinction is made between *ba* and *va* and *ś* and *ṣ*; syllables are sometimes omitted, as *kana* in *ālō-kana* l. 17 and *va* in *īva* l. 18; consonants after *ra* are doubled or not in accordance with the optional character of the grammatical rule concerned; the *anuvāra* is used for *n* in *haraṇa narakam* l. 23 of the second inscription. We also notice *tri* for *tri* l. 2, *ri* for *ra* in *kiriṇa* l. 22. Several examples of superfluous punctuation are also noticed, especially in the third, fourth and the fifth plates, on which the names of the donees are engraved. We have only one example of the lingual *ḥ*, in the name *Maḥivāda* in l. 11 of the second inscription.

The six plates described in this paper contain two documents, both issued by king Chandra-dēva of Kānyakubja (Kannauj) in the years Vikrama-Samvat 1150 and 1156 respectively.

These inscriptions are interesting; for they supply the old official names of a large number of localities, which are discussed below in another paragraph. But there is another point which is equally interesting. The only dates so far known of king Chandra-dēva are Vikrama-Samvat 1148 (A.D. 1090-1) and 1154 (A.D. 1097-8). The inscriptions published here supply two more dates, namely Vikrama-Samvat 1150 (A.D. 1092-93) and 1156 (A.D. 1098-99), thus extending Chandra-dēva's reign by at least two years. We learn from the Basāhi plate of

¹ *Ep. Ind.*, Vol. IX, pp. 302 sq.

Mahārāja-putra Govindachandra-Dēva that his father Madanapāla-Dēva was ruling in Vikrama-Samvat 1161. We may, therefore, assume that Chandra-Dēva must have died and his son Madanapāla-Dēva succeeded him some time between Vikrama-Samvat 1156 and 1161. We have for Chandra-Dēva no earlier dates than V. S. 1148. So we cannot yet determine the date of his coming to the throne of Kānyakubja, which he is said in the inscriptions to have conquered.

PLATES OF VIKRAMA-SAMVAT 1150.

The first document is inscribed on five plates, comprising a total of ninety lines. It begins with an invocation to the Goddess Śrī, consort of Vishnu, favourite deity of the kings of the Gāhaḍavāla family, and goes on to describe the genealogy of the donor, king Chandra-Dēva, and his conquest of Kanauj. This is followed by the royal order announcing that the *Parama-bhaṭṭāraka Mahārāj-ādhirāja Param-ēivara Param-māhēśvara Śrīmach-Chandrāditya-Dēva*, after bathing at the *Svarga-dvāra tīrtha* at the confluence of the Śarayū and the Ghargharā in Ayōdhyā, conferred on a body of 500 Brāhmanas (*pañchatata-saṁkhyēbhyaḥ*) the *pattalā* of Kāṭhēhālī with the exception of certain villages formerly given to temples, Brāhmanas etc., on Sunday the fifteenth day of the dark half of the month of Āśvina in the year Samvat 1150 (expressed both in words and figures), on the sacred occasion of a solar eclipse. The date corresponds to A.D. 1093, October 23. He also gave away the village of Sarisōḍa in the *Vṛihadrīhēvamkānai pattalā* for the residence of the same community of Brāhmanas. The document winds up with nine verses, the first seven of which are of an impr-atory nature. The eighth mentions the name and the parentage of the scribe Hridayadhara, son of the illustrious Śivastambha, and the last eulogizes the donor Chandra-Dēva as the king by the resoundings of whose copper-plates bearing grants of land, "at the time of their being engraved with rows of closely written lines, the universe has become deafened."

It is interesting to note that one of the *ghāṭs* of Ayōdhyā still bears the name of *Svarga-dvāra*. The *pattalā* of Kāṭhēhālī is now known as Kāṭhīr, the largest *pargana* in the district of Benares. "It is bounded on the south by Athaganwan, Sheopur and Jahlupur, on the east by the Ganges and the *pargana* Barah of *Taḥsil* Chandauli, on the west by Kol Aslah and on the north by the small *pargana* of Sultanipur and the river Gumti." Its ancient boundaries (*chatur-āghāṭa*), as recorded in this inscription, were "Kōllakanandivāra *pattalā*, the Gōmatī, Bhāgirathī and Varanā." We may assume that the *pattalā* of Kāṭhēhālī was nearly co-extensive with its modern representative; for, though one of the old boundaries, Kōllakanandivāra has not been identified with certainty, it is not impossible that it is the same as Kol Aslah which now marks the western limit of the Kāṭhīr *pargana*. We note in support of this that Kol Aslah is also a *pargana* and its first component may well be a remnant of "Kōllaka."

TEXT.¹

1. 11 — — — — — सोयं नरपतिमुकुटमकरिकामर-
कतप्रभापटलपङ्कवितपादपोठो गजपतिगलगर्जितप्रलयपंचाननस्त्रिशंकुपतिक-
1. 12 पटपाटनक्रकचपातचपलपंचालचूलचूवनचणचंद्रहासो गिरिपतिपिबुपिण्डचण्डमा-
रुतः कवलितकलिकालकपटपेटको निर्व्वानपथिकलोपाकदशनः समधिग-
1. 13 तसकलदर्शनस्वरसपेशलज्ञानसंपद्विजितमुनिमनोवृत्तिराश्रयः श्रेयसामाकरः स्व-
विद्यानामालयः कलानामाधारः सा(स्वा)मिसंपदां परमभट्टारकमहाराजा-
धिराजप-

¹ From the plates.

1. 14 रमेश्वरपरममाहेश्वरनिजभुजोप जिंतश्रीकन्यकुलाधिपत्यश्रीमच्चन्द्रादित्यदेवो विजयी
॥ ॐ ॥ कठेहलीपत्तलानिवासिनो निखिलजनपदानुपगतानपि च रा-
1. 15 जराज्ञोद्युवराजमंचिसेनापतिपुरोहितप्रतोहाराक्षपटलिकभाण्डागारिकभिषग्वैमिस्त-
कान्तःपुरिकदूतकरितुरगपत्तनाकरस्थानविषयगोकुलप्रसुखाधिकारिपु-
1. 16 रुघानपारनपि यथार्ह मानयति बोधयत्याज्ञापयति च यथास्तु वो विदितैव
तावदियमनित्यता जगतः कतिपयदिवसावलोकरमणोया मधुमांसकु-
सुमसंपदिव सं-
1. 17 पत(त्) सततगत्वरस्वरूपं गिरिकटकवाहिनीपुलिनवालुकाकूटमिव देहिनामा-
युरापातमधुराः कटुकपाकिनो दुर्जरास्तिलखला इव विषयभोगाः सदस-
दालो[कन*]पर-
1. 18 सुखानि स्वार्थैकनिष्ठानि वेश्याविलसितानोव दुरुपचाराणीन्द्रियाणि कतिपय-
कलाविलासिनी जलबुद्बुदस्तवकसंपदि[व] यौवनश्रीस्तदिदमस्माभिरपि
सकलदर्शनावि-
1. 19 संवादिनोभिः प्रामाणिकोभिः श्रुतिभिः परिच्छिद्य हरिहरकमलासनमुना-
सोरपुरभोगभाजनं भूमिदानमिति कृतनिश्चयेरुत्तरकोशलाभिधानायामधोध्या

Plate II.

1. 20 यां पंचाशदधिकैकादशशतसंवत्सरे आश्विने मासि अमावस्यायां रविदिनेह्येपि
संवत् ११५० आश्विनवदि १५ रवौ सूर्योपरागपञ्चमिणि अनितसरयूधर्धरा-
1. 21 घमर्षणे स्वर्गहारनाम्नि तीर्थे स्नात्वा विधिवन्मन्त्रदेवमुनिमभुजभूतपितृगणांस्त-
र्पयित्वा तिमिरपटलपाटनपटुमङ्ग[समु]ष्णरोचिषमुपस्थाय चित्तिजलदहनपवनग-
1. 22 गनयजमानतुङ्गिनकिरि(र)णाक्षवपुषमोषधीपतिशकलशेखरं समभ्यर्च्य भगवत-
स्त्रिभुवनचातुर्वासुदेवस्य पूजां विधाय प्रचुरपायसेन हविषा हविर्भुजं
हुत्वा पिबपि-
1. 23 शङ्खचक्रनिर्वृत्य उपरिलिखितपत्तला सजलस्थलगिरिगङ्गनगर्तोपरपाषाणलोह-
लवणाकरा समधूकचूतवनवाटिकाविटपटुण्युतिगोचरपर्यता विशेषतो निर्हेच-
(हिंश्य)-
1. 24 माणपूर्वदत्तदेवहिजविकरग्रामवर्जिता कोलकनंदिवारपत्तलागोमतीभागीरथी-
वरणासरिद्विचतुराघाटविशुद्धा निर्हेच(निर्हेश्य)माणनानानामगोत्रेभ्यस्तुषर-
णचा(चो)तु(तुः)शु-

* Cf. राजयोर्द्वेजा तस्य नवमे भूमौ प्रवत् *Rājatarāṅgi* of Kalhana, Bk. V, verse 19.

三三.

W. GRIGGS & SONS, LTD., PHOTO-LITH.

38
 40
 42
 44
 46
 48
 50
 52
 54

38
 40
 42
 44
 46
 48
 50
 52
 54

[illegible]

1. 25 तिपाठकेभ्यः पंचशतसंख्येभ्यो ब्राह्मणेभ्यो गौतमैश्वर्यपूतकरतलोदकपूर्वमाप-
द्मसन्नो ह्यहुकान्तं यावच्छासनीकृत्य प्रदत्ता तद्ब्रह्मपुरीनिवासाय वृह-
द्धेवंकाणैप-
1. 26 तत्तायां सरिसीडग्रामः प्रदत्त इति मत्वा यथादीयमानभागभोगकरतुरुष्क-
दण्डप्रत्यादायविषयदाण(न)प्रभृतिसमस्तादायान् तथा स्वनौकाभाटकतरादा-
यानेभ्यः उपने-
1. 27 [त*]व्य[ान*]उपनेव्येति ॥ च्छ ॥ अस्यां पत्तलायां देवद्विजविकरग्रामास्तथा
देवग्रामाः ॥ भंडदह । उडेल्ली । पणिहली । खचुरी । तलभाम ।
भायी । लघुवडवि-
1. 28 छी । मलेथी । दूणा । उंधरौहा । भागमग्रामाहं । जिगणा ।
लघुवडमवली । संचलवण । चठतरा । सोणक । अधिव ।
उपलाहच । वृहलीउ । वृहत्वंचलाम । सोणदहा ।
1. 29 कधिवी । अणदौरी । अणदौरा । चमेख । कुण्डाम । द्विजग्रा-
माः ॥ चुदवासडादयक । तलहुति । विकरग्रामाः । चिरिविलो ।
सेविली । गुलघट । वडयला । दीवाक-
1. 30 छ । चिलाड— — — — —
1. 35 द्विजवरनतिरक्तः शुद्धकायस्ववंशो
हृदयधरसमाख्यः श्रीशिवस्तंभसूनुः ।
अलिखदखिलवर्णव्यक्तपंक्तिप्रशस्यं
नवकिश(स)लयकान्तं ताम्ने(भमे)तद्वि(द्वि)जानाम् ॥
1. 36 किं तस्य चन्द्रनृपतेर्वृत वर्णु(र्ण)यामो
यस्य द्विजेन्द्रसुरशासनताम्रपट्टैः ।
उत्कीर्यमाणनिविडाक्षरपंक्तिजाल-
वाचालितैर्वधिरभावमियाय विश्वम् ॥

TRANSLATION

(ll. 14-30, 35-36).

(Lines 14-6) He (Chandrāditya-Dēva) respects, informs and commands, according to their position, all the people resident at the *pattalā* of Kaphēhali, and visitors, and also Kings, Queens, *Yucarājas*, counsellors, commanders of troops, chaplains, chamberlains, keepers of records, superintendents of stores, physicians, astrologers, superintendents of gynæceums, envoys, officers in charge of elephants, horses, towns, mines, stations, districts and *gōkulas* (cattle stations) and others, as follows :—

(Ll. 16-26) The transitoriness of this world is, indeed, known to you. Prosperity is charming to the eyes only for a few days, like the beauty of the flowers of the spring season.

The life of men is always moving, like a heap of sand on the bank of a river flowing along the slope of a mountain. The enjoyment of the pleasures, sweet in the beginning, bitter in the end, is difficult to digest, like oil-cakes. The senses are hard to deal with, always given to their selfish ends, and averse to discriminating between good and bad, like the coquetry of prostitutes. Youth lasts only for a few seconds, like a cluster of bubbles of water. Therefore we too, having resolved—according to the authentic precepts of the Vedas, not disagreeing with all the *Śāstras*—that the giving of land leads one to the attainment of the abode of Hari, Hara, Brahmā, and Indra, after having bathed at the Svarga-dvāra *Mrtha* at the sin-effacing (confluence) of the Sarayū and the Ghargharā at Ayōdhya—also called Uttara-Kōśala—, on Sunday the fifteenth day of the dark half of the month of Āśvina, in the year eleven hundred increased by fifty, also in figures Samvat 1150, Āśvina, vadi 15, Sunday, on the sacred occasion of a solar eclipse—after having duly satisfied the sacred texts, divinities, saints, men, beings and the group of the departed ancestors—after having worshipped the sun, whose splendour is potent in rending the veil of darkness—after having praised him (Śiva) whose crest is a portion of the moon and whose body consists of the earth, water, fire, air, ether, the sacrificing priest, the moon and the sun—after having performed adoration to the holy Vāsudēva, the protector of the three worlds—after having sacrificed to fire an oblation of abundant milk, rice and sugar—after having offered oblations to manes—have conferred the above-named *pattalā*, with its water and dry land, hills and forests, ravines and saline wastes, stones, mines of iron and salt, with and including its groves of *madhūka* and mango trees, enclosed gardens, bushes, grass and pasture land, clearly defined by four boundaries consisting of the Kōllakanandivāra *pattalā* and the rivers Gōmatī, Bhāgirathī, and Varāṇas, with the exception of certain specified villages formerly given to temples, Brāhmaṇas and to *vīkṛas*,¹ upon five hundred Brāhmaṇas of the different names and *gōtras* specified below, versed in the four Vedas with their divisions—(confirming our gift) with (the pouring out) from the palm of our hand of water purified with *kudā* grass and *gōkarṇa* (and) ordaining (that it should be theirs) as long as the sun and moon (endure). The village of Sarisōḍa in the Vṛihadrihēvamkāṇai *pattalā* has (also) been given away for the residence of the same community of Brāhmaṇas.

(Li. 26-30) Aware of this, you will present to them every usually rendered kind of income, the due share of the produce, the *bhōga*, *kara*, *turushkadāṇḍa*, *pratyādāya*, *vishayadāna* etc.² In this *pattalā* the villages (given to) the temples, Brāhmaṇas and to persons deprived of hands, are the following:—Villages of temples: Bhaṇḍadaha, Uḍḍī, Paṇihali, Khajurī, Talabhāma, Bhāyī, Laghuvaḍaviṇḍī, Malēṇī, Dūpā, Umdharanubhā, half of the village of Bhāgama, Jigāṇā, Laghukamavali, Sēmchalavaṇa, Chaṭhatarā, Sōpaka, Adhiva, Upalāḥṇa, Vṛihatsū, Vṛihatyaṁchalāma, Sōpadahā, Kadhivi, Anadaurā, Anadsuri, Chamēkha, Kuṇḍāma. Brāhmaṇa villages: Chudavāsadvāḍasaka, Talahuti. The villages belonging to *vīkṛas*:¹ Chirivili, Sēmṇī, Gulavaṇa, Vaḍethalā, Divākakaha and Chilaḍa.

(L. 35) Hridayadhara, the son of the illustrious Śivastambha, fond of saluting the Brāhmaṇas and belonging to a pure Kāyastha family, has written this copper-plate of the Brāhmaṇas, smooth like a fresh leaf, and adorned with lines in which the lettering is quite clear. What should I speak of the King Chandra, by the sound produced from whose copper-plate grants given to Brāhmaṇas and divinities, at the time of their being engraved with rows of closely written lines, the universe has become deafened.

¹ The word *vīkṛas* would naturally mean 'tax-free'; but we may expect a more technical meaning. In the case of Kirtipāla's inscription of Samvat 1167 (*Ep. Ind.* Vol. VII, pp. 94, 96) Kielhorn took the word as proper name of a village.—F. W. T.]

² On these taxes see Vol. XI, p. 21 and ref.

PLATE OF VIKRAMA-SAMVAT 1156.

This document is inscribed on one plate only and comprises twenty-four lines of writing. The inscription begins with the remark that this grant was made after a munificent gift of gold and other valuables equal to the king's weight (*tulā-purusha*) and a thousand cows before the beautiful image of the illustrious *Ādi-kēśava*. After the usual genealogical information the inscription goes on to record that the *Parama-bhaṭṭāraka Mahārāj-ādhirāja Param-śēvara Param-māhēśvara Śrīmad-Chandraditya-Dēva*, having bathed at the *ghāṭ* of *Śrīmad-Ādikēśava* at the confluence of the rivers *Gaṅgā* and *Varaṇā*, bestowed thirty villages in the *Vṛihadṛihēdēvaratha pattalā* and two villages in the *Kaṭhēhālī pattalā* upon the same five hundred *Brāhmaṇas* who were the donees in the previous copper-plates of *Vikrama-Samvat 1150*. The inscription also records the dedication of the village of *Majauḍa*, situated in the *Vamkāṇai pattalā*, together with all its revenues, for the maintenance of the shrine of *Śrī-Chandramādhava* at *Chandrāvati*. The grant was made in the year *Samvat 1156*, on Saturday, the third day of the bright half of the month of *Vaiśākha*. The date corresponds to A.D. 1100, April 14.

The temple of *Chandramādhava* is no longer extant. Mr. Chhote Lal, Executive Engineer, Benares, has expressed the opinion¹ that this designation of the town was probably given to it by *Chandra-Dēva*. Similarly we may assume that the shrine was also founded by the same king and that it was for this reason that he selected it for his special grant on this occasion. On my visit to *Chandrāvati* I learnt that the site of a *Śvētāmbara* *Jaina* temple in the village is still known to the Hindu inhabitants of *Chandrāvati* by the name of *Chandramādhō*. There are two inscriptions in this temple. One of them, bearing the date *Vikrama-Samvat 1757*, is built in the north wall, and the other, which is dated in the *Vikrama-Samvat* year 1564, is carved on the base of an image of *Śāntinātha* worshipped in this temple. It seems obvious that the temple of *Chandramādhava* must have disappeared before *Vikrama-Samvat 1757*, when the *Jaina* temple was constructed on its site. The temple was probably washed away by the river. The box which contained the six plates was found near the modern site of the temple. We may assume that they were deposited in the temple and escaped destruction because possibly they were buried deep in the ground or a little farther away from the river bank. Copper-plates bearing records of grants of land and other gifts to religious establishments have been frequently found buried under the foundations or floors of buildings for whose maintenance they had been issued. The other five plates which were issued in favour of the five hundred *Brāhmaṇas* were preserved in the same box with the *Chandramādhava* plate, because, we may infer, those *Brāhmaṇas* were the trustees or guardians of the temple. This should account also for the special favour shown to them by the king in bestowing upon them a large number of villages by two consecutive grants in the course of six years.

Extracts from the TEXT (ll. 1, 8-21, 24).²

1. 1 श्री । देवश्रीमदादिकेशवदक्षिणमूर्ती तुलापुरुषगोसहस्रमहादान-
समनन्तरम् । — — — — —
1. 8 सोयं नरपतिमुकुटमकरिकामरकतप्रभापटलपद्मवितपादपीठो गजपतिगजम-
र्जितप्रलयपंचाननस्त्रिशंकुपतिकपटपाटनक्रकचपातो निर्वाणपविकलोपाकदर्य-

¹ *Ep. Ind.*, Vol. IX, pp. 302 sq.² From the plate.

1. 9 नः परमभट्टारकमहाराजाधिराजपरमेश्वरपरममाहेश्वरनिजभुजोपार्जितश्रीकन्ध-
कुलाधिपत्यश्रीमच्छन्द्रादित्यदेवो विजयो ॥ ॐ ॥ वृहद्वृहदेवरठपत्तलायां
गोइज-
1. 10 र । मयडसिद्ध । गंगडडा । देउली । सपाटकसिरिसी । भडौहा ।
टकौली । मणिभ । घडसिय । कोसण्ड । इन्दिणी । माण्डु ।
पटणा । कठासी । गडसंडा । कडलासी । गोडडी । ॐतेसु ।
के-
1. 11 श्रौच्छी । भरघी । लघुकोली । चन्दवली । मक्किवाड । मलुयी ।
पकडिधा । बुधरामौयी । संखवायी । वमणा । दिधवंट । बरेठा ।
एवं ग्रामास्त्रिंशदङ्गतोपि ग्राम ३० तथा कठहे(ठह)सीपत्तलायां
टकौर । पव-
1. 12 शाहपुर । ग्राम २ उभयं पत्तलाइये ग्राम ३२ एषु निवासिनो
निखिलजनपदानुपगतानपि च राजराश्रीयुवराजमन्त्रिसेनापतिपुरोहितभिव-
न्मैमित्तिकान्तःपुरिकदूतकरि-
1. 13 तुरगपत्तनाकरस्थानगोकुलाधिकारिपुरुषानाञ्चापयति बोधयत्नादिशति च ।
अस्तु वो विदितैव तावदियमनित्यता जगतः कतिपयदिवसावलीकरमणीया
मधुमासकुसुमसंप-
1. 14 दिव संपता(त्) सततगत्वरं गिरिकटकवाहिनीपुलिनवास्तुकाकूटमिव देहि-
नामायुरापातमधुराः, कटुकपाकिनी दुर्जरास्तिलखला इव विषयभोगाः
सदसदाशोकनपरास्तुखानि वे-
1. 15 श्लाघितसितानोव दुष्पचाराशीन्द्रियाणि । तदिदमस्माभिरपि सकलशास्त्रा-
विसंवादिनीभिः ग्रामाणिकीभिः श्रुतिभिर्विदुष्य पटुं चाशदधिकशतैकदेश-
(कादश)संवत्सरे वैशाखसिताक्षतः(त)-
1. 16 तृतीयायां शनिदिने अद्याक्षततृतीयायां^१ युगादिपर्वणि जनितसुरसरिहर-
णावमर्षणे श्रीमदादिकेशवचहे ज्ञात्वा विधिवन्मन्त्रदेवमुनिमनुजभूतपिढ-
गणांस्तर्पयित्वा तिभिरपटलपा-
1. 17 टनपटुमहसमुष्णरोचिसुपक्काय चित्तिजलदहनपवनगगनयजमानतुहिनकिरि-
(र)शास्त्रवपुषमोवधिपतिग्रन्थेश्वरं समभ्यर्च्य भगवती^२ वासुदेवस्य पूजां
विधाय प्रशुरपा-

^१ This syllable is engraved above the line.^२ * is added at the bottom of the line.

ॐ नमो भगवते वासुदेवाय ॥ ॐ नमो भगवते वासुदेवाय ॥ ॐ नमो भगवते वासुदेवाय ॥

[The following text is highly degraded and mostly illegible due to extreme fading and damage.]

1. 18 यस्य हविषा हविर्भुजं हुत्वा पिष्टपिष्टयज्ञं निर्वृत्य उपरिलिखितधामाः
सजलस्यलग्निरिगहनगर्तोपरपाषाणलोहलवणाकराः समधूकचूतवनवाटिकावि-
टपटणयूतिगोचर-
1. 19 पर्यन्ताद्यतुराघाटविश्रवाः कठेहलीसक्तताम्रपचलिखितनानानामगोचेभ्यो ब्राह्म-
णेभ्यश्चतुस्त्रयचा(च)तु[*]श्रुतिपाठकेभ्यः पञ्चशतसंख्येभ्यो गोकर्षकुशपूतकर-
तलोदकपूर्वमाप-
1. 20 असन्नो ह्यहुकान्तं यावच्छासनीकृत्य प्रदत्ता मत्वा यथादीयमानभागभो-
गकरतुल्यदण्डप्रभृतिसमस्तादायानेभ्यः समुपनेष्येति तथा वंकाणैपत्तज्ञायां
मनुष्यद्वयम् [*] सर्वादायसहि-
1. 21 तः चंद्रावत्यां देवयोचंद्रमाधवाय पूजायर्थं शासनीकृत्य प्रदत्त इति ।
1. 24 उत्तोर्य माधवेनेदं श्रीगंगाधरसुनुना ।
श्रीचन्द्रमाधवो येन घटितोऽयं हंसनि(सन्नि)व ॥

TRANSLATION

(ll. 1, 9-21, 24).

(Line 1) Ōm. After giving away gold etc. equal to his own weight and a thousand cows before the excellent image of the divine (and) illustrious Ādi-kēśava

(ll. 9-21) Victorious is he, the illustrious Chandraditya-Dēva, the Parama-bhaṭṭāraka, Mahārāj-ādhirāja, Param-ēśvara, the devout worshipper of Mahēśvara, who, by his arm, has acquired the sovereignty over the glorious Kanyakubja . . . In the pattalā of Vṛihadṛihēdēva-rāṭha, the villages Gōimjara, Mayaḍasitna, Gaṃgahadā, Dēuli, Sapātakasirisi, Bhaḍanḥā, Takauli, Maṇia, Ghaḍasitna, Kōsaṇḍa, Indipi, Maṇḍu, Paṭanā, Kāṭhāli, Gaḍasamḍā, Kaṅkalāsi, Gōūḍi, Chohhatēmbu, Kaithnōḍi, Bharathī, Laghukōli, Chandavali, Maḷivāḍa, Maluyi, Pakāḍiā, Vudharāmauyi, Saṃkhaṇvāyi, Vamaṇā, Dighavamṭa, Varēṭhā, these thirty villages, in figures also, villages 30; also, in the pattalā of Kāṭhēhali, two villages, Takaura, Pavaṇāhapura, making thirty-two villages in both the pattalās: in these (villages) (the king, Chandra-Dēva) commands, informs and directs all the people, resident and visitors, also Kings, Queens, Yuvarājās, counsellors, commanders of troops, priests, physicians, astrologers, superintendents of gynaeceums, envoys, officers in charge of elephants, horses, towns, mines, stations and gōkulas: The transitoriness of the world should, indeed, be known to you; prosperity is charming to the eyes only for a few days, like the beauty of the flowers of the spring season; the life of men is always moving, like a heap of sand on the bank of a river flowing along the slope of a mountain; the enjoyment of the pleasures, sweet in the beginning, bitter in the end, is difficult to digest like oil-cakes; the senses are difficult to deal with, averse to discriminating between good and evil, like the coquetry of prostitutes. Therefore, we, too, having considered, with the help of authentic precepts of the Vēdas and the Smṛitis, not disagreeing with all the Śāstras, and having bathed at the glorious Ādi-kēśava ghaṭṭa at the sin-effacing (confluence) of the Ganges and the Varanā, on Saturday, the akshata third day of the dark fortnight of Vaisākha, in the year eleven hundred increased by fifty-six, to-day on the akshata-

¹ ह is engraved above the line.

tritiyā, in the yugādī parvan, after having duly satisfied the sacred texts, divinities, sages, men, beings and the group of departed ancestors—after having worshipped the sun, whose splendour is potent in rending the mass of darkness—after having praised him (Śiva) whose body consists of the earth, water, fire, air, ether, the sacrificing priest, the moon and the sun, and whose crest is a portion of the moon—after having performed adoration to the holy Vāsudēva—after having sacrificed to the fire an oblation of abundant milk, rice and sugar—after having offered oblations to the manes—have given away the above-mentioned villages with their water, dry land, hills, forests, ravines, saline wastes, stones and mines, of iron and salt, together with and including their groves of *madhoka* and mango trees, enclosed gardens, bushes, grass and pasture land, with their four boundaries clearly defined, to the five hundred Brāhmins, versed in the four *Vēdas* with their four divisions, whose different names and *gōtras* are recorded in the copper-plate pertaining to Kāthēhālī, (confirming our gift) with (the pouring out) from the palm of our hand of water purified with *gōkarna*¹ and *kūśa* grass, and ordaining (that it should be theirs) as long as the sun and the moon (endure). Aware (of this), you will present to them every kind of income, the due share of the produce, the *bhōga*, *kara*, *turushka-dāṇḍa* etc. At the same time the village of Majuṣa in the Vamkānai pattala, with all usually rendered kinds of income, has been given as a grant to (the temple of) the divine and illustrious Chandramādhava at Chandrāvati for purposes of worship.

(L. 24) (The deed) was engraved by Mādhava, the son of the illustrious Gaṅgādhara, who made (the image of) the illustrious Chandramādhava, which puts to shame the other (images).

Of the localities mentioned in the plates the most interesting are Laghukamavali and Chandavali. The first is probably the same as the modern Kamauli, situated 8 miles south of Chandrāvati. It was here that a plate of Śīngara Vatsarāja² and 21 Gāhaḍavāla plates³ were found. We may presume that the village was divided into two portions, the "smaller Kamavali" and the "larger Kamavali." Chandavali, situated 18 or 20 miles south-east of Chandrāvati, is a *Tahsil* in the Benares district. The following is an alphabetical list of the other localities referred to in the plates, with their modern names as far as I have been able to ascertain them :—

(1) Adhiva.

Ādi-kēśava *ghaṭṭa*. There is a bathing *ghaṭ* at Benares which still bears this name.

Anadaurā.

Anadauri.

Bhadauhā. This is the same as *Baḍuā*, situated in Kāthēhir pargana 3 miles south-west of Chandrāvati.

Bhaṇḍadaha. Same as Bhaṇḍahā, situated 2 miles north of Chandrāvati.

Bhāgama.

Bharathi.

Bhāyi.

Bṛihatsiū.

Bṛihatyaṁchalāma.

Chamēkha.

Chāṭhatarā.

Cchhatāmbu.

Chilāḍa.

¹ The meaning of this word is not clear. *Gōkarna* is the name of a place of pilgrimage on the Malabar Coast. Perhaps *kūśa* grass of that place was considered to be of extra sanctity. [See above, Vol. XI, p. 303 and ref. to Kielhorn, *Indian Antiquary*, Vol. XV, p. 10, n. 57.—F. W. T.]

² *Ep. Ind.*, Vol. IV, pp. 130 sq.

³ *Ep. Ind.*, Vol. IV, pp. 27 sq.

- Chirivili.
 Chudavāsa.
 Divākaksha.
 Dēuli. There is a village Déoria, 4 *kōs* south of Chandrāvati.
 Dighavamṭa. This is identical with Dighavaṭ, a *pargana* in the Chandrāvati *Taḥṣīl*.
 Dūpā.
 Gaṅgahadā. Same as Gaṅgēhara, 18 miles to the south of Chandrāvati.
 Gaḍasamḍā. This is identical with Gaḍasara, a village south of Kaṭāri.
 Gaḍasitha.
 Gōimjara.
 Gōūdi. This is the same as the village Gauri, situated 6 miles west of Chandrāvati.
 Gulavaṭa. Known by its modern name Guravaṭa; it lies 3 miles south of Chandrāvati.
 Indipi.
 Jigapā.
 Kadhivō.
 Kaithnōṇḍi.
 Kaṅkalāsi.
 Kaṭhāli. A village named Kaṭāri is situated 8 miles west of Chandrāvati.
 Khajuri. Is a village or Mahalla near *Chungi*.
 Kōllakanandivāra *pattalā*, possibly the same as the modern *pargana* of Kol Aslah.
 Kōsaṇḍa.
 Kuṇḍāma. There is a village Kuṇḍā 10 miles to the south of Chandrāvati.
 Laghukōli.
 Laghuvaḍaviṇḍi.
 Majuaḍa is probably Mahuar, situated 2 miles to the south-east of Chandrāvati.
 Malēpi.
 Maḷivaḍa. Majwar is a *pargana* in *Taḥṣīl* Chandauli.
 Maluyi is a village lying 8 miles to the south of Chandrāvati.
 Maṇḍu. There is a village Maṇḍu-dih, 16 miles south of Chandrāvati.
 Mania. A village called Mansi is situated across the Ganges, 2 miles to the east of Chandrāvati.
 Mayaḍasiṭna.
 Pakadā. There is a village Pakadi 8 miles south of Chandrāvati.
 Paṇihālī is a village 3 miles south of Chandrāvati.
 Paṭaṇā is situated 6 miles north of Chandrāvati.
 Pavaṇāhapura.
 Samkhavayī.
 Sapātakasirisī. Sirisī is a village 6 miles south of Chandrāvati in Alhupur *pargana*.
Paṭaka means "outlying hamlet."
 Sarisōḍa. Sarasvar or Sarasval is a village 2 miles south-east of Chandrāvati.
 Sēmivili. A village named Simari is situated 14 miles to the north-east of Chandrāvati.
 Semchalavapa.
 Sōnadahā, known by its modern name Sōnadahām, is situated between the 5th and 6th miles on the Benares-Ghazipur Road.
 Sōnaka.
 Ṭakaulī. There is a village named Ṭikāri 4 *kōs* to the east of Chandrāvati.
 Ṭakaura.
 Talabhāma.
 Talahuti.
 Uḍēḍi.

Umdharaumha. There is a village Udharā 8 miles to the south of Chandravati.

Upalaicha.

Vaṭathala, modern Barathala, is a village lying 3 miles to the south of Chandravati.

Vamaṣa.

Vamkaṇai pattala.

Varēṭha.

Vudharaṁsuvi. There is a pargaṇa named Mavai, in the *Taḥsil* of Chandavali.

Vṛihadṛihēdēvarāṭha pattala.

Vṛihadṛihēvamkaṇai pattala.

List of Donors.

Serial No.	Name.	Gōtra.	Serial No.	Name.	Gōtra.
1	Āchārya-panḍita Vṛitikaṛa.	Vasiṣṭha.	25	Dūhapa . . .	Bhāradvāja.
2	Śrī Rīgvedacharaṇḍe chatur-vēdin Jāta.	Kā(ś)yapa.	26	Sivāicha . . .	Bhāradvāja.
3	Padmanābha . . .	Vasiṣṭha.	27	Āhapa . . .	Sāmkṛitya.
4	Vishṇu . . .	Kāyapa.	28	Amṛitadhara . . .	Sāmkṛitya.
5	Sāthū . . .	S(Ś)āṇḍilya.	29	Nāra(ṇ)ha . . .	Kṛishṇātrēya.
6	Padmē . . .	Gautama.	30	Gaṇḍādharā . . .	Kauṇḍinya.
7	Dēvagarbha . . .	Gautama.	31	Mahīpati . . .	Kauṇḍinya.
8	Nārāyaṇa . . .	Gautama.	32	Pavaṇāha . . .	S(Ś)āṇḍilya.
9	Nālhaṇa . . .	Bhāradvāja.	33	Gōlhaṇa . . .	Gautama.
10	Kōki . . .	Vata.	34	Sōmadatta . . .	Gautama.
11	Śrīdhara . . .	Kṛishṇātrēya.	35	Dāyīm . . .	Kau(ś)ika.
12	Yōga-Svāmin . . .	Vandhula.	36	Yas(ś)ahpāla . . .	Bārkara.
13	Vīṭhu . . .	Kṛishṇātrēya.	37	Vīṭhu . . .	Sāmkṛitya.
14	Rajapāla . . .	Sāmkṛitya.	38	Gōpati . . .	Sāṇḍilya.
15	Māhava . . .	Sāmkṛitya.	39	Yajūna . . .	Upamanyu.
16	Harivarman . . .	Sāṇḍilya.	40	Sāhu . . .	Sāmkṛitya.
17	Kā(ś)ava . . .	Sāmkṛitya.	41	Dharaṇīdhara . . .	Sāmkṛitya.
18	Bhāskara . . .	Kau(ś)ika.	42	Gāga . . .	Bha(Sā)mkṛitya.
19	Māhula . . .	Kapishṭhala.	43	Yōgē . . .	Sāmkṛitya.
20	Hari . . .	Kṛishṇātrēya.	44	Mahēvara . . .	Sāmkṛitya.
21	Dēmla . . .	Bhāradvāja.	45	Ālhū . . .	Maunya.
22	Gayādharā . . .	Kāyapa.	46	Mahīdhara . . .	Sau(Śau)ṇaka.
23	Vahudhara . . .	Kāyapa.	47	Vālō . . .	Kātyāyana.
24	Yas(ś)ōdhara . . .	Kāyapa.	48	Sāpa . . .	Kāyapa.
			49	Būbē . . .	Gautama.

Serial No.	Name.	Gōtra.	Serial No.	Name.	Gōtra.
50	Śrīkumbha . . .	Kāśyapa.	81	Lakshmana . . .	Kṛishṇātrēya.
51	Pavaṇa . . .	Kāśyapa.	82	Salakhū . . .	Sāmkṛitya.
52	Mahāri(ri)shi . . .	Kāśyapa.	83	Kaḍuācha . . .	Sāmkṛitya.
53	Māyādhara . . .	Bhāradvāja.	84	Dēva-Svāmin . . .	Gārgya.
54	Ālha . . .	Bhāradvāja.	85	Pāṇidhara . . .	Kausika.
55	Lakshmidhara . . .	Bhāradvāja.	86	Kshira-Svāmin . . .	Kausika.
56	Tihupa-Svāmin . . .	Bhāradvāja.	87	Tikama . . .	Kāśyapa.
57	Bharatha . . .	Kāśyapa.	88	Tikama . . .	Kṛishṇātrēya.
58	Dēvadatta . . .	Bhāradvāja.	89	Dāmara . . .	Kṛishṇātrēya.
59	Mahāsarpa (or śar- man).	Kṛishṇātrēya.	90	Pavaṇa . . .	Gārgya.
60	Dādā . . .	Vandhula.	91	Vāmana-Svāmin . . .	Gārgya.
61	Vyāsa . . .	Bhārgava.	92	Kaḍuātha . . .	Kāśyapa.
62	Lakshmidhara . . .	Kāśyapa.	93	Gaja . . .	Kāśyapa.
63	Lakshmidha(ra) . . .	Śāṇḍilya.	94	Pālho . . .	Vasishtha.
64	Jānō . . .	Sāmkṛitya.	95	Bhāskara . . .	Kṛishṇātrēya.
65	Dēva(ś)arman . . .	Upamanyu.	96	Vasurāta . . .	Śāṇḍilya.
66	Kāsa(śa)va . . .	Bhāradvāja.	97	Gaṅgādhara . . .	Bhāradvāja.
67	Rāghava . . .	Vasishtha.	98	Lōkānanda . . .	Vata.
68	Dāyīn . . .	Pārāśara.	99	Chakra . . .	Bhāradvāja.
69	Lāhaḍa . . .	Jivantyāyana.	100	Udharana . . .	Bhāradvāja.
70	Pīthana . . .	Jivantyāyana.	101	Dhāyīn . . .	Dhaumya.
71	Mādhava . . .	Kṛishṇātrēya.	102	Madhu . . .	Sauśravasa.
72	Nārāyaṇa . . .	Bhārgava.	103	Vīlhaṇa . . .	Dhaumya.
73	Dāmara . . .	Kausika.	104	Jāta . . .	Sauśravasa.
74	Lakshmana . . .	Garga.	105	Gayādhara . . .	Kāśyapa.
75	Madhusūdana . . .	Garga.	106	Gaṅgādhara . . .	Dhaumya.
76	Kōśava . . .	Kāśyapa.	107	Sīma . . .	Vasishtha.
77	Dāyīn . . .	Kāśyapa.	108	Sātē . . .	Bhāradvāja.
78	Dhavana-B[ṛ]āmin . . .	Kāśyapa.	109	Malu . . .	Upamanyu.
79	Gayādhara . . .	Kṛishṇātrēya.	110	Vata . . .	Kāśyapa.
80	Hariśchandra . . .	Kṛishṇātrēya.	111	ada . . . Dēdē . . .	Vata.
			112	Jāta . . .	Vasishtha.

Serial No.	Name.	Gōtra.	Serial No.	Name.	Gōtra.
113	Vālū . . .	Vasishtha.	144	Brahman . . .	Kāśyapa.
114	Dharaṇidhara . . .	Vasishtha.	145	Pahākara . . .	Vasishtha.
115	Janārdana . . .	Kāśyapa.	146	Vahada . . .	Dhaumya.
116	Prabhākara . . .	Kāśyapa.	147	Rajapāla . . .	Dhaumya.
117	Jālū . . .	Bhāradvāja.	148	Sūdhā . . .	Vasishtha.
118	Dafaratha . . .	Sāvarka.	149	Viṭhu . . .	Bhā[ra]dvāja.
119	Vāmadēva . . .	Sāvarka.	150	Hari . . .	Gautama.
120	Dharaṇidhara . . .	Kṛishṇātrēya.	151	Vasudēva . . .	Bhārgava.
121	Vaśis(ṭh)adhara . . .	Bhārgava.	152	Rājō . . .	Kapishthala.
122	Janārdana . . .	Gautama.	153	Mādō . . .	Kapishthala.
123	Mādhala . . .	Gautama.	154	Kuhila . . .	Kapishthala.
124	Pāpata . . .	Upamanyu.	155	Thirū . . .	Kausika.
125	Tithu . . .	Gautama.	156	Nāgarahi . . .	Gautama.
126	Sri Yajur-vēda-charaṇē chatur-vēdin Vilha.	Vasishtha.	157	Bhābhū . . .	Bhāradvāja.
127	Sahārāṇa . . .	Bhārgava.	158	Purushōttama . . .	Bhāradvāja.
128	Dhārē . . .	Bhāradvāja.	159	Sōmata . . .	Gālava.
129	Viṭhu . . .	Bhāradvāja.	160	Dāmara . . .	Sārakra.
130	Rācō . . .	Sauśravaṇa.	161	Viśvarūpa . . .	Śāṇḍilya.
131	Ganō . . .	Sauśravaṇa.	162	Śrīdhara . . .	Sārkarākha.
132	Manū . . .	Vasishtha.	163	Gōvinda . . .	Sārkarākha.
133	Yayīm . . .	Vasishtha.	164	Yāsū . . .	Kāśyapa.
134	Yasōdhara . . .	Vasishtha.	165	Rishi (Rishi) . . .	Vasishtha.
135	Śubbarikara . . .	Vasishtha.	166	Gālhē . . .	Sāmkṛitya.
136	Gaṁgādihara . . .	Vasishtha.	167	Nārāyana . . .	Kāśyapa.
137	Jāgū . . .	Sauśravaṇa.	168	Mahādhara . . .	Bhāradvāja.
138	Dafaratha . . .	Vasishtha.	169	Padmanābha . . .	Pārāśara.
139	Brahmānanda . . .	Kāśyapa.	170	Bhagavata . . .	Gautama.
140	Mādhava . . .	Bhārgava.	171	Nārāyana . . .	Kāśyapa.
141	Yāsū . . .	Kutaa.	172	Paṇḍita Dālā . . .	Bhāradvāja.
142	Rālhē . . .	Kāśyapa.	173	Svapata . . .	Bhāradvāja.
143	Pāpīdhara . . .	Kāśyapa.	174	Agasti . . .	Bhāradvāja.
144			175	Dhājama . . .	Bhāradvāja.

Serial No.	Name.	Gōtra.	Serial No.	Name.	Gōtra.
176	Bājē . . .	Bhāradvāja.	208	Ābhata . . .	Bhāradvāja.
177	Prabhākara . . .	Dhaumya.	209	Gayādhara . . .	Bhāradvāja.
178	Śivānanda . . .	Bhāradvāja.	210	Dēvadharma . . .	Vasiṣṭha.
179	Brahma . . .	Sauśravaṣa.	211	Dēvēśvara . . .	Vasiṣṭha.
180	Gōlhapa . . .	Bhārgava.	212	Dāgū . . .	Bhāradvāja.
181	Dāmara . . .	Bhāradvāja.	213	Drōpa . . .	Bhāradvāja.
182	Vāyīr . . .	Bhāradvāja.	214	Sōma . . .	Bhāradvāja.
183	Vasādhana . . .	Bhārgava.	215	Achasa . . .	Bhāradvāja.
184	Gayādhara . . .	Bhārgava.	216	Vāṇu . . .	Bhāradvāja.
185	Sōmēśvara . . .	Chau(Sau)śravaṣa.	217	Sūpaṭa . . .	Dhaumya.
186	Nārāyaṇa . . .	Bhārgava.	218	Gāgū . . .	Bhārgava.
187	Madhu . . .	Bhārgava.	219	Dēvaradha (dhara) . . .	Bhāradvāja.
188	Bhānapāla . . .	Bhāradvāja.	220	Dēvēśvara . . .	Dhaumya.
189	Yasa(śaṭ)pāla . . .	Bhāradvāja.	221	Gāhē . . .	Bhāradvāja.
190	Vasodēva . . .	Vasiṣṭha.	222	Śrī Atharvac h a r a ṇ ḍ dvivēdin Chhīhila.	Bhāradvāja.
191	Risū . . .	Vasiṣṭha.	223	Mahidhara . . .	Vasiṣṭha.
192	Jālā . . .	Vasiṣṭha.	224	Śrīdhara . . .	Vasiṣṭha.
193	Gargādhara . . .	Bhāradvāja.	225	Dēvadharma . . .	Vasiṣṭha.
194	Gargādhara . . .	Bhārgava.	226	Śāmkara . . .	Bhāradvāja.
195	Jāta . . .	Sauśravaṣa.	227	Dhāhaḍa . . .	Vasiṣṭha.
196	Gargavara . . .	Dakha.	228	Vāhaḍa . . .	Vasiṣṭha.
197	Brahma . . .	Bhāradvāja.	229	Dēvēśvara . . .	Vasiṣṭha.
198	Vasādhara . . .	Bhāradvāja.	230	Gōdhana . . .	Vasiṣṭha.
199	Titē . . .	Bhāradvāja.	231	Dēvēśvara . . .	Dhaumya.
200	Śubhākara . . .	Bhāradvāja.	232	Sūpaṭa . . .	Dhaumya.
201	Rāma . . .	Vasiṣṭha.	233	Vasādhara . . .	Vasiṣṭha.
202	Lālā . . .	Vasiṣṭha.	234	Mābava . . .	Dhaumya.
203	Pitbē . . .	Sauśravaṣa.	235	Sōkhē . . .	Bhārgava.
204	Garga . . .	Sauśravaṣa.	236	Dhāmō . . .	Bhāradvāja.
205	Gāngu . . .	Vasiṣṭha.	237	Titē . . .	Dhaumya.
206	Pitbū . . .	Bhāradvāja.	238	Pavanāha . . .	Bhāradvāja.
207	Jālā . . .	Bhāradvāja.			

Serial No.	Name.	Gōtra.	Serial No.	Name.	Gōtra.
239	Gautama	Vasishtha.	271	Dhavana-S[ylāmin	Kāśyapa.
240	Gira(ṭ)dhara	Vasishtha.	272	Nānā	Kāśyapa.
241	Sahārāpa	Sauśravaṇa.	273	Sōṭa	Vatṣa.
242	Nānā	Bhāradvāja.	274	Manōratha	Vatṣa.
243	Pithū	Bhāradvāja.	275	Gōyī	Vatṣa.
244	Kūṇḍa	Sauśravaṇa.	276	Mahādōva	Vatṣa.
245	Lākṣhaṇa	Sauśravaṇa.	277	Sahārāpa	Sāṅḍilya.
246	Bhārāpa	Sauśravaṇa.	278	Titi	Sāṅkṛitya.
247	Pāpya	Bhāradvāja.	279	Nāntē	Sāṅkṛitya.
248	Janārdhana	Bhāradvāja.	280	Gāgū	Kāśyapa.
249	Rājapāla	Sāṅḍilya.	281	Nārīyapa	Sāṅkṛitya.
250	Pālā	Dharmya.	282	Sahārāpa	Kāśyapa.
251	Gōvinda	Pārāśara.	283	Dēvadhara	Sārkaṇa(rā).
252	Lakṣmīdhara	Kāśyapa.	284	Kīthācha	Bhāradvāja.
253	Vasudēva	Sāṅḍilya.	285	Mādhū	Kauṣika.
254	Sāṅkū	Kātyāyanakilla.	286	Siri	Gautama.
255	Nānā	Kātyāyanakilla.	287	Chāṇḍō	Sāṅḍilya.
256	Brahman	Chandrātṛeya.	288	Purisa	Kāśyapa.
257	Nānū	Chandrātṛeya.	289	Kalyō	Kāśyapa.
258	Lakṣmīdhara	Sāṅkṛitya.	290	Vānki	Kāśyapa.
259	Sṛidhara	Kṛishṇātṛeya.	291	Kūḥ	Vasishtha.
260	Dhāmṛū	Vatṣa.	292	Pārāśara	Vatṣa.
261	Kṛishṇa	Gautama.	293	Vārḍhamāna	Sāṅḍilya.
262	Sūpata	Garga.	294	Āśadhara	Gautama.
263	Sōḍala	Sāṅkṛitya.	295	Dēśvara	Vatṣa.
264	Pahākara	Kāśyapa.	296	Madhusūdana	Kāśyapa.
265	Abhā	Bhāradvāja.	297	Pavanāha	Gautama.
266	Vādhala	Upamanyu.	298	Jagā[ḍ]dhara	Vasishthapada.
267	Gōpāl	Gautama.	299	Gāṅgū	Kāśyapa.
268	Somadatta	Kāśyapa.	300	Brahmarshi	Sāṅkṛitya.
269	Nārīyapa	Kāśyapa.	301	Dēśarman	Bhārgava.
270	Mahōḍāthi	Sāraṇa.	302	Dharaṇidhara	Kṛishṇātṛeya.

No. 15.] CHANDRAVATI PLATES OF CHANDRA-DEVA : V. S. 1150 AND 1156. 207

Serial No.	Name.	Gōtra.	Serial No.	Name.	Gōtra.
303	Madhava	Kandika	335	[Nara]pati	Gautama
304	Mahidhara	Vasishtha	336	Golhā	Kāśyapa
305	Dulhapa	Krishnātrēya	337	Mālā	Kāśyapa
306	Dēvakara	Kāśyapa	338	Shā	Krishnātrēya
307	Shā	Kāśyapa	339	Vithu	Gautama
308	Yogēśvara	Bhāradvāja	340	Golhā	Gautama
309	Vithu	Krishnātrēya	341	Bhālapa	Śāṇḍilya
310	Gōch(vi)nda	Krishnātrēya	342	Gāngū	Vasishtha
311	Vahula	Krishnātrēya	343	Rāma	Śāṇḍilya
312	Lāla	Vasishtha	344	Purōhita Śrī Dēvadhara	Sārkarākha
313	Higē	Sāvarga	345	Mīra Paṇḍita Mahi- dhara.	Sārkarākha
314	Golhā	Kandika	346	Paṇḍita Gōdhana	Sārkarākha
315	Ripi	Jātukara	347	Gāngūdhara	Pip[p]alāda
316	Bhāskara	Krishnātrēya	348	Salhapa	Krishnātrēya
317	Mahua	Krishnātrēya	349	Jalhapa	Krishnātrēya
318	Vāthū	Kāśyapa	350	Jasāpārida	Vasishtha
319	Mahēśvara	Kāśyapa	351	Dhāro	Śāṇḍilya
320	Salhā	Upamānya	352	Dāmara	Gautama
321	Jā	Vata	353	Kēśava	Kāśyapa
322	Hāchēhapa	Kāśyapa	354	Śrīdhara	Kāśyapa
323	Divākara	Krishnātrēya	355	Dinākara	Vata
324	Pabākara	Krishnātrēya	356	Abhū	Kāśyapa
325	Bhāskara	Krishnātrēya	357	Hāri	Manya
326	Dālā	[Kri]shnātrēya	358	Dharapādhara	Kāśyapa
327	So(Śa)mkhapāqi	Kāśyapa	359	Voda	Kāśyapa
328	Dēvasarman	Sāmkṛitya	360	Sahārapa	Jaka
329	Kēśava	Krishnātrēya	361	Lakshmidhara	Bhāradvāja
330	Vithu	Krishnātrēya	362	Rāma	Śāṇḍilya
331	Subhāmaka	Krishnātrēya	363	Golhapa	Krishnātrēya
332	Bhāskara	Gautama	364	Mahēśvara	Sāmkṛitya
333	[Gō]vinda	Gautama	365	Lakshmidhara	Krishnātrēya
334	Sāmkara	Gautama	366	Śrīdhara	Kāśyapa

1 Omitted in the plate.

Serial No.	Name.	Gōtra.	Serial No.	Name.	Gōtra.
367	Hari . . .	Kāśyapa.	399	Pāpaṭa . . .	Sārkarāksha.
368	Gōpati . . .	Gautama.	400	Śrīdhara . . .	Kauṭika.
369	Kōśava . . .	Kāśyapa.	401	Kujātra . . .	Maudgalya.
370	Viśvarūpa . . .	Śāṇḍilya.	402	Gāṅgaṭa . . .	Bhāradvāja.
371	Dharaṇīdhara . . .	Hārīta.	403	Chākū . . .	Kauṭika.
372	Nārāyaṇa . . .	Bhāradvāja.	404	Harīśarma . . .	Kāśyapa.
373	Gaṅgādharma . . .	Kauṇḍinya.	405	Divākara . . .	Kauṭika.
374	Pāṇi . . .	Bhāradvāja.	406	Vṛatikara . . .	Bhāradvāja.
375	Pada . . . ; Kōśava . . .	Vasiṣṭha.	407	Vāṇa . . .	Sārkarāksha.
376	Mahāśoṇa . . .	Kuṭsa.	408	Dūhaga . . .	Sārkarāksha.
377	Vilha . . .	Kuṭsa.	409	Khalu . . .	Pārśara.
378	Vata . . .	Vata.	410	Lakṣmīdhara . . .	Kapishthala.
379	Jayaśarma . . .	Bhāradvāja.	411	Nārāyaṇa . . .	Kāśyapa.
380	Śubhāṅkara . . .	Vata.	412	Sōmēśvara . . .	Bhāradvāja.
381	Yasōdhara . . .	Bhāradvāja.	413	Mumjāla . . .	Darbha.
382	Rishi (Rishi) . . .	Jivant[ya]yana.	414	Śrīdhara . . .	Kāśyapa.
383	Vijhu . . .	Bhārgava.	415	Lōhika . . .	Kapishthala.
384	Chhotō . . .	Sāṅkṛitya.	416	Dēvarahi . . .	Kāśyapa.
385	Ājusha . . .	Kāśyapa.	417	Nānā . . .	Darbha.
386	Kōśava . . .	Kāśyapa.	418	Lālā . . .	Kāśyapa.
387	Yasōdhara . . .	Maunya.	419	Ālaṇa . . .	Kapishthala.
388	Dūhaga . . .	Vasiṣṭha.	420	Vasurāta . . .	Bhāradvāja. —
389	Mahāśoṇa . . .	Śā[ṇ]ḍilya.	421	Śrī-chhandōga - charaṇē tripāṇṭhi(tripāṭhi)n Śrī Dōdiga.	Vata.
390	Māṇi . . .	Śāṇḍilya.	422	Rāhila . . .	Kapishthala.
391	Gōpāla . . .	Vasiṣṭha.	423	Nārasiṅha . . .	Vata.
392	Gahilā . . .	Upamanyu.	424	Pavapāha . . .	Kapishthala.
393	Gāyādharma . . .	Jivantiyana.	425	Viśvēśvara . . .	Kṛishṇātrēya.
394	Jayapāla . . .	Vasiṣṭha.	426	Rāghava . . .	Kapishthala.
395	Lakṣmīdhara . . .	Jivantiyana.	427	Sōmēśvara . . .	Bhāradvāja.
396	Jāihē . . .	Vata.	428	Pavapāha . . .	Kṛishṇātrēya.
397	Jahmaṇi . . .	Sārkarāksha.	429	Gōdhapa(na) . . .	Kapishthala.
398	Nāgadhara . . .	Sārkarāksha.			

Serial No.	Name.	Gōtra.	Serial No.	Name.	Gōtra.
430	Jālhō . . .	Kautsa.	463	Sūpā . . .	Bhāradvāja.
431	Aniruddha . . .	Kapishthala.	464	Bhāskara . . .	Bhārgava.
432	Pālhaṇa . . .	Vatsa.	465	Dēva-Svāmin . . .	Kauṇḍinya.
433	Ālhaṇa . . .	Sāvaraṇa.	466	Mahārishi(rishi) . . .	Ātrēya.
434	Kṛṣṇa . . .	Kṛishṇātrēya.	467	Nārāyaṇa . . .	Kāśyapa.
435	Kānha . . .	Śāṇḍilya.	468	Vidhi-karaṇi Gaṅgādharma.	Srī Vasishṭha.
436	Kṛishṇa . . .	Sāvaraṇa.	469	Bhasi(Śaśi)dharma . . .	Vasishṭha.
437	Bhadrēśvara . . .	Kṛishṇātrēya.	470	Siṇa . . .	Vasishṭha.
438	Vāhmaṇa . . .	Kaṇva.	471	Māmē . . .	Upamanyu.
439	Yama(śaṇ)kara . . .	Maunasa.	472	Chāvaṇa or Rāvaṇa . . .	Pārśara.
440	Dēvaśarma . . .	Maunasa.	473	Māgha . . .	Gautama.
441	Dālā . . .	Bhāradvāja.	474	Madhācha . . .	Pārśara.
442	Nārāyaṇa . . .	Bhāradvāja.	475	Isarācha . . .	Śāṇḍilya.
443	Gāka . . .	Śāṇḍilya.	476	Viṭhu . . .	Bhāradvāja.
444	Yasācha . . .	Pārśara.	477	Jānū . . .	Śāṇḍilya.
445	Vidyākara . . .	Pārśara.	478	Jāna . . .	Kāśyapa.
446	Dhāvana . . .	Gautama.	479	Śrīdhara . . .	Śāṇḍilya.
447	Bhāvaśarma . . .	Gautama.	480	Jamaka . . .	Śāṇḍilya.
448	Lakshmidhara . . .	Gautama.	481	Gacchhū . . .	Pārśara.
449	Śubhaśarma . . .	Gautama.	482	Pārśara . . .	Śāṇḍilya.
450	Nārāyaṇa . . .	Gautama.	483	Dhāvana . . .	Bhāradvāja.
451	Gayādharma . . .	Gautama.	484	Śrīkara . . .	Kāśyapa.
452	Brahmāditya . . .	Vatsa.	485	Vasudēva . . .	Bhāradvāja.
453	Kṛṣṇa . . .	Śāṇḍilya.	486	Viṭhu . . .	Pārśara.
454	Punācha . . .	Sārkarāksha.	487	Nārāyaṇa . . .	Pārśara.
455	Nārā[ya]ṇa . . .	Śāṇḍilya.	488	Vidyādharma . . .	Bhāradvāja.
456	Puruṣottama . . .	Gālava.	489	Tikṣṇa . . .	Śāṇḍilya.
457	Rilhū . . .	Kāśyapa.	490	Amṛtadhara . . .	Bhāradvāja.
458	Bhābhū . . .	Vatsa.	491	Sahāraṇa . . .	Vasishṭha.
459	Siṇa . . .	Kāśyapa.	492	Trilochana . . .	Kuśika.
460	Dēvadharma . . .	Agastī.	493	Āśadhara . . .	Bhāradvāja.
461	Gahilāda . . .	Bhāradvāja.	494	Lālā . . .	Sauśrama.
462	Garga . . .	Kāśyapa.	495	Ratikara . . .	Bhārgava.

No. 16.—BEVINAHALLI GRANT OF SADASIIVA-RAYA : SAKA 1473.

By PROFESSOR S. V. VENKATESWARA, M.A., AND S. V. VISWANATHAN, M.A., KUMBAKONAM.

These plates were obtained by Rao Sahib H. Krishna Sastri from Bashir ud-Din Ahmad, Esq., the Collector of Raichur, and are now in possession of the latter. We edit the inscription from excellent ink-impressions supplied to us by Mr. Krishna Sastri.

The inscription is on seven copper plates, which measure 10½ in. by 7½ in. All the plates are engraved on both sides, except the first and the last, which are inscribed on one side. The rims of the plates are raised a little. Holes are bored at the top of the plates to let in a ring intended to hold the plates together. The hole measures 6 in. in diameter. The plates are numbered in Tefnig-Kannada numerals.

The characters of the inscription are Nandi-Nāgarī, and the language Sanskrit, and the whole is in verse, excepting *Śrī Gaṇādhīpatayā namaḥ*, and the signature at the bottom *Śrī Virūpakṣa*, which is, as usual, written in large Kannada characters. The metres used are the usual Anuṣṭubh, etc. The inscription is practically free from mistakes, and there are only a few orthographical peculiarities worth noticing. Stops are not supplied in their proper places. Mistakes of this kind have been corrected in the text. In the latter portion of the inscription long *i* is represented only by a loop over the consonants. A case of redundant *anusvāra* is found in *kaṁnyā* in l. 105, and various instances where *anusvāra* and *visarga* have been omitted are noted in the footnotes to the text. We find a needless reduplication of a consonant after *r*, as in *śanur-Ddēvaṇa* in l. 161. There is confusion in these plates also, as in other plates of the Vijayanagara kings, though not to so great an extent, between the sibilants *śa* and *ṣa*, e.g. *nāṇiyasiva* in l. 73 f. for *nāṇiyasiva*; *nilasitām* in l. 76 in the place of *nilasitām* and *śeṣmanah* in l. 126 instead of *śeṣmanah*. In one instance long *i* is represented by a vertical stroke and an *i*-loop over short *i*, as if the latter were a consonant, e.g. l. 301. A conjunct consonant is, as usual, expressed by combining the full form of the first consonant and the secondary form of the second consonant. The vernacular sound *r* is represented by an *r* sign over the consonant *r*. Instances of these are *māra* in l. 80 and *Ararajī* in l. 104. The forms *tāmra-sāsana* in l. 309, *vāṣadhi* in l. 78, and *Vobāṣabikā* in ll. 24-25 are due to vernacular pronunciation.

The inscription records the grant of the village of Bēvinahalli, otherwise known as Rāmasamudram, with a small hamlet by name Ponnāpuri to learned Brahmins of various *Gotras* and *Sūtras*. The grant was made by Rāma-Rāja, the Karṇāṭa minister and brother-in-law of Sadasiiva-Rāja, at the request of a subordinate Muhammadan chieftain Aṇana Malukka, who seems to have been a great patron of Brahmins. The village granted is styled '*gaṇa-bhōgyam*,' to be enjoyed by Brahmins and subordinate ministers of the king, a very small portion being allotted to the gods Hari and Hara. It is given in perpetuity as *sarva-mānya* to be enjoyed by the donees and their successors. The boundaries of the village, the details regarding the donees, their *Gotras*, *Sūtras* and the number of shares that fell to each are likewise clearly set forth in the grant.

The inscription gives in detail the genealogy of the family to which Rāma-Rāja belonged. It is, however, somewhat different from others, in that in the place of Śrīranga-Rāja, the third in the line and the father of Rāma-Rāja, we find Śrī Rāma-Rāja. This probably is a mistake on the part of the engraver.

The genealogy of Rāma-Rāja.

Āravīti Bukka m. Ballāmbikā.

Rāma-Rāja m. Lakkāmbikā.

Śri Rāma-Rāja.

Rāma-Rāja.

The year in which the grant was made is given in numerical words *Gur-āśva-vēda-sitāmsu*, i.e. 1473. The date of the grant is thus Śaka 1473; Virōdhikrit; Āshādha; bright Dvādaśi; Monday. Thus all the details regarding the date are given. We have to add here that the date as given in Appendix A to *Epigr. Rep.*, 1914-1915, p. 8, 'Śaka 1473, Virōdhikrit; Āshādha *su. di. 11*' is not correct, as the week day is there omitted and the *tithi* is given as Ēkādaśi instead of Dvādaśi.¹

As regards the names of persons occurring in the grant, Sadāsiva-Rāya had a large number of ministers and subordinate chieftains under him. The most powerful of these was Rāma-Rāja, the Karpāta minister and brother-in-law of the king; Rāma-Rāja was the *de facto* sovereign in the reign of Sadāsiva until his death, which took place at the battle of Talikōṭa, 23rd Jan. 1565. His place in the Vijayanagara court was taken by his brother Tirumala, whom we know as a great author and who set up the third Vijayanagara dynasty. Rāma-Rāja is seen to bear various *birudas* (vv. 55-58), of which *Antembavaraganda* and *Aibiruda-rāya rāhuta-vēdy-aika-bhujāṅga* are the most important.

We are told in the record that it was as a result of the request of Ainana Malukka to Rāma-Rāja that the village was granted by Sadāsiva. Ainana Malukka was evidently therefore a Muhammadan subordinate chieftain under Sadāsiva-Rāya. About Ainana Malukka Rao Sahib H. Krishna Sastri has inserted in his report² the following note from Mr. Henry Cousens' *Guide to Bijapur* :—

"About 2 miles away to the east of Bijapur is the tomb of Ain-ul-Mulk." "It is a square, massive-looking building, surrounded by a very elegantly shaped dome. Within upon the walls are some very pretty stucco work in the shape of great pendants hanging down upon the face of each. This is the burial place of Ain-ul-Mulk, one of the officers of Ibrahim I, who rebelled against him and was killed near Bijapur in 1556. Beside the tomb is the mosque." "The Muhammadan chief Ainana Malukka must evidently be identical with Ain-ul-Mulk, whose sympathy for the Brāhmanas deserves to be noticed. In Vol. III, p. 381, of Briggs' *Ferishta* we find mention made of Mullik Ein-ool-Mulk Geelany, who was a friend of Rāmarāj and was treated by him as a brother on account of his bravery. Geelany is perhaps the chief Ainana Malukka referred to in the inscription." Since both the father and the son are known by the same name in our inscription, it is difficult to find out to which of these exactly the references will apply.

The village granted is divided into 135 *vrittis* and allotted to various Brāhmanas and ministers of the king, leaving a very small portion to the gods. The total number of *vrittis* distributed among the donees comes to only 133½, while according to the grant there ought to be 135. There is thus a mistake here that cannot be accounted for. The names of the Brāhmanas, their fathers' names, their *Gotras*, *Sūtras* and the number of shares allotted to each are appended below in the form of a table.

¹ [According to Mr. L. D. Swamikannu Pillai's *Epigramms* the date regularly corresponds to Monday, June 15, A.D. 1551. —H. K. S.]

² *Epigraphical Reports*, 1914-1915, p. 112.

Name.	Father's Name.	Gotra.	Sakhā.	Number of Shares.	Remarks.
(1) & (3) Hari and Hara				1 + 1	
(2) Mahā-Mahādēva-Bhāṭṭa	Rāmachandra	Kāśyapa	Bahv-riśha	4	
(4) Mahā-Guṇapati	Mahā-Rāmachandra	Do.	Do.	4	Sūri.
(5) Mahā-Vishnu-Bhāṭṭa	Mahā-Mudgala-Bhāṭṭa	Do.	Do.	4	
(6) Mahā-Krishna-Bhāṭṭa	Ditto	Do.	Do.	14	
(7) Mahā-Gopāla-Bhāṭṭa	Mahā-Rāmachandra	Do.	Do.	2	
(8) Dattam-Bhāṭṭa	Raghunātha-Sudhā	Parāśara	Do.	2	
(9) Nārāyaṇa-Bhāṭṭa	Akṣai-Vishnu-Bhāṭṭa	Kaṇḍinya	Yajus	2	
(10) Kaṇḍa-Bhāṭṭa	Ananta-Bhāṭṭa	Gautama	Bahv-riśha	2	
(11) Harvā-Bhāṭṭa	Ditto	Bhavadvāja	Yajus	2	Satān varab.
(12) Nāgēv-Adhvarin	Nṛsinha-Bhāṭṭa	Gārgya	Do.	2	Viprōdra.
(13) Yallam-Bhāṭṭa	Purusōttama-Bhāṭṭa	Do.	Do.	2	
(14) Saha-Bhāṭṭa	Ananta-Bhāṭṭa	Bhavadvāja	Do.	2	
(15) Phani-Bhāṭṭa	Narasinha-Sudhā	Gārgya	Do.	2	
(16) Gāḍaga-Bhāṭṭa	Ananta-Bhāṭṭa	Srivata	Do.	2	
(17) Nāga-Bhāṭṭa	Ditto	Gautama	Bahv-riśha	2	Satān varab.
(18) Timma-Bhāṭṭa	Purusōttama-Bhāṭṭa	Gārgya	Yajus	2	Goṇin and Dhimān.
(19) Krishna-Bhāṭṭa	Ananta-Bhāṭṭa	Bhavadvāja	Do.	2	
(20) Śrinat-Timma-Bhāṭṭa	Narasinha-Sudhā	Gārgya	Do.	2	
(21) Ananta-Bhāṭṭa	Nāma-Bhāṭṭa	Kāśyapa	Do.	2	
(22) Kāma-Bhāṭṭa	Kāma-Bhāṭṭa	Do.	Do.	2	Sudhā.
(23) Sōmantha-Bhāṭṭa	Purusōttama-Bhāṭṭa	Gārgya	Do.	2	

Nama.	Father's Name.	Gotra.	Śakha.	Number of Shares.	Remarks.
(48) Tippapa-Bhatta	Mayi-Bhatta	Bhāradvāja	Yajus	1½	Dhīmān.
(50) Nārasinha Sudhi	Rāmōvara-Bhatta	Kāśyapa	Do.	1½	
(51) Brahma-Bhatta	Nāmapa-Bhatta	Kaundinya	Bahv-ṛcha	1½	Sudhi.
(52) Vēnmapa-Bhatta	Liogapa-Bhatta	Kāśyapa	Yajus	1½	Do.
(53) Dharma-Bhatta	Narasinha Sudhi	Kaṇva	Do.	1½	Do.
(54) Kopdu-Bhatta	Ananta-Bhatta	Bhāradvāja	Do.	1½	
(55) Kōṣṛi-Bhatta	Budhi-Bhatta	Parāśara	Do.	1½	
(56) Mudgala-Bhatta	Rāmōvara-Bhatta	Harita	Bahv-ṛcha	1½	
(57) Bāghava	Kaṇvā-Bhatta	Gārgya	Yajus	1½	Dhīmān.
(58) Śingari Sudhi	Anbha-Bhatta	Do.	Do.	1½	
(59) Timmapa Sudhi	Nārāyaṇa-Bhatta	Kaundinya	Do.	1½	
(60) Kṛtiṇ Hiranya-Bhatta	Mudgala-Bhatta	Kāṇva Śyāvāśva		1	
(61) Parvata-Bhatta	Lakṣmapa Manahin	Ātreya	Yajus	1	
(62) Namapa-Bhatta	Kaṇvā-Bhatta	Bhāradvāja	Do.	1	Dhīmān.
(63) Kṛishna-Bhatta	Dharma-Bhatta	Kāśyapa	Do.	1	
(64) Viśvaśātha-Bhatta	Nārāyaṇa-Bhatta	Kaundinya	Do.	1	
(65) Malli-Bhatta	Nāmapa-Bhatta	Do.	Bahv-ṛcha	1	
(66) Kōṣṛi-Bhatta	Ditto	Kandika	Yajus	1	Gupin.
(67) Manahin Giri-Bhatta	Vināyaka-Bhatta	Harita	Do.	1	
(68) Timmapa Sudhi	Kōṣṛi-Bhatta		Bahv-ṛcha	1	The (adopted) son of another Kōṣṛi-Bhatta.
(69) Yalam-Bhatta	Ditto	Gautama	Do.	1	Dhīmān varā).
(70) Bhāra-Bhatta	Gaṅgapa-Bhatta	Śrīvatsa		½	

Among the names specially interesting to us are Rāyasa Veṅkaṭādrī, the son of Timmayy-āmātra, who may certainly be identified with Rāyasam Veṅkaṭādrī, son of Mosalimaḍugu Timmarāja, who is mentioned in the Ūnamāñjērī plates and the Tirupukkuli stone inscription (No. C. 175 of 1916, Madras) as a subordinate of Sadāśiva Rāya. It is clear from our plates, however, that there are two Veṅkaṭādrīs, both sons of ministers of Achyuta by name Timma. The other Veṅkaṭādrī is the son of Kāmarasa Timm-āmātya. The Rāja seems to have provided for some other sons of ministers as well, as indicated by the names 74, 76, 78, 80 and 81.

The names of donees are derived from Sanskrit or from colloquial Kannada corruptions of Sanskrit names. In a few cases only do they seem to be connected with territory. The most interesting of the latter is Mailāpura Mādarasa, which seems to suggest the modern names Mylapore and Madras. The etymology of the word Madras is uncertain, and we may well suggest for Madrasa-patnam of the East India Company's records the origin from some Mādarasa in the 16th century or earlier. In any case our inscription is nearly a century before the foundation of Fort St. George and is probably the oldest record suggestive of a derivation for the word 'Madras.' That Mailapur is one of the very oldest parts of Madras is clear from the Syrian Christian traditions regarding the visit of St. Thomas to that place. [We cannot also ignore the fact that Mailāpura is mentioned as suburb of Bēvinahalli in l. 278 f.—H. K. S.]

It is clear from the above table that of the 80 Brahmans among whom the land was divided 46 were students of the *Yajur-vēda*; 31 of the *Ṛig-vēda*; and of the remaining 3 it is not stated to which *Śākhā* they belonged. This is interesting on account of the non-mention of the *Sāma-vēda* and of the *Sūtras* to which the *Sāma-vēdin* Brāhmaṇas belonged. Among the *gōtras* rare in South India at the present day are Kapi *gōtra* of Nos. 45 and 47; Vasishṭha *gōtra* (No. 38); and Agastya *gōtra* (No. 79). It is possible that Kapi *gōtra* is a contraction of Kapila *gōtra*. These *gōtras* were not unknown in South India in earlier times. We find two names of donees of the Kapi *gōtra* in the Tanjantōṭṭam plates¹ of Pallava Vijaya-Nandivikrama-varman. One of them belongs to the *Āpastamba-sūtra* and the other to the *Prāvachana-sūtra*. In the same plates we have four donees of the Vasishṭha *gōtra*, all of whom are of the *Āpastamba-sūtra*.

After the names of the donees, etc., have thus been given, there appear in the grant the surrounding villages, the neighbouring locality and certain other marks for identifying the places granted. These are recorded in the Kannada dialect, the *Dēsa-bhāṣā*, as it is called in our grant.

The edict was composed by Sabhāpati Svayambhu at the order of the king. The engraver of the grant is Viranāchārya, son of Virāṇa.

TEXT.²

[Metres: vv. 1-4, 6-8, 13, 19-20, 37-41, 43-53, 60-152, 155-9, *Anuṣṭubh*; v. 9, *Harīṣṭ*; v. 36, *Dodhaka*; v. 160, *Śālinī*; vv. 5, 21, 25, 29-30, 32-3, 35, 42, *Sārdūlavikrīḍita*; vv. 5, 8, 10, 11, 22-3, 34, *Sragdharā*; vv. 14, 54, 59, *Indravajrā*; vv. 24, 26, *Malint*; vv. 27-28, 31, *Upendravajrā*; vv. 55-8, *Vasantatilakā*.]

First plate.

1 श्रीगणाधिपतये नमः । नमस्तुंगशिरधुविचंद्रचामरचार-

2 वे । त्रैलोक्यनगरारंभमूलस्तंभाय शंभवे ।[१*] हरेर्लीलावराहस्य³ दं-

¹ *South-Indian Inscriptions*, Vol. II, Pt. V, p. 534.

² From the ink-impressions.

³ Another reading is °वराहस्य, as we find in "Conjeeveram plates of Krishṇadēva-Rāya" published by us (*Ep. Ind.*, Vol. XIII, pp. 123 ff.). [But the plate has there °वराहस्य, perhaps an error for °वराहस्य.—H. K. S.]

- 3 द्वादंङः स पातु वः । हेमाद्रिकलशा यत्र धात्री कृत्रयियं दधौ ।[२*]
 कल्याणा-
 4 यास्तु तद्वाम प्रत्युहतिमिरापहं । यद्गजोप्यगजोद्भूतं हरिणापि च पू-
 5 ज्यते ।[३*] अस्ति चीरमयादेवैर्मध्यमानाम्हावुधेः । नवनीतमिवोद्भू-
 6 तमपनीततमी महः ।[४*] तस्यासोत्तनयस्तपोभिरतुलैरन्वयनामा बु-
 7 धः पुण्यैरस्व पुरुरवा भुजवलैरायुद्विषां^१ निघ्नतः । तस्यायुर्नहुषीस्व
 8 तस्य परुषो युडे ययाति[*] क्षितौ (i) स्यातस्तस्य तु तुर्वसुर्वसुनिभः श्रीदे-
 9 वयानीपतेः ।[५*] तद्वंशे देवकीजानिर्दिदोपे तिमभूपतिः । यशस्वी तुलुवे-^२
 10 द्रेषु यदोः कृष्ण इवान्वये ।[६*] ततोभूदुक्कमाजानिरोश्वरक्षितिपा-
 लकः । अ-
 11 त्वासमगुणभ्रंशं मौलिरत्नं महीभुजां ।[७*] सरसादुदभूतस्मात्तरसाव-
 12 निपालकः । देवकीनन्दनात्कामो देवकीनन्दनादिव ।[८*] विविधसुकृतोद्वा-
 13 मे रामेश्वरप्रमुखे सुहृद्मदितद्वदय[*] स्थाने स्थाने व्यधत्त यथाविधि । बु-
 14 धपरिवृतो नानादानानि यो भुवि षोडश त्रिभुवनजनोद्भूतं स्मीतं
 15 यशः पुनरुक्तयन् ।[९*] कावेरीमायु बध्ना बह्वलजलरयां तां विलंघ्यैव
 16 शत्रुं जीवग्राहं गृह्णीत्वा समिति भुजवलात्तंचराज्यं तदीयं । कृत्वा
 श्रीर-
 17 गपूर्वं तदपि निजवसे^३ पट्टणं यो बभासे ।^४ कीर्त्तिस्तंभं निखाय त्रिभुव-
 18 नभवनस्तूयमानापदानः ।[१०*] चेरं चोलं च पांड्यं तमपि च मधुरावक्त्रं
 19 मानभूषं वीर्योदयं तुरुष्कं गजपतिनृपतिं चापि जित्वा तदन्यान् ।
 20 आगंगातीरलंकाप्रथमचरमभूभृत्तटांतं नितांतं ख्यातः क्षीणोपतो-
 21 नां सज्जमिव शिरसां शासनं यो व्यतानीत् ।[११*] तिप्पाजीनागलादेव्यैः^५
 की-
 22 सन्ध्याश्रीसुमित्रयोः । देव्योरिव नृसिंहेंद्रात्तस्मात्पंक्तिरथादिव ।[१२*] वीरौ
 23 विनयिनौ रामलक्ष्मणाविव नन्दनौ [१*] जातौ वीरनृसिंहेंद्रकृष्णरायभ-
 24 ञ्जीपतौ ।[१३*] रंगक्षितीन्द्राच्युतदेवरायौ रक्षाधुरीणाविव रामकृष्णौ । वो-
 25 वांविकायां नरसक्षितीन्द्रादुभावभूतान्मुरगेंद्र^६सारी ।[१४*] वीरश्रीनार-

^१ Read °रायुद्विषां.^२ Read प्र.^३ Read श्रीः.^४ Read वं.^५ Omit stop.^६ Read श्री.^७ The same reading is found in the Krishnapuram plates of Sadasiva-Raya (*Ep. Ind.*, Vol. IX). The British Museum plates have मृतान्मुरगेंद्र. Prof. Kielhorn corrects this into मूर्ता नरकेंद्र, while Dr. Sten Konow proposes *मामुरगेंद्र. The last seems to be the best reading.

- 26 श्रीनारसिंहः स विजयनगरे रत्नसिंहासनस्थः कीर्त्या नीत्या निरख-
 27 नृगनलनहुषानध्यवन्धामथान्धान् । आसेतोरासुमेरोरवनिसुर-
 28 नुतः स्वैरमाचोदयाद्रेरापाद्याचलांतादखिलहृदयमापज्यं राज्यं
 29 शशास ।[। १५*] नानादानान्यकार्पास्किनकसदसि यः श्रीविरूपाक्ष-
 देवस्थाने
 30 श्रीकालहस्तीशितुरपि नगरे वैकटाद्री च कांच्या । श्रीशैले शोणशैले

Plate II.

- 31 महति हरिहरेहोबले संगमे च (।) श्रीरंगे कुंभघोणे इततम-
 32 सि महानंदितोर्थे निवृत्तो ।[। १६*] गोकर्णे रामसेतौ जगति तदितरेष्व-
 33 प्यशेषेषु पुण्यस्थानेष्वारव्यनानाविधवहलमहादानवारिप्रवाहैः ।
 34 यत्सोदंचतुरंगः(।)प्रकरस्वररजः(।)शुष्यदंभोधिभग्ग(।) आभृत्यचक्रिदौ-
 35 द्यत्तरत्कुलिशधरोत्कांठिता कुंठिताभूत् ।[। १७*] ब्रह्मांडं विश्वचक्रं घटमुदि-
 36 तमहाभूतकं रत्नधेनुं (।) सप्तांबोधोद्य कल्पचितिरुहलतिके कांचनीं
 37 कांभधेनुं । स्वर्णक्ष्मां योहिरण्याश्वरथमपि तुलापूरुषं गोसहस्रं । हेमा-
 38 थं हेमगर्भं कनककरिरथं पंचलांगल्यतानीत् ।[। १८*] प्राज्यं प्रशास्य
 निर्वि-
 39 ष्णं राज्यं द्यामिव शासितुं । तस्मिन् गुणेन विख्याते क्षितेरिंद्रे दिवं
 गते ।[। १९*] ततोप्य-
 40 वार्यवोर्यः[*] श्रीकृष्णरायमहीपतिः । विभर्त्ति मणिकेयूरनिर्विशेषं महौ सु-
 41 जे ।[। २०*] कीर्त्या यस्य समंततः प्रसृतया विश्वं रुचैष्यं व्रजे-
 दिव्याशंख पुरा पुरा-
 42 रिरभवद्भालिचणः प्रायशः । पद्माक्षोपि चतुर्भुजोऽजनि चतुर्वक्त्रोद्भवपद्म-
 43 भूः (।) कालो खड्गमधाद्रमा च कमलं वोणां च वाणी करे ।[। २१*]
 शत्रूणां वासमेते द-
 44 दत इति रुपा किं नु सप्तांबुराश्रीनानासेनातुरंगदुटितवसुमतीधूलिका-
 45 पालिकाभिः । संशोष्य स्वैरमेतव्यतिनिधिलक्ष्मिणिका यो विधत्ते (।) ब्रह्मां-
 46 ङ्खर्णमेरुप्रमुखनिजमहादानतोयैरमेयैः ।[। २२*] स्तुत्यौदार्यं सुधीभिस्त वि-
 47 जयनगरे रत्नसिंहासनस्थः आपालान्कृष्णरायचितिपतिरधरोक्त्य
 48 नीत्या नृगादीन् । आ पूर्वाद्रेरधास्तचितिथरकटकादा च हेमाचलांता-

* Omit one श्रीनार.

* Read 'वक्त्रोद्भव'.

* Read 'सुलक्ष्मिणिका'.

* Read 'आ'.

* Read 'तु'.

- 49 दा सेतोरर्धिसार्धयमिह बहलोकस्य कीर्त्या बभासे ।[२३*] कृतवति
सुरलो-
50 कं क्षणराये निजांशं^१ तदनु तदनुजन्मा पुण्यकर्माच्युतेन्द्रः । अखिलम-
51 वनिलोकं स्वांशमेत्यारिजेता विलसति हरिचेता विद्वदिष्टप्रदाता ।
[२४*] अ-
52 भीदेन निपोवमानसलिलोगस्थेन पीतोकि^२तस्तप्तो राघवसायकाम्नि-
53 शिष्यया संतप्यमानः सदा । अंतस्त्वैवंडवामुखानलशिखाजालैर्विभुष्को
54 ध्रुवं यद्दानां बुरं बुधिरयं पूर्णः समुद्योतते ।[२५*] समजनि नरपालः
सत्वध-
55 मंप्रतिष्टो^३ विजयनगरराजद्रुसिंहासनस्यः ।[२६*] कृमनलनडुपादीबोध-
56 यद्वाजनीत्या निरुपमभुजवीर्योदायंभूरच्युतेन्द्रः ।[२६*] चितिप्रतिष्ठापित-
कीर्त्ति-
57 देहे प्राप्ते पदं वैष्णवमत्युतेष्टे^४ । अन्त्यास्य भद्रासनमस्य सूलुवीरो बभौ वै-
58 कटदेवरायः ।[२७*] प्रशास्य राक्षं प्रशवांस्वरूपे विद्वन्निधौ वैकटराय-
भूपे । अ-
59 भागवेयादचिरात्प्रजानामाखंडलावासमवाधिरुडे ।[२८*] तिमांवावर-
गर्भमौ-

Plate II; side ii.

- 60 शिकमणी रंगचितींद्रात्मजः क्षत्रालंकरणेन पालितमहाकर्णा-
61 दराज्यश्रिया । शौर्योदायं दयावता स्वभगिनोभक्षा^५ जगन्नायिना^६ (i) राम-
62 आपतिनाप्यमात्यतिलकैः क^{१०}साभिषेकक्रमः ।[२९*] श्रीविद्यानगरो-
ललामनि
63 महासा^{११}म्राज्यसिंहासने संतानद्वुरिव स्फुरन्मुरगिरौ संहृत्य विद्वेषिणः ।
64 सा सेतोरपि वा हिमाद्रि रचयन्नाम्नो निजाज्ञाकरान्धर्वा^७ पाक्षयते सदाशि-
65 वमहारायचिराय चमां ।[३०*] विख्यातविक्रांतिनयस्य यस्य पद्मा-
भिषेके गिय-
66 तं प्रजानां । आनंदजाप्यैरभिषिच्यमाना देवीपदं दशयते शरित्री ।
[३१*] गोत्रो-

^१ The reading elsewhere is नितानं.

^२ Read जिह्वा.

^३ Read घनां बुरं बुधि.

^४ Read डी.

^५ Read हा.

^६ Read "च्युतेष्टे.

^७ Read प्रसवा.

^८ Read "भक्षा.

^९ Read जगन्नायिका.

^{१०} Read कृमा. The reading here may be justified by the rule रक्षवीरभेदः

^{११} Read सा.

- 67 चरविशारदं कुवलयपीडापहारोदुर (i) सत्यायत्तमतिं समस्तसुम-
 68 नस्तोमावनैकायनं [1*] संजातधृतिभूरुचिं सविजयं संनंदकञ्चीभरं (i)
 69 यं शंसन्ति यशोदयांचितगुणं कृष्णावतारं वृद्धाः ।[३२*] विख्यातं
 बहुभोगयु-
 70 गविभवैरुहामदानोदुरं (i) धर्मेण धृतिमावतोपि भुवने दत्तं प्रजारक्ष-
 71 णे । प्राप्तां यस्य भुजं भुजंगमहिष्ठिदंतिकूर्मोपमं पातिब्रत्यपताकिके-
 72 ति धरणी^१ जानंतु सर्वे जनाः ।[३३*] यत्सेनाधूलिपाली शकम-
 शकसमुच्चाटने
 73 धूमरेखा रोमाली कीर्तिवध्वा इव भुवनमिदं सर्वमंतर्वहंत्याः । वेणी ना-
 74 णीयश्रीव^२ प्रकटितविह्वतेर्वीरलक्ष्म्या रणाग्रे (i) शाल्ये जीमूतपङ्क्ति^३
 किल सक्-
 75 लखलस्तोमदावानलानां ।[३४*] तुंगामेव दयां पदांबुजयुगं शोणं च
 कृष्णां तनुं
 76 रत्नागोलयितां^४ त्रिवेणिमनघां शोचा^५ गिरं नमंदां [1*] तीर्थानीति समा-
 वहत्य-
 77 वयवैः शेषाद्रिवासी विभुः प्रायो यस्य विशेषभक्तिमुदितः पद्मभिषेक-
 त्रिये ।
 78 [1३५*] वो^६षधिपत्युपमायितगंडस्तोषणरूपजितासमकांडः [1*] भावेगीतपुवरा-
 79 यरगंडः पोषणनिर्भरभूनवखंडः ।[३६*] राजाधिराजविरुद्धो राज-
 राजसमां-
 80 ह्वतिः । स्वाराजराजमान(ः)त्री[1*] श्रीराजपरमेस्वरः ।[३७*] मूर्धराय-
 रगंडांको मेह-
 81 लंघियशोभरः । शरणागतमंदारः पररायभयंकरः ।[३८*] करदाखि-
 लभूपा-
 82 लः परदारसहोदरः । हिंदुरायसुरत्राण इंदुवंशशिखामणिः ।[३९*]
 गजी-
 83 घगंडमेहंडो^७ हरिभक्तिसुधानिधिः । वर्धमानापदानश्रीरर्हनारीन-
 84 टेवरः ।[४०*] इत्यादि विषदैर्वदितव्या नित्यमभिष्टुतः । 'कांभोज-
 भोजका-

^१ Read 'श'.

^२ Read 'श्री'.

^३ Read 'यश्रीव'.

^४ Read 'यान्ये...पंक्ति'.

^५ Read 'विधा'.

^६ Read 'वीणा'.

^७ Read 'श्री'.

^८ This reading seems to be better than that in the Krishnadyksham plates, which read "हरीभक्तमेहंडो",
^९ Read 'कांभोज'.

- 85 लिंगकरहाटादिपार्थिवैः साविदल्लपदं प्राप्तेः संदर्शितवृत्तपोपदः ।[४१*]
 86 सोयं भीतिविशारदः सुरतरुस्फडालविश्राणनः सर्वोर्वीशनतः स-
 87 दाशिवमहारायल्लमानायकः । बाह्यावगदनिविशेषमखिलां स-
 88 वंसहामुहहन्विद्वज्जाणपरायणो विजयते वीरप्रतापोन्नतः ।[४२*] गु-
 89 णाश्ववेदशीतांशुगणिते शकवत्सरे । वर्षे विरोधिकृत्वाञ्चि मा-

Third plate; side i.

- 90 सि चापाटनामनि ।[४३*] पक्षे वलक्षेपु[प्ये][क्षे*] हादश्यामिन्दुवासरे ।
 91 तुंगमद्रानदीतीरे विट्टलेश्वरसंनिधौ ।[४४*] नानाशाखाभिधागो-
 92 वसूत्रेभ्यश्चास्त्रवित्तया । विख्यातेभ्यो द्विजातिभ्यो वेदविद्भ्यो विशे-
 93 षतः । [४५*] वक्त्रिणे हस्तिनावल्याम्बोकेऋवडिनाडुके । रौडकुं दीयसी-
 94 मायामपि विख्यातिमाश्रितं ।[४६*] ग्रामाहुडूरुनाम्नोपि प्राचं सोमन-
 95 हक्त्रितं^१ । जालोहक्यभिधाहामाहृत्तिणस्यां दिशि स्थितं ।[४७*]
 जालोह-
 96 क्लीकारटिकग्रामयोरुभयोरपि । सीमांतात्संयुतादाशां पश्चि[मां*]-
 97 समुपाश्रितं ।[४८*] ग्रामात्कारिकाभिध्यादुत्तरां दिशमाश्रितं । श्रीम-
 98 द्रामसमुद्राख्यामपरां समुपाश्रितं ।[४९*] पौनापुराभिधानेन ग्राम-
 99 केश समन्वितं । ग्रामं वेविनहृक्यास्थं सर्वसस्योपशोभितं ।[५०*] स^२-
 100 मान्यं चतुस्त्रीमासंयुतं च समंततः । निधिनिक्षेपपाषाणसिद्धसा-
 101 ख्यज[ला*]न्वितं ।[५१*] अक्षिण्यागामिसंयुक्तं गणभोग्यं सभूरुहं । वापीकूप-
 102 तटाकैश्च करच्छारामैश्च^३ संयुतं ।[५२*] पुत्रपौत्रादिभिर्भोग्यं क्रमादाचंद्रता-
 103 रकं । दानाधमनविक्रीतियोग्यं विनिमयोचित ।[५३*] भूकल्प-
 शास्त्री
 104 प्रथितार्वीटिवुक्कक्षमापोजनि पुण्यशोलः । शङ्काविका तस्य
 105 बभूव पत्नी पुरंदरस्त्रेव पुलोमकान्या^४ ।[५४*] पश्चादग्नेयभुवना-
 106 वन[वारिजाचा]^५ शृंगारराजवदजायत रामराजः । लक्ष्मीस-
 107 मानचरिता ललनामतल्लो लङ्काविका रतिरिवाजनि तस्य
 108 देवी ।[५५*] तस्याधिकैस्समभवत्तनयस्तपोभिश्च श्रीरामराजनृप-
 109 तिश्च शिवंशदीपः । यस्याव्वलन्भुजमहांसि यथा तथासन्नेत्रा-

^१ Read सी.

^२ Read त.

^३ Read °कान्या.

^४ Read सदायु.

^५ Read ज.

^६ Read यु.

^७ Read °कारामैव.

^८ The bracketed letters appear to have been written over as erasure.

- 110 णि वैरिसदृशां¹ च निरञ्जनानि ।[५६*] खैरोपकंठविहृतिसदृशां वि-
 111 शालस्त्रालोऽदूरिततमास्तनयस्तदीयः । अवासवृत्तिरव-
 112 दातगुणानुवर्त्ती श्रीरामराजनरपालमणिसमिधे ।[५७*] यस्मि-
 113 न्प्रशासति महीं जगदेकवीरे भंगो नदीपु² च पक्षपातः । वल्लीपु
 114 पञ्चवरुचिर्वनितारतेषु नीवीविमोचनमभून्नियतं प्रजानां ।[५८*]
 115 इन्दुर्यशोविन्दुरपि प्रतापतेजस्कुलिंगस्त परं पतंगः । कंतु-
 116 श्रिययो यस्य तु चाटुकारः कर्णोधमर्णः करदानवेत्याः ।[५९*]
 सुमतेरस्य

- 117 धीरस्य सुता³मसमतेजसः । सोमवंशावतंसस्य सुकृतस्य मनी-

Third plate; side ii.

- 118 पिणां ।[६०*] आत्रेयगोत्रालंकारमणिर्मनुनयस्थितेः । अंतैववर-
 119 गंडस्य हरिभक्तिसुधानिधिः⁴ ।[६१*] नहुषोपमस्य नानावर्णश्री-
 120 मंडलोकगंडस्य । ऐविरु[द]रायराहुतवेश्यैकभुजंगवि-
 121 रुदभरितस्य ।[६२*] विख्यातविरुदमनियविभाकूलस्य विजयशो-
 122 लस्य । विश्वंभराभृतिस्फुटविद्युतधरणीवराहविरुदस्य ।[६३*] क-
 123 न्यार्नकुलरत्नेन काश्यपीकल्पशाखिना । प्रौढै(टै)ननमलुकेंद्रपू-
 124 र्वपुष्पफलात्मना ।[६४*] वीरेननमलुकेंद्रविजितारातिभूमुजा⁵ ॥
 125 विहिताञ्जलिबंधेन यांचितस्य यशोनिधेः ।[६५*] विनयौदार्य-
 126 गांभीर्यविक्रमावासवेक्षणः⁶ । वीरस्य रामराजस्य विज्ज-
 127 मिमनुपालयन् ।[६६*] परीतः प्रयतैः स्निग्धैः पुरोहितपुरोग-
 128 मैः । विविधैर्विवृष्टैश्चोत्पथिकैरधिकैर्गिरा ।[६७*] सदाशिव-
 129 महारायो माननीयो मनस्विनां । सहिरण्यपयोधारापूर्व-
 130 कं दत्तवान्सुदा ॥[६८*] पञ्चविंश[यु]तं वृत्तिशतं ग्रामेव संक्षिते ।
 वृत्ति-

- 131 संतो विलिख्यन्ते विप्रा क्देतांतपारगाः ।[६९*] कृतसंनिधये ग्रामे क-
 132 पाकूपारचक्षुषे । अर्पिता वृत्तिरेकात्र सुधाहाराय शंभवे ।[७०*]
 विष्ण-

- 133 वे ग्रामदेवाय विश्वरत्नाविधायिने । विधातुं प्रत्यहं पूजां वृ-

¹ Read °सदृशां.

² Read सु.

³ Read मंयो नदीपु पक्षगपु.

⁴ Read सुवा°.

⁵ Read °निधेः.

⁶ Read क्षा. [This correction is unnecessary. A more desirable correction would be °मलुकेंद्र for °मलुकेंद्र.—
 H. K. S.]

⁷ Read या. The preceding aks/ara is confused.

⁸ Read °हमनः.

⁹ Read या.

226

SCALE 40

1114

W. GRIGGS & SONS, LTD., PHOTO-LITH

- 134 तिरिकाव कल्पिता ।[७१*] महामहादेवभट्टश्रीमहारामचंद्रजः । च-
 135 'तुहत्तोरि[हा]प्रोति बह्वचः^१[*] काश्यपान्वयः ।[७२*] महागणपतिस्सू-
 रिश्यो
 136 महारामचंद्रजः । काश्यपान्वयजो हत्तोयतस्रोत्रैहि^२ बह्वचः^३ ।[७३*]
 137 श्रीमहाविष्णुभट्टो महामुत्तलभट्टजः । चतस्रो बह्वचोभ्येति
 138 हत्तीः काश्यपगोत्रजः ।[७४*] श्रीमहाकृष्णभट्टो महामुत्तलभट्ट-
 जः । सार्द्ध-
 139 कवृत्तिमाप्रोति बह्वचः काश्यपान्वयः ।[७५*] श्रीमहारामचंद्रार्यसुनुः
 काश्य-
 140 पगोत्रजः । महागोपालभट्टो हत्ती द्वे बह्वचोभ्युते ।[७६*] रघुनाथसुधीसुनु-
 141 श्रीयपराशरगोत्रजः । हत्तिद्वयमवाप्रोति दत्तभट्टो बह्वचः ।[७७*] आकृति-
 142 विष्णुभट्टस्य सुनुः कौडिन्यगोत्रजः । श्रीनारायणभट्टाख्यो या-
 143 जुषोत्र द्विहत्तिकः ।[७८*] नंदनोनंतभट्टस्य गौतमान्वयसंभवः ।
 144 हत्तिद्वयमवाप्रोति कौडुभट्टो बह्वचः ।[७९*] भारद्वाजान्व-
 145 योद्धतो याजुषोनंतभट्टजः । हत्तिद्वयमिहाप्रोति सर्वाभट्टस्ततां [वरः] ।[८०*]

Plate IV; side i.

- 146 सुनुर्त्तसिंहभट्टस्य याजुषो गार्ग्यगोत्रजः । नागावधानो विप्र-
 147 द्रो हत्तिद्वयमिहाभ्युते ।[८१*] पुरुषोत्तमभट्टस्य नंदनो गार्ग्यगोत्रजः ।
 हत्तिद्व-
 148 यमवाप्रोति यत्तभट्टो याजुषः ।[८२*] नंदनोनंतभट्टस्य भारद्वाजान्वयो-
 द्वयः ।
 149 याजुषशेषभट्टाख्यो हत्तिद्वयमिहाभ्युते ।[८३*] गार्ग्यगोत्रसमुद्धृतो नरसिंह-
 150 सुधीसुतः । हत्तिद्वयमवाप्रोति फणिभट्टो याजुषः ।[८४*] याजुषोनंत-
 भट्ट-
 151 स्य सुनुः श्रीवल्लभगोत्रजः । अत्र गंगणभट्टाख्यो हत्तिद्वयमिहाभ्युते ।[८५*]
 नंदनो-
 152 नत्तभट्टस्य नागाभट्टस्ततां वरः । अत्र द्विहत्तिमाप्रोति बह्वचो गौतमान्व-
 153 यः ।[८६*] पुरुषोत्तमभट्टस्य नंदनो गार्ग्यगोत्रजः । गुणो 'द्विहत्ति-
 को धोमांस्त्रिं-

^१ Read 'तुह' गो.^२ Read बह्वचः.^३ Read 'वै' ति.

- 154 माभटोत्र याजुषः ।[८७*] नंदनोनंतभट्टस्य भारद्वाजान्वयोद्धवः ।
याजुषः कृष्णभ-
- 155 द्वाष्ट्यो वृत्तिद्वयमिहाश्रुते ।[८८*] नरसिंहसुधोसुनु'याजुषो गार्ग्य-
गोत्रजः श्री-
- 156 मत्तिमणभट्टाष्ट्यसुधोत्र द्विवृत्तिकः ।[८९*] सुनुर्नामणभट्टस्य काश्यपान्वय-
- 157 संभवः । याजुषोनंतभट्टाष्ट्यो वृत्तिद्वयमिहाश्रुते ।[९०*] श्रीम[त्का]मण-
भट्टाष्ट्यसु-
- 158 धीः कामणभट्टजः । वृत्तिद्वयमिहाप्रोति याजुषः काश्यपान्वयः ।[९१*]
श्रीमोमना-
- 159 [य]भट्टाष्ट्यः पुरुषोत्तमभट्टजः । कृती द्विवृत्तिमानत्र याजुषो गार्ग्यगोत्र-
- 160 जः ।[९२*] सुनुर्लिङ्गणभट्टस्य सुधोरात्रेयगोत्रजः । तिस्माव-
धानी हे वृत्ती या-
- 161 जुषोत्र समश्रुते ।[९३*] सुनुर्द्वेवणभट्टस्य बहुचो गार्ग्यगोत्रजः
धीमांस्तिम-
- 162 णभट्टाष्ट्यो वृत्तिद्वयमिहाश्रुते ।[९४*] भारद्वाजान्वयोद्धूतो धर्मा-
भट्टतनू-
- 163 द्ववः । बहुचो जंनिभट्टाष्ट्यो वृत्तिद्वयमिहाश्रुते ।[९५*] सुनुस्ति-
प्पणभट्ट
- 164 स्य याजुषः काश्यपान्वयः । वृत्तिद्वयमिहाप्रोपि कामाभट्टो महा-
- 165 मतिः ।[९६*] पराशरान्वयोद्धूतो वृश्चिभट्टस्य नंदनः । याजुषो वृश्चि-
- 166 भट्टोत्र सूखिर्यो द्विवृत्तिकः ।[९७*] सुनुर्नामणभट्टस्य सुधीः कौडि-
- 167 न्यगोत्रजः । श्रीमत्तिस्मणभट्टाष्ट्यो बहुचोत्र द्विवृत्तिकः ।[९८*]
धर्मा-
- 168 भट्टतनूजश्रीभारद्वाजान्वयोद्धवः । कृती हिरण्यभट्टाष्ट्यो व-
- 169 हृचोत्र द्विवृत्तिकः ।[९९*] सुनुस्तिप्पणभट्टस्य काश्यपान्वय-
संभवः । या-
- 170 जुषः कृष्णभट्टाष्ट्यो वृत्तिद्वयमिहाश्रुते ।[१००*] सुनुस्तिमणभट्टस्य
भारद्वा-
- 171 जान्वयोद्धवः । श्रीरामेश्वरभट्टाष्ट्यो याजुषोत्र द्विवृत्तिकः ।[१०१*] भार-
द्वाजा-
- 172 न्वयोद्धूतस्मर्वाभट्टतनूद्ववः । याजुषोनंतभट्टाष्ट्यो वृत्तिद्वयमिहाश्रु-

173 ते ।[१०२*] श्रीमत्तिमणभट्टाख्यो धीमांस्तिप्पणभट्टजः । काश्चपा-
न्ययसंभूतो या-

Plate IV; side ii.

174 जुषोव द्वित्तिकः ।[१०३*] याजुषो भैरवाभिख्यसुधीर्भैरवभट्ट-
175 जः । द्वित्तियमिहाप्रोति कौडिन्यान्वयसंभवः ।[१०४*] गोपालपंडि-
176 तश्रेष्ठमालीपंततनूद्वजः । बह्वचोर्वैति वृत्ति द्वे श्रीपराशरगो-
177 व्रजः ।[१०५*] कौडिन्यगोव्रसंभूतो लक्ष्मीधरमनीषिजः । बह्वचो
हरि-

178 भट्टाख्यो द्वित्तियमिहाश्रुते ।[१०६*] यज्ञभट्टोचो^१ धोमान्वसिष्ठान्वयसंभ-
179 वः । अंतंभट्टाद्वयो द्वित्तियमवैति बह्वचः ।[१०७*] नंदनो भीडु-
भट्टस्य जा-

180 मदद्वान्वयोद्वजः^२ । बह्वचोवाश्रुते द्वित्तियं गणपतिस्तुधीः ।[१०८*] कौडि-
181 न्यगोव्रजस्तुनुरचिभट्टस्य याजुषः । गुणो द्वित्तित्तमानव सोम-
182 भट्टो द्विजोत्तमः ।[१०९*] भारद्वाजान्वयोद्वृतो यज्ञभट्टस्य नंदनः ।
बह्वचो

183 पेदिभट्टाख्यो द्वित्तियमिहाश्रुते ।[११०*] नंदनः कौडुभट्टस्य नागा-
184 भट्टस्ततां वरः । द्वित्तियमिहाप्रोति बह्वचो गौतमान्वयः ।[१११*]
श्रीरा-

185 मेश्वरभट्टस्य स्तुः कौशिकगोव्रजः । याजुषश्श्रीधरसुधीरव
186 सार्धैकवृत्तिकः ।[११२*] नंदनो गिरिभट्टस्य नागाभट्टस्ततां वरः ।
सार्धैक-

187 द्वित्तित्तमानव याजुषः कौशिकान्वयः ।[११३*] पुरुषोत्तमभट्टः^३ श्रीरामे-
188 श्वरमनीषिजः । सार्धैकवृत्तित्तमानव याजुषः कपिगोव्रजः ।[११४*]
धीमां-

189 स्तिमणभट्टाख्यो गिरिभट्टात्मसंभवः । कौशिकान्वयशो वृत्तिं सा-
190 र्धैकां याजुषोश्रुते ।[११५*] श्रीरामेश्वरभट्टस्य नंदनः कपिगोव्रजः ।
[ना]

191 गामट्टोव्र सार्धैकवृत्तित्तमाप्रोति याजुषः ।[११६*] भारद्वाजान्वयोद्वृतः क-
192 सवामभट्टनंदनः । याजुषो वामनसुधीरव सार्धैकवृत्तिकः ।[११७*]
193 भारद्वाजान्वयस्तुनूर्मायिभट्टस्य याजुषः । धीमांस्तिप्प-

^१ Read यज्ञभट्टात्मजी.

^२ Read अनं, the name Anantabhatta being more common than Antam.^३

^३ Read जामदग्न्यान्वयो.

- 194 णभट्टोव साहेकाहत्तिमश्रुते ।[११८*] श्रीरामेश्वरभट्टस्य नन्द-
 195 नः काश्यपान्वयः । याजुषो नारसिंहाख्यसुधोस्माहे-
 196 कवृत्तिकः ।[११९*] स्रुनुर्नामणभट्टस्य सुधीः कौडिन्यगोत्रजः । ब्र-
 197 ह्माभट्टोव साहेकवृत्तिमानत्र बह्वचः ।[१२०*] स्रुनुर्गिण-
 198 भट्टस्य याजुषः काश्यपान्वयः । सुधीः प्रोमणभट्टोव सा-
 199 हेकां वृत्तिमश्रुते ।[१२१*] नारसिंहसुधोस्रुनुः याजुषः कण्वगोत्रजः ।
 200 धर्माभट्टो भवत्यत्र सुधोस्माहेकवृत्तिकः ।[१२२*] नन्दनोनंतभट्ट-
 201 स्य भारद्वाजान्वयोद्भवः । साहेकवृत्तिमात्राति कौडुभ-
 202 ट्टोव याजुषः ।[१२३*] नन्दनोवृत्तिभट्टस्य ओपराशरगोत्रजः ।

Plate V; side i.

- 203 कोनिरिभट्टस्माहेकवृत्तिमानत्र याजु-
 204 षः ।[१२४*] श्रीरामेश्वरभट्टस्य नन्दनो हरितान्वयः । वृत्ति-
 205 सुद्वलभट्टोव साहेकां बह्वचोश्रुते ।[१२५*] धोमावाघवभट्टाख्यः
 206 कसवाभट्टनन्दनः । साहेकवृत्तिमानत्र याजुषो गार्ग्य-
 207 गोत्रजः ।[१२६*] स्रुनुर्भट्टभट्टस्य गार्ग्यगोत्रसमुद्भवः । याजु-
 208 षः शिंजरिसुधोरत्र साहेकवृत्तिकः ।[१२७*] श्रीनारायणभट्ट-
 209 स्य स्रुनुः कौडिन्यगोत्रजः । याजुषस्तिमणसुधोरत्र साहे-
 210 कवृत्तिकः ।[१२८*] स्रुनुर्मुद्वलभट्टस्य काण्वरश्मावाघगोत्रजः ।
 211 कृती हरिष्यभट्टोव वृत्तिमेकां समश्रुते ।[१२९*] सुधीः पर्वतभ-
 212 ट्टाख्यो लक्ष्मणाख्यमनीषिजः । याजुषोवाश्रुते वृत्तिमेका-
 213 मात्रेयगोत्रजः ।[१३०*] भारद्वाजान्वयोद्भूतः कसवाभट्टनन्द-
 214 नः । धोमानमणभट्टाख्यो याजुषोवैकवृत्तिकः ।[१३१*] काश्य-
 215 पान्वयसंभूतो धर्माभट्टनूद्भवः । याजुषः कृष्णभट्टोव
 216 वृत्तिमेकां समश्रुते ।[१३२*] श्रीनारायणभट्टस्य स्रुनुः कौडि-
 217 न्यगोत्रजः । श्रीविश्वनाथभट्टाख्यो याजुषोवैकवृत्ति-
 218 कः ।[१३३*] स्रुनुर्नामणभट्टस्य कौडिन्यान्यसंभवः । मज्जिभ-
 219 ट्टो भवत्येकवृत्तिमानत्र बह्वचः ।[१३४*] स्रुनुर्नामणभट्टस्य
 220 याजुषः कौशिकान्वयः । सुणी कोनिरिभट्टाख्यो वृत्तिमे-
 221 कामिहाश्रुते ।[१३५*] मनीषो गिरिभट्टाख्यश्रीविनायकभट्ट-
 222 जः । वृत्तिमेकामिहाश्रुति याजुषो हरितान्वयः ।[१३६*] स्रुनुः

- 223 कोनिरिभट्टस्य सुधोः कोनिरिभट्टजः । बह्वचस्तिमण-
 224 सुधीरवैकां हृत्तिमश्रुते ।[१३७*] गीतमान्वयसंभूतो बह्वचो
 225 धीमतां वरः । यत्तंभट्टोश्रुतेवैकां हृत्तिं कोनिरिभट्ट-
 226 जः ।[१३८*] सुतुर्गणभट्टस्य श्रीवत्मान्वयसंभवः । भानुभट्टो
 227 भवत्यहं हृत्तिमानव याजुषः ।[१३९*] हरितान्वयसंभूतः श्री-
 228 मत्तक्षरसालजः । याजुषश्चोतिंमरसस्तिपाहृत्तिमिहा-

Plate V: side ii.

- 229 श्रुते ।[१४०*] कौडिन्यगोत्रसंभूतश्चोविरुपरसालजः ।
 230 बह्वचोव विपाहृत्तिमेति हंपरससुधोः ।[१४१*] याजुषस्तिं-
 231 मयामाल्यनंदनो हरितान्वयः । रायसश्चोविकटादिर-
 232 वैकां हृत्तिमश्रुते ।[१४२*] हरितान्वयजश्चोमइसवामाल्यनं-
 233 दनः । बह्वचो धीरपामाल्यो हृत्तिमेकामिहाश्रुते ।[१४३*] भारद्वा-
 234 जान्वयोऽश्रुतश्चोवीरमरसालजः । बह्वचः श्रोतिंमरसो
 235 धीमानवैकहृत्तिमान् ।[१४४*] चेडिकेवसवामाल्यसूनुः कौडि-
 236 न्यगोत्रजः । बह्वचस्तिमपामाल्यो हृत्तिमेकामिहाश्रुते ।[१४५*]
 237 वैकटाद्रिः कामरसतिमयामाल्यनंदनः । बह्वचो हृत्ति-
 238 मवैकां भारद्वाजान्वयोश्रुते ।[१४६*] बह्वचस्तिमयामाल्यो नंज-
 239 यामाल्यनंदनः । हृत्तिमेकामिहाप्रोति काश्यपान्वयसं-
 240 भवः ।[१४७*] बह्वचः श्रीवैरसनंदनोगस्त्यगोत्रजः । अत्रैका-
 241 मश्रुते हृत्तिं श्रीमडूमरससुधोः ।[१४८*] सुकुवागिलकोनिरि-
 242 देवजो हरितान्वयः । गणपत्याह्वयोमाल्यो बह्वचोवैकहृ-
 243 त्तिकः ।[१४९*] कौडिन्यगोत्रजः काण्वो वसवामाल्यशेखरः
 श्रीदे-
 244 चिराजवसवराजजोवैकहृत्तिकः ।[१५०*] भारद्वाजान्वयो मै-
 245 लापुरमादरसालजः । याजुषो वसवप्योत्र हृत्तिमेकां
 246 समश्रुते ।[१५१*] ग्रामस्थस्यैव सीमानो दिक्षु प्राच्यादिषु क्रमा-
 247 त् । तत्र चिह्नसमायुक्ता लिख्यन्ते देशभाषया ।[१५२*] पीनापुर-
 248 वैव ग्रामशाससहितवाद वेविनहक्किग प्रतिनामवा-
 249 द रामसमुद्रवैव सर्वमान्याग्रहारद वक्केयद विवर
 250 मूडक्किगे रवुडकुंदीदारि आ दारिगे दक्षिण कोडिहक्कुद व-
 251 ङि सोकुक्किन वक्किय वामनमुद्रे । अदके दक्षिण चंद्रन-
 252 हक्कियिंद बंद दारि वक्किय वामनमुद्रे । अदके पडुववु

Plate VI; side i.

- 253 चंद्रनहक्कीदारि आ मुंदे वेकसर आ मुंदे कारडिकेसीमे होदि-
 254 द हक्कद बकिय वामनमुद्रे । अजिंदं मुंदे कोत्तिकवागि दक्षि-
 255 ण होक्क कारडिकेयलु तिंमरसमान्यद बकिय वामन-
 256 मुद्रे । अदके पश्चिम कारडिकेयिंद बंद दारि बकिय वाम-
 257 नमुद्रे । अदके पश्चिम कारडिकेवेविनहक्किपोनापुरहोल
 258 कूडिद सुगुडे बकिय वामनमुद्रे । अजिंदं दक्षिण कारडि-
 259 केयिंद वेविनहक्किगे बंददारि बकिय वामनमुद्रे । अद-
 260 के दक्षिण मंग्योडीवेन्हे बकिय वामनमुद्रे । अजिंदं दक्षिण
 261 कारडिकेयिंदलु नविलिगे होद दारोवकियण काल्वेक-
 262 हेमेलण बकिय वामनमुद्रे । अजिंदं मुंदे पश्चिम कार-
 263 टिकेचेकूरवेविनहक्किमुगुड्डे लोकीवेन्हेयोक्कण वाम-
 264 नमुद्रे लिंगमुद्रे । अजिंदं पश्चिमवेकियहुडुगुहुवकि-
 265 य वानमुद्रे¹ । अजिंदं मुंदे ग्रामके दक्षिण पट्टणद मार्ग [1^{*}] अ-
 266 जिंदं मुंदे पश्चिमदलु चेकूर गौडनमान्यद बकिय नवि-
 267 लिमार्गदोक्कण वामनमुद्रे । अदके पश्चिम ग्रामके नैर्-
 268 ल्य हुणिसेगुहुवकिय सोमनहक्कीचेकूरवेविनहक्कीसुगु-
 269 ड्डेबकिय वामनमुद्रे करसगट्टु अदके उत्तर सोमनहक्किंदं
 270 वेवि[न]हक्कि(गे) बंद मार्गद बकिय वामनमुद्रे । अजिंदं मुंदे
 271 उत्तर उप्पारंर होलद बकिय वामनमुद्रे । अदके उत्त-
 272 र जडगोडवसवन होलद बकिय वामनमुद्रे । अदके
 273 उत्तर हुडुगुड्डिन बकिय वामनमुद्रे । अदके उत्तर ग्रा-
 274 मके पश्चिम सोमनहक्किवेन्हे बकिय [वा]मनमुद्रे । अजिं-
 275 दं पश्चिम कोतलवागिगुडूरसोमनहक्किवेविनहक्कि-
 276 सुगुडे बकिय वामनमुद्रे लिंगमुद्रे । अजिंदं उत्तर त-
 277 क्वारर होलद बकिय वेकियगुडि[न] मेले पश्चिमदक्षि

Plate VI; side ii.

- 278 वामनमुद्रे¹ । अजिंदं सुत्तर मैसापुरगुडूरहोलद मेरैय व-
 279 कि अरयमेलण वामनमुद्रे । अजिंदं उत्तर मैसापुरविंद-
 280 लु वेविनहक्किगे बंद दारियोक्कण वामनमुद्रे । अदके

¹ Read वामनमुद्रे.² Read उ.³ Read 'लिं.

vi.

vii.

230
232
234
236
238
240
242
244
246
248
250
252

...
...
...
...
...
...
...
...
...
...
...
...

254
256
258
260
262
264
266
268
270
272
274
276

...
...
...
...
...
...
...
...
...
...
...
...

viii.

ix.

278
280
282
284
286
288
290
292
294
296
298
300
302

...
...
...
...
...
...
...
...
...
...
...
...
...

304
306
308
310
312
314
316
318

...
...
...
...
...
...
...
...
...

- 281 उत्तर गाणद पर्वतन होलन होदिद मैलापुरद सनवोव
 282 मङ्गरसन होलद वक्रिय वामनमुद्रे [1*] अदके उत्तर रेखिय*]लप
 283 चिकरामयलपन होलन होदिद वक्रिय वामनमुद्रे । अलिंद
 284 उत्तर मैलापुरदिंद बंद हकुद वक्रिय वामनमुद्रे । अलिंद उत्त-
 285 र हकुद आचयलि ग्रामके वाय[व्य] मैलापुरजालीहकीवेविन-
 286 हकीमुगुडेदारीवक्रिय वामनमुद्रे । अलिंद मूडलु जालीहकी-
 287 यलु रामयदेवर मान्यद वक्रिय वामनमुद्रे । अदके मूडलु ह-
 288 कुद नाल[न] वक्रिय वामनमुद्रे । अदके मूडलु जालीहकीयलु वि-
 289 रूपाक्षदेवरिसे सलुव मान्यद वक्रिय वामनमुद्रे [1*] अलिं-
 290 दं दक्षिण कोत्तकवागि होक था विरूपाक्षदेवर मान्यद
 291 वक्रिय वामनमुद्रे । अलिंद मूडलु ग्रामके उत्तर जालीह-
 292 कीयिंद बंद मार्गद वक्रिय वामनमुद्रे । अदके मूडलु जाली-
 293 हकीयिंद कारटिके होद मार्गदलि वामनमुद्रे । अलिंद
 294 मू[ड]लु जालीहकी नम मेरेयलि वामनमुद्रेगिले यरड [1*] अ-
 295 लिंद दक्षिणवागि होक जालीहकीवेविनहकीपीनापुर-
 296 मुगुडेयलि वामनमुद्रे नकुगिले । अलिंद, मूडलु गह-
 297 दोडियर होलद वक्रिय वामनमुद्रे । अदके मूडलु पीना-
 298 पुरदलि सनवोव तिंमरसहंपरसर मान्यद वक्रिय
 299 वामनमुद्रे ॥ । अदके मूडलु जालीहकीयिंद कीतनूरिगे
 300 होद दारि वक्रिय वामनमुद्रे । अलिंद मूडलु पीनापुर-
 301 दलु रामयदेवमान्यद वक्रिय ग्रामके ईशान्यदलु
 302 पीनापुरजालीहकीमुगुडे वक्रिय वामनमुद्रे । अलिं-

Plate VII.

- 303 दं दक्षिण रामयदेवर होलद वक्रिय 'समकीहकीहो-
 304 लद वक्रिय वामनमुद्रे । अलिंद दक्षिण हुडुविकिय-
 305 गुंडु करियगुंडु । अलिंद दक्षिण वडविनकुद्रे हसुत-
 306 थोकुद्रे वक्रिय वामनमुद्रे । अलिंद दक्षिण ग्रामके
 307 मूडलु रवुडकुंदीदारिय कूडितु ॥
 308 सरससदाशिवरायचितिपतिवर्यस्व कोर्त्ति*धुर्यस्व । शासनमिदं
 309 शरासनदाशरथेरमितहेमदानरते: । [1 १५३*] सदुपदमिति तांभ*शासना-
 310 शासनार्थमहितसदाशिवरायशासनेन । अभणदनुगुणं वचोम-

- 311 द्विजा सरसतरेण सभापतिः स्वयंभूः ।[१५४*] सदाशिवमहारायमास-
नाक्षीरणा-
- 312 अजः । त्वष्टा श्रीवीरणाचार्यो व्यलिखतां समासनं ।[१५५*] दान-
पालनयोर्मध्ये दा-
- 313 नाच्छेद्योनुपालनं । दानात्स्वर्गमवाप्नोति पालनादच्युतं पदं ।[१५६*]
स्वदतादिगुणं
- 314 पुण्यं परदत्तानुपालनं । परदत्तापहारेण स्वदत्तं निःस्फुल्लं भवेत् ।[१५७*]
स्वदत्तां
- 315 परदत्तां वा यो हरेत वसुंधरां । षष्टिं र्ष(व)र्षसहस्राणि विष्टायां जायते
क्रिमिः ।[१५८*]
- 316 एकैव भगिनी लोके सर्वेषामेव भूभुजा । न भोज्या न करग्राह्या विप्रदत्ता
- 317 वसुंधरा ।[१५९*] सामान्योऽयं धर्मस्तुर्लपाणां काले काले पाल-
नीयो भवद्भिः ।
- 318 सर्वानेताम्भाविनः पथिवेन्द्राभूयो भूयो याचते रामचंद्रः ॥ श्री ।[१६०*]
श्रीविरूपाक्ष*

ABSTRACT OF CONTENTS.

- (Verses 1-3) Invocation to Śambhu, the Varāha avatāra of Viṣṇu, and Gaṇeśa.
- (Vv. 4-8) The genealogy as far as Narasa.
- (Vv. 9-11) Praises of Narasa ; his generosity and exploits.
- (Vv. 12 and 13) Mention of Vira-Nṛsiṃha and Kṛishṇa-Rāya as the sons of Narasa by Tippāji and Nāgalā.
- (V. 14) Mention of Raṅga and Achyuta-dēva-Rāya as the two other sons of Narasa by Ōbāmbikā.
- (Vv. 15-19) The conquests of Vira-Nṛsiṃha ; his gifts at the various places of pilgrimage and death.
- (V. 20) Kṛishṇa-Rāya ascends the throne.
- (Vv. 21-23) Praises of Kṛishṇa-Rāya, etc.
- (V. 24) Achyuta, Kṛishṇa-Rāya's brother, succeeds him.
- (Vv. 25 and 26) Praises of Achyuta-Rāya.
- (V. 27) Venkātādēva-Rāya succeeds his father Achyuta.
- (Vv. 28-30) At the death of Venkāta Sadāśiva, the son of Raṅga, the lord of earth, by Timbāmbā, was installed on the throne of Śrī Vidyānagarī by king Rāma of Kārṇāṭa, a brother-in-law of Sadāśiva.
- (Vv. 31-35) Praises of Sadāśiva.
- (Vv. 36-40) The titles of the king.
- (Vv. 41 and 42) Praises continued.

* Read श्री.

* Read श्री.

* Read स्वदत्तादिगुणं.

* In Kannada characters.

(Vv. 43 and 45) In the Saka year *Gur-āra-vēda-tītāmta* (i.e., 1473), according to the *Sālivāhana* reckoning in the year *Virōdhikrit*, in the month of *Āshāḍha*, on the *Dvādaśī* day of the bright fortnight, on Monday (is made the gift) on the banks of the *Tuṅgabhadra*, in the vicinity of *Viṭṭhalēśvara*, to Brahmins of various *gōtras*, *sūtras*, etc., who are well-versed in the *Vēdas*.

(Vv. 46-50) The object of the grant is the village of *Bēvinahalli*, otherwise known as *Rāma-samudra*, with the hamlet of *Ponnāpura*. It was situated in *Raudakundi simā*, in *Kēlavaḍi nāḍu*, in the *vaṭṭa* of *Hastinavati* (*Anegondi*) to the east of *Guḍūru* and *Somanahalli*, to the south of *Jāliballi*, to the west of the borderland between the villages of *Jāliballi* and *Kāraṭika* and to the north of *Kāraṭika*.

(Vv. 51 and 53) The terms of the grant, as commonly seen in all *Vijayanagara* grants.

(Vv. 54-57) The genealogy of the *Āraviti* family down to *Rāma-Rāja*.

(Vv. 58-63) Praises of *Rāma-Rāja*, his titles, etc.

(Vv. 64-68) Mention that the grant was made at the request of *Ainana Malukka*, the son of the chief *Ainana Malukka* of the *Kanyārna* race.

(V. 69) The village was split up into 135 *vr̥ttis*.

(Vv. 70 and 71) Grant to *Śambhū* and *Vishṇu*, the village deities.

(Vv. 72-151) The names of the donees, etc., the shares ranging from 4 to $\frac{1}{2}$ of a share.

(V. 152) The boundaries and certain marks of identification of the places granted are described in the language of the country (*dēśa-bhāṣā*).

(Lines 247-307) Written in the *Kannāḍa* language.

(Vv. 153 and 154) The edict was composed by *Sabhāpati Svayambhu*.

(V. 155) The engraver of the grant *Virāṇa*, son of *Virāṇa*.

(Vv. 156-160) The usual admonitory verses. *Śrī-Virūpākṣa*.

No. 17.—THE KUDIYANTANDAL GRANT OF VĪRA-NRISIMHA : SAKA 1429.

By PROFESSOR S. V. VENKATESWARA, M.A., AND S. V. VISWANATHAN, M.A., KUMBakonam.

The grant is engraved on three copper-plates, bored at the top and secured by a ring. They were discovered by us in the *maṭha* of the *Śaṅkarāchārya* of the *Kāmakōṭi pīṭha* of *Conjeeveram*, who was kind enough to lend them to us for examination and publication in the *Epigraphia Indica*.

The plates measure 7·9 in. by 6·8 in., except in the middle, where they are longer, 10·3 in., on account of the arch at the top. The ring has a diameter of 2·5 in. The holes through which the ring passes have a diameter of 1·6 in. The plates were apparently secured by a seal in the *Vijayanagara* fashion; but the seal was missing in them as handed over to us. All the plates have raised rims. The writing runs throughout across their entire breadth. It is quite legible, except in a few places. The first and third plates are engraved only on one side, the second on both sides. The inscription contains 85 lines in all, excluding the signature at the bottom. The height of each line is 3 in. on the first plate and 2 in. on the others. In the signature the letters are larger than elsewhere.

The language is *Sanskrit*, and the whole inscription is in verse, except the opening invocation to *Gaṇādhipati*. The metres used are those which are generally found in the *Vijayanagara* plates—the *Śārdūlavikrīḍita*, *Anuṣṭubh*, *Śragdharā*, etc. The poetry is of a very low order. The characters are *Nandī-nāgarī*, except the signature, which is in *Kannāḍa* characters, engraved at the bottom of the last plate.

The inscription abounds in orthographical irregularities. Stops are often omitted at the end of a verse, though the half verses are always marked off by a single vertical stroke. The omissions have been marked and supplied in the text below. There are innumerable instances of confusion between the use of the long and the short *i* and *u*. Noteworthy among these are *mula-stambhāya* for *māla-stambhāya* in line 2; *navanitam* for *navanītam* in line 9; *Pururava*^o for *Purūrava*^o in line 12; *Tippāji* for *Tippāji* in line 34; *Śivarupinē* for *Śivarūpinē* in line 72. These mistakes could hardly be due to the ignorance of the engraver, and are partly accounted for by the fact that both long and short vowels are represented by similar kinds of marks over or under letters. The letters *ya*, *va*, *pa*, *ta* and *na* assume forms which are capable of passing into one another. In a few instances the terminations for the Imperfect and the Pluperfect third person singular are left out, e.g., *vyatāni* for *vyatānti* in line 33. As in other plates of the Vijayanagara dynasty, a conjunct consonant is expressed by combining the full form of the first with the secondary form of the second consonant; e.g., *rya*. The confusion of consonants to be compounded is seen in line 41 (*shra* for *rsha*), l. 77 (*vra* for *vea*), l. 84 (*mradyē* for *madhyē*). The influence of the Dravidian languages in the pronunciation of Sanskrit words is clear from *irāja* (for *rāja*) in l. 55, *yidam*^o (for *idam*^o) in l. 80, *Mallanāsāri* and *Virañāsāri* (for *Mallañāchārya* and *Virañāchārya*¹) in ll. 82, 83, and in *Achchuta* (for *Achyuta*) in l. 85.

The inscription is very important, as the first copper-plate record that we have of *Vira-Nṛsiṃha* of the second Vijayanagara dynasty. It makes the king the son of *Narasa Avani-pālaka* by *Tippāji*. This *Narasa*, better known as *Narasa-Nāyaka*, is supposed to be the founder of the Tuluva dynasty. But the plates before us have the genealogy thus:—*Timma Bhūpati*, *Īśvara Kṣhitipālaka*, and *Narasa Avani-pālaka*.

The titles seem to imply that the nearest ancestors of 'Narasa Nāyaka' were ruling kings and not merely local chieftains. The king *Vira-Nṛsiṃhendra*, alias *Vira Sri Nārasimha*, assumes the titles *Rājādhirāja*, *Vira-pratāpa*, etc. It is interesting that *Kṛishṇa-Rāya* is referred to as *mahīpati*, while his brother was yet ruling. This circumstance lends weight to the view that the brothers were ever friendly, and that *Kṛishṇa-Rāya* succeeded to the throne only after the demise of his elder brother *Narasimha*. Cf. *Tasmān guṇēna vikhyātē kṣhitē indrē divanī gatē tatōpyavdrya-vīrya-śrīḥ Kṛishṇa-rāya-Mahīpatiḥ* in the *Udayambakam* grant of *Kṛishṇa-dēva-Rāya* (Pl. II, Side 1, ll. 8, 9). At the same time this passage enhances the credibility of the tradition embodied in the *Kṛishṇarājaviṣayamu* of *Kumāra-Dhārjaṭi*, a Telugu poet who lived later in the same century. He states that *Kṛishṇa-Rāja* succeeded his father directly. It is quite possible that *Narasa* left the throne to his sons, who were both apparently crowned in his lifetime.

The village granted is *Kuḍiyāntaṇḍal* in the Chingleput district. The boundaries of the village are not clearly engraved on the grant. The village is situated in the *Varakkāṭaru* *śimā*, *Kālyāṇ-kōshṭha*, *Kānci nāgu*, *Paḍaviḍu rājya*, in *Jaya(mkonda)-Chōla maṇḍala*. It was bounded on the north by *Kaḷakāṭṭaru*, on the east by *Śurittiluru*, on the south by *Śittilep-pākkam*, and on the west by *Kunantāgal*.

The donee is *Mahādēva Sarasvatī*, the disciple of *Sadāśiva Sarasvatī*, a teacher undoubtedly belonging to the *maṭha* of *Śaṅkarāchārya*. This point has to be made out here at some length. Remarking on the plates of *Kṛishṇadēva-Rāya* lent for examination by Mr. Venkateswara, the Epigraphist to the Madras Government states as follows: " . . . it looks suspicious why the name *Śaṅkarāchārya* is not mentioned even incidentally in any one of the copper-plates under reference." (Enclosure to G. O. No. 1260-Public, dated 25th August 1915, page 117.) Elsewhere in the same report he remarks on the grant of *Vijaya-Gaṇḍa-gopāla* as follows: "Mr. Venkateswara Ayyar is editing in the *Ep. Ind.* an earlier copper-

¹ As we find in other Vijayanagara copper-plates.

plate grant, which belongs to the same *maṭha*, but is not included in Appendix A. . . . It is not clearly stated in the record if the *maṭha* presided over by the Śaṅkarārya herein referred to was identical with the Śaṅkarāchārya *maṭha* at Conjeeveram."

In the first place, the Āchāryas of the *maṭha* have each a proper name like Mahādēva, Sadāśiva and Chandrasēkhara, while all of them are styled Śaṅkarāchārya by the people. This will be clear from the *Guru-paramparā* of the *maṭha*, extracts from which we reproduce below, and which must be at least three centuries old. Secondly, the attributes of the great Śaṅkara such as *parama-hansa parivrājakāchārya*, etc., are found in these copper-plates. Thirdly, the plates make it clear that the donee was a great teacher of Advaitism: cf. line 68 *śiṣya-pāda-devandeva-duḥkha-vyatitāya mahātmanē*. Also, *nigamānta-rahasyārtham śiṣyābhyāṃ suvīriṇavatē* in the grant of Vijaya-Gaṇḍagopāla. The teacher is styled *tapasvin* in the present grant, and *Śiva-chētas* and *Yati-rāja* in the plates of Kṛishṇadēva-Rāya, and also an exponent of the *māyā-vāda*. Fourthly, the Āchārya has his seat in Kāñchi-puram, and the plate of Vijaya-Gaṇḍagopāla locates the *maṭha* as situated to the west of the temple of Hasti-śaila-nātha. Unless the critic could prove the existence of another *maṭha* at Conjeeveram to which the above attributes can be applied, there seems to be no point in calling in question the identification of the *maṭha* to which the grants were made with the *maṭha* of Śaṅkarāchārya at Conjeeveram. As a matter of fact the *maṭha* owns, even at the present time, lands in Ambikāpuram and various other villages granted in these copper-plates.

The date of the grant is Śaka 1429, Śukla, Māgha, on the occasion of the *Mahodaya*, which is considered a very auspicious conjunction of constellations. The week-day is not mentioned, nor is the *tithi*. But the mention of the cyclic year is important. It shows that Vira-Nṛisimhēndra must have ascended the throne at the latest by 1506 A.D.

The chief interest of the grant, however, is that, taken together with the copper-plates of Kṛishṇadēva-Rāya and Vijaya-Gaṇḍagopāla, it enables us to determine approximately the date of the great Śaṅkarāchārya. The *Gurus* of the Śaṅkarāchārya *maṭha* named in the plates are—(1) Śrī Śaṅkara-yōgin, 1291 A.D., (2) Sadāśiva, Mahādēva and Chandrasēkhara, and Sadāśiva, contemporaneous with the Vijayanagara kings Vira-Nṛisimhēndra and Kṛishṇa-Rāya (1506 to 1527 A.D.). Fortunately for us, we find these names in the old list of the Āchāryas preserved in the *maṭha*. One of the teachers, the third in apostolic descent from Sadāśiva (1527 A.D.), composed a *Guru-rāja-ratna-mālā-stava*, of which the following are the closing stanzas:—

निजनोददग्रहेतिखेदं त्यज नेपालनृपालपूज्यपादः ।

स पुरो मम साधु सन्निधत्तां विपुलानन्दसदाशिवो ऽप्रमत्तः ॥

बहुधाहितं सुखभाष्यशान्तिः बहुलामोदवहस्यमयशान्तिः ।

शमलं ससुदृढं शं ममालं स महादेवगुरुर्दिशेत्तलीलम् ॥

सतताहितचन्द्रमौलिसेवः श्रितकाञ्चीपुर एव शुद्धभावः ।

सृजतात्मसं चन्द्रचूडमौनी स जयं सर्वत एव साधुमानो ॥

अथ मे स सदाशिवः कृपोष्टः प्रथमं बोधपदेन तच्चदेष्टा ।

कुशलं कुशलायणीः प्रकामं प्रशमो ऽप्युज्ज्वलमूर्तिरासक्तकामः ॥

हृदये स पदं सदा विधत्तां सदयो मे प्रणुदन् प्रसादवत्ताम ।

निगमान्तगुरुः परश्शिवात्मा सुगमस्त्वाधुततेर्यमी महात्मा ॥

यदुदोक्षणलेशतो जनानां विदुरद्वैतमतिं दितां धुनानाम् ।
 तमहं परमाक्षितं शिवेन्दं शम्भवन्तं शरणं अये यमीन्द्रम् ॥
 इति नायनया ऽऽत्मबोधनाम्नो यतिराजस्य सदाशिवेन्द्रभूम्ना ।
 कलिता जयताइसन्तमालापडशीत्या गुरुराजरत्नमाला ॥

इति श्रीमत्परमहंसपरिव्राजकाचार्यवर्यश्रीसदाशिवब्रह्मेन्द्रकृतिषु गुरुराजरत्नमालास्तवः
 संपूर्णः ।

The fact that the *gurus* after the 16th century are not mentioned in this *stotra* may be taken as indicating that there has been no addition to it since the author's lifetime. The author cannot be regarded as an authority regarding the generations of *gurus* remote from his time; but the tradition embodied by him in relation to that epoch may be treated with some consideration. The *guru-paramparā* of the *maṭha*, as gathered from this work, may be thus arranged:—

- | | |
|-----------------------|-------------------------|
| 1. Śaṅkara. | 28. Bōdha. |
| 2. Surēśvara. | 29. Sacchidānandaghana. |
| 3. Sarvajña. | 30. Chandrasēkhara. |
| 4. Satyabōdha. | 31. Chitsakhēndra. |
| 5. Jñānānanda. | 32. Vidyāghana. |
| 6. Śuddhānanda. | 33. Śrī Śaṅkara. |
| 7. Ānandajñāna Yōgin. | 34. Sacchidvilāsa. |
| 8. Kaivalya Yōgin. | 35. Mahādēva. |
| 9. Kṛipāśaṅkara. | 36. Gaṅgādharā. |
| 10. Mahēśvara. | 37. Purnabōdha. |
| 11. Chiddharā. | 38. Brahmānandaghana. |
| 12. Chandrachūḍa. | 39. Ānandaghana. |
| 13. Sacchidighana. | 40. Paraśiva. |
| 14. Vidyāghana. | 41. Bōdha. |
| 15. Gaṅgādharā. | 42. Chandrachūḍa. |
| 16. Sadāśiva. | 43. Chidvilāsa. |
| 17. Surēndra. | 44. Mahādēva. |
| 18. Vidyāghana. | 45. Chandrasēkhara. |
| 19. Śaṅkarēndra. | 46. Vidyātīrtha. |
| 20. Chandrachūḍa. | 47. Śiva Yōgin. |
| 21. Paripurnabōdha. | 48. Śaṅkarānanda. |
| 22. Sacchitsukha. | 49. Sadāśiva. |
| 23. Chitsukha. | 50. Mahādēva. |
| 24. Chidānandaghana. | 51. Chandrachūḍa. |
| 25. Prājñāghana. | 52. Sadāśiva. |
| 26. Chidvilāsa. | 53. Paraśiva. |
| 27. Mahādēva. | 54. Ātmabōdha. |
| | 55. Śivēndra. |

It will be clear from the above genealogy that, though some names occur more than once, it is only at wide intervals. The Āchāryas mentioned in the copper-plate grants of Vira-Nṛsiṃha and Kṛishṇa-dēva-Rāya are the 49th to 52nd in the list. The identification is confirmed by the mention of the Nepalese king in the *śloka* referred to above. Bühler has noted¹ that a certain *Swāmin* of South India went to Nepal about 1503 and that he was named Somaśekharaṇanda. Our copper-plates show that Chandrasekhara Sarasvati was also named Chandrachūḍa. 'Somaśekhara' may be another variant, as it has the same meaning. It is more than merely possible that the Sadāśiva of the *śloka* may have sent one of his disciples, Chandrachūḍa, alias Somaśekhara, to Nepal at the request of its king. The date of our grant of Nṛsiṃha is 1506, and then the *Swāmin* was Mahādēva, a disciple of Sadāśiva. It follows therefore that Sadāśiva may have lived till 1506. If so, his sending a *śiṣya* to Nepal in 1503 may be accepted as a fact.

It remains to consider who was the *guru* in the genealogical list corresponding to Śrī Śaṅkarārya *guru* alias Śaṅkara Yōgin mentioned in the copper-plate grant of Vijaya-Gaṇḍa-gōpāla. There are in the list only two such names which could be thought of, viz. No. 19 Śaṅkarēndra and No. 33 Śrī Śaṅkara. The date of the plate being 1291, it could hardly be of the time of No. 19, as in that case there would be 30 generations from him to Sadāśiva of 1503 A.D., covering a period of only two centuries. So the Śaṅkara of the plate should be identified with No. 33. We then get 16 generations for a period of 215 years, i.e. on the average $13\frac{1}{2}$ years for a generation. This should not be regarded as a low figure,² as in most cases a man becomes the head of the *maṭha* only when advanced in years, and is generally succeeded by the oldest among his disciples. Counting back at the same rate of $13\frac{1}{2}$ years, we get the 9th century A.D. for the great Śaṅkarāchārya. It has been shown elsewhere³ that this date agrees with all known or inferable data, external and internal, in relation to the date of Śaṅkarāchārya.

The engraver of the grant is Virapāchāri, son of Mallapāchāri. Elsewhere they are styled Virapāchārya and Mallapāchārya. But *āchāri* or more properly *āsāri* is a Dravidian word which means 'artisan' even now. It may therefore be assumed that the engraver was of the *āsāri* or artisan caste. This caste had a practical monopoly of work on metals, wood or stone.

As regards the descendants of Mallapa we know that Virapa, his son, surnamed *vaṣṭri*, the engraver of the present grant, was engraver to Kṛishṇadēva-Rāya and Achyuta-Rāya; and that he had a son, also named Virapa, who was the engraver to Sadāśiva-Rāya.

Of the localities mentioned the following may be identified with villages of modern times in Chingleput and North Arcot districts :—

Varakūṭaru is probably the same as Velkūru in Chittoor *tāluk*.

Kajakūṭṭaru is the same as the village of the same name in Palmanūr *tāluk*, N. Arcot district.

Surittiluru is perhaps the same as Suruttal in Arcot.

Śittileppākkam is the same as Śittileppākkam in Arcot.

Kudiyāntaṇḍala is known to-day by the name Kuṇḍiyāntaṇḍala in N. Arcot district.

¹ *Inscriptions from Nepal*, p. 40.

² Compare the Jaina *Guru-paramparā* of the Tūpā Gachchha (cited by Mr. Venkateswara) in *J. R. A. S.*, Jan. 1917, p. 127, which gives 376 or 386 years for 23 generations of *śāhasiras*.

³ See Mr. S. V. Venkateswara Ayyar's paper on the date of Śaṅkarāchārya in the *J. R. A. S.* for January 1916. See also his note on the contemporaneity of Sarvajñātman, the *pratiśhys* of Śaṅkara, and the Chōja king Aditya I, 880-907, (*Ind. Ant.* for 1914, p. 238).

TEXT.¹

[Metres : vv. 1-4, 6-8, 12, 13, 18-20, 22-31, 33 and 34, *Anuṣṭubh* ; v. 5, *Śārdūlavikrīḍita* ; v. 9, *Harip* ; vv. 10, 11, 14-17, *Brāgharā* ; vv. 21, 32, *Malini*.

Plate I.

- 1 श्री गणाधिपतय^{1a} नमः [॥*] नमस्तुगशीरचुं²-
- 2 विचंद्रचामरचारवे । त्रैलोक्यानगराकारसु-
- 3 लस्तंभाय शंभवे ।[1*] हरलीलावतार-
- 4 स्य दंष्ट्रादंडस^{3a} पातु वः [1*] हेमाद्रिकलशा यत्र धा-
- 5 त्री कृतत्रियं दधौ ।[2*] कल्याणयास्त⁴ ते धाम
- 6 प्रत्यु⁵हतिभिरापहं । दहलोप्यगजोदूतं
- 7 हरिणापि च पु⁶न्यते ।[3*] अस्ति चि⁷रमया-
- 8 हेवैर्मत्तध्वमानम्बहांवधिः⁸ ।
- 9 नवनितमीवोभुत⁹मपनीतत-
- 10 मो महः ।[4*] तस्यासीत्तनयस्तपो-
- 11 भिरतुलैरन्वर्धनामा पु¹⁰धः पुण्यै-
- 12 रस्य पु¹¹रवा भुजवलैरायुर्हि-
- 13 यां निघ्नतः । तस्यायु¹²नष्टपोस्य त-
- 14 स्य पुरुषो [यु]हे र्य¹³थाति[.] चितौ स्यातस्तस्य
- 15 तु भुवभुव¹⁴सुनिभ[.] श्रीदेवयान¹⁵पतेः ।[5*]
- 16 तदंशे देवकिजानि दि¹⁶दीपे तिस्रभु¹⁶-
- 17 पतिः । यशस्वी तुर्वेदेषु तदा¹⁷ ल-
- 18 ण्य इवान्वये ।[6*]

Plate II, side i.

- 19 ततोभूहकराजानामि¹⁹श्वरचितिपालकः । अता²⁰धमगुणभंश मो-

¹ From the plates.² Read शे.³ Read ०शुगशीरचुं.⁴ Read वैलोक....सू The usual reading in what follows is नगरारंभ⁴, the verse being quoted from Bhaṭṭa's *Harsha-Charita* (Benedictory stanza).⁵ Read लो.⁶ Read स्य.⁷ Read सु.⁸ Read ल.⁷ Read ०ह.⁸ Read प.⁹ Read श्री.⁸ Read ०संयमानाम्बहांवधिः.⁹ Read नवनितमीवोभुत.¹⁰ Read तु.¹² Read स.¹⁰ Read न.¹¹ Read पुरुषो . . . व.¹³ Read सुवसुव.¹¹ Read श्री.¹² Read देवकीजानिदि.¹⁶ Read भु.¹² Read यदी.¹⁹ Read ततोभूहकराजानिरी.²⁰ Read अताधमगुणभंश.



- 20 खिरत्तं महीभुजां ।[7*] सचस्त्रादुदभुत्तस्मात् नरसोवनिपालक¹ ।[8*]
 21 देवकि²नंदनाकामो³ देवकिनंदनादिभिः⁴ ।[8*] विविधसुज्जते स्था
 22 ने⁵ र⁶मेश्वरप्रमुखे सुहृद्मुदितहृदय स्थाने स्थान त्वध⁷
 23 त्त यथाविधि⁸ । व⁹धपरिवृतो नानादनीनि¹⁰ यो भुवि षाड-^{10a}
 24 श चिभवनजनीहीत¹¹ सौवर्णवानुस¹² यथावि-
 25 धिः⁹ ।[9*] कावेरीमाय वध्वा वहलज्जलभरां यो विलंघ्ये-
 26 व चतु¹³ जीवघ्राहं गृहीत्वा प्रथितभुजवलात्तं-
 27 चराज्य प्रदीप्य¹⁴ ।[1] कृत्वा शौरंगपूर्वं तदपि निजवशे
 28 पट्टणं यो व(व)भासे कीर्त्ति¹⁵स्तंभं निखातं तिसुवनभ-
 29 वनं¹⁶स्तूयमानापदानः ।[10*] चेरं चा¹⁵स्तं च पा¹⁶द्य तद
 30 पि च मधुरावज्जभं मानभुषा¹⁷ वि¹⁸योदधं तुरुष्कं
 31 गजपतिव¹⁹पतिं चापि जित्वा दन्या²⁰ ।[1] आगंगाति²¹रभूमि
 32 घघमचरमदयतटात्तं²² निता²³ स्थातः क्षोणी-
 33 पतीनां भुजमिव²⁴ शिरसा शामनं यो व्यतानि²⁵ ।[11*]
 34 तो²⁶प्याजीनागलादेव्यो²⁷ कौसेव्या²⁸शोसुमित्रयोः । दे-
 35 व्यरिव²⁹ नृसिंहेंद्रात्तस्मात्पत्त³⁰रधादि³¹ ।[12*] विरी³² निजधनी³³ राम-
 36 लक्ष्मणाविव नंदनी ।[1*] जातो विरनसिंहेंद्र³⁴लक्ष्मणायम-
 37 ङ्गीपती ।[13*] विरसीह³⁵ स विजयनगरे राज्यसिंहासन-
 38 स्थः कीर्त्त्या नीत्या निरस्व³⁶ नृगनलनहुषानप्यवन्धाः³⁷ प्र-
 39 दाता³⁸ । आ सेतीरा सुमेरीरप³⁹निसुरनुत[:*] स्त्रैरमाचो-

¹ Read सरसादुदभुत्तस्मात् . . . पालकः.

² Read देवकीनंदनादिभः.

³ Read स्थाने व्यध.

⁴ Read °दानानि.

⁵ The reading in other Vijayanagara plates, e.g. Krishna-Bāya plates, is क्रीतं ययः पुनरवज्जन्. This seems to be the better.

⁶ Read वध्वा.

⁷ Read ति.

⁸ Read पाद्यं तनपि.

⁹ Read व.

¹⁰ & ^{10a} Read प्रघमचरमभुत्तटात्तं नितातं.

¹¹ Read ति.

¹² Read देव्योरिव.

¹³ & ¹⁴ The reading in the other grants of the kings of Vijayanagara is वीरी विनविनी. The meaning of the reading in the present plate would be "who are wealth to themselves" or something like that. The reading विनविनी is to be preferred.

¹⁵ Read वीरवृ°.

¹⁶ & ^{16a} Read °वन्धानावन्धाः.

¹⁷ Read विविधसुज्जतीहामि.

¹⁸ Omit vicarya.

¹⁹ Read वीड.

²⁰ The reading in other plates is तदीयं.

²¹ Read व.

²² Read वज्जभं मानभूयं.

²³ Read तदन्त्यान्.

²⁴ Read सज्जमिव शिरसा

²⁵ Read वीः.

²⁶ Read व्यङ्गि.

²⁷ & ²⁸ Read देवकी . . . नारदा°.

²⁹ Read रा.

³⁰ Read वृ.

³¹ Read तिसु . . . तं.

³² Read वीडं च.

³³ Read वी.

³⁴ Read ती.

³⁵ Read व्यतानीत्.

³⁶ Read वीडव्या.

³⁷ Read °रधादिह

³⁸ Read निरस्वन्.

³⁹ Read वीरवीनारसिंहः.

⁴⁰ Read रयः.

- 40 दयाद्वैरापाद्य¹चलांतादखिलहृदयमावर्ज्य
 41 राव्यं शशास ।। 14*² ननादानन्यकापीत्³ कनकसी⁴ वी-
 42 रुपाक्षदेवस्तने अ⁵कालहस्तोशितुरपि नगरे वे-
 43 कटाद्री च काचं⁶ ।।*⁷ त्रिशैले⁸ शोणशैले मह⁹ हरि-
 44 हरे त्वीभ¹⁰लाख्ये गिरौ¹¹ च श्रीरंगे कुम्भकोणे ह-
 45 ततमसी¹² महानंदितीर्थे निव्रतौ¹³ ।। 15*

Plate II, side ii.

- 46 गोकर्णे रामसे[तौ] जगति तरेष्वप्यशेषपु¹⁴ पुण्यग्रामेश्वा-
 47 रव्यनानाविधवह्मलमहादानवारिप्रवाहे¹⁵ । यस्योदं-
 48 चं¹⁶तुरंगप्रकरसुर¹⁷शृण्वदंभोधिवांत्तः¹⁸छा-
 49 भत¹⁹पञ्चचिदौत्तर²⁰कुलिशधरोत्कुठिता क²¹ठिता-
 50 सीत् ।। 16*²² ब्रह्मांडं विश्वचक्रं घटमुदितमहाबु²³त-
 51 कं रत्नधेनु²⁴ सप्ता²⁵भोधीन् हिरण्याश्वरयमपि तुल-
 52 पुषं²⁶ गोसहस्रं । हेमाश्वं हेमगर्भं²⁷ कनककरि-
 53 रयं पंचलांगव्यतानी²⁸ धर्मकक्षातन्वृत्तिः²⁹
 54 प्रतिन³⁰पतिशिरैरन्नकि[ञ्चि]³¹प्रतापः ।। 17*³² राजाधिराज
 55 [इ]राज³³ इत्युक्तः यो राजपरमेश्वरः । मूकरायस-
 56 गंडय पररायभयंकरः³⁴ ।। 18*³⁵ इ³⁶दुरायसुरत्वा-
 57 यो दुष्टशार्दु³⁷लमर्दनः । वि³⁸प्रताप इत्यादिविशेषै-
 58 रुचितयातः³⁹ ।। 19*⁴⁰ वि⁴¹र देव महाराय जय जीवेति
 59 वादिभिः ।।*⁴² अंगवंगकलिंगाद्यै राजभिस्त्रेव्य-

¹ Read पाशाया.

⁴ Read विष्णुपाथ ... स्थाने.

⁷ Read लांया.

¹⁰ Read होयले.

¹³ Read सि.

¹⁶ Read छै.

¹⁹ Read मय.

²² Read रुठिता कुठिताभीत्.

²⁵ Read मी.

²⁸ Read नीत्.

³¹ Read शिरैरन्नकीचि.

³⁴ Read हि.

³⁷ Read युंत्.

² Read नानादानान्यकापीत्.

⁵ Read श्री.

⁸ Read श्रीशैले.

¹¹ Read संशैले. [Notes 10 and 11 are not quite necessary.—H. K. S.]

¹⁴ Read निह सी.

¹⁷ Omit *anuvāda*.

²⁰ Read भूत्.

²³ Read भू.

²⁶ Read तुषापुषं.

²⁹ Read लांयाति.

³² Omit इराज.

³⁵ Read इ.

³⁸ Read वीर.

³ Read कनकसदसिधयो.

⁶ Read वं.

⁹ Read महति.

¹² Read तद्विशेषपुण्ये.

¹⁵ Insert रत्न after सुर.

¹⁸ Read छिदीय.


²¹ Read रत्नधेनु.

²⁴ Read मं.

²⁷ Read इ.

³⁰ Read कष्ट.

³³ Read श्री.



74 ॐ नमो भगवते वासुदेवाय ॥ श्रीगणेशाय नमः ॥ श्रीगणेशाय नमः ॥ श्रीगणेशाय नमः ॥
76 श्रीगणेशाय नमः ॥ श्रीगणेशाय नमः ॥ श्रीगणेशाय नमः ॥ श्रीगणेशाय नमः ॥
78 श्रीगणेशाय नमः ॥ श्रीगणेशाय नमः ॥ श्रीगणेशाय नमः ॥ श्रीगणेशाय नमः ॥
80 श्रीगणेशाय नमः ॥ श्रीगणेशाय नमः ॥ श्रीगणेशाय नमः ॥ श्रीगणेशाय नमः ॥
82 श्रीगणेशाय नमः ॥ श्रीगणेशाय नमः ॥ श्रीगणेशाय नमः ॥ श्रीगणेशाय नमः ॥
84 श्रीगणेशाय नमः ॥ श्रीगणेशाय नमः ॥ श्रीगणेशाय नमः ॥ श्रीगणेशाय नमः ॥

ॐ नमो भगवते वासुदेवाय ॥

- 60 ते च यः ।[20*] विज'नगरमध्ये रत्नसि'हासनस्यः ज-
 61 यति[स*]भुवि वीर'शीतीसिंहचित्तिंद्रः¹ । नृगनहुषययाती-
 62 नत्थयन् भु'सुराणां सुरतरिव धीरः पुण्यकि²-
 63 तिप्रतापः ।[21*] शकाब्दे शालिवाहस्य सहस्रेभ्यस्तुश-
 64 तैः । एकोनचतु'शता³ गच्छे युक्तनामनि वस्तुरे⁴ ।[22*] विख्या-
 65 ते मासि माघाख्ये पुण्यकालि महोदये तु'गभद्रन-
 66 दीतिरे⁵ त्रिविह⁶पाचसन्धीधे⁷ ।[23*] परह⁸सपरिव्राजकाचा-
 67 र्याय सुसुचवे । भस्मोदुलितगवाय⁹ रुद्राचावलि-
 68 धारिणे ।[24*] शितोष्णदादिद्वंद्वंखाव्यतिताय¹⁰ महात्मने [1*]
 69 समस्तशास्त्रपाधोर्थ¹¹पारगाय तपस्विने ।[25*] अष्टा-
 70 गयोगयुक्ताय दयाशीलाय ध¹²मते [1*] सदाशीव¹³-
 71 सरस्वत्यैशीष्यायामिततेजसे¹⁴ ।[26*] महे¹⁵वसर-
 72 स्वयै गुरवे शीवर¹⁶पिणे ।

Plate III.

- 73 मंडले जयचोलस्य पडवीडुसुराज्यके ।[27*] काची¹⁷नाडुसमा-
 74 युक्तंवलकारु¹⁸सीमनि । [कृष्णवंशपत्तु¹⁹नागुक्तं] कालीयुक्कोट्टसन्नित²⁰ ।[28*]
 75 कलकाट्टरुसुधामाद²¹चोणस्यां दिशि स्थितं । शरिट्टिलुम-
 76 हाग्रामाप्र²²तीच्यां दिशमायितं ।[29*] शित्तिलपाकसुधामादुत्तरस्या²³ दि-
 77 शि स्थितं [1*] कुनंतागल्यधामा पुत्रस्या²⁴ दिशिसुपायितं ।[30*] नालिकेरा-
 78 ²⁵त्रपनशतालक्षितालशोभितं । सर्वस्यामृद्ध्या²⁶ च राजमानं
 79 शुभान्वितं । कुडियांतंडलाख्यातं ग्रामरत्नं प्रदत्त्वा-
 80 न् ।[31*] यि²⁷दमधित नृपाणा मौलिराज्यकिट²⁸स्फुरितमणिगणानां
 81 कान्तिनीराजिताधे²⁹ । असत³⁰मनघपद्यशासनं नम्रपात्रं³¹

¹ Read 'विजय.

² Read भु.

³ Read वसर.

⁴ Read 'सनिधौ.

metre.—H. K. S.]

⁵ Read 'श्रीतीष्ठादिद्वंद्वं खाव्यतिताय.

intended.—H. K. S.]

⁶ & ⁷ Read सदाशिवसरस्वत्याशिष्याया.

⁸ Read शिव.

⁹ The writing here is confused so much that it is difficult to decipher exactly what it is.

¹⁰ Read 'समन्वितं.

¹¹ Read श्री.

¹² Read सर्वसंख्यमृद्ध्या.

¹³ Read शिव.

¹⁴ Read शिव.

¹⁵ Read सि.

¹⁶ Read श्री.

¹⁷ & ¹⁸ Read तुंगभद्रानदीतीरे.

¹⁹ Read परमहं. [This correction is wrong. It offends against the

²⁰ Read मन्मोहलितनामाय.

²¹ We should suggest 'श्रीशार्च. [पाधोर्थ is evidently what was

²² Read श्री.

²³ Read श्री.

²⁴ Read श्री.

²⁵ Read श्री.

²⁶ Read श्री.

²⁷ Read श्री.

²⁸ Read श्री. The context is ungrammatical.

²⁹ & ³⁰ Read श्रीशिवसिद्धिचिन्मः.

³¹ Read नि'शता

³² Read श्री.

³³ Read श्री.

³⁴ Read श्री.

³⁵ Read श्री.

³⁶ Read श्री.

³⁷ Read श्री.

³⁸ Read श्री.

³⁹ Read श्री.

⁴⁰ Read श्री.

- 82 जयतु भुवनमोक्षि त्रिभुविहृतिदः¹ ।। 32*] मङ्गलाशारिपुत्रे²
 83 विरणाशारि³संज्ञिना । लिखितं लाक्षविदतिनत⁴ तदिदं ताम्रशा-
 84 सनं ।। 33*] दानपालनयोम्ये⁵ दानात्रे⁶योनुपालनं । दानास्त्रय⁷-
 85 मवाप्नोति पालनादनु⁸तं पदं ।। 34*]

— श्रीविरूपाक्ष —

ABSTRACT OF CONTENTS.

- V. 1. Invocation to Śambhu.
 V. 2. To the boar incarnation of Viṣṇu.
 V. 3. To Gaṇeśa.
 Vv. 4 & 5. Descent of the family from the moon through Buddha, Purāṇavas, Āyus, Nahusha, Yayāti and Turvaṣu.
 Vv. 6, 7 & 8. Genealogy as far as Narasa, who was born of the son of Dēvaki (Bukka) as Kāma was from the son of Dēvaki (Kṛishṇa).
 V. 9. The munificent gifts of Narasa in holy places.
 Vv. 10 & 11. His exploits and victory over his enemies such as the Chēras, Chōlas, Pāṇḍyas, etc.
 Vv. 12 & 13. To that king were born of Tippāji and Nāgālā Dēvi, the sons Vira-Nṛisimhēndra and Kṛishṇa-Rāya, who were brave yet well-behaved, as Rāma and Lakṣmaṇa were born to Paṇktiratha (Daśaratha) of Kausalyā and Sumitrā.
 V. 14. The brave Vira-Narasimha, seated on his jewelled throne at Vijayanagara, eclipsed in fame and policy other kings of the world like Nṛiga, Nala and Nahusha. He ruled the kingdom between the eastern and western mountains, drawing to him the hearts of all people.
 Vv. 15 & 16. His gifts at holy places such as Chidambaram, Kālabasti, Tirupati, Śrīraṅgam, Kumbhakōṇam, Conjeeveram, Ahōbalaṃ, Gōkarna, Rāmasēṭu, etc.
 V. 17. His praises.
 V. 18. His *virūdas*.
 Vv. 19-21. Praises of the king.
 Vv. 22-27. In the Śaka year 1429 according to the Śālivāha reckoning, in the year, Śukla, in the famous month Māgha, in the holy Mahōḍaya, on the bank of the Tuṅgabhadra, in the vicinity of Śrī Virūpākṣa (the gift was made) to the Guru. Mahādēva Sarasvatī, the disciple of Sadāśiva Sarasvatī, etc.
 Vv. 27-31. Name of the village granted with its boundaries, etc.
 V. 32. Praises of the king Vira-Nṛisimha for the grant.
 V. 33. The engraver of the grant was Virapāśāri, son of Mahapāśāri.
 V. 34. The merits of charity.
 Signature in Kannaḍa, Śrī Virūpākṣa.

¹ Read श्रीविहृतिदः.

² [Read मङ्गलाशारि?—F. W. T.]

³ Read मङ्गल.

⁴ Read लाय.

⁵ Read लोच.

⁶ Read लु.

⁷ Read श्रीविरूपाक्ष.

⁸ Read दानात्रे.

No. 18.—THE TRUE LONGITUDE OF THE SUN IN HINDU ASTRONOMY.

THE SIDDHĀNTA-ŚIRŌMAṆI.

By ROBERT SEWELL (I.C.S., RETIRED).

(Continued from *Epig. Ind. XIV. p. 66.*)

257. In my last article I have given Tables for finding the longitude of the sun, both mean and true, at any time of any year according to two of the great Indian astronomical authorities, the *First Ārya-Siddhānta* or *Āryabhaṭīya* of Āryabhaṭa (A.D. 499) and the *Present Sūrya-Siddhānta* (exact date unknown, introduced about A.D. 1100). The present Table affords similar information for the *Siddhānta-Śirōmaṇi* (12th century).

As soon as I obtain definite assurance as to the value assigned by Brahmagupta to each of the twenty-four base-sines of angles, I shall be able to provide a similar Table for his *Brahma-Siddhānta* (A.D. 623). For the present this is not possible. We know that the sine-values given in detail in the *Sūrya-Siddhānta* (ii, 15-22) were the same as those used by Āryabhaṭa six centuries earlier (see *Ārya-Siddhānta, gītikā-pāda*, v. 10, and the Hindi Commentary by Udayanāraṇya Singh—*Mosafarpur, 1906*—with list of differences between the sines); but according to the printed Benares edition of the *Brahma-Siddhānta*, with which one MS. copy in the India Office agrees (see II, *Spashṭa-adhikāra*, vv. 2-5), Brahmagupta used a totally different set of sine-values, and these actually erroneous ones, while the values used a century before his time and 500 years later were as nearly as possible mathematically correct.¹

Seeing no reason why Brahmagupta should have made his calculations by a set of sines that may be condemned as positively wrong, in opposition to the correct set in use before his day, I have instituted enquiries in order to ascertain whether perhaps the Benares edition of his *Siddhānta* may have followed a MS. which by some mischance contained a copyist's error, equally the source of error in the MS. in the India Office. Unfortunately two other MSS. in the India Office and one in the Bibliothèque Nationale in Paris are wanting in the passage which contains the sine-values.

Oxford possesses no copy. I have sought for information from India, but this is not yet to hand.

I hope to be allowed hereafter to publish a Table for work by the *Siddhānta-Śirōmaṇi* assimilated to Table I of the *Indian Calendar*, which will enable us to ascertain the tithi, yoga, nakshatra and solar month according to that authority as easily as we have been enabled to do according to the *Ārya*- and *Sūrya-Siddhāntas*; and this will, I hope, be followed by similar Tables for work by the *Ārya* and possibly by the *Brahma-Siddhānta*.

Epigraphists will then be in a better position than heretofore to judge of the authenticity of inscription dates.

In case my Tables should be considered over-minute in detail, running as the entries do to several decimal points, I would ask readers to remember that they are designed as standard Tables for the settlement of the closest possible cases. Such a case as is mentioned in my former paper (*above*, Vol. XIII, 2, §§ 206, 207, on the cycle of Jupiter) proves that permanent reference Tables can hardly be too accurate. I have found other cases somewhat similar in

¹ Sin. 90° = radius. With π (ratio of diam. to circumf.) = 3.14159 the radius = 3437.74967. The *Sūrya-Siddhānta* and *Ārya-Siddhānta* radius is 3438'. The *Brahma-Siddhānta* value of Sin. 90° or radius is 3270', which implies a ratio π = 3.303. The ratio according to Archimedes (B. C. 250) was 3.14285. If the ratio 1 : $\sqrt{10}$ mentioned in the *Sūrya-Siddhānta* should be adopted, we should have the ratio 3.16223. Brahmagupta's implied ratio, 3.303, is quite different from any of these.

calculating the intercalated and suppressed lunar months by the *Siddhānta-Śirōmaṇi*. In ordinary cases it will always suffice to work with merely the whole numbers.

Elements of the Siddhānta-Śirōmaṇi.

258. The *Siddhānta-Śirōmaṇi* by Bhāskarāchārya dates, it is believed, from about A.D. 1150, though Dr. Bhanu Dāji (J. R. A. S. n. s. I. 392) placed it in about 1105. It was used in some tracts and for some periods—we have yet to learn which—for the preparation of local almanacs. My future Tables will embrace the period A.D. 1100 to 1750. The earlier date will suffice for safety, and it is not necessary to work for years later than 1750.

According to this authority the length of the year from mean Mēsha-saṁkrānti to mean Mēsha-saṁkrānti is $365^d\ 6^h\ 12^m\ 9^s$ or $365^d\ 258437500$.

Its sine-values of angles are the same as in the *Ārya-* and *Sūrya-Siddhāntas*, with radius taken as equal to 3438'.

For the sun's mean motion in days, hours, etc., see Table XLIII (above, Vol. XIV).

The twenty-four base equations are given in col. 9 of Table XLVII of the same article with the differences per minute of anomaly angle (col. 10), and in fuller detail in Table XLVII, A, cols. 9-10.

¹ The epicycle of the sun not being considered as contracted at any part of the orbit, as it is in the *Sūrya-Siddhānta*, and the circumference of the epicycle being given as $13^{\circ}\ 40'$ or $820'$, the equation (a being the sun's mean anomaly, or the angular distance of the mean sun from the perigee-point of his orbit) is $\frac{13^{\circ}\ 40'}{360^{\circ}} \sin. a$, or $\frac{820'}{21600'} \sin. a$, or finally $\frac{41}{1080} \sin. a$.

This *Siddhānta* postulates a constant forward shift in the line of apsides of the sun's orbit. This shift is more rapid than the *Sūrya-Siddhānta's* shift and amounts to $0^{\circ}\ 0174$ or $1^{\circ}\ 044$ per annum, and to $11^{\circ}\ 18' 6$ or $11^{\circ}\ 31$ in the 650 years succeeding A.D. 1100.²

According to the *Siddhānta-Śirōmaṇi* the Kaliyuga began, or in other words K. Y. 0 began, with a conjunction at celestial longitude 0° or 360° of mean sun, mean moon and other planets at the moment of mean sunrise or 6 A.M. on Friday 18th February B.C. 3102 or 18th February $0^h\ 0^m\ 0^s$ Lanka time. This was the moment of mean Mēsha-saṁkrānti in that year. True Mēsha-saṁkrānti, the moment when the true or apparent sun touched long. 0° , occurred by the same authority on Tuesday 15th Feb. in that year at $19^h\ 52^m\ 21\frac{1}{2}^s$ after mean sunrise.

The interval between these two occurrences, which we call the *śodhya*, and which is the time occupied by the sun in travelling over the arc of the equation-angle, was $2^d\ 171971$ or $2^d\ 4^h\ 7^m\ 38\frac{1}{2}^s$ according to Dr. Schram's calculation (see "*Indian Chronography*," Table, p. 16).²

259. In the matter of the sun's equation and true longitude it should be noted that every entry in cols. 6 to 9 of Table XLVIII has been separately calculated from the value of his mean anomaly at each twenty-four hour period measured from the moment of true Mēsha-saṁkrānti, by use of the *Siddhānta-Śirōmaṇi* equation Table.

¹ The shift according to the *Ārya-Siddhānta* is nil.

" " *Brahma-Siddhānta* $0^{\circ}\ 144$ per ann.

" " *Sūrya-Siddhānta* $0^{\circ}\ 1151$ "

" " *Siddhānta-Śirōmaṇi* $1^{\circ}\ 044$ "

" " *2nd Ārya-Siddhānta* $0^{\circ}\ 1383$ "

(Jacobi, *Epig. Ind.* I. 441.)

² For explanation of technical matters see above, Vol. XIV, §§ 249-255.

260. The forward shift of the sun's apsis, while leaving the sun's mean longitude unaffected, causes a slight change every year in the sun's mean anomaly (his mean distance from the perigee-point), this becoming each year proportionally less as the perigee-point moves forward. And since the shift induces a corresponding, though very minute, change in the velocity of the sun (considered as a planet) at all times of the year, the sun's equation and true longitude are each year a little different from what they were in the year previous.

The change in mean anomaly is stated in Table LI below.

The change caused by the shift of the apsis in the equation and true longitude of the sun at true Mēsha-saṁkrānti amounts to only 2" (actually 1".9675) in the 300 years on either side of K. Y. 4500, which is the base-year of my main Table XLVIII, — the annual change being at the rate of about 0".0066 per annum.¹

The corresponding time-difference, or change in the *śodhya*-value, is about 0".16 per annum (actually 0".15975) by which amount the *śodhya*-value at true Mēsha-saṁkrānti increases every year. In 300 years this amounts to 47".925 or about 48". (For particulars see Table LII.)

261. The length of the solar year from mean Mēsha-saṁkrānti to mean Mēsha-saṁkrānti according to this Siddhānta being $365^d 6^h 12^m 9^s$, it differs from that of the *Ārya-Siddhānta* year of $365^d 6^h 12^m 30^s$ by 21^s every year since K. Y. 0. The difference-Table given in *Indian Chronography*, p. 61, is here reprinted for ready reference (Table LIII). The difference is cumulative from K. Y. 0. In A.D. 1120, which is the very earliest date possible for the *Siddhānta-Śirōmaṇi* to have come into use (it was probably 30 years later), the moment of mean Mēsha-saṁkrānti by that authority was already $1^d 0^h 37^m 21^s$ earlier than the same according to the *Ārya-Siddhānta*, and the difference between them increased with every subsequent year. Consequently both mean and true Mēsha-saṁkrānti by the *Siddhānta-Śirōmaṇi* always fell respectively on the day previous to their occurrence by *Ārya-Siddhānta* reckoning, the time of which is given in the "*Indian Calendar*," Table I, cols. 13 to 17.

When therefore we are examining a date and have worked in the ordinary way for settlement of details by the *Ārya-Siddhānta*, using the *Indian Calendar* process for finding the values a , b , c , s and n , if we desire to find roughly the value of s according to the *Siddhānta-Śirōmaṇi* by use of the new Table XLVIII below for determination of the nakshatra by that authority, we must take the Table value of s (cols. 8-9) not for the Day-number given in the Table, but for the day next following. *E.g.*, if we suppose that preliminary examination of a date by the *Indian Calendar* process proves the record-date to be Day 120 (as measured from 1st Jan.) and that Table I, cols. 13-17, shew that by the *Ārya-Siddhānta* true Mēsha-saṁkrānti took place on Day 85, then in order to ascertain the equation and longitude of the sun by the *Siddhānta-Śirōmaṇi* we must take the details given in Table XLVIII not as given for (120-85) Day 35, but for Day 36, that number of days having elapsed since true Mēsha-saṁkrānti by the latter authority. For accuracy the difference between the times of true Mēsha-saṁkrānti by the two authorities must be allowed for.

262. Since the Table-entries are for each twenty-four hour period from true Mēsha-saṁkrānti in any year it is necessary to know the number of hours and minutes since sunrise of the occurrence of true Mēsha-saṁkrānti in the year in question, and deduct the sun's movement during those hours and minutes, in order to arrive at his true longitude at mean sunrise of the given day. For this purpose we may use Tables XLIX and L (in Vol. XIV above).² The

¹ Minus for years earlier, plus for years later, than the base-year.

² These stand exact for the *Ārya-Siddhānta*, but are close enough for general use. For absolute exactness see my last article (above, Vol. XIV, § 243).

method for finding these hours and minutes is detailed in *Indian Chronography*, pp. 27, 28, 61, 62; but to save reference it is repeated here, with the accompanying Table.

To find time of true *Mēsha-samkrānti* by the *Siddhānta-Śirōmaṇi*; (i) *The longer rule.* Take the moment of true *Mēsha-samkrānti* by the *Ārya-Siddhānta* from Table I of the *Indian Calendar*, cols. 13 to 17, adding 39^s in odd A.D. years, none in even (*Hist 20*, p. 79, *Indian Chronography*). Add the *śodhya* by that authority—always $2^d 3^h 32^m 30^s$. This gives time of mean *Mēsha-samkrānti*. Deduct for every year of the *Kaliyuga* expired at the given date the amount obtained from Table LIII below. This gives time of mean *Mēsha-samkrānti* by the *Siddhānta-Śirōmaṇi*. Deduct the amount of *śodhya* noted in Table LII below for the given year; for great exactness it may be found from col. 3, difference for the year in minutes and seconds being calculated from the entry for the beginning of each century: for close approximation take, without further calculation, the century entry in col. 4. The result is the required time of true *Mēsha-samkrānti* by the *Siddhānta-Śirōmaṇi*.

(ii) *The shorter rule.* Take the *Ārya-Siddhānta* time of true *Mēsha-samkrānti*—the first process in (i). Add together the amounts gathered from Table LIII—the third process in (i)—and the number of minutes for the century in col. 5 of Table LII. Deduct the total from the *Ārya-Siddhānta* time of true *Mēsha-samkrānti*. The result gives the required time of true *Mēsha-samkrānti* by the *Siddhānta-Śirōmaṇi* with sufficient exactness for ordinary purposes. Examples are given in *Indian Chronography*, p. 27, and need not be repeated.

My future Tables will entirely do away with the necessity of finding the moment of true *Mēsha-samkrānti* by the *Siddhānta-Śirōmaṇi*, the correct time being given for each year.

263. Calculation for the correct tithi-index by the *Siddhānta-Śirōmaṇi* may for the present be considered as sufficiently carried out by work according to the *Ārya-Siddhānta*; there will often be a difference between the two. Correction of the equation (*see above*, Vol. XIV, § 247, ii, the tithi) may cause a difference of one unit in the tithi-index, and there may be a slight difference in consequence of a different mean anomaly value requiring the equation to be calculated from a different base-angle.

Construction of the Main-Table XLVIII C.

264. In order to conform to my similar Tables for the *Ārya- and Sūrya-Siddhāntas* (*above*, Vol. XIV, Tables XLVIII A and B), I have worked for the year K. Y. 4500, expired, A.D. 1399-1400. The first thing was to fix the exact value of the sun's mean anomaly in that year at the moment of true *Mēsha-samkrānti*.

From Dr. Schram's fixture of the sun's equation of the centre by the *Siddhānta-Śirōmaṇi* at that moment in K. Y. 4000 as $2^{\circ} 8' 52'' 761328955$ and in K. Y. 5000 as $2^{\circ} 8' 59'' 319753357$ we find the equation in K. Y. 4500 to be $2^{\circ} 8' 56'' 040541156$, or, in 10,000ths of the circle, 59-691670842.

From Prof. Jacobi's determination of the position of the sun's apsis (I take perigee, not apogee) at that moment as $259^{\circ} 55' 12''$ in K. Y. 4000 and $259^{\circ} 12' 36''$ in K. Y. 5000 we find the perigee-point in K. Y. 4500 to be $259^{\circ} 3' 54''$, or, in 10,000ths of the circle, 7196-250 (exact).

The sun's mean anomaly at any moment is 360° minus the longitude of perigee and the equation of the centre. This, using the above figures, gives us his mean anomaly at that moment in K. Y. 4500 as $98^{\circ} 47' 9'' 959458844$ or, in decimals of a minute for purposes of calculation, $98^{\circ} 47' 163990981$; or, in 10,000ths of the circle, 2744-048329158.

Tested by the sine-and-equation-Table (Vol. XIV, Tables XLVII and XLVIII A) with use of the most accurate possible details (*for method see text* § 256, *above*, Vol. XIV) I find

that the result of calculation from that amount of mean anomaly gives the sun's true longitude as exactly 360° down to four decimals of a second. The figures, then, are accurate for the moment of true Mēsha-samkrānti in K. Y. 4500.

The sun's mean longitude at any moment is his true longitude less the equation of the centre, here $360^\circ - 2^\circ 8' 56'' 040541156$ or $357^\circ 51' 3'' 959458844$, or, in 10,000ths, 9940308329158.

These figures are given for the moment of true Mēsha-samkrānti at the head of the main Table.

Example.

265. An inscription is found dated "Śaka 1571 Virōdhin, 15 kṛishṇa of Mārgaśīra, Sunday, (nakshatra) Pūrva-Āshādhā, 24 Dhanu."

We work first by the Tables of the *Indian Calendar* in order to obtain a close approximation according to the *Ārya-Siddhānta*.

The year was K. Y. 4750 expired, or A.D. 1649-50. Its samvatsara-name was Virōdhin. In that year the lunar month Āshādhā was intercalated.

Calculation for the lunar tithi proceeds as usual—

	d.	se-d.	a.	b.	c.
(Beginning of lunar year) ...	63	1	29	415	212
(Table IV. Intercalating days) ...	294	0	9558	670	805
	357	1	9587	85	17
(Eqn. b, Table VI) ...			211		
(Eqn. c, Table VII) ...			54		
(Tithi-index) $t=9852$					

The day, 357, was (Table IX) 23 Dec. 1649 A.D. The week-day was 1 Sunday. The value of t shows that at mean sunrise of that day the tithi was 15 kṛishṇa (Table VIII).

For the nakshatra, as by the rough rule—

($c \times 10$) ...	170
(Constant) ...	7207
	7377
(Less eqn. c) ...	-54
	7323 ¹
(Sun's true longitude) ...	$s=$
(Tithi-index (above)) ...	$t=$ 9852
	7175
(Nakshatra-index) ...	$n=$

This nakshatra-index shews (Table VIII) that by the equal-space system of nakshatras the moon stood, at mean sunrise of the day in question, in Pūrva-Āshādhā.

¹ Calculation by Tables XLVIII and B shews that this value of s at mean sunrise of the Sunday in question is correct according to the *Ārya-Siddhānta*, the actual value being 7322.775. By the *Sārya-Siddhānta* it was 7320.7094.

For the solar month and date—

Table I, cols. 13-17, shews that true Mēsha-samkrānti in the given year took place on day 87 (measured from 1 Jan.), Wednesday, at 14^h 2^m after mean sunrise. The interval to Dhanus-samkrānti (*Indian Chronography*, Table XVIII) was 246^d 7^h 18^m.

d.	w-d.	h.	m.
87	4	14	2
246	1	7	18
333	5	21	20

The Dhanus-samkrānti took place late in the day on day 333 and by all rules the civil day called "1 Dhanus" was day 334, (6) Friday. The given day (above) being 357 there are 23 intervening days to be added to 1 Dhanus.

	d.	w-d.
1 Dhanus=	334	6
23	23	2
24 Dhanus=	357	1 (Sunday).

The day of the date was therefore in solar reckoning Sunday 24 Dhanus. Thus all the details of the date are proved correct by the *Ārya-Siddhānta*.

What would be the correct description of the date if it had been calculated by the *Siddhānta-Śirōmaṇi*? i.e. how would Sunday 23 Dec. 1649 A.D. have been described?

Since true Mēsha-samkrānti always took place by that authority a day earlier than by the *Ārya-Siddhānta*, the Sunday would have been 25, not 24, Dhanus.

The details of the tithi may, for present purposes, be taken as the same by both authorities, or almost the same.

To find the sun's true longitude, s , by the *Siddhānta-Śirōmaṇi*, we must first ascertain the moment of occurrence of true Mēsha-samkrānti in the given year by that authority. Future Tables will state this in the same way that Table I, *Indian Calendar*, does for the *Ārya-Siddhānta* (cols. 13-17). For the present it must be sought for. The rule is given above.

The given year was K. Y. 4750. Table LIII gives us the difference between the times of Mēsha-samkrānti according to the *Ārya-Siddhānta* and *Siddhānta-Śirōmaṇi* due to the difference in their year-lengths.

		h.	m.	s.
Diff. in 4000 years	...	23	20	0
700 "	...	4	5	0
50 "	...		17	30
		27	42	30

or 1^d 3^h 42^m 30^s. Add to this the difference due to shift of apsis—here, shortly, 48^m (col. 5). Total difference 1^d 4^h 30^m 30^s.

	d.	h.	m.	s.	
(Table I) True Mēsha-samk. by <i>Ārya-Siddh.</i>	87	14	2	30	
Less	— 1	4	30	30	
True Mēsha-samk. by <i>Siddh.-Śirōmaṇi</i>	...	86	9	32	0

True Mēsha-samkrānti by the *Siddhānta-Śirōmaṇi* took place in the given year on day 86 (measured from 1 Jan.) or Saturday 22 Dec. A.D. 1649.

The day of the inscription (measured from 1 Jan.) was 357. $357 - 86 = 271$, i.e. the inscription-day was 271 periods of 24 hours each after the moment of true Mēsha-saṁkrānti, and that moment was $9^h 32^m$ after mean sunrise.

Table XLVIII below shews that at $9^h 32^m$ after mean sunrise on Day 271 (measured from true Mēsha-saṁk.) the sun's true long., in 10,000ths of the circle, was 7365·9104. We deduct the sun's true motion for 9^h (on Day 271, Table XLIX) 10·6500 and for 32^m (Table L) 0·6084. Total 11·2584. $7365·9104 - 11·2584 = 7354·6520$. This is the exact sun's true long. at mean sunrise on the given day, Sunday 23 Dec. 1649. $s =$ (say) 7355 (the *Ārya-Siddhānta* gave this as = 7323, as we have seen above). Add the tithi-index, 9852, and we find n , the nakshatra-index, = 7207 by the *Siddhānta-Śirōmaṇi*.

Table VIII shews that the moon was by the equal-space system in Pūrva-Āshāḍhā. But it is almost certain that in the matter of nakshatras the *Siddhānta-Śirōmaṇi* followed the *Brahma-Siddhānta*, and, if so, the moon at mean sunrise would have been in Uttara-Āshāḍhā and this would have given its name to the day.

Thus the details 24 Dhanus and Pūrva-Āshāḍhā were correct according to the *Ārya-Siddhānta* for mean sunrise of 23 Dec. A.D. 1649 (they were also correct by *Sūrya-Siddhānta* calculation); but the correct details for the same date, if originally calculated by the *Siddhānta-Śirōmaṇi*, would have been "25 Dhanus" and "Uttara-Āshāḍhā."

266. This being so, the necessity for Tables for correct calculation by the *Siddhānta-Śirōmaṇi* and *Brahma-Siddhānta* is at once apparent; for, as matters stand, most chronologists, finding in a record-date the description of the solar month and nakshatra seemingly wrong by one place each, would class the date as irregular in two respects; and in using it for fixing the accession-date of a king, would give it scant attention. Whereas it was in fact perfectly correct and regular in all respects, but was calculated by a different standard authority from that followed by the modern verifier.

Prof. Jacobi's special Tables (*above*, Vol. I), no doubt, enable these problems to be worked out; but they are rather troublesome to handle, and do not yield the time-result so easily as does calculation by the a, b, c method which he first introduced to us. His later Tables (Vol. XI, p. 158 ff.) can be made available; but before using them the day of the solar month has to be accurately determined; and, like the *Indian Calendar* method, they are wanting in sufficiently close fixtue of the sun's true longitude at the given moment.

NOTE.

The figures in the following Table are correct for K. Y. 4500, A.D. 1399-1400. In ordinary work for computation of the sun's true longitude ("s" in the *Indian Calendar system*) they may be taken as applicable to all years during which the *Siddhanta-Siromaṇi* was in use.

But for very great accuracy in other calculations the figures are subject to the following alterations:—

(Cols. 2, 3, 4, 5).—Sun's mean anomaly and mean longitude. For every 100 years earlier than A.D. 1400 add (cols. 2, 4) $1^{\circ} 45' 0558$, or (cols. 3, 5) 0.8106 . For every 100 years later deduct the same.

(Cols. 6, 7).—Sun's equation of the centre. For every 100 years earlier than A.D. 1400 deduct (column 6) 0.6558 , or (col. 7) 0.0051 . For every 100 years later add the same.

TABLE XLVIII.C—Contd.

Siddhanta Sīromani.

24-hour periods from true Maha-sankranti.	Sun's mean anomaly (or mean sun's distance from perige- point) ($^{\circ}$ $0'$ $3''$).			Sun's mean longitude.		Sun's equation of the centre. +		Sun's true longitude ($^{\circ}$ $8'$ $3''$).						
	1	2	3	4	5	6	7	8	9					
										10,000ths of circle.	10,000ths of circle.	10,000ths of circle.		
16	114	33-34537	3183-1045	13	37	14-72	378-3543	1	53	40-56	15	35	55-28	433-3909
17	115	32-48158	3209-4823	14	36	22-89	408-7322	1	57	44-97	16	34	7-86	460-2458
18	116	31-01779	3236-8601	15	35	31-07	433-1101	1	56	46-39	17	33	17-95	487-1756
19	117	30-76400	3264-2380	16	34	39-24	460-4880	1	55	43-31	18	30	22-85	514-0652
20	118	29-80021	3291-6158	17	33	47-41	487-8658	1	54	40-33	19	28	27-75	540-3543
21	119	29-02642	3318-9987	18	32	55-59	515-2437	1	53	37-05	20	26	32-64	567-8445
22	120	28-16263	3346-3716	19	31	3-76	543-6316	1	52	29-38	21	24	33-18	594-7005
23	121	27-29884	3373-7495	20	31	11-93	569-9995	1	51	18-46	22	22	30-39	621-5808
24	122	26-43505	3401-1273	21	30	20-10	597-3773	1	50	7-50	23	20	27-60	648-3611
25	123	25-57126	3428-5052	22	29	28-28	624-7552	1	48	56-54	24	18	24-81	675-1915
26	124	24-70747	3455-8631	23	28	36-45	652-1331	1	47	39-36	25	16	15-80	701-9738
27	125	23-84369	3483-2610	24	27	44-62	679-5110	1	46	20-70	26	14	5-83	728-7443
28	126	22-97990	3510-6388	25	26	53-79	706-8888	1	45	2-05	27	11	64-85	755-5158
29	127	22-11611	3538-0167	26	25	0-97	734-2667	1	43	43-40	28	9	44-37	782-2868
30	128	21-25232	3565-3943	27	25	9-14	761-6445	1	42	19-43	29	7	28-60	809-0170
31	129	20-38853	3592-7725	28	24	17-31	789-0225	1	40	53-71	30	5	11-03	835-7332
32	130	19-52474	3620-1503	29	23	25-48	816-4003	1	39	27-97	31	3	53-45	862-4495
33	131	18-66095	3647-5282	30	22	33-66	843-7782	1	38	2-34	32	0	36-00	889-1687
34	132	17-79716	3674-9061	31	21	41-83	871-1561	1	36	30-09	33	58	11-92	915-8337
35	133	16-93387	3702-2840	32	20	50-00	898-5340	1	34	57-84	34	55	47-84	942-4988
36	134	16-06958	3729-6618	33	19	58-18	925-9118	1	33	25-59	35	53	23-76	969-1643
37	135	15-20579	3757-0397	34	19	6-35	953-2897	1	31	52-04	36	50	58-38	995-8209
38	136	14-34201	3784-4176	35	18	14-53	980-6676	1	30	13-87	37	48	28-39	1022-4413
39	137	13-47822	3811-7955	36	17	22-69	1008-0455	1	28	35-70	38	45	53-40	1049-0617
40	138	12-61443	3839-1733	37	16	30-87	1035-4233	1	26	57-54	39	43	28-40	1075-6831

1	2	3	4	5	6	7	8	9					
41	139	11-75054	38	15	39-04	1032-8012	1	25	16-54	39	40	55-58	1102-2915
42	140	10-88685	39	14	47-21	1090-1791	1	23	32-56	38	39	19-77	1128-8563
43	141	10-02306	40	13	55-38	1117-5570	1	21	48-48	37	38	43-87	1155-4311
44	142	9-15927	41	12	9-56	1144-9848	1	20	4-40	36	37	7-96	1182-0069
45	143	8-20543	42	11	11-73	1172-3137	1	18	16-54	35	36	28-37	1208-5615
46	144	7-43189	43	10	19-90	1199-9306	1	16	27-14	34	35	47-04	1235-0853
47	145	6-56790	44	9	28-07	1227-0685	1	14	37-74	33	34	5-31	1261-6189
48	146	5-70412	45	8	36-25	1254-4463	1	12	48-34	32	33	24-58	1288-1526
49	147	4-84033	46	7	44-42	1281-8242	1	10	54-36	31	32	38-78	1314-6511
50	148	3-97654	47	6	52-59	1309-2021	1	9	0-23	30	31	52-32	1341-1483
51	149	3-11275	48	5	0-76	1336-5800	1	7	6-10	29	30	6-56	1367-6455
52	150	2-24896	49	4	8-94	1363-9579	1	6	10-98	28	29	19-02	1394-1352
53	151	1-38517	50	3	17-11	1391-3357	1	5	12-12	27	28	29-23	1420-5359
54	152	0-52138	51	2	25-28	1418-7136	1	4	13-25	26	27	38-53	1447-0566
55	153	59-65759	52	1	33-45	1446-0915	0	59	14-39	25	26	47-84	1473-5173
56	154	58-70890	53	0	41-63	1473-4094	0	57	13-53	24	25	55-16	1499-9626
57	155	57-98001	54	0	49-80	1500-8472	0	55	10-53	23	24	0-33	1526-3914
58	156	57-06022	55	0	57-97	1528-2251	0	53	7-53	22	23	5-50	1553-8303
59	157	56-30244	56	0	6-15	1555-6030	0	51	4-52	21	22	10-07	1579-2490
60	158	55-33865	57	0	14-32	1582-9809	0	49	1-55	20	21	15-88	1605-6781
61	159	54-47436	58	0	22-49	1610-3587	0	47	56-19	19	20	18-68	1632-0886
62	160	53-61107	59	0	30-56	1637-7366	0	45	50-82	18	19	21-49	1658-4991
63	161	52-74728	60	0	38-84	1665-1145	0	43	45-45	17	18	24-29	1684-9066
64	162	51-88349	61	0	47-01	1692-4924	0	41	38-54	16	17	28-55	1711-2928
65	163	51-01970	62	0	55-18	1719-8702	0	39	27-62	15	16	32-80	1737-6760
66	164	50-15591	63	0	63-35	1747-2481	0	37	18-70	14	15	36-06	1764-0591
67	165	49-29212	64	0	71-53	1774-6260	0	35	9-79	13	14	39-31	1790-4423
68	166	48-42833	65	0	79-70	1802-0039	0	33	59-71	12	13	42-56	1816-8164
69	167	47-56454	66	0	87-87	1829-3817	0	31	48-43	11	12	45-81	1843-1813
70	168	46-70076	67	0	96-05	1856-7596	0	29	37-15	10	11	49-06	1869-5462
71	169	45-83697	68	0	104-22	1884-1375	0	27	26-51	9	10	52-31	1895-9161
72	170	44-97318	69	0	112-39	1911-5154	0	25	13-45	8	9	55-56	1922-2873
73	171	44-10939	70	0	120-56	1938-8933	0	23	0-30	7	8	58-81	1948-6185
74	172	43-24560	71	0	128-73	1966-2711	0	21	47-34	6	7	62-07	1974-9637
75	173	42-38181	72	0	136-90	1993-6490	0	19	34-62	5	6	65-32	2001-3335

TABLE XLV III-C—Contd.

24-hour periods from true Māha-samkrānti.	Sun's mean anomaly (or mean sun's distance from perige- point) ($^{\circ}$ $0'$).				Sun's mean longitude.		Sun's equation of the centre. +		Sun's true longitude ($^{\circ}$ $8'$).		Siddhānta-Sirōmaṇi.
	1	2	3	4	5	6	7	8	9	10,000ths of circle.	
76	173 41-51802	4824-7769	72 45 25-08	0 14 20-38	0-6387	72 59 45-46	2027-0656				
77	174 40-65423	4852-1547	73 44 33-25	0 12 5-14	0-6029	73 56 39-39	2054-0076				
78	175 39-79044	4879-5326	74 43 41-43	0 9 51-90	4-5671	74 53 33-33	2080-8497				
79	176 38-92665	4906-9105	75 42 49-60	0 7 37-95	3-5335	75 50 27-55	2106-6940				
80	177 38-06286	4934-2884	76 41 57-77	0 5 23-12	2-4932	76 47 20-89	2133-0315				
81	178 37-19908	4961-6662	77 41 5-94	0 3 8-29	1-4528	77 44 14-23	2159-8691				
82	179 36-33529	4989-0441	78 40 14-12	0 0 53-45	0-4125	78 41 7-57	2185-7066				
Sun in apogee	180 0-0	5000-0	79 3 54-00	0 0 0-0	0-0	79 3 54-00	2195-3333				
The sun's equation of the centre is—, minus, after his mean anomaly = 180° till it reaches 360° .											
	Sun's equation of the centre.				Sun's equation of the centre.				Sun's equation of the centre.		
83	180 35-47150	5016-4220	70 39 23-39	0 1 20-88	0-0340	70 38 1-41	2212-0480				
84	181 34-60771	5043-7989	80 38 30-46	0 3 35-71	1-0644	80 34 51-76	2239-3853				
85	182 33-74392	5071-1777	81 37 39-64	0 5 50-54	2-0748	81 31 49-10	2264-7230				
86	183 32-88013	5098-5565	82 36 40-81	0 8 5-37	3-0451	82 24 41-44	2291-0605				
87	184 32-01634	5125-9335	83 35 54-92	0 10 19-23	4-0780	83 25 35-65	2317-4055				
88	185 31-15255	5153-3114	84 35 3-15	0 12 33-47	5-0138	84 22 29-69	2343-7473				
89	186 30-28876	5180-6892	85 34 11-33	0 14 47-71	6-0496	85 19 23-62	2370-0897				
90	187 29-42497	5208-0671	86 33 19-50	0 17 1-94	7-0854	86 16 17-55	2396-4317				
91	188 28-56118	5235-4450	87 32 27-67	0 19 14-48	8-0981	87 13 13-19	2422-7839				
92	189 27-69740	5262-8229	88 31 35-84	0 21 27-54	9-0947	88 10 8-30	2449-1381				
93	190 26-83361	5290-2007	89 30 44-02	0 23 40-60	10-0614	89 7 3-42	2475-4893				
94	191 25-96982	5317-5786	90 29 52-19	0 25 52-74	11-0810	90 3 59-45	2491-8476				
95	192 25-10603	5344-9565	91 28 0-35	0 28 4-02	12-0940	91 0 56-34	2518-2125				
96	193 24-24224	5372-3344	92 28 8-53	0 30 15-31	13-0070	91 57 53-23	2544-5774				
97	194 23-37845	5399-7123	93 27 16-71	0 32 26-59	14-0200	92 54 50-12	2580-9423				

1	2	3	4	5	6	7	8	9						
98	195	5427-0901	94	26	24-88	2823-3401	0	34	36-30	16-0206	93	51	48-58	2607-3108
99	196	5454-4080	95	25	33-05	2950-7180	0	35	46-22	17-0156	94	48	47-83	2633-7024
100	197	5481-8459	96	24	41-22	2678-0959	0	38	54-14	18-0103	95	45	47-09	2660-0855
101	198	5509-2237	97	23	49-40	2705-4737	0	41	3-06	19-0061	96	42	46-34	2686-4657
102	199	5536-5010	98	22	57-57	2732-8516	0	43	9-15	19-0780	97	39	45-42	2712-8730
103	200	5563-8795	99	23	5-74	2760-2295	0	45	14-52	20-0454	98	36	51-22	2739-2841
104	201	5591-3574	100	21	13-92	2787-6074	0	47	19-89	21-0127	99	33	54-03	2765-6947
105	202	5618-7352	101	20	22-09	2814-9853	0	49	25-26	22-8801	100	30	56-83	2792-1062
106	203	5646-1131	102	19	30-26	2842-3631	0	51	30-13	23-8436	101	28	0-13	2818-5195
107	204	5673-4910	103	18	38-43	2869-7410	0	53	33-14	24-7927	102	25	5-30	2844-9453
108	205	5700-8689	104	17	46-61	2897-1189	0	55	36-14	25-7418	103	22	10-47	2871-3770
109	206	5728-2468	105	16	54-78	2924-4968	0	57	39-14	26-6909	104	19	15-38	2897-8058
110	207	5755-6246	106	15	2-95	2951-8746	0	59	37-09	27-6010	105	16	25-80	2924-2736
111	208	5783-0025	107	15	11-12	2979-2525	1	1	35-96	28-5182	106	13	35-17	2950-7343
112	209	5810-3804	108	14	19-30	3006-6304	1	3	34-82	29-4353	107	10	44-45	2977-1060
113	210	5837-7583	109	13	27-47	3034-0083	1	5	33-95	30-3545	108	7	53-52	3003-6597
114	211	5865-1361	110	12	35-64	3061-3861	1	7	28-08	31-2352	109	5	7-55	3030-1509
115	212	5892-5140	111	11	43-81	3088-7640	1	9	22-21	32-1158	110	2	21-00	3056-6482
116	213	5919-8919	112	10	51-99	3116-1419	1	11	16-85	32-9965	110	59	35-54	3083-1454
117	214	5947-2698	113	10	0-16	3143-5198	1	13	9-50	33-8703	111	56	50-56	3109-6494
118	215	5974-6476	114	9	8-33	3170-8976	1	14	59-00	34-7145	112	54	9-34	3136-1831
119	216	6002-0255	115	8	16-51	3198-2755	1	16	48-40	35-5586	113	51	28-11	3162-7169
120	217	6029-4034	116	7	24-68	3225-6534	1	18	37-80	36-4028	114	48	46-88	3189-2506
121	218	6056-7813	117	6	32-85	3253-0313	1	20	24-85	37-2288	115	45	8-00	3215-8025
122	219	6084-1591	118	5	41-02	3280-4091	1	22	8-93	38-0319	116	43	32-10	3242-3773
123	220	6111-5370	119	4	49-20	3307-7870	1	23	53-01	38-8349	117	40	56-19	3268-9521
124	221	6138-9149	120	3	57-37	3335-1649	1	25	37-09	39-6380	118	38	20-28	3295-6289
125	222	6166-2928	121	3	5-54	3362-5428	1	27	17-08	40-4096	119	35	48-46	3322-1332
126	223	6193-6706	122	2	13-71	3389-9206	1	28	55-25	41-1070	120	33	18-47	3348-7536
127	224	6221-0485	123	1	21-89	3417-2985	1	30	33-41	41-9245	121	30	49-47	3375-3740
128	225	6248-4264	124	0	30-06	3444-6764	1	32	11-58	42-6819	122	28	18-48	3401-9944
129	226	6275-8043	125	59	38-23	3472-0543	1	33	44-23	43-3968	123	25	54-00	3428-0574
130	227	6303-1821	126	58	46-40	3499-4821	1	35	16-48	44-1083	124	23	20-92	3455-3235
131	228	6330-5600	127	57	54-58	3526-8100	1	36	48-73	44-8205	125	21	5-64	3481-9895
132	229	6357-9379	128	57	2-15	3554-1879	1	38	19-87	45-5237	126	18	42-88	3506-6642

TABLE XLVIII.C—Contd.

24-hour periods from true Mēṣa-samkrānti.	Sun's mean anomaly (or mean sun's distance from perigee- point) (° C ²).			Sun's mean longitude.		Sun's equation of the centre.		Sun's true longitude (° S ²).		Siddhānta-Sirōmānī.	
	1	2	3	4	5	6		7	8		9
						°	'				
			10 000ths of circle.	°	'	°	'	10,000ths of circle.	°	'	10,000ths of circle.
133	229	62-28204	6385-3158	128 56	10-02	1 39	45-61	40-1853	127 16	26-31	3535-3805
134	230	61-41825	6412-0936	129 56	10-10	1 41	11-36	40-8409	128 14	7-73	3563-0907
135	231	60-55447	6440-0716	130 54	27-27	1 42	37-11	47-5086	129 11	50-16	3588-8180
136	232	49-09068	6467-4494	131 53	35-44	1 43	59-27	49-1479	130 9	85-47	3615-5516
137	233	48-82689	6494-8273	132 52	43-61	1 45	18-62	48-7548	131 7	25-00	3642-3225
138	234	47-96310	6522-2051	133 51	51-79	1 46	37-27	49-3616	132 5	14-52	3669-3085
139	235	47-09931	6549-5830	134 50	59-98	1 47	55-22	49-0685	133 3	4-04	3696-8645
140	236	46-23552	6576-9609	135 50	8-18	1 49	9-65	50-5374	134 0	58-48	3722-6785
141	237	45-37173	6604-3388	136 49	16-30	1 50	20-61	51-0850	134 58	55-69	3749-5038
142	238	44-50794	6631-7166	137 48	24-43	1 51	31-68	51-6325	135 56	52-90	3776-8241
143	239	43-64415	6659-0945	138 47	32-55	1 52	49-54	52-1801	136 54	50-11	3803-1044
144	240	42-78036	6686-4724	139 46	40-82	1 53	49-00	52-6929	137 52	51-42	3830-0905
145	241	41-91657	6713-8503	140 45	48-99	1 54	52-27	53-1811	138 50	56-72	3856-9191
146	242	41-05279	6741-2281	141 44	57-17	1 55	55-55	53-6894	139 49	1-02	3883-8088
147	243	40-18900	6768-6060	142 44	5-34	1 56	58-83	54-1576	140 47	6-51	3910-6984
148	244	39-32521	6795-9839	143 43	13-51	1 57	55-73	54-5967	141 45	17-78	3937-5972
149	245	38-46142	6823-3618	144 42	21-69	1 58	61-32	55-0259	142 43	30-36	3964-5862
150	246	37-59763	6850-7396	145 41	29-86	1 59	49-91	55-4545	143 41	42-96	3991-5351
151	247	36-73384	6878-1175	146 40	38-03	2 0	41-89	55-8788	144 39	56-14	4018-4888
152	248	35-87005	6905-4954	147 39	46-20	2 1	29-20	56-2489	145 38	17-01	4045-5016
153	249	35-00626	6932-8733	148 38	54-38	2 2	16-51	56-6998	146 36	37-87	4072-5144
154	250	34-14247	6960-2511	149 38	2-55	2 3	8-81	56-9739	147 34	58-73	4099-5273
155	251	33-27868	6987-6290	150 37	10-72	2 4	48-51	57-3187	148 33	22-21	4126-5603
156	252	32-41489	7015-0069	151 36	18-89	2 5	27-54	57-6193	149 31	51-36	4153-5970
157	253	31-55111	7042-3848	152 35	27-07	2 5	6-57	57-9211	150 30	50-50	4180-7137

1	2	3	4	5	6	7	8	9						
158	254	7069-7625	153	34	35-24	4266-0128	2	5	45-00	58-2222	151	28	49-54	4307-7904
159	255	7067-1405	154	33	43-41	4293-3905	2	6	20-01	58-4377	152	27	23-40	4334-9028
160	256	7124-5184	155	32	51-55	4320-7684	2	6	50-76	58-7250	153	26	0-83	4362-0434
161	257	7151-8963	156	31	59-76	4348-1463	2	7	21-51	58-9523	154	24	38-35	4380-1840
162	258	7179-2741	157	31	7-93	4376-5241	2	7	52-26	59-1995	155	23	15-07	4310-3245
163	259	7206-6530	158	30	18-10	4402-9020	2	8	15-27	59-3825	156	22	0-18	4343-5195
164	260	7234-0299	159	29	24-27	4430-2799	2	8	37-85	59-5513	157	20	40-43	4370-7386
165	261	7261-4078	160	28	32-45	4457-6578	2	8	59-73	59-7203	158	19	32-71	4397-9376
166	262	7288-7856	161	27	40-83	4485-0356	2	9	21-01	59-8890	159	18	19-01	4425-1467
167	263	7316-1635	162	26	48-79	4512-4135	2	9	30-59	60-0045	160	17	12-21	4452-4030
168	264	7343-5414	163	25	56-97	4539-7914	2	9	49-60	60-1049	161	16	7-37	4479-5805
169	265	7370-9193	164	24	5-14	4567-1693	2	10	2-01	60-2053	162	15	2-53	4506-9640
170	266	7398-2972	165	24	13-31	4594-5473	2	10	15-43	60-3042	163	13	57-88	4534-2439
171	267	7425-6750	166	23	21-48	4621-9250	2	10	19-57	60-3962	164	13	1-92	4561-5889
172	268	7453-0529	167	22	29-66	4649-3029	2	10	23-71	60-3681	165	12	5-95	4588-9345
173	269	7480-4308	168	21	37-83	4676-6808	2	10	27-35	60-4001	166	11	9-98	4616-2807
174	270	7507-8087	169	20	46-00	4704-0587	2	10	29-82	60-4153	167	10	16-18	4643-6434
175	271	7535-1865	170	19	54-17	4731-4365	2	10	25-68	60-3893	168	9	28-49	4671-0632
176	272	7562-5644	171	19	2-35	4758-8144	2	10	21-54	60-3514	169	8	40-81	4698-4030
177	273	7589-9423	172	18	10-52	4786-1923	2	10	17-40	60-3195	170	7	53-12	4725-5738
178	274	7617-3202	173	17	18-09	4813-5701	2	10	8-51	60-2531	171	7	9-39	4753-3170
179	275	7644-6980	174	16	26-86	4840-9480	2	9	55-80	60-1527	172	6	31-07	4780-7953
180	276	7672-0759	175	15	35-04	4868-3259	2	9	42-79	60-0524	173	5	52-25	4808-2736
181	277	7699-4538	176	14	43-21	4895-7038	2	9	29-78	59-9520	174	5	13-43	4835-7018
182	278	7726-8317	177	13	51-35	4923-0817	2	9	10-16	59-8006	175	4	41-22	4863-2810
183	279	7754-2096	178	12	59-56	4950-4596	2	8	48-28	59-6318	176	4	11-28	4890-8277
184	280	7781-5874	179	12	7-73	4977-8374	2	8	26-40	59-4630	177	3	41-38	4918-3744
185	281	7808-9653	180	11	15-90	5005-2153	2	8	4-32	59-2941	178	3	11-38	4945-9212
186	282	7835-3432	181	10	24-07	5032-5932	2	7	39-59	59-0678	179	2	59-19	4973-5354
187	283	7862-7210	182	9	32-25	5059-9710	2	7	3-14	58-8205	180	2	29-11	5001-1505
188	284	7889-0989	183	8	0-42	5087-3490	2	6	32-38	58-6832	181	2	8-03	5028-7657
189	285	7916-4768	184	7	8-59	5114-7268	2	6	1-93	58-3481	182	1	46-07	5056-3786
190	286	7943-8547	185	6	56-76	5142-1047	2	5	23-89	58-0470	183	1	33-87	5084-0577
191	287	7970-2325	186	5	4-94	5169-4825	2	4	43-86	57-7458	184	1	21-08	5111-7307
192	288	8000-6104	187	5	13-11	5196-8604	2	4	4-83	57-4447	185	1	8-28	5139-4157

TABLE XLVIII-C—Contd.

Siddhanta-Sirōmani.														
24-hour periods from true. Māsa-sankranti.	Sun's mean anomaly (or mean sun's distance from perige- point) ($^{\circ}$ $0'$ $''$).				Sun's mean longitude.			Sun's equation of the centre.		Sun's true longitude ($^{\circ}$ $8'$ $''$).				
	1	2	3	4		5	6	7	8		9			
				°	'									
	°	'	10,000ths of circle.	°	'	°	'	10,000ths of circle.	°	'	10,000ths of circle.			
198	289	0-45470	8027-9883	188	4	21-28	2	3	24-08	57-1303	185	0	57-20	5167-1080
199	289	59-80090	8055-3062	189	3	29-45	2	2	36-77	58-7052	187	0	52-68	5194-8709
200	290	58-72712	8082-7440	190	2	37-63	2	1	49-04	59-4002	188	0	48-16	5222-5939
201	291	57-86338	8110-1219	191	1	45-80	2	1	2-15	60-0351	189	0	43-65	5250-8308
202	292	56-99954	8137-4998	192	0	53-97	2	0	11-12	60-6414	190	0	42-85	5278-1084
203	293	56-13675	8164-8777	193	0	2-15	1	59	15-53	61-2124	191	0	46-61	5305-9152
204	294	55-27196	8192-2555	194	59	10-32	1	58	19-94	61-7835	192	0	50-37	5333-7230
205	295	54-40817	8219-6334	195	58	18-49	1	57	24-36	62-3546	193	0	54-13	5361-5288
206	296	53-54439	8247-0113	196	57	26-66	1	56	28-42	62-9257	194	1	3-24	5389-3738
207	297	52-68060	8274-3892	197	56	34-84	1	55	32-15	63-4968	195	1	14-69	5417-2430
208	298	51-81681	8301-7670	198	55	43-01	1	54	35-87	64-0679	196	1	26-14	5445-1091
209	299	50-95302	8329-1449	199	54	51-18	1	53	39-60	64-6390	197	1	37-58	5472-9752
210	300	50-08923	8356-5228	200	53	59-35	1	52	43-32	65-2101	198	1	49-37	5500-8404
211	301	49-22544	8383-9007	201	52	67-52	1	51	47-04	65-7812	199	2	16-37	5528-6956
212	302	48-36165	8411-2786	202	51	75-69	1	50	50-76	66-3523	200	2	34-51	5556-5508
213	303	47-49786	8438-6564	203	50	83-86	1	49	54-48	66-9234	201	2	52-03	5584-4060
214	304	46-63407	8466-0343	204	49	92-03	1	48	58-20	67-4945	202	3	21-85	5612-2612
215	305	45-77028	8493-4122	205	48	100-20	1	47	61-92	68-0656	203	3	48-67	5640-1164
216	306	44-90649	8520-7901	206	47	108-37	1	46	65-64	68-6367	204	4	15-50	5668-0031
217	307	44-04271	8548-1679	207	46	116-54	1	45	69-36	69-2078	205	4	43-15	5696-0002
218	308	43-17892	8575-5458	208	45	124-71	1	44	73-08	69-7789	206	5	17-17	5724-0087
219	309	42-31513	8602-9237	209	44	132-88	1	43	76-80	70-3500	207	5	50-59	5752-0082
220	310	41-45134	8630-3016	210	43	141-05	1	42	80-52	70-9211	208	6	24-31	5780-0077
221	311	40-58755	8657-6794	211	42	149-22	1	41	84-24	71-4922	209	7	1-11	5808-0049
222	312	39-72376	8685-0573	212	41	157-39	1	40	87-96	72-0633	210	7	41-54	5836-0040

1	2	3	4	5	6	7	8	9						
218	313	8712.4352	212	43	45.60	5908.0853	1	34	23.63	43.7009	211	8	21.96	5864.9843
219	314	8739.8130	213	41	53.77	5926.0630	1	32	61.38	43.6891	212	9	2.39	5893.0740
220	315	8767.1908	214	41	1.94	5943.4409	1	31	15.64	43.2503	213	9	40.31	5921.1906
221	316	8794.5686	215	40	10.13	5960.8188	1	29	37.47	41.4928	214	10	23.64	5949.3860
222	317	8821.9467	216	39	18.29	5978.1967	1	27	59.31	40.7384	215	11	18.98	5977.4613
223	318	8849.3245	217	38	26.46	6005.5745	1	26	21.14	39.9779	216	12	5.32	6006.5966
224	319	8876.7024	218	37	34.63	6032.9524	1	24	38.05	39.1855	217	12	56.58	6033.7699
225	320	8904.0803	219	36	42.81	6060.3303	1	22	53.97	38.3794	218	13	43.84	6061.9609
226	321	8931.4582	220	35	50.98	6087.7082	1	21	9.89	37.5753	219	14	41.09	6090.1319
227	322	8958.8361	221	34	59.16	6115.0861	1	19	25.38	36.7699	220	15	33.77	6118.3161
228	323	8986.2139	222	34	7.33	6142.4639	1	17	35.98	35.9258	221	16	31.35	6145.5382
229	324	9013.5918	223	33	15.50	6169.8418	1	15	46.58	35.0816	222	17	28.92	6174.7803
230	325	9040.9697	224	32	23.67	6197.2197	1	13	57.17	34.2375	223	18	26.80	6202.9822
231	326	9068.3476	225	31	31.84	6224.5976	1	12	6.18	33.3934	224	19	25.60	6231.2155
232	327	9095.7254	226	30	40.02	6251.9754	1	10	12.05	32.5504	225	20	27.97	6259.4751
233	328	9123.1033	227	29	48.19	6279.3533	1	8	17.91	31.7071	226	21	30.27	6287.7336
234	329	9150.4812	228	28	56.36	6306.7312	1	6	28.78	30.7800	227	22	33.58	6315.9931
235	330	9177.8591	229	28	4.53	6334.1091	1	4	26.91	29.8872	228	23	37.63	6344.2718
236	331	9205.2369	230	27	12.71	6361.4869	1	2	25.04	28.9201	229	24	44.66	6372.5668
237	332	9232.6148	231	26	20.88	6388.8648	1	0	23.18	28.0023	230	25	51.70	6400.8619
238	333	9260.9927	232	25	29.05	6416.2427	0	58	30.32	27.0858	231	26	58.74	6429.1569
239	334	9288.3706	233	24	37.22	6443.6206	0	56	27.92	26.1414	232	28	9.30	6457.4792
240	335	9315.7484	234	23	45.40	6471.9984	0	54	24.92	25.1923	233	29	20.48	6485.8061
241	336	9343.1263	235	22	53.57	6500.3763	0	52	21.93	24.2432	234	30	31.05	6514.1331
242	337	9370.5042	236	22	1.74	6528.7542	0	50	18.91	23.2933	235	31	42.83	6542.4008
243	338	9397.8821	237	21	9.91	6557.1321	0	48	15.08	22.3885	236	32	54.84	6570.7935
244	339	9425.2599	238	20	18.09	6585.5099	0	46	9.71	21.3712	237	34	6.38	6599.1387
245	340	9452.6377	239	19	26.26	6613.8878	0	44	4.34	20.4038	238	35	21.92	6627.4840
246	341	9480.0156	240	18	34.43	6642.2657	0	41	58.97	19.4865	239	36	35.46	6655.8292
247	342	9507.3935	241	17	42.61	6670.6436	0	39	48.74	18.4816	240	37	53.87	6684.2119
248	343	9534.7714	242	16	50.78	6699.0214	0	37	39.82	17.4869	241	39	10.96	6721.5845
249	344	9562.1493	243	15	58.95	6727.3993	0	35	30.90	16.4432	242	40	28.05	6749.9371
250	345	9589.5272	244	15	7.12	6755.7772	0	33	22.32	15.6900	243	41	44.81	6778.2722
251	346	9616.9051	245	14	15.30	6784.1551	0	31	11.03	14.4370	244	43	4.36	6797.7181
252	347	9644.2830	246	13	23.47	6812.5329	0	29	59.75	13.4240	245	44	23.72	6826.1089

TABLE XLVIII-C—Contd.

Siddhānta-Sirōmapi															
24-hour periods from true Māha-sankrānti.	Sun's mean anomaly (or mean sun's distance from perigee- point) ($^{\circ} 0^{\circ}$).			Sun's mean longitude.		Sun's equation of the centre.			Sun's true longitude ($^{\circ} 8^{\circ}$).			10,000ths of circle.			
	1	2	3	4	5	6	7	8	9						
			10,000ths of circle.												
253	348	8-62735	9670-0808	247	12	31-64	6865-9108	0	26	48-47	12-4110	246	45	43-17	6854-4698
254	349	7-76356	9698-0397	248	11	39-81	6894-2887	0	24	37-17	11-3979	247	47	2-64	6882-8908
255	350	6-89078	9725-4150	249	10	47-99	6921-6666	0	22	24-11	10-3713	248	48	23-97	6911-2953
256	351	6-03699	9752-7944	250	9	56-16	6949-0444	0	20	11-06	9-3446	249	49	45-10	6939-6999
257	352	5-17220	9780-1723	251	9	4-33	6976-4223	0	17	58-00	8-3179	250	51	6-33	6968-1044
258	353	4-30841	9807-5502	252	8	12-50	7003-8002	0	15	44-84	7-2904	251	52	27-66	6996-5097
259	354	3-44462	9834-9281	253	7	20-68	7031-1781	0	13	30-60	6-2647	252	53	50-07	7024-9234
260	355	2-58063	9862-3059	254	6	28-86	7058-5559	0	11	16-36	5-2189	253	55	13-49	7053-3371
261	356	1-71704	9889-6838	255	5	37-02	7085-9338	0	9	2-12	4-1831	254	56	34-90	7081-7508
262	357	0-85325	9917-0617	256	4	45-20	7113-3117	0	6	47-95	3-1478	255	57	57-24	7110-1039
263	357	59-08946	9944-4396	257	3	53-37	7140-6896	0	4	33-12	2-1074	256	59	30-24	7138-5321
264	358	50-12567	9971-8174	258	3	1-54	7168-0674	0	2	18-39	1-0671	258	0	43-25	7167-0004
265	359	59-26188	9999-1953	259	2	9-71	7195-4453	0	0	3-46	0-0267	259	2	6-25	7195-4186
Sun in perigee	360	0-0	10000-0	260	3	54-00	7195-8233	0	0	0-0	0-0	260	3	54-00	7195-8233
(The sun's equation of the centre is +, plus, after his mean anomaly = 360° till it reaches 180° .)													Sun's equation of the centre.		
266	0	57-39810	26-5292	260	1	17-89	7222-8232	0	2	10-87	1-0988	260	3	28-76	7223-8830
267	1	56-63431	63-9511	261	0	26-06	7250-2011	0	4	25-70	2-0501	261	4	51-76	7252-2512
268	2	55-07052	81-3289	261	59	34-23	7277-5789	0	6	40-53	3-0905	262	6	14-76	7280-6694
269	3	54-00373	108-7068	262	58	42-40	7304-9568	0	8	54-76	4-1262	263	7	37-16	7309-0831
270	4	53-94294	136-0847	263	57	50-58	7332-3347	0	11	9-00	5-1620	264	8	59-58	7337-4957
271	5	53-07915	163-4626	264	56	58-75	7359-7126	0	13	23-24	6-1978	265	10	21-99	7365-9104
272	6	52-21536	190-8404	265	56	6-92	7387-0904	0	15	37-48	7-2336	266	11	44-40	7394-3241
273	7	51-35157	218-2183	266	55	15-09	7414-4683	0	17	50-76	8-2621	267	13	5-66	7423-7304
274	8	50-48778	245-5962	267	54	23-27	7441-8462	0	20	3-82	9-2887	268	14	27-09	7451-1349
275	9	49-62399	272-9741	268	53	31-44	7469-2241	0	22	16-88	10-3154	269	15	48-32	7479-5395

	1	2	3	4	5	6	7	8	9						
276	10	45-76089	800-3519	269	52	39-61	7496-6019	0	24	29-03	11-3421	270	17	9-54	7507-9440
277	11	47-89643	827-7298	270	51	47-78	7523-5798	0	26	41-42	12-3666	271	18	29-20	7536-9304
278	12	47-03263	855-1077	271	50	55-96	7551-5677	0	28	52-70	13-3696	272	19	48-66	7564-7273
279	13	46-16884	882-4856	272	50	4-13	7578-7356	0	31	3-98	14-3826	273	21	8-11	7593-1182
280	14	45-30606	408-8634	273	49	12-30	7606-1134	0	33	15-27	15-3956	274	22	27-57	7621-5090
281	15	44-44196	437-2413	274	48	20-48	7633-4913	0	35	24-10	16-3897	275	23	44-58	7649-8810
282	16	43-57747	464-6192	275	47	28-06	7660-8692	0	37	33-02	17-3844	276	25	1-67	7678-2536
283	17	42-71368	491-9971	276	46	36-82	7688-2471	0	39	41-94	18-3792	277	25	18-76	7706-6262
284	18	41-84989	519-3760	277	45	44-09	7715-6250	0	41	50-85	19-3739	278	27	35-85	7734-9988
285	19	40-98610	546-7528	278	44	53-17	7743-0025	0	43	65-08	20-3867	279	28	48-80	7763-3396
286	20	40-12231	574-1807	279	44	1-34	7770-3807	0	46	1-00	21-3040	280	30	2-34	7791-9647
287	21	39-25832	601-5086	280	43	9-51	7797-7596	0	48	6-37	22-2714	281	31	15-88	7820-1900
288	22	38-39474	628-8865	281	42	17-68	7825-1365	0	50	12-74	23-2464	282	32	30-42	7848-3829
289	23	37-53095	656-2643	282	41	25-86	7852-5143	0	52	15-74	24-1955	283	33	41-60	7876-7099
290	24	36-66716	683-6422	283	40	34-03	7879-8922	0	54	16-75	25-1439	284	34	52-77	7906-0388
291	25	35-80337	711-0201	284	39	42-20	7907-2701	0	56	21-75	26-0937	285	35	3-95	7933-3638
292	26	34-93958	738-3980	285	38	50-37	7934-6480	0	58	23-30	27-0239	286	37	12-08	7961-9719
293	27	34-07579	765-7758	286	37	58-55	7963-0368	1	0	21-16	27-9411	287	38	19-71	7989-9689
294	28	33-21200	793-1537	287	37	6-72	7989-4037	1	2	20-03	28-8583	288	39	26-75	8018-3619
295	29	32-34821	820-5316	288	36	14-89	8016-7816	1	4	18-99	29-7754	289	40	33-78	8046-5570
296	30	31-48442	847-9025	289	35	23-07	8044-1596	1	6	18-26	30-6811	290	41	39-33	8074-8406
297	31	30-62063	875-2873	290	34	31-24	8071-5373	1	8	10-40	31-5617	291	42	41-64	8103-0990
298	32	29-75684	902-6652	291	33	39-41	8098-9152	1	10	4-53	32-4424	292	43	43-94	8131-3576
299	33	28-89306	930-0431	292	32	47-58	8126-2931	1	11	58-66	33-3230	293	44	49-25	8159-6161
300	34	28-02927	957-4210	293	31	56-76	8153-6710	1	13	50-16	34-1833	294	45	45-92	8187-8543
301	35	27-16548	984-7988	294	31	8-93	8181-0488	1	15	39-56	35-0275	295	46	43-49	8216-0753
302	36	26-30169	1012-1767	295	30	12-10	8208-4307	1	17	28-96	35-8716	296	47	41-06	8244-2983
303	37	25-43790	1039-5546	296	29	20-27	8235-8046	1	19	18-37	36-7158	297	48	38-64	8273-5204
304	38	24-57411	1066-9325	297	28	28-45	8263-1825	1	21	3-44	37-5255	298	49	31-89	8300-7090
305	39	23-71032	1094-3103	298	27	36-62	8290-5003	1	22	47-52	38-3296	299	50	24-14	8328-8900
306	40	22-84653	1121-6882	299	26	44-79	8317-9882	1	24	31-60	39-1327	300	51	16-39	8357-0709
307	41	21-98274	1149-0661	300	25	52-96	8345-3161	1	26	15-31	39-9330	301	52	8-28	8385-2491
308	42	21-11895	1176-4440	301	25	1-14	8372-6940	1	27	53-48	40-6904	302	52	64-63	8413-3844
309	43	20-25516	1203-8218	302	24	9-31	8400-0718	1	29	31-65	41-4479	303	53	40-96	8441-5197
310	44	19-39138	1231-1997	303	23	17-48	8427-4497	1	31	9-51	42-2053	304	54	27-29	8469-6550

TABLE XLVIII.C—Conold.

24-hour periods from true Mēṣa-samkrānti.		Sun's mean anomaly (or mean sun's distance from perigeo- point) ($^{\circ} 6'$).			Sun's mean longitude.			Sun's equation of the centre. +			Sun's true longitude ($^{\circ} 8'$).		
1		2	3	4	5	6	7	8	9				
			10,000ths of circle.		10,000ths of circle.		10,000ths of circle.		10,000ths of circle.				10,000ths of circle.
311	45	18-53759	1268-5776	304	23	25-56	8454-8276	1	32	46-18	305	55	11-34
312	46	17-65380	1282-9555	305	21	33-53	8482-2055	1	34	18-43	306	55	52-28
313	47	16-80001	1313-3333	306	20	42-00	8509-5833	1	36	56-69	307	56	32-68
314	48	15-93622	1340-7112	307	19	50-17	8536-9612	1	37	22-94	308	57	13-11
315	49	15-07243	1368-0891	308	18	58-35	8564-3391	1	38	51-66	309	57	50-01
316	50	14-20864	1396-4670	309	18	6-53	8591-7170	1	40	17-41	310	58	23-33
317	51	13-34485	1422-8448	310	17	14-59	8619-0948	1	41	43-16	311	58	57-85
318	52	12-48106	1450-2227	311	16	22-86	8646-4727	1	43	8-90	312	59	31-77
319	53	11-61727	1477-6006	312	15	31-04	8673-8506	1	44	29-13	313	0	0-17
320	54	10-75349	1504-9785	313	14	39-21	8701-2285	1	45	47-78	315	0	26-99
321	55	9-88970	1532-3563	314	13	47-38	8728-6063	1	47	6-43	316	0	53-81
322	56	9-02591	1559-7342	315	13	55-55	8755-9842	1	48	23-08	317	1	20-64
323	57	8-16212	1587-1121	316	12	3-73	8783-3621	1	49	35-96	318	1	39-69
324	58	7-29833	1614-4900	317	11	11-90	8810-7400	1	50	48-02	319	1	58-82
325	59	6-43454	1641-8678	318	10	30-07	8838-1178	1	51	57-59	320	2	17-96
326	60	5-57075	1669-2457	319	9	28-25	8865-4957	1	53	9-18	321	2	37-43
327	61	4-70696	1696-6236	320	8	36-43	8892-8736	1	54	12-45	322	2	48-88
328	62	3-84317	1724-0015	321	7	44-69	8920-2515	1	55	15-73	323	3	0-32
329	63	2-97938	1751-3793	322	6	52-76	8947-6293	1	56	19-01	324	3	11-77
330	64	2-11559	1778-7572	323	5	0-94	8975-0072	1	57	30-76	325	3	21-69
331	65	1-25181	1806-1351	324	5	9-11	9002-3851	1	58	16-34	326	3	26-45
332	66	0-38802	1833-5130	325	4	17-28	9029-7630	1	59	11-33	327	3	29-21
333	67	53-52423	1860-8908	326	3	26-45	9057-1408	2	0	7-52	328	3	32-97
334	68	53-66044	1888-2687	327	2	33-63	9084-5187	2	0	59-43	329	3	33-05
335	69	57-79665	1916-0466	328	1	41-80	9111-8966	2	1	46-74	330	3	26-54
336	70	57-93286	1943-4245	329	0	49-51	9139-2745	2	1	46-74	331	3	26-54
337	71	58-06907	1970-8024	330	0	58-02	9166-6524	2	1	46-74	332	3	26-54
338	72	58-20528	1998-1803	331	0	66-13	9194-0303	2	1	46-74	333	3	26-54
339	73	58-34149	2025-5582	332	0	74-24	9221-4082	2	1	46-74	334	3	26-54
340	74	58-47770	2053-9361	333	0	82-35	9248-7861	2	1	46-74	335	3	26-54
341	75	58-61391	2081-3140	334	0	90-46	9276-1640	2	1	46-74	336	3	26-54
342	76	58-75012	2108-6919	335	0	98-57	9303-5419	2	1	46-74	337	3	26-54
343	77	58-88633	2136-0698	336	0	106-68	9330-9198	2	1	46-74	338	3	26-54
344	78	59-02254	2163-4477	337	0	114-79	9358-2977	2	1	46-74	339	3	26-54
345	79	59-15875	2190-8256	338	0	122-90	9385-6756	2	1	46-74	340	3	26-54
346	80	59-29496	2218-2035	339	0	131-01	9413-0535	2	1	46-74	341	3	26-54
347	81	59-43117	2245-5814	340	0	139-12	9440-4314	2	1	46-74	342	3	26-54
348	82	59-56738	2272-9593	341	0	147-23	9467-8093	2	1	46-74	343	3	26-54
349	83	59-70359	2300-3372	342	0	155-34	9495-1872	2	1	46-74	344	3	26-54
350	84	59-83980	2327-7151	343	0	163-45	9522-5651	2	1	46-74	345	3	26-54
351	85	59-97601	2355-0930	344	0	171-56	9550-9430	2	1	46-74	346	3	26-54
352	86	60-11222	2382-4709	345	0	179-67	9578-3209	2	1	46-74	347	3	26-54
353	87	60-24843	2409-8488	346	0	187-78	9605-6988	2	1	46-74	348	3	26-54
354	88	60-38464	2437-2267	347	0	195-89	9633-0767	2	1	46-74	349	3	26-54
355	89	60-52085	2464-6046	348	0	204-00	9660-4546	2	1	46-74	350	3	26-54
356	90	60-65706	2491-9825	349	0	212-11	9687-8325	2	1	46-74	351	3	26-54
357	91	60-79327	2519-3604	350	0	220-22	9715-2104	2	1	46-74	352	3	26-54
358	92	60-92948	2546-7383	351	0	228-33	9742-5883	2	1	46-74	353	3	26-54
359	93	61-06569	2574-1162	352	0	236-44	9770-9662	2	1	46-74	354	3	26-54
360	94	61-20190	2601-4941	353	0	244-55	9798-3441	2	1	46-74	355	3	26-54
361	95	61-33811	2628-8720	354	0	252-66	9825-7220	2	1	46-74	356	3	26-54
362	96	61-47432	2656-2499	355	0	260-77	9853-0999	2	1	46-74	357	3	26-54
363	97	61-61053	2683-6278	356	0	268-88	9880-4778	2	1	46-74	358	3	26-54
364	98	61-74674	2711-0057	357	0	276-99	9907-8557	2	1	46-74	359	3	26-54
365	99	61-88295	2738-3836	358	0	285-10	9935-2336	2	1	46-74	360	3	26-54
366	100	62-01916	2765-7615	359	0	293-21	9962-6115	2	1	46-74	361	3	26-54
367	101	62-15537	2793-1394	360	0	301-32	9990-9894	2	1	46-74	362	3	26-54
368	102	62-29158	2820-5173	361	0	309-43	10018-3673	2	1	46-74	363	3	26-54
369	103	62-42779	2847-8952	362	0	317-54	10046-7452	2	1	46-74	364	3	26-54
370	104	62-56400	2875-2731	363	0	325-65	10074-1231	2	1	46-74	365	3	26-54
371	105	62-69921	2902-6510	364	0	333-76	10102-5010	2	1	46-74	366	3	26-54
372	106	62-83542	2930-0289	365	0	341-87	10130-8789	2	1	46-74	367	3	26-54
373	107	62-97163	2957-4068	366	0	349-98	10158-2568	2	1	46-74	368	3	26-54
374	108	63-10784	2984-7847	367	0	358-09	10186-6347	2	1	46-74	369	3	26-54
375	109	63-24405	3012-1626	368	0	366-20	10214-0126	2	1	46-74	370	3	26-54
376	110	63-38026	3039-5405	369	0	374-31	10242-3905	2	1	46-74	371	3	26-54
377	111	63-51647	3066-9184	370	0	382-42	10270-7684	2	1	46-74	372	3	26-54
378	112	63-65268	3094-2963	371	0	390-53	10298-1463	2	1	46-74	373	3	26-54
379	113	63-78889	3121-6742	372	0	398-64	10326-5242	2	1	46-74	374	3	26-54
380	114	63-92510	3149-0521	373	0	406-75	10354-9021	2	1	46-74	375	3	26-54
381	115	64-06131	3176-4300	374	0	414-86	10383-2800	2	1	46-74	376	3	26-54
382	116	64-19752	3203-8079	375	0	422-97	10411-6579	2	1	46-74	377	3	26-54
383	117	64-33373	3231-1858	376	0	431-08	10440-0358	2	1	46-74	378	3	26-54
384	118	64-46994	3258-5637	377	0	439-19	10468-4137	2	1	46-74	379	3	26-54
385	119	64-60615	3285-9416	378	0	447-30	10496-7916	2	1	46-74	380	3	26-54
386	120	64-74236	3313-3195	379	0	455-41	10525-1695	2	1	46-74	381	3	26-54
387	121	64-87857	3340-6974	380	0	463-52	10553-5474	2	1	46-74	382	3	26-54
388	122	65-01478	3368-0753	381	0	471-63	10581-9253	2	1	46-74	383	3	26-54
389	123	65-15099	3395-4532	382	0	479-74	10610-3032	2	1	46-74	384	3	26-54
390	124	65-28720	3422-8311	383	0	487-85	10638-6811	2	1	46-74	385	3	26-54
391	125	65-42341	3450-2090	384	0	495-96	10667-0590	2	1	46-74	386	3	26-54
392	126	65-55962	3477-5869	385	0	504-07	10695-4369	2	1	46-74	387	3	26-54
393	127	65-69583	3504-9648	386	0	512-18	10723-8148	2	1	46-74	388	3	26-54
394	128	65-83204	3532-3427	387	0	520-29	10752-1927	2	1	46-74	389	3	26-54
395	129	65-96825	3559-7206	388	0	528-40	10780-5706	2	1	46-74	390	3	26-54
396	130	66-10446	3587-0985	389	0	536-51	10808-9485	2	1	46-74	391	3	26-54
397	131	66-24067	3614-4764	390	0	544-62	10837-3264	2	1	46-74	392	3	26-54
398	132	66-37688	3641-8543	391	0	552-73	10865-7043	2	1	46-74	393	3	26-54
39													

1	2	3	4	5	6	7	8	9
336	69 56-33286	1943-0245	329 0 49-07	9139-2745	2 2 3 34-05	56-7442	331 3 24-02	9196-0187
337	70 56-06907	1970-4023	329 59 58-14	9166-6523	2 2 3 21-38	57-1092	332 3 19-50	9223-7016
338	71 55-20328	1997-7802	330 59 6-32	9194-0302	2 2 4 2-08	57-4304	333 3 9-30	9251-4606
339	72 54-34149	2025-1581	331 58 14-49	9221-4081	2 2 4 42-01	57-7310	334 2 56-50	9279-1397
340	73 53-47770	2052-5360	332 57 23-06	9248-7860	2 2 5 21-04	58-0327	335 2 43-70	9306-8187
341	74 52-61391	2079-9138	333 56 30-83	9276-1638	2 2 6 0-07	58-3339	336 2 30-00	9334-4977
342	75 51-75013	2107-2917	334 55 39-01	9303-5417	2 2 6 31-41	58-5757	337 2 10-42	9362-1174
343	76 50-89234	2134-6696	335 54 47-18	9330-9196	2 2 7 2-16	58-8180	338 1 49-34	9389-7326
344	77 50-02556	2162-0475	336 53 55-35	9358-2975	2 2 7 32-91	59-0502	339 1 28-26	9417-3477
345	78 49-15876	2189-4254	337 53 3-53	9385-9754	2 2 8 2-21	59-2763	340 1 5-73	9444-9616
346	79 48-20497	2216-8032	338 52 11-70	9413-0532	2 2 8 24-09	59-4451	341 0 35-78	9472-4383
347	80 47-43118	2244-1811	339 51 19-67	9440-4311	2 2 8 45-97	59-6139	342 0 5-84	9500-0450
348	81 46-56739	2271-5590	340 50 28-04	9467-8090	2 2 9 7-85	59-7828	343 59 35-82	9527-5917
349	82 45-70360	2298-9369	341 49 36-23	9495-1869	2 2 9 28-40	60-9414	343 59 4-02	9555-1282
350	83 44-83981	2325-3147	342 48 44-39	9522-5647	2 2 9 41-41	60-0417	344 58 25-91	9582-8065
351	84 43-97602	2353-6926	343 47 52-56	9549-9426	2 2 9 54-42	60-1421	345 57 46-98	9610-0847
352	85 43-11223	2381-0705	344 47 0-73	9577-3205	2 2 10 7-43	60-2425	346 57 8-16	9637-5630
353	86 42-24845	2408-4484	345 46 8-91	9604-6984	2 2 10 16-06	60-3161	347 56 25-67	9665-0144
354	87 41-38466	2435-8263	346 45 17-08	9632-0762	2 2 10 21-10	60-3480	348 55 38-18	9692-4242
355	88 40-52087	2463-2041	347 44 25-25	9659-4541	2 2 10 25-24	60-3800	349 54 50-49	9719-8341
356	89 39-65708	2490-5820	348 43 33-42	9686-8320	2 2 10 29-38	60-4119	350 54 2-81	9747-2439
357	90 38-79329	2517-9599	349 42 41-60	9714-2099	2 2 10 28-28	60-4034	351 53 9-88	9774-6133
358	91 37-92950	2545-3377	350 41 49-77	9741-5877	2 2 10 24-14	60-3715	352 53 13-91	9801-9592
359	92 37-06571	2572-7156	351 40 57-04	9768-9656	2 2 10 20-01	60-3395	353 51 17-95	9829-3051
360	93 36-20192	2600-0935	352 40 6-12	9796-3435	2 2 10 15-87	60-3076	354 50 21-98	9856-6511
361	94 35-33813	2627-4714	353 39 14-39	9823-7214	2 2 10 3-06	60-2159	355 49 18-27	9883-9373
362	95 34-47434	2654-8493	354 38 22-46	9851-0992	2 2 9 50-97	60-1155	356 48 13-43	9911-2148
363	96 33-61055	2682-2271	355 37 30-53	9878-4771	2 2 9 27-95	60-0151	357 47 8-59	9938-4322
364	97 32-74677	2709-6050	356 36 38-51	9905-8550	2 2 9 23-83	59-9093	358 46 2-73	9965-7613
365	98 31-88298	2736-9829	357 35 46-08	9933-2329	2 2 9 2-05	59-7380	359 44 47-03	9992-9709

TABLE LI.

THE CHANGE IN THE VALUE OF THE SUN'S MEAN ANOMALY FROM THE VALUE GIVEN TABLE XLVIII-C, COLS. 2, 3, FOR THE BASE-YEAR OF THAT TABLE, caused by the annual shift of the apsis of the sun's orbit postulated by the Siddhānta-Sirōmani.

[Add for years earlier, deduct for years later, than K. Y. 4500, A.D. 1399-1400.]

Years.	CHANGE.		Years.	CHANGE.		Years.	CHANGE.	
	Minutes and seconds.	10,000ths of circle.		Minutes and seconds.	10,000ths of circle.		Minutes and seconds.	10,000ths of circle.
1	0° 0' 174, or 1° 0' 44	0·0805	10	0° 1' 74, or 10° 44	0·0805	100	1° 74, or 1° 44 ^m 4	0·805
2	0° 0' 348, or 2° 0' 68	0·0161	20	0° 2' 48, or 20° 88	0·161	200	2° 48, or 2° 28 ^m 8	1·61
3	0° 0' 522, or 3° 0' 132	0·02415	30	0° 3' 522, or 31° 32	0·2415	300	3° 22, or 3° 13 ^m 2	2·415
4	0° 0' 696, or 4° 0' 176	0·032	40	0° 4' 696, or 41° 76	0·32			
5	0° 0' 870, or 5° 0' 220	0·04027	50	0° 5' 870, or 52° 20	0·4027			
6	0° 0' 1044, or 6° 0' 264	0·0483	60	1° 0' 44, or 1° 2' 64	0·483			
7	0° 0' 1218, or 7° 0' 308	0·05635	70	1° 1' 218, or 1° 13° 08	0·5635			
8	0° 0' 1392, or 8° 0' 352	0·064	80	1° 2' 392, or 1° 22° 52	0·64			
9	0° 0' 1566, or 9° 0' 396	0·07245	90	1° 3' 566, or 1° 33° 56	0·7245			

TABLE LII.

VALUE OF *śodhya* BY THE *SIDDHĀNTA-ŚIRŌMAṆI*,as fixed by Dr. Schram for seven centuries, and Table of difference between that authority and the *First Ārya-Siddhānta*.

In the year K. Y. expired	In A.D.	Exact value of <i>śodhya</i> .				Value to be used in calcu- lation by the longer rule.			Diff. between <i>Ārya- Siddh.</i> and <i>Siddh. Śirōmaṇi</i> values of <i>śodhya</i> ; for use by the shorter rule.
1	2	3				4			5
		d.	h.	m.	s.	d.	h.	m.	Minutes.
4200	1099-1100	2	4	18	49.0	2	4	19	46
4300	1199-1200	2	4	19	4.975	2	4	19	47
4400	1299-1300	2	4	19	20.95	2	4	19	47
4500	1399-1400	2	4	19	36.925	2	4	20	47
4600	1499-1500	2	4	19	52.9	2	4	20	47
4700	1599-1600	2	4	20	8.875	2	4	20	48
4800	1699-1700	2	4	20	24.85	2	4	20	48

The *śodhya* increases annually in amount by about 0.16, actually 0.15975.

TABLE LIII.

DIFFERENCE BETWEEN THE MOMENTS OF MEAN MĒSHA-SAMKRĀNTI AS CALCULATED BY (i) THE FIRST ĀRYA-SIDDHĀNTA, (ii) THE SIDDHĀNTA-ŚIRŌMAṆI, the two having been together at K. Y. 0 or B.C. 3102.

[The moment of mean Mēsha-samkrānti by the Ārya-Siddhānta having been found, deduct from this the time-difference for the K. Y. year of the given date. Result is moment of mean Mēsha-samkrānti by the Siddhānta-Śirōmaṇi.]

Diff. in years.	Time Difference.	Diff. in years.	Time Difference.	Diff. in years.	Time Difference.	Diff. in years.	Time Difference.
1	2	1	2	1	2	1	2
	h. m. s.		h. m. s.		h. m. s.		h. m. s.
1	0 0 21	10	0 3 30	100	0 35 0	1000	5 50 0
2	0 0 42	20	0 7 0	200	1 10 0	2000	11 40 0
3	0 1 3	30	0 10 30	300	1 45 0	3000	17 30 0
4	0 1 24	40	0 14 0	400	2 20 0	4000	23 20 0
5	0 1 45	50	0 17 30	500	2 55 0		
6	0 2 6	60	0 21 0	600	3 30 0		
7	0 2 27	70	0 24 30	700	4 5 0		
8	0 2 48	80	0 28 0	800	4 40 0		
9	0 3 9	90	0 31 30	900	5 15 0		

No. 19.—TWO INSCRIPTIONS FROM KURGOD.

BY LIONEL D. BARNETT.

Kurgōḍ is a village in the Bellary *tāluka* of the Bellary District, Madras: it is shown in the Indian Atlas sheet 58 (1827) as "Koorgode," in lat. 15° 21', long. 76° 54', about fourteen miles north-north-west from Bellary. The records now published give the name in the full form of Kurugōḍu; and the first of them puts the place in the Ballakundā *vishaya* (l. 17) or Ballakunde *nāḍ* (ll. 19, 47),—known from other sources as a three-hundred district,—which, again, it puts in the Kuntala country (ll. 14, 17). The name Kurugōḍu seems to mean "(the hill) having a small or low top," from *kuru* and *koḍu*, with reference to one or another of the hills which lie on the north and west of the place. The inscriptions place here a hill-fort (see A, vv. 12, 13, and B, l. 9). They speak of it in bombastic terms; but it seems to have been in ancient times really a fortress of strength and repute, as it is mentioned in the list of strongholds which were reduced by the Hoysala king Vishṇuvardhana I (see *Ep. Carn. XI* Dg. 25, p. 55) and Ballāla II (see Vol. XIII above, p. 176).

In 1801 Major Colin Mackenzie found at Kurgōḍ a stone tablet, nearly five feet high and three feet wide and about eleven inches thick. He removed it with the consent of the principal inhabitants, and it is now in the Imperial Museum at Calcutta. This stone bears two inscriptions, one on its front and the other on the back, the first of which, A below,¹ was brought to notice by a translation which was furnished to Major Mackenzie and was published in 1807 by Colebrooke in *Asiatic Researches*, Vol. IX, p. 433; see also Colebrooke's *Essays*, Vol. II, p. 240. That translation was not a very satisfactory one: to say nothing of its numerous errors of omission and commission, it introduced, quite gratuitously, the name of Śālivāhana into both the dates, regarding which point and its connections see Dr. Fleet's paper on "Śālivāhana and the Śaka Era" in *Journ. R. As. Soc.*, 1916, p. 809. I now edit the two records from ink-impressions placed at my disposal by the late Dr. Fleet, which are now in the British Museum.

A.—OF SOMESVARA IV AND THE SINDA PRINCE RACHAMALLA II:
SAKA 1095 AND 1103.

This record is on the front of the stone. Over it there are sculptures as usual: in the centre a *liṅga*; at the sides, the bull Nandi and probably a cow and calf; and above them, the sun and moon. The writing covers an area of about 3 ft. 8½ in. in height by 2 ft. 9 in. in width, and is in an excellent state of preservation.

The characters are Kanarese, about ½ in. in height on the average. They are well formed, of the upright type characteristic of the period. They include in line 1 three interesting letters which have been illustrated by Dr. Fleet in *Ind. Ant.*, Vol. XV, p. 364: the opening syllable *frt*, about 2½ in. high, is elaborated so as to present on the right side the front part of an elephant; and the *dra* of *chandra* and the *bha* of *Śambhava*, of the same height, are treated so as to form the front parts of two birds. With this may be compared the inscription *Ep. Carn. XI* (Chitaldroog), Cd. No. 47, which boasts of its engraver's skill in feats of this kind. In the same line the *ā* of *Sevayambhā* and the upper part of the *ai* in *trailōkya* are drawn out and expanded into ornamental designs, and the *i* in *chambi* is enlarged. On the last line also a number of subscript vowels and consonants are prolonged downwards in sweeping flourishes. The inscription is also remarkable for the frequent use that it makes of the special characters for *m*, *y*, and *v* noted above, Vol. XII, p. 335. Thus in lines 1-3 the proportion of the special to

¹ This record is entered as No. 253 in Professor Kieihorn's List of the Inscriptions of Southern India, Vol. VII above, appendix.

the regular *m* is 4 to 1, in lines 30-33 it is 15 to 10; the proportion of the special to the regular *v* in lines 1-3 is 4 to 14, in lines 30-33 it is 10 to 12.¹ The special *y* occurs 17 times. The *anusvara* is written sometimes above, sometimes on the right side of the preceding *akshara*.

The inscription has the unusual feature of being composed in three languages. Vv. 1-3 are Sanskrit; v. 4 is Prakrit;² and all the rest of the record is Kanarese, ll. 15-17 being prose, followed by poetry (vv. 10-24), including in verse 6 a metre, *Utsāha*, which is not of common occurrence, with occasional short prefaces in prose, a prose passage (ll. 32-35), a verse (v. 25), more prose (ll. 35-37), a verse (v. 26), and then prose from l. 38 to the end. The Sanskrit is ordinary. The Prakrit is more interesting. It is intended to be in the Śaurasēni dialect, and comes fairly near to success: thus its *-achchhō*, *-rakkhō*, and *Ḷachchhī*, as regards their internal consonants, are justified by the forms *achchhi*, *rakkha*, and *Ḷachchhi* authenticated for Śaurasēni (Pischel, *Gramm. d. Prakrit-sprachen*, pp. 219, 220, 216 respectively), though the *Ḷ* of *Ḷachchhī* is wrong, as is also *-vachchhō* (Śaurasēni *vakkha*: Pischel, *ib.*, p. 221). The rather rare word *akkhāra* deserves mention: see Pischel, *ib.*, p. 90. The Kanarese is of the ancient dialect in the metrical portions (an exception being *horeya*, l. 20); the prose is in the medieval language, with some vacillation as regards the conversion of initial *p* to *h* (e.g. *Piriya*, l. 36, *paḍuval*, ll. 40, 47, 48, *paḍuvala*, l. 41, *pū*, l. 40, but *Hāhe*, l. 40, *Hiriya*, l. 44, *hōha*, l. 48, etc.). The spelling *akāḷe* may be noted: Kittel gives only *akale*. The archaic *ḷ* is nowhere used. There is an instance of the accusative ending in *-a*, *tanna* (l. 20), on which see Dr. Fleet's remarks above, Vol. XI, p. 3, and note. Lexically interesting are: *°vabhayād*, l. 4; *gamgarim*, ll. 18-19; *irakeyane*, l. 21; *aḍaguntī*, l. 26 (cf. the Bankāpār inscription, l. 26, above, Vol. XIII, p. 171); *takkil*, unploughed land,³ ll. 40 ff.; *kammata*, l. 40; *dharmmēta*, l. 41; *hole*, ll. 41 ff.; *chinnageykada*, "goldsmith's work," l. 50 (with the phrase *chinnageykada-nakharanḡaḷ* there we may compare *māṇikyā-nakhara*, *m°-nakara*, *m°-nagara*, *māṇika-nakhara*, and *māṇika-nakara* in *Inscr. of Śravaṇa Belgōḷa*, Nos. 91, 94-5, 97, 106, 129), and *vaṭṭi[u°]g-āyam*, l. 50.

The inscription, though in reality a connected whole written at or soon after the time of the second date given in it, divides itself into three parts: the end of the first part, in l. 44, is marked by three conch shells, and the end of the second part is marked by one such shell at the end of l. 47. The first part, after eight introductory verses, mentions the Western Chālukya Sōmēśvara [IV] Tribhuvanamalla as the reigning king of Kuntala, ruling at the *nole-viḍu*, the standing-camp or cantonment,⁴ at Kalyāṇa (l. 16). It then proceeds to sing the praises of the province of Ballakunde (vv. 10, 11) and the hill-fort (*durga*) of Kurugōḍu (vv. 12-16), which is fancifully said to hold in check the Chōḷas, Gārjaras, Lāḷas (people of Southern Gujarāt), Pāḍyās, and Telugus (v. 13), and then goes to give an account of the family of the Sinda Mahāmaṇḍalēśvaras ruling in Kurugōḍu under the suzerainty of the Western Chālukyas. The first of them to be mentioned is the reigning prince, Irmaḍi-Rāchamalla, i.e. Rāchamalla II (v. 17); and we are told that his race sprang from an eponymous hero Sinda, born from the union of a Nāga king with the radiance from Śiva's sword (v. 18). In the lineage of Sinda arose Rāchamalla [I],⁵ who by Sōvala-dēvi begot Iruṅguja (vv. 19-20); the latter by Bala-dēvi had two sons, Rāchamalla II and Sōma (v. 21). Rācha-

¹ This includes the ligature *vve*, which regularly presents the special form.

² An instance of Prakrit occurring in the middle of a *prastuti* is found in *Ep. Carn.*, Vol. XI, Dg. No. 41.

³ I take this opportunity to call attention to the use of this term in the Ittagi inscription A, l. 81, above, Vol. XII, p. 49.

⁴ On the meaning of the term *nole-viḍu* see Dr. Fleet's paper "Neleviḍu: Appayagaviḍu" in *Journ. R. As. Soc.*, 1917, p. 115.

⁵ This Rāchamalla I is probably identical with the Sinda Rāchamalla who is known from other sources to have been ruling Ballakunde, in conjunction with his elder brother Irmaḍi-Bhima (Bhima II), as feudatories of Jagadōkamalla II (*Progr. Report of Asst. Arch. Supt. for Epigr., South. Circle, 1913-14*, pp. 87 f.).

malla II's prosperity, due to his devotion to Śiva, is described (vv. 22-24). Next we are introduced to a high minister of Rāchamalla I, the General and *Haḍapavaḷa* (bearer of the royal betel-bag) Bēchirāja (Bēcharasa or Bēchaiya), who built a temple to Śiva-Svayambhū and presented a memorial on the subject to Piriya-Rāchamalla, i.e. Rāchamalla I, who accordingly granted for its endowment in Śaka 1095 an estate which he vested in a certain Bāla Śivāchārya, an *āchārya* of the Kālāmukha and Lakulīśvara theology,¹ as trustee (ll. 33-44).

The second part (ll. 44 to 47) tells us that in Śaka 1103 Irmaḍi-Rāchamalla, i.e. Rāchamalla II, made an endowment, comprising the village of Jintegrāma and certain other concessions, to the same temple and trustee.

The third part (l. 48 to the end) records a grant of some land at Kurugōḍu to the same temple. And it then proceeds to tell us that, as the record euphemistically puts it, when Bēchirāja was going to Kailāsa in bodily form, that is, when he had died and his corpse was being cremated, his wives Baiḷiyakka and Malpāṇiyakka entered the fire, that is, immolated themselves with his corpse by the rite of Suttee, and, just before doing that, obtained the permission of the ruling prince for the making of certain other grants, naturally to the same temple.²

The inscription contains two dates, regarding which Dr. Fleet has given me the following remarks:—"In the first date (l. 38 f.) the details are: the cyclic year Vijaya, being the Śaka year 1095 (expired, = A.D. 1173-74); the new-moon *tithi* of Mārgaśīra; Sōmavāra (Monday); an eclipse of the sun. This date is an irregular one, in that the given *tithi* had no connection with a Monday: it answers to Thursday, 6 December, A.D. 1173, on which day it ended at about 20 h. 16 m. after mean sunrise (for Ujjain). Also, though there was a total annular eclipse of the sun, it was not visible in India.

"In the second date (l. 45) the details are: the cyclic year Plava, being the Śaka year 1103 (expired, = A.D. 1181-82); the full-moon *tithi* of Kārttika; Sōmavāra; an eclipse of the moon. This date, also, is irregular, as the given *tithi* here again had no connection with a Monday: it answers to Saturday, 24 October, A.D. 1181, on which day it ended at about 6 h. 18 m. after mean sunrise (for Ujjain); and there was no eclipse."

Geographical names are fairly numerous in this record. The chief are: Kuntala (ll. 14, 17); the *nale-viḍu* Kalyāṇa (l. 16); the country of Ballakunde (ll. 17, 19, 41, 47); Kurugōḍu (ll. 20-1, 23-4, 39, 48); the rivers Niraballa (l. 39) and Uppuvalla (l. 48); Bāḍanahatti (l. 41); Biyanahatti (l. 42); Arakere (ll. 42, 48); Domḍavatti (l. 43); Śripura (l. 45); Tekkekai (l. 46); Araḷiyahāḷu (l. 47); Haṁgave (l. 47); Goṛanahāḷu (l. 47); Jintegrāma (l. 47); Orvāyālūr (l. 48); Maṇivūr (l. 49); and Sūgūr (l. 49). Of the site of Kurugōḍu, the modern Kurgōḍ, we have already spoken. The Ballakunde district, in which it lay, is mentioned as a three-hundred district in an inscription of A.D. 1107 at Huvvinamaḍagu in Mysore (*Ep. Carn.*, Vol. XI, Chitaldroog, Dg. 128; cf. *ibid.* 126, and *Progress Report of Asst. Arch. Supt. for Epigr., South. Circle*, 1913-14, p. 88), and evidently was a division of the Sindavāḍi country, on which see Dr. Fleet's note in *Ind. Ant.*, Vol. XXX, p. 257.³ It took its name from what is now an insignificant village on the western bank of the river Hagari or Vēdavati in lat. 15° 32', long. 77°, marked on the Indian Atlas sheet 58 (1837) as "Bullakoondy"; it lies about fifteen miles north-east-by-north from Kurgōḍ. Bāḍanahatti appears on the same map as "Badanhattu," about two miles S.S.W. from Kurgōḍ; Orvāyālūr

¹ See *Progress Report of Asst. Archaeol. Supt. for Epigr., Southern Circle*, 1907-8, p. 88, 1914-15, pp. 88, 91, 101, and my remarks on the Yēvūr inscr. G, above, Vol. XII, p. 337.

Another epigraphic record of a case of Suttee, also attended by the making of grants, is found in the Rejastara inscription of A.D. 1057, Vol. VI above, p. 215.

It appears also in *Ep. Carn.*, Vol. XI, Dg. 126, 128.

perhaps as "Woravoy" ("Wórvayee" in the Registration List of Bellary District), some seven miles W. of Kurgōd; Mañivūr as "Munoor" (i.e. Mañūru), on the river Tungabhadra, in lat. 15° 20', long. 76° 47'; Sūgūru as "Soogoor," also on the Tungabhadra,¹ in lat. 15° 20', long. 76° 48'. Goranahālu (if I have read the name aright) may possibly be "Goranhully," some sixteen miles S.W. from Kurgōd; and Tekkekal may be safely identified with Tekkalakōṭe ("Tekkulkota" of the old maps), in lat. 15° 32', long. 77° 1½', the ending *kōṭe*, *kōṭa*, "fort," being a later addition, as in Bāgalkōṭ, the ancient Bāgaḍage.

The Sinda Princes.

The Sinda race² claimed to belong to the Nāga-vamśa, or lineage of the mythical Snakes, and the members of it usually bore the title of "lord of Bhōgavati." Including the dynasty of Kurgōd, we know of several reigning houses of this stock. The earliest branch that appears on record is that which ruled in Bāgaḍage (now Bāgalkōṭ) as feudatories of the Western Chālukyas at the end of the tenth and beginning of the eleventh centuries. Of them we have the pedigree: Kammayyarasa—Pulikāla (Śaka 912)—Nāgātiyarasa (Śaka 955)—Polasinda—Sōvyarasa (see *Ep. Ind.* above, Vol. III, p. 230; Kielhorn's *List*, *ibid.*, Vol. VII, app., Nos. 144 and 156).

Not very long after this we find another and a far more important branch, the Sindas of Erambarage (Yelburga), ruling in the same neighbourhood. The chief of these were Āchugi II, c. A.D. 1122, who governed the Kisukāḍu Seventy and the Nareyaṅgal Twelve as a feudatory of the Western Chālukya Vikramāditya VI; Permāḍi I, c. A.D. 1144, who ruled over the same provinces as well as the Kelavāḍi Three-hundred and the Bāgaḍage Seventy under Vikramāditya VI and Jagadēkamalla II; Chāvuṇḍa II, c. A.D. 1163-9, originally a feudatory of the Western Chālukya Taila III, who administered the Kisukāḍu Seventy, the Bāgaḍage Seventy, and the Kelavāḍi Three-hundred; and four sons of Chāvuṇḍa, Āchugi or Āchidēva III, A.D. 1163, Permāḍi II, A.D. 1163, Bijjala, A.D. 1169, and Vikrama, A.D. 1169 (see *J. Bo. B. R. A. S.*, Vol. XI, p. 219 ff.; *PSOI*, Nos. 67, 83; *Ind. Ant.*, Vols. IX, p. 96, and XXX, p. 266; Kielhorn's *List, Ep. Ind.*, Vol. VII, app., Nos. 218, 224, 233-4, 243). Āchugi II and Permāḍi I waged successful wars against the Kādambas of Gōva (Goa) and the Hoysaḷas of Dorasamudra. But the glory of their dynasty was short-lived: towards the end of the twelfth century the Hoysaḷas consolidated their kingdom to the north of the Tungabhadra, and before their risen star the Sindas of Yelburga apparently faded out of existence.

To this branch belonged a family that has left a record of itself in an inscription at Sāḍi, which will be published with others from that town in this journal. We learn thence that Āchugi or Ācharasa II, the son of Siṅgarasa II (a son of Āchugi I), begot by Siriyā-dēvi Permāḍi-dēva and Chāvuṇḍa II. Chāvuṇḍa married another Siriyā-dēvi, a daughter of Bijjala the Kaḷachurya; and their sons were Bijjala and Vikkayya (Vikrama). Vikkayya was ruling over Kisukāḍ, under the suzerainty of his cousin the Kaḷachurya Saṅkama, at the time of the grant (*Dyn. Kan. Distr.*, p. 576).

Yet another branch under the suzerainty of the Western Chālukyas is that represented by the Mahāmaṇḍalāśvara Muñja, ruling under Vikramāditya VI over the province of Arasibiḍi in Bijāpūr; he was the son of Sindarāja, who in turn was the son of Bhīma, governor of the Pratyāṇḍaka Four-thousand (see above, Vol. III, p. 306; Kielhorn's *List, ibid.*, Vol. VII, app., No. 189; *Ind. Ant.*, Vol. XXX, p. 266).

Another section of the same race was that which bore the title "lord of Karahāṭa" (in the Sātārā District); cf. *Ep. Carn.*, Vol. VII, 1, HL. 20, 50, Vol. XI, Dg. 42. To this belonged

¹ This is proved by the reference to a temple of the river-goddess, l. 49.

² See, generally, *Dynasties of the Kan. Distr.*, pp. 281 n., 299 n., 443, 450, 452, 458, 460, 462 f., 476 f., 495, 498, 497 f., 572-8.

the Sindas of Belagavatti, who at one time ruled over the Edavatte-nāḍ in Bellave, the Muduvalla Thirty, the Narigalige Forty, etc. They were descendants of Chattrassa I, whose grandson, Chattrassa II, was reigning in 1117 A.D.; the last of them on record is Haravira or Viradēva, in 1244-7. Of this family was a certain Īśvara at Halavūr, governing parts of the Banavāsi and Santalige provinces in 1165-72 A.D. under the suzerainty of the Kalachuryas (see *PSOCI*, No. 119; *Mysore Inscr.*, No. 32, p. 60; *Ind. Ant.*, Vol. XXX, p. 378; *Ep. Carn.*, Vol. XI, Dg. 42; Kielhorn's *List*, above, Vol. VII, app., No. 238). In the same connection belong the *Mahāmaṇḍalīśvara* Īśvara-dēva in Koppale about 1180 A.D., who is said to have conquered the Yādavas, etc. (see *Ep. Carn.*, VIII, 2, Sb. No. 276), and Īśvara-dēva of Belagavatti in 1193 A.D. (ib., Sa. No. 4).

We may also mention the following: Mulgunda-Sinda Jātarasa, who was governing the Kadambalige Thousand in 992 A.D. (*Ep. Carn.*, XI, Dg. No. 114); the *mahāsīmanta* Sindarasa, administering the *vaḍḍa-rāvuḷa-suṅka* of the Nolambavāḍi Thirty-two Thousand under the Chālukyas in 1108 A.D. (ib., Jl. No. 12); and the *mahāsīmanta* Barmadēvarasa in Arasibāḍi (*Ind. Ant.*, Vol. XXX, 1901, p. 266). Some references to minor Sindas in these regions of the Dekhan are to be found in *Ep. Carn.*, Vol. VIII, 2, Sb. Nos. 209, 203, 295, and Vol. XI, Hk. No. 23.

Finally we may notice a branch of the family in the Central Provinces. Here have been found records of a number of kings at Bastar, dating from 1065 A.D. onwards, who claimed to belong to the Chhinda or Chhindaka (i.e. Sinda) branch of the Nāga-vamśa, and bore the title "lords of Bhōgāvati" (*Ep. Ind.*, Vol. IX, p. 174; Vol. X, pp. 31, 35, 37, and perhaps 40; *Progr. Rept. Asst. Arch. Supt. for Epigr., South. Circle*, 1908-9, p. 111). The family-name as given here, *Chhinda* or *Chhindaka*, supplies us with the true etymology of the word *Sinda*: evidently the two words are identical, *Sinda* being the Dravidian equivalent (cf., e.g., Kanar. *sattige* from *chhattriḱā*). The Chhinda race is mentioned (under the form *Chhanda*) as one of the thirty-six Agni-kulas in Chand Bardāi's *Prithvirāj Rāsō*, I, p. 54, of the Nāgari-prachārīnt Sabhā's edition. It would thus seem that the Chhindas or Sindas were originally a family sprung from some Nāga tribe in the Central Provinces or thereabouts, whence some of them migrated towards the west.

Native legend supplies fanciful accounts of the origin of the race and its name. The present record (v. 18) tells us that the eponymous hero Sinda was born from the union of a Snake-king with the flashing sword in Śiva's arm (possibly an attempt to connect etymologically the name *Chhinda* or *Sinda* with the Sanskrit root *chhid*, "cut"); and again it announces in v. 22 (as also does B, v. 11) that his descendant Rāchamalla II was suckled by a tigress and had a cobra's dilated hood as an umbrella, which seems to point to some rites practised in the Sinda family to commemorate miracles supposed to have happened to their eponymous ancestor.¹ Light is thrown upon the two latter verses by a passage in the Bāgaḍage record (*Ep. Ind.*, Vol. III, p. 230 ff., ll. 10 ff.), where we are told that, when the serpent-king Dharanendra and his wife came upon the earth from the nether world, she gave birth at Abichchhattra, in the region of the river Sindhu (i.e. in Sindh), to a babe, which was hence named Sinda; the serpent-king gave him into the charge of a tigress, and on his attaining manhood made him king of that country; Sinda then married a Kaḍamba princess, and by her had three sons, from whom the Sinda family was descended. Here the birth of Sinda is localised at Abichchhattra (literally, "Snake-umbrella"), now Rāmnagar in the Bareilly District, apparently for no other reason than because popular etymology found in its name an allusion to the device of a Nāga on the state-umbrellas of the Sinda princes. We find a similar legend

¹ In the verse of A the suckling by the tigress and the cobra-umbrella may be referred grammatically to Sinda; but in B they are clearly predicated of Rāchamalla.

in the record of Īvara of Halavūr already mentioned (above, p. 269), according to which Sinda was the offspring of Śiva and the river Siadhu, and Śiva created a tigress to suckle him.

The memory of the Sindas' connection with the territory in the neighbourhood of Bellary is still preserved in local names: see Dr. Fleet's note on the Sindavādi country in *Ind. Ant.*, Vol. XXX, p. 257. A clear trace, as Dr. Fleet has pointed out to me, survives in the name of Sindanūr, "Sinda's Town," in the Mudgal division of the Nizam's territory, which is marked as "Sindunoor" in the Indian Atlas sheet 58 (1827), in lat. 15° 46', long. 76° 49', about twenty-nine miles north-by-west from Kurgōd.

TEXT.¹

[Metres: v. 1, *Śloka* (*Anuṣṭubh*); v. 2, *Mālinī*; vv. 3, 5, 11, *Śardulavikrīḍita*; v. 4, *Sragdharā*; v. 6, *Utsaha*; vv. 7, 21, 22, *Mattēbhavikrīḍita*; vv. 8-10, *Mahāsrāgharā*; vv. 12, 15-19, 24-26, *Kanda*; vv. 13, 20, *Utpalamālā*; vv. 14, 23, *Champakamālā*.]

- 1 Śri-Svayambhū-nāthāya namaḥ || Namaḥ-tuṅga-śiraś-chumbi-chaṁdra-chāmara-chāravā
[1*] traiḷōkyā-nagar-ārambha-mūla-stambhāya Śambhāvā || [1*]
- 2 Jayati viśada-kīrtiḥ prārthit-ārttha-prapūrtiḥ sakaḷa-bhuvana-varṭti dēvatā-chakra-
varṭti | vigata-Ditiya-dambhaḥ Pārvvati-pārirambhaḥ
- 3 pravinata-vidhu(du)-Śambhur-ddēva-dēva-Svayambhūḥ || [2*] Yasy-ōdvṛtta-pura-
trayaśya vijayā bhāl-ēkshaṇ-āgny-archchishā avidyach-chaṁdra-kaḷā-sravadbhir-amṛi-
tair-ujjivitaḥ sa stuvan || (1)
- 4 [mō]dē dēva-śiraś-karōṭi-nikaras-taj-jāta-rāv-ōdbhayād-Gauryyā yaḥ parirambhaḥ
smita-mukhas-tasmai namaḥ Śambhāvā || [3*] ²Gori-pipa-tthapa-ttha-tthagida-
ghuṣiṇa-diṇṇ-ekka-vaṇṇ-o(u)ggha-vachchhō
- 5 Kaṁdapp-o(u)ddappa-vipphāḷaṇa-ṇa-ṇivāṇō vichchhuranta-ttiṇchchhō | giḇbāp-
o(u)kkēra-rakkhō tiḷuvāṇa-bhavaṇ-ārambha-sambhanta-kambhō Lachchhi-ṇāḥa-
ppiyō so
- 6 jēnā sāt-jās paṁma-Sambhū Sayambhū || [4*] Śri-dēvi-ramaṇa-praṁ(pṛa)ṇṭta-
mahimam Bhābhṛit-sutā-vallabham pād-ānamra-sur-āsura-Endra-maku-
7 t-ōdyat-ōṣa-māṇikya-rak-prādur-bhḥḥṭa-diśam maṇō-mudado Sadyōjāta-vaktram
Svayambhū-dēvam namag-āgaḷam kuḍuge bha-
- 8 kti-śriyumaṁ śriyumaṁ || [5*] Utsāham || ³Vilasad-Amara-rāja-Rāja-rāja-Ditiya-
rāja-samkuḷa-viśāḷa-maḷi-ghṛiṣṭa-chaḷaṇa-naḷina-yoga-
- 9 lakam | saḷiḷa-dharapi-pavana-gaḷana-dahana-tarapi-āsādhara-ātma-lasad-aṣṭa-mūrti
Sambhu kuḍuge namag-abhiṣṭamaṁ || [6*] Padināḷkum bhu-
- 10 vanamgaḷam paḍadu tann-ichchh-ādi-śakti-tray-āspadadindam paripāḷisutt-akhiḷa-
bhṭa-brātadoḷ-jivit-ābhūdayaṁ māḍida Sambhu bhakta-
- 11 janatā-ohēta[s*]-athan-āg-irddu sammadadin-tamṇane tōrut-ikke satataṁ man-
māṇas-āmbhōjadoḷ || [7*] Mahāsrāgharā || Himavad-dhātṛi-dha-
- 12 rēndr-ātmaje kīru pereyam nōḍe jūṭa-sthamam tām kamaṭy-āḷōkadim tannaya
pere-nosaloḷ nīḷda bel-dimgaḷim pārpṇimey-āḷgal dēva | bāl-ēndu-
- 13 v-akaḷey-atipōṇṇ-ēmduvimḍ-ādud-ēmb-uttama-mugdhatvakke mechch-irdd-atīṣaya-
mahimam Sambhu rakshikke nammaṁ || [8*] Kaḷal-ēḷum dvipav-ēḷum kuḷa-
naga-chayav-ēḷum samāvēṣṭiṣal chelv-ōḍe Jami-

¹ From the ink-impression.

² The corresponding Sanskrit of this verse would be: Gauri-pīṇa-stana-stha-sthagita-ghuṣiṇa-datt-aiḷa-varṇ-
ōḍgha-vakṣhāḥ Kaṇḍarp-ōḷdarpa-viṣphāḷaṇa-ḷiḷa-nivāṇō vichchhurat-tryakṣhō | gīrvāṇ-ōḷkārya-rakṣha-
trībhuvana-bhavan-ārambha-sambhṛanta-skambhō Lakṣmi-nātha-priyāḥ sa jayati sātī-jayā narma-Śambhūḥ
Svayambhūḥ ||

³ Metre: *Utsaha* (see Nāgavarma's *Kannada Chāṇḍasaṁ*, Kittel's ed., p. 126). The *prasa* is imperfect, be-
cause in *vijāḍa*, *samāḷa*, and *saḷiḷa* being answered by *i* in *lasad*.

- 14 bādāvīpav-ā dvīpada Bharata-maht-bhāgado[-nādeyam nōrppado¹ kaṅg-atyanta-śobh-
āvaḥam-ene nega[-d-ī Kumtala-kahmāta-śrig-odeyam Chālukya-vamā-otpala-
vikasana-chandram viṣā-
- 15 [ā²-Āmarāndram || [9*] Mattam tat-prasasti-ent-endaḍe || Svasti
Samasta-bhuvan-āśrayam Śrī-Prithvi-vallabham mahārājādhirājam paramēśvara
paramabhaṭṭārakam Satyāśraya-
- 16 kuṣa-tīlakam Chālukya-ābharaṇam śrīmat-Tribhuvanamalla-Vīra-Sōmēśvara-dēvan-
uttarōttar-ābhividdhi-pravaraddhamānam-ā-chand-ārka-tāram Kalyāṇada
nele-viḍino[-sukha-samkathā-vinōdadin rā-
- 17 jyam geyyuttam-iral-ittal || Vṛi || ³Jaladhi-byāvēṣaṭṭi-ōrvvī-mahilege viṣaṣa-lōla-
bhāla-etha[-i-Kumtala-dēśan-tān-enipp-aunt-iral-esava lasat-Kumtala-kshōṇig-udyat-
tīlakam tām Ballakundā-vishaya-
- 18 m-adhika-lakshmi-samāsēvitam bhū-lalanā-lilā-viṣā-sphurita-kabarikā-kundad-ant-oppi
tōrkkuṁ || [10*] Ad-ent-endaḍe || Ūr-ār-ddappade pāta-bhūta-lateyīm
matt-āliyiṁ sāliyiṁ-ār-ār-ddappade gam-
- 19 garim kuḍiyarim śrīmatantaram kantarim-ār-ār-ddappade dēvatā-nīlayadin sad-
bhaktarim chelvu-vett-ār-ār-ddappade Ballakunde-naḍu-nā[-santam basantam
karam || [11*] Antu nāda naḍuve || Kam || ⁴Kela-balada jala-
- 20 da durggaṅgalan-alevudu nereya horeya taru-giri-durggaṅgalan-iṣi tanna⁵
meravudu kula-giri Kurugōḍa durgga-ā[r]ggam durggam || [12*] Vṛi ||
Chōlanan-ālav-aḍuvudu Gūrjjaranam sale tarjijukū
- 21 karam Lālanan-āli māḍuvudu Pāṇḍyanan-aṇḍalegum Teluṅga-bhūpālanan-ālid-
irkeyane māḍuvud-ī Kurugōḍa kōṭe tām kālegav-endaḍ-ā[-u-maḍi perchehuvud-
achchariy-āro kāḍuvar || [13*] Ā
- 22 kōṭeya pora-vo[-al-ent-endaḍe || Tīlaka-tamāla-tāla-kada[-i-vaku]-āvali-pāṭal-āli-
pippala-dala-māṭuṅga-ghanasāraka-kēsara-karṇāikāra-sālmali(li)-lava[-i-lavaṅga-saha-
kāra-kimśuka-nālikāra-
- 23 samkuṣa-sakaṣa-rttu-nandanadin-oppugum-ī Kurugōḍa suttalum || [14*] Mattav-
ā paṭṭanadol || Kam || Dhanadan-āli[-par-ddhanikar-vvanadhipanam nāguvar-
alli ratna-vivēkar-Mmanuvam polvar-jjanaper-jjana-nutav-ida polkuv-alto Bhō-
- 24 gāvatiyam || [15*] Bhaktiya mane bhaktiya nele bhaktiy-avati(to)⁶ bhaktiy-
ēlge bhaktiya rājam bhaktiya bhaṇḍaram Śiva-bhaktiya siri baṇḍu nelasit-
ī Kurugōḍo || [16*] Ā nagarakk-adhinātham Śrī-nāri-kucha-vilōla-kum-
- 25 kuma-vakham bhū-nutan-esedam nisadan-tān-Irmaḍi-Rāchamallān-spratimallam ||
[17*] Va || Ā nripan-aṇvayam-ent-endaḍe || Kam || Mṛidāna niḍu-dōla
bālina kaḍu-vogarina polapan-uragi gett-uragēndramn-to-
- 26 ḍardalli bhāva-ratiyind-ōḍan-ogedam Sīndan-akhīla-bhuvan-ābanda[m] || [18*]
Ant-ante Sīnda-bhāpana santatiy-aḍagunt perchoḥe perchohidan-ativikrāntam
Jaya-kāntam Śrī-kāntam Śrī-Rāchamalla-dharapi-kāntam || [19*] Śrī-vanit-ā-
- 27 śvarāṅge Śiva-pāda-sikhāmaṇi Rāchamalla-dēv-āvanipālakaṅge sati Sōvala-dēvige
puṭṭidam yasaḥ-śrī-varan-arthiga[-g-ereda poṅgalan-iṣṭakarāṅgalam samast-
āvanibhṛt-sa-maṅgalan-Irūṅgalan-īvan-n-

¹ For nōlpaḍe.² This second ā is superfluous.³ The *prāsa* is imperfect, unless we correct *lalanā* to *lalanā*.⁴ The *prāsa* is irregular, the alliteration being on the words *kēla*, *durgga-āṅgalan* (twice).⁵ See above, p. 266.⁶ The reading of this word is not certain; but I can think of nothing better.

- 28 datta-maṅgaḷaṁ || [20*] Mudadiṁ śrīmad-Iraṅguḷa-kṣhiti-vadhā-nāthaṅgav-
udyad-guṇ-āspadey-appe(ppa) Bala-dēvigan-tanayar-ādar-Bhbbīmanuṁ Pārtthanuṁ
toḍal-ill-embinēgaṁ kram-ōnnatiyoḷ-ā-
- 29 śā-varitti-sat-kirtti-sampadan-int-Irmaḍi-Rāchamalla-nīpanuṁ śrī-Sōma-bhūpāḷanuṁ
|| [21*] Ā yirvvarol tad-agraḷana mahimey-ent-eṁdaḍe || Vṛi || ¹Puli-
vāḷaṁ naliḍ-ūḍa śaktiy-ahiy-ōka-
- 30 ohh[eh]attrav²-āg-irdda peṁp-ala-vatt-ā chamari-mṛigaṁ chamara-jam tad-bhadra-
jāt-ibha-saṁkula-bhadr-āsana-rāḷya-chihua-sahitaṁ śrī-Sinda-Gōvindaṁ-ār-aḷav-all-
Irmaḍi-Rāchamallaṁ-adaṭim Bhōgindra-vamś-odbhavaṁ || [22*] Dhṛita-
mahimaṁ
- 31 mahi-nuta-sukh-ābhīnav-ātīśayaṁ yaśah-prakāśita-bhuvanaṁ nav-Ābja-nayanaṁ
naya-nandana-saṁhutaṁ tanūkṛita-Kaḷi-kāḷimaṁ maḷina-dāritan-Irmaḍi-
Rāchamalla-bhūpati-tīlakaṁ kaḷā-
- 32 kuṣaḷaṁ-āhava-chakkradoḷ-ā Ttrivikkramaṁ || [23*] Kaṁ || Poḍaviya samasta-
bhaktara naḍave Mṛiḍaṁ meechehi nicheha-varavaṁ kuḍal-Irmaḍi-Rācha-
malla-dēvaṁ paḍedaṁ nitya-prāsada-rāḷya-śrīyaṁ || [24*] Va || Anit-enisi ne-
gaḷda śrīman-mahāmaṇḍaḷēśvaraṁ-Irmaḍi-Rāchamalla-dēvaṁ rāḷyam-uttarōttaraṁ
susthiraṁ-āgutt-ire | tat-pāda-padm-ōpajivi Śiv-aika-bhāvi Kāśyapa-gōtra-pavitraṁ
Āohharasana putraṁ sarvv-ādhi-
- 34 kārī Telgara māri pati-kāryya-dhurandharan-abhinava-yugandharaṁ Vājasanēya-
kaḷ-āmbara-dyumaṇi māntri-chūḍāmaṇi Svayaṁbhū-dēva-labha-vara-prasādaṁ
śrīman-mahā-pradhānaṁ haḍapava-
- 35 jam Bēchirāḷana mahimey-ent-eṁdaḍe || Ka || Oḍaveyan-oḍalaṁ dēvargg-oḍan-
oḍano nivēdisutt[n*] Śiya-saonidhiyaṁ paḍedaṁ lōkadoḷ-orvvane haḍapavaḷaṁ
daṇḍanāyakaṁ Bēcharasaṁ || [25*] Va || Ant-ā Bēchara-
- 36 saṁ śrī-Svayaṁbhū-dēvargge dēv-ālayamaṁ-ettisi nija-patige dharmma-kāryyamam
vijūḍipala śrīman-mahāmaṇḍaḷēśvaraṁ Piriya-Rāchamalla-dēvarasar śrī-
Svayaṁbhū-dēvar-aṁga-bhōga-raṁga-bhōgakaṁ
- 37 alliya sthān-āchāryyaru avasti yama-niyama-svādhyāya-dhyāna-dhāraṇa-mō(maṇ)-n-
ānushṭhāna-Śiva-pūjā-tatparar-app-avara mahimey-ent-eṁdaḍe || Ka || Ā
Lākuḷēvar-āgama-Kaḷā(lā)mukha-
- 38 darśanaṅgaḷaṁ-tāḷdi tayo-lilege muv-ānt-irppaṁ Bāla-Śivāchāryya varyyan-
agaṇita-dhairyyaṁ || [26*] Va || Anit-enisida Bāla-Śivāchāryyara kāḷam
kacchehi vā(dhā)rā-pūrvvakam māḍi Sa(sa)ka-va-
- 39 rsha³ 1085neya Vije(ja)ya-samvatsaradha(da) Mārggaśirad-amāvāsyō Sōmavāra
sāryya-grahaṇa-tā(ta)t-kāledandu śrī-Svayaṁbhū-dēvargge koṭṭa keyi
Kurugōḍim mūḍa-voladalli Nīra-
- 40 haḷḷadiṁ paḍuval takkila mattaru 3 araṇata kammatadiṁ paḍuval sauḷ
mattar 1 Pūṇḍartakana keṛeyim mūḍaṇa pū-domṭa 1 dēvara montana gūḇa
2 Hāho-kall⁴ mū-
- 41 da-volada Ballakumḍeya hōle-veṛeyim paḍuval takkil mattar 12 ā vāra
Eraḍa keṛeyim teṁkalaṁ kiṇu-vattar⁵ 5 Bāḍanahattiyalū dharmmētaḍa
sthaḷadiṁ teṁkalaṁ takkila ma 1

¹ The *prās* in this verse is imperfect; the alliterative words are *puli*, *saṁkula*, *aḷa*, *aḷav*.

² Read *āḷa-āchāryyaru*.

³ It is to be noted that neither here nor in the second date in L. 45 below does the original contain the word *śālivāhana*; see remarks on p. 265 above.

⁴ Possibly, but less probably, *mattar*; see L. 48.

1. ...
 2. ...
 3. ...
 4. ...
 5. ...
 6. ...
 7. ...
 8. ...
 9. ...
 10. ...
 11. ...
 12. ...
 13. ...
 14. ...
 15. ...
 16. ...
 17. ...
 18. ...
 19. ...
 20. ...
 21. ...
 22. ...
 23. ...
 24. ...
 25. ...
 26. ...
 27. ...
 28. ...
 29. ...
 30. ...
 31. ...
 32. ...
 33. ...
 34. ...
 35. ...
 36. ...
 37. ...
 38. ...
 39. ...
 40. ...
 41. ...
 42. ...
 43. ...
 44. ...
 45. ...
 46. ...
 47. ...
 48. ...
 49. ...
 50. ...

- 42 alii Biyanahattiya dāriyīm temkaṇa kisu kammaṁ 450 Biyanahattiya-ūriṁ
temka Bhimanūtha-dēvara keyyīm mūḍaṇa takkila mattar 1 kammaṁ 450
Arakeṇyaḷu
- 43 Domdavaṭṭiya dāriyīm mūḍaṇa sṭhalav-eradaḱkaṁ kisu kamma. 700 alliya
bādumbeyanīm baḍagaṇa gadde-kaṭṭu 5 Puṇḍarikana kereya keḷage gadde-
kaṭṭu 3 int-iv-iniṭum
- 44 Hiriya-Rāchamalla-dēvaru munnaṁ koṭṭ-irddavu¹ [||*] Mattaṁ Simda-Gōvinda
sita[ga*]ra gaṁḍaṁ Pātāla-chakravartti Bhōgāvati-puravar-ādhivaram śri-
Vira-Kalidēva-nitya-prasādaṁ śri-
- 45 man-mahāmapḍalaśvaram Yirmmaḍi-Rāchamalla-dēvarasaru Śaka-varsha 1103
neya² Flava-samvatsu(tsa)rada Kārttika-punnami Sōmavāra sōma-grahapadaṁdu
Śripuravan-agrahāravam mūḍuva kālādala Bāla-Siva-dēva-
- 46 ra kūlaṁ karechi dhārā-pūrvvakam śri-Svayambhu-dēvar-aṁga-bhōgaṁ(ga)-raṁga-
bhōga-naivēdya-jirṇa-oddhāra-Chaitra-pavitra-svādhyāya-Vaiśeṣika-byākhyāna-khaṇḍi-
ka-Siva-dharma-purāṇa-pāṭhanav-anna-dānav-int-iniṭakkaṁ Tekkekala
- 47 hole-vēreyīm mūḍal Araliyahāḷa sṭmeyīm temkal Haṁgavoyīm paḍuval
Goranaḥāḷa³ sṭmeyīm baḍaḷa Ballakunde-nāḍa baḷiya pūrvva-sim-ānvitav-āgi-
koṭṭal Jintegrāma 1⁴ [||*]
- 48 Mattaṁ Kurugōḍa holadala Uppuvalladiṁ mūḍaṇa kisu-vattar 3 Or
vāyalūriṁ⁵ mūḍal Arakeṇya hole-vēreyīm paḍuval takkil ma 1 kamma
300 [||*] Mattaṁ Bēchaiyan-oḍale Kaiḷāsakke hōha
- 49 same(ma)yadal-agni-pravēśavam mūḍuvalli dharmma-patni patibrate Baiḷiyak-
kanuṁ Malpāṇiyakkanuṁ śrīmad-arasaram bēdi koṇḍu Maṇivūra sṭhaladala
Taṁgabhadra-dēviyīm temkal Sūgūra hole-vēre-
- 50 yīm mūḍuvala⁶ koṭṭa takkila mattar 2 chinnageykada-nakharasōgaḷuṁ kōḍi
aṇchēhina moḷeyalli koṭṭa dalakke viṣa 2 kōṇi 2 mattav-avaru koṭṭa(nḍa)lli
so 2 koṭṭalli so 2 mattaṁ aḅgaḍiyala saṭṭ[u*]g-āyam 1

TRANSLATION.

(Line 1.) Homage to the blessed Lord Svayambhū !

(Verse 1.) Homage to Śambhu, beauteous with the yak-tail fan which is the moon kissing his lofty head, the foundation-column for the construction of the city that is the threefold world !

(Verse 2.) Victorious is he of brilliant glory, fulfilling the objects of desire, pervading all worlds, emperor of gods, dispeller of Daityas' pride, embracer of Pārvati, Śambhu to whom sages bow, the Svayambhū who is god of gods.

(Verse 3.) Homage to that Śambhu on whose conquest of the haughty Three Cities by the fiery ray from his frontal eye the multitude of gods' skulls were restored to life by the nectars streaming from his oozing moon-digit, and praised him in delight ; and who smiles as Gauri embraces him in an access of terror at the clamour arising thence.

(Verse 4.) Victorious in victory over women is he whose magnificent breast has been given the same colour as the covering saffron lying on Gauri's full bosom, who is truly skilful in crushing Kāndarpa's pride, who has three flashing eyes, who protects the company of the

¹ After this word there are three *saṅkhas* on the stone, marking the end of that part of the record.

² The writer first wrote the figure 1102, and then corrected the 2 into a 3, not very successfully.

The syllable *Go* is somewhat doubtful.

Instead of *Or vāyalūriṁ* as two words, read *Orvāyalūriṁ*.

³ After this figure is the sign of a *saṅkha*.

⁴ Read *mūḍala*.

gods, through whom tremble the columns in the foundations of the structure of the three worlds, the friend of Lakshmi's Lord [Vishṇu], Śaṁbhu engaged in sport,¹ the Svayambhū.

(Verse 5.) May he whose majesty is extolled by the goddess Fortune's Lover [Vishṇu], the darling of the Mountain's Daughter [Umā], who illumines the regions of space with the radiance of the high ruddy rubies on the diadems of the princes of gods and demons bowing at his feet, who wears the Sadyōjāta-face,² the god Svayambhū, with joy of soul ever grant us fortune in devotion and prosperity.

(Verse 6.) May Śaṁbhu, whose two lotus-feet are grazed by the broad diadems of the brilliant King of Gods [Indra], the King of Kings [Vishṇu],³ and the multitude of princes of Daityas, and who bears the eight bright forms of water, earth, air, sky, fire, sun, moon, and soul,⁴ grant us (our) desire.

(Verse 7.) May Śaṁbhu, who, pervading and protecting the fourteen worlds from the seat of his three Powers of Will, etc.,⁵ creates prosperous life in the multitudes of all beings, dwelling in the souls of votaries, everlastingly with joy bestow a revelation of himself in the lotus of my spirit!

(Verse 8.) May Śaṁbhu of surpassing majesty preserve us—he who praises for her supreme simplicity the great mountain Himavat's Daughter, who, when she saw the little moon-crescent on his locks, (and) when through the bright light spreading over his moon-like brow in lovely lustre there was the phenomenon of a full moon, cried: "Lo, O God, the young moon has grown to an over-full moon!"

(Verse 9.) A place of beauty is the continent of Jambūdvīpa, which is surrounded by the seven seas, seven continents, and seven ranges of central mountains; as in the region of Bharata belonging to this continent there is to be seen a province [Kuntala], the lord of the goddess of this land of Kuntala, which is famed for displaying to the eye exceeding brilliance, is a moon expanding the lotuses of the Chālukya race, an Indra of bright semblance.

¹ I understand *paśāṁ-Saṁbhū* as *narma-Śaṁbhū*, comparing such expressions as *Nṛīta-Gaṇapati*, *Gita-Gōvinda*, etc.

² This is one of the *pañcā-mukha* or five faces or phases of Śiva. The beginning of this cult appears in the *pañcā-brāhma-māntra*, i.e. Taitt. Āraṇyaka X. 43-47, in which Sadyōjāta, Vāmadēva, Aghōra, Tatpuruṣa, and Īśāna are worshipped; Śāyana in loco says that Sadyōjāta is the western face, Vāmadēva the northern, Aghōra the southern, and Tatpuruṣa the eastern. This is elaborated in the *Pañcā-brāhma Upaniṣad* (especially § 7); and the *Bṛīhaj-Jālā Upaniṣad* i. 8 says that from the Sadyōjāta face arose Earth, thence the Nivṛtti Kalā, etc. The Southern Śaivas teach that Īśāna is the supreme phase, having the function of grace (*anugraha*), and termed *mūrti* ("embodied"); Tatpuruṣa, termed "mouth" (*vaktra*), with the function of concealment (*tirōdhāna*), pervades all souls as *antaryāmin* and conceals the nature of the universe by means of the *sapta-jālā* arising from the Nāda and Bindu; Aghōra, termed "heart" (*hṛdaya*), has the function of dissolution (*saṁhāra*); Vāmadēva, termed "secret organ" (*guhya*), with the function of maintaining the cosmos (*sthāiti*), keeps souls fettered in the illusion of Māyā and educes discriminate perception (*viśūṣa*), etc., from the Bindu; and Sadyōjāta, termed "body" (*mūrti*), with the function of creation (*śṛishṭi*), unites bodies to souls. Cf. Nallaivami Pillai's translation of Arupandi's *Śiva-śāstra-siddhāntar*, p. 156 n. The formula quoted in *Sarva-darśana-saṅgraha* (Calcutta edn., 1872, p. 95) identifies Īśāna with the head, Tatpuruṣa with the mouth, Aghōra with the heart, Vāmadēva with the secret parts, and Sadyōjāta with the feet; cf. Cowell and Gough's translation, p. 117. Cf. Gopinatha Rao, *Elements of Hindu Iconography*, Vol. II, pp. 64, 97 f., 365 f., 375-9, 384, 388, 404. See also *Mṛigendra Āgama* iii. 8, and also on the ritual *Kāraṇa Āgama* i. 64.

³ *Rāja-rāja*: cf. Śāvara-śākhara-vilāsa ii. 29, *ananta-bhūṣitaṇ-iṣṭādhara-rājan*.

⁴ Cf. *Mahābhārata* VII. ccli. 67 (Pratapchandra Ray's edn.), the opening stanzas of *Abhījñāna-sakuntala* and *Mālavikāgnimitra*, etc.; see also Nallaivami Pillai's *Studies in Saiva-siddhānta*, p. 93 ff., and Gopinatha Rao, *Elements of Hindu Iconography*, Vol. II, pp. 403 ff.

⁵ Namely, Thought (*jñāna*), Will (*icchā*), and Action (*kriyā*).

(Lines 15-17.) And as regards his titles: Hail! the asylum of the whole world, beloved of Fortune and Earth, the great Emperor, the *paramēśvara*, the *paramabhaṭṭāraka*, ornament of Śatyāśraya's race, embellishment of the Chāṭukyas, the fortunate Tribhuvanamalla Vira-Sōmēśvara-dēva, in a course of continually increasing prosperity reigning for as long as moon, sun, and stars endure at the standing-camp at Kalyāṇa in the enjoyment of pleasant conversations, then—

(Verse 10.) As one may call it "the land of Kuntala, the brilliant graceful brow of the Lady of the ocean-encompassed Earth," there is displayed of the radiantly brilliant land of Kuntala a high forehead-ornament, the county of Ballakundā, haunted by extreme good fortune, like a jasmine on the braided tresses, quivering in sportive grace, of the Lady Earth.

(Line 18.) If it be asked how this is:—

(Verse 11.) Adorned with pure creeping-plants, eager bees, (and) rice-crops, never a village failing; with *ganigas*, yeomen, wealthy and charming persons, never a village failing; with temples of gods, never a village failing; with worthy votaries, never a village failing—the mid-county of Ballakunde is delightful, in truth (*like*) the spring.

(Line 19.) So the midst of the county—

(Verse 12.) The stronghold of Kurugōḍa puts to shame the strongholds of the oceans on the right and left; surpassing strongholds of woods and hills on the adjoining sides, it displays itself (*like*) a central mountain, impassable to all.

(Verse 13.) This fortress of Kurugōḍu holds in control the Choḷa; it verily threatens the Gārjara; truly it rules over the Lāṭa¹; it presses sorely upon the Pāṇḍya; it confronts with opposition the monarch of the Telugas; in the matter of warfare it waxes seven times greater—a marvel! who can disturb it?

(Lines 21-22.) As regards the outer town of this fastness:—

(Verse 14.) It is resplendent around this Kurugōḍu with rows of *tīlakas* [*symplocos racemosa*], *tamāḷas* [*xanthochymus pictorius*], palmyras [*borassus flabelliformis*], plantains, *vakulas* [*mimusops elengi*]; with lines of trumpet-flowers [*bignonia suaveolens*]; with clumps of fig-trees [*figs religiosa*]; with multitudes of citron-trees [*citrus medica*], camphor-trees, *kāśaras*,² *karpikāras* [*pterispermum acerifolium*], silk-cotton trees, *lavāḷas*,³ clove-trees [*myristica caryophyllata*], mangoes, *kintukas* [*butea frondosa*], and coconut palms; and with parks of all seasons.

(Line 23.) Furthermore, in this town—

(Verse 15.) The wealthy make naught of the Wealth-giver [Kubēra]; the jewellers there laugh at the Lord of the Ocean [Varuṇa]; the rulers resemble Manu; famed among men, it is verily like Bhōgāvati.

(Verse 16.) A home of devotion; a site of devotion; an established order (?) of devotion; a (seat of) growth of devotion; a realm of devotion; a treasure of devotion—the spirit of devotion to Śiva has come and settled in this Kurugōḍu.

(Verse 17.) There has arisen in sooth a ruler of this town, whose bosom wears the charming saffron of the breasts of the Lady Fortune, the peerless Irmaḍi-Rāchamalla [i.e. Rāchamalla II].

(Line 25.) With regard to this king's lineage:—

(Verse 18.) When a lord of snakes, deeming the brightly flashing lustre of the sword in the long arm of the Gracious [Śiva] to be a female snake, had embraced it with delight of spirit, there was born Śinda, joy of all the world.

¹ Scil., the natives of Lāṭa, Southern Gujarat.

² The *Averrhoa acidula* or *Cicca disticha*.

³ Either the *Mesua ferrea* or *Bottleria tinctoria*.

(Verse 19.) When thus the line of king Sinda's descendants had waxed great, there grew to greatness the blessed Rāchamalla [I], a darling of Earth, exceedingly valorous, beloved of Victory, beloved of Fortune.

(Verse 20.) To king Rāchamalla-dēva [I], lord of the damsel Fortune, who bore as his crest-jewel Śiva's feet, and to the good lady Sōvals-dēvi was born a wooer of the goddess Fame, (namely) Iruṅguḷa, peer in blessings to all monarchs, exalted in blessings, a giver of gracious largesses of gold craved by suitors.

(Verse 21.) To (their) joy there were born to the blessed Iruṅguḷa, lord of the damsel Earth, and to Bala-dēvi, who was a seat of lofty virtues, sons who were in respective distinction a Bhīma and a Pārtha [Arjuna], as one may aver without untruth: to wit, king Irmadi-Rāchamalla [i.e. Rāchamalla II], endowed with goodly glory pervading the regions of space, and the fortunate king Sōma.

(Line 29.) As regards the greatness of the elder of these two:—

(Verse 22.) As he possesses the majesty of one who joyfully sucked and consumed a tigress's milk (and) had the unique umbrella of a Snake,¹ and bears as tokens of royalty these yak-cows, the offspring of the yak, a multitude of high-bred elephants, a throne of honour, and royal insignia, to whom is not peer in pride the blest Gōvinda of the Sindas, Rāchamalla II, scion of the lineage of the Snake-lords?

(Verse 23.) Possessing majesty, enjoying a singularly high degree of world-famed happiness, illuminating the world by his fame, a new Lotus-eyed [Viṣṇu], renowned in the Nandana-park of polity, reducing the impurity of the Kali (Age), far removed from impurity, is the ornament of kings Rāchamalla II, skilful in arts, that Trivikrama² in the circle of battle.

(Verse 24.) As the Gracious [Śiva], approving of him among all votaries of the earth, granted him a lasting boon, Rāchamalla-dēva II obtained royal fortune as a constant gift of grace.

(Lines 32-35.) As the kingdom of the Mahāmaṇḍalēśvara Rāchamalla-dēva II, who is thus renowned, was continuing in increasing security:—as regards the greatness of him who lives upon the lotuses of his feet, solely devoted to Śiva, purifying the Gōtra of Kaśyapa, son of Āchharasa, a General Officer, destroyer of Telugas, manager of his lord's affairs, a modern *yugandhara*,³ a sun in the sky of the Vājasanīya race, crest-jewel of ministers, receiver of the grace of boons from the god Svayambhū, the High Minister, the Bearer of the Betel-bag, Bēchirāja:

(Verse 25.) The Bearer of the Betel-bag, the General Bēcharasa, having offered immediately substance and body⁴ to the god, alone in the world was favoured with a revelation of Śiva.

(Lines 35-36.) So this Bēcharasa having raised a temple to the god Svayambhū and presented to his lord a memorial regarding the holy cult—

(Lines 36-37.) The Mahāmaṇḍalēśvara Piriya-Rāchamalla-dēvarasa [i.e. Rāchamalla I] for the personal enjoyment and theatrical entertainment of the god Svayambhū,—the local Āchārya there, a person devoted to—hail!—the major and minor disciplines, scriptural study, meditation, spiritual concentration, observance of (the vow of) silence, and worship of Śiva, as regards whose greatness—

¹ See above, p. 269.

² This epithet is chosen to indicate (1) that the king has the attributes of Viṣṇu, and (2) that he is extremely valiant (*tri-vikrama*, "triple prowess").

³ Literally, "supporter of the age." The title has been given to some ancient Jain teachers of supposed catholic importance.

⁴ Cf. the North Indian phrase *man tan dhan*, "soul, body, and property" (devoted to the deity).

(Verse 26.) The excellent Bāla Śivāchārya, immeasurable in strength of will, maintaining the Lākuṭṭisvara traditional lore and Kālamukha doctrines, applies himself to ascetic devotion as to a sport—

(Lines 38-44.) Having washed the feet of this Bāla Śivāchārya, with pouring of water, on Monday, the new-moon day of Mārgaśīra of the 1095th Śaka year, the cyclic year Vijaya, on the occasion of an eclipse of the sun, granted an estate to the god Svayambhū : viz. in the field east of Kurugōḍu, west of the Nirahalla stream, 3 *matṭar* of unploughed land ; on the west of the king's *kammata*¹, 1 *matṭar* of *saṇṭ*² ; to the east of Puṇḍarika's Tank, 1 flower-garden ; in front of (the temple of) the god, 2 oil-mills ; of the eastern field of Hāhe-kallu [the Doll's Stone], west of the boundary of the dry-lands³ of Ballakunde, 12 *matṭar* of unploughed land ; on the south of the Jujube-tree Tank of that town, 5 *matṭar* of red land (*kin*) ; in Bāḍanahatti, south of the grounds of the *dharmā*, 1 *matṭar* of unploughed land ; in the same, to the south of the road to Biyanahatti, 450 *kamma* of red land ; to the south of the village of Biyanahatti, east of the field of the god Bhīmanātha, 1 *matṭar* 450 *kamma* of unploughed land ; in Arakere, of the two grounds on the east of the road to Doṇḍavatti, 700 *kamma* of red land ; on the north of the *bāḍumbeya* of the same place, 5 paddy-fields⁴ ; below Puṇḍarika's Tank, 3 paddy-fields : this much was formerly granted by Rāchamalla-dēva I.

(Lines 44-45.) Furthermore, the Gōvinda of the Sindas, warrior to the wanton, emperor of Pātāla, lord of Bhōgāvati best of cities, endowed with constant boons from Vira Kalidēva, the Mahāmaṇḍalēśvara Rāchamalla-dēvarasa II,

(Lines 45-48.) on Monday, the full-moon day of Kārttika of the 1103rd Śaka year, the cyclic year Plava, during an eclipse of the moon, on the occasion of making Śrīpura an Agrahāra, after washing the feet of Bāla Śiva-dēva, with pouring of water, granted for the god Svayambhū's personal enjoyment, theatrical entertainment, offerings of food, restoration of worn-out (buildings), the *Chaitra* and *panitra*,⁵ scriptural study, lectures on the Vaiśeṣika, class-reading⁶ of the *Śīva-dharma-purāṇa*,⁷ and charitable gifts of food, the one [entire] village of Jintagrāma with its former bounds, within the county of Ballakunde, situate on the east of the boundary of the dry-lands⁸ of Tekkekal, south of the bound of Araḷiyahāḷu, west of Haṁgave, north of the bound of Goranahāḷu (?). Likewise, in the fields of Kurugōḍu, to the east of the Uppuvalḷa stream, 3 *matṭar* of red land ; to the east of Orvāyalūr, west of the boundary of the dry-lands of Arakere, 1 *matṭar* 300 *kamma* of unploughed land.

(Lines 48-50.) Furthermore, when they were entering the fire on the occasion when Bāchāya was going to Kailāsa in bodily form [lit. by his body⁹], his lawful wives the

¹ Possibly this is the same as the modern *kamata* (see Kittel, s.v.), but I doubt it.

² This would seem to be connected with *saṇṭu*, *saṇṭu*, "brackishness," also "muriate of lime."

³ *Hole*, dry land unsuitable for growing rice.

⁴ *Gadde-kutṭu*, ground suitable for growing paddy.

⁵ See *Ind. Ant.*, Vol. XXXVIII, p. 52.

⁶ Cf. *khaṇḍikada dharmā*, *Ep. Carn.* VII. 1, Hl. No. 66. A *khaṇḍika* is a class of students (ib. III. 1, TN. No. 27 ; VII. 1, Sk. No. 185 ; IX. Ba. No. 6 ; III. 1, TN. 27).

⁷ A book called *Śīva-dharma*, perhaps the same as this, is mentioned in *Ep. Carn.* Vol. VII. 1, Sk. No. 185. Cf. Aufrecht's *Catal. Catal.* s.v.

⁸ *Hole* : Mr. Narasimhaiah suggests however that this is a variant for *hola*.

⁹ *Oḍale* : Mr. R. Narasimhaiah in a letter to me has kindly pointed out that this is the instrumental case of *oḍale* with suffix -e. "Though Kōṣīrāja," he adds, "limits the suffix -e to neuter words ending in -a (*Śābdamaṇi-darpaṇa*, s. 107), we have examples of the suffix used in words of other genders and endings : *aṭṭiye* ('with affection'), *Ajita-purāṇa* I. 77-8 ; *muni-patiye pāle-paṭṭaṇḍu* ('it was stated by the lord of sages') ; *alkāre taḷke-geydu* ('having embraced with affection'), *ṭileye nuṅṅueva mṛityu* ('Death which swallows with ease').

devoted Baiḷiyakka and Malpāṇiyakka made a request to the king, and (with his permission) granted in the grounds of Maṇivūr, south of (the sanctuary of) the goddess Tuṅgabhadra, east of the boundary of the dry-lands of Sūgūr, 2 mattar of unploughed land. On the (?) mintage,¹ jointly with the goldsmith-burgesses, there was granted on the *daḷa* 2 *viśa* 2 *kāṇi*; also on their buying 2 *so[llage?]* and on their selling 2 *so[llage]*; also in the shops a tax of one ladleful.²

B.—OF THE SAME REIGN.

This epigraph, an unfinished one, is carved on the back of the stone which has inscription A on its face.—The writing covers an area of approximately 2 ft. 4½ in. in height and 2 ft. 9 in. in width. It is much worn, and in places is almost illegible; but careful study has made it possible to recover practically the whole of the text; and it has been found worth illustrating by a plate to exhibit some features in the characters mentioned below.

The character is a good Kanarese, similar in type to that of A. The letters vary in height from ½ in. to ¾ in. The scribe is fond of flourishes. In line 1 the first word, *Śrī*, is almost as ornate as in A; the *r* in *chandra* is curled round the *d* in bold floral decoration; and some other letters are prolonged upwards in sweeping flourishes, while several subscript letters on the left-hand margin of various lines are similarly extended downwards. Some letters are much larger than the rest: for instance, *vē* in *Sambhavē* (l. 1), *ṭha* in *kaṇṭhaṇ* (l. 4), *la* in *Mahākāḷa* (l. 16), *kaṇaḷa* (l. 27), and *dhavaḷa* (l. 28), and *ṭha* in *nāṭha* (l. 16). The special characters for *m*, *y*, and *v* are common, as in A. In ll. 1-3 the special *m* occurs 14 times, the ordinary *m* only 7 times; the special *v* is also very frequent, and the peculiar *y* appears 9 times.

The language is Old Kanarese, prose and verse, with introductory formula and verse 1 in Sanskrit. Of some lexical interest are *uddriṇ* (l. 3), *unmuktā* (l. 4), *unmantra* (l. 35), the prefix *ud* expressing high degree. As regards orthography, we may note that the archaic *j* never occurs in words where it is primitive; but, as if to make amends for this, it is written wrongly in four Sanskrit words—*kaḷa* (l. 6), *Mahākāḷa* (l. 16), *kaṇaḷa* (l. 27), and *dhavaḷa* (l. 28),—and in the last three of these the character is made exceptionally large, as if to bid defiance to laws of grammar. Final *-m* alternates with *-v* before vowels, and it is sometimes hard to decide which is the true reading.

The record refers itself to the same reign as A. It opens with an invocation of Udbhava-Rāchamallēśvara, a phase of the god Śiva, which we shall find explained below, ll. 19-21; and after the regular verse of salutation to Śiva (v. 1) comes a stanza adoring the god under the name Rāchamallēśvara (v. 2). After a fanciful description of the ocean (v. 3: see note *in loco*) we are informed that in Jambū-dvīpa lies Bharata-kṣētra, and in the latter is the province of Kuntala, the reigning sovereign of which is Tribhuvanamalla Vira-Sōmēśvara-dēva (IV). In Kuntala is the county of Ballakunde (v. 4), and in Ballakunde is the hill-fortress of Kuṛugōḍu, which is described in glowing terms (ll. 8-12). The Sinda Rāchamalla (I), Mahāmaṇḍalēśvara of Kuṛugōḍu, is then eulogised with due fulness (ll. 12-14); and we learn that in the course of his pious and glorious reign he was favoured with an epiphany of the god Śiva and his attendant spirits (ll. 14-18); he accordingly rose to exceedingly high estate in life, and after death was translated to *śibhva* in Śiva's heaven, subsequently appearing on earth as a manifestation of Śiva in the form of a self-created Liṅga³

¹ Mr. Narasimhachar suggests that this may mean a place or shop.

² For the explanation of this passage I am again indebted to Mr. Narasimhachar. The ladleful is perhaps of grain.

³ The Śaiva Āgamas recognise six kinds of Liṅgas, viz. (1) *svayambhūta*, self-created, (2) *bāṇa-liṅga*, prepared by Śiva, (3) *daśa*, set up by gods, (4) *āraṇya*, prepared by Rishis, (5) *gāṇa* or *gāṇavat*, set up by Śiva's Gāṇas or goblin troop, and (6) *māṇaṇḍa*, prepared by godly and instructed men (*Kāśikā Āgama*, ch. 50, vv. 35-38). Cf. Gopinatha Rao, *Elements of Hindu Iconography*, Vol. II, pp. 79-82, 86.

on the west of the temple of Svayambhū (Śiva) in Kurugōdu, where a sanctuary was raised and worship paid to him under the name of Udbhava-Rāchamallēśvara, "the god Śvara of Rāchamalla in (miraculous) revelation" (ll. 18-21). We then learn that Rāchamalla I begot by Sōvala-dēvi Iruṅgōla (not Iruṅguḷa, as in A), who by Ēchala-dēvi begot Rāchamalla II (ll. 21-22); and upon the power and blessed estate of the last-named our poet dilates in ll. 23-26. We may note the statement that his hero was suckled by a tigress, was covered by the hood of a cobra, rode on elephants, and had Kalidēva as the tutelary god of his race (v. 11); on this see above, p. 269. It is then announced that in his reign there was a high minister, the royal treasurer Rēchirāja, the son of Sāyidēva (Sāvidēva or Svāmidēva) and Savitri, and Sāyidēva was the son of an elder Rēchirāja by Rēkāmbikā-dēvi (ll. 30-35). The inscription here breaks off; presumably it was intended to record an endowment of the temple of Udbhava-Rāchamallēśvara by the Mahāmaṇḍalēśvara at the instance of the younger Rēchirāja.

TEXT.¹

[Metres: v. 1, *Śloka* (*Anuṣṭubh*); vv. 2, 13-15, *Sragdharā*; vv. 3, 6, 7, 9, *Mahāśragdharā*; v. 4, *Uṭpalamālā*; v. 5, *Kanda*; vv. 8, 10, *Mattāphavikrīḍita*; v. 11, *Champakamālā*; v. 12, *Śardūlavikrīḍita*.]

- 1 *Śrīmat-Udbhava-Rāchamallēśvarāya [namaḥ ||*] Namas-tuṅga-śiraś-chumbi-
chandra-chāmara-chāravā ||*] triḷōkya-nagar-ārambha-mūla-atambhāya Śambhava ||
[1*]
- 2 Śrīmat-śailēndra²-putri-pati namag-abhivāṁchchh-ārtihamam māḷke tēja[s*]-stōmam
prastutya-nity-ōdbhavav-esar(v)-esav-i Rāchamallēśvar-ā-
- 3 khy-ōddāman nissīma-nāman stuvad-akhiḷa-lasat-sāman-śtm-ābhirāman bhīman jāt-
āgra-sōman viṇuta-jana-manah-prēman-uddigu-lalāman || [2*] Jala-kallōl-āḷi
bāhā-
- 4 yugala | v-esēvi(va) kūrmmam padam | hāḷa-mīm kap | polev-anumuktāphalam
pal | kuḷisame nakha | v-ā kambu kamtham | sanīlam viḷasat-kēs-āvakāśam |
tolasuva pavalam bāy | ka[ra]m
- 5 padmarāgam talam-āgal | rōji ratnākarana vol-esagum rāja-chadram⁴
samudram || [3*] Ant-enisida gambhīrara⁵-ratnākaraniṁ parivṛitav-āda
Jambūdvīpada Bharataśhetradolū
- 6 Kumtala-vishayam-unṭalli || Svasti Samasta-bhuvan-āśrayam Śrī-Prithvī-vallabham
mahārājadhīrājāṁ paramēśvaram paramabhaṭṭarakam Satyāśraya-kuḷa(la)-tīḷakam
Chāḷuky-ābharaṇam
- 7 śrīmat-Tribhuvanamalla-Vīra-Sōmēśvara-dēvana rājyam-uttarōttarav-āgutt-iral-ittal ||
Vri || Ant-enis-irdda Bhārata-mahī-mahīlā-mahaniya-bhāḷadoḷu kumtala-
- 8 [d-ante] śōbbisuva Kumtala-bhūṭala-bhāmeg-o(ā)vagam kāmṭa-mukh-āntadoḷ-pīdida
kaṁṇaḍiy-anname chennan-āgi vōr-ant-ire Ballakuṁde naḍu-nāḷ-karam-
oppugum-etta nōḷpadam || [4*] Va || Ant-ā nā-
- 9 ḍa naḍuve rājad-rāja-nagara-ramaṇi-ramaṇiya-maṇidarppaṇṣyamānam-enise Bhargg-
ādriy-ant-ārggav-ari-durggamam-āda Kurugōḍa giri-durggada pora-voḷala
viḷasam-eint-eṁḍade || Kaṁ ||

¹ From the ink-impressions.Read *Śrīmaś-chhāṭṭēndra*.² This word is preceded by the *saṅkha* symbol.³ Read *rāja-mudram*; cf. the inscription *PSOCI*. No. 83 (*Ind. Ant.*, Vol. IX, pp. 96 f.), v. 2, and the *Sabara-śaṅkara-viḷāsa*, i. 30.⁴ Read *gambhīra*.

- 26 yuma[r̥] bhāgado | rārājan-mukhādo | bhujā-yugaḷado | dik-chakrado |
varttisaḷ viraṅg-Irmaḍi-Rāchamalla-mahipaṅg-inn-ārppar-ēm baṁdapar ||
[12*] Imtu negaḷtegam pogalṭegam
- 27 neley-enisi | Svasti Samadhigata-paṁcha-mahā-śabda-mahāmaṇḍaḷśēvaranum
Ballakumḍā-dēś-ādhiśvaranum Bhōgāvati-puravar-ādhiśvaranum Siṁda-kuḷa-
kamala(la)-mārttaṁḍanum sitagara gaṁḍanum śārddū-
- 28 la-vijaya-patākanum samuddaṁḍa-maṇḍaḷi(la)ka-bhayamkara-chaturāṅg-āṇkanum
daśa-diśā-varttita-dhavaḷa(la)-kirttiyūm Patāḷa-chakravarttiyūm śrī-Vira-Kalidēva-
dibya-śrī-pāda-
- 29 padma-nitya-prasād-āsādit-ātma-prabhāvanum saṁgaḍada maṇḍaḷikara taleyam
kāvanum bēḍidargg-ill-ennad-Ivanum-enisi negaḷda śrīmad-Irmaḍi-Rāchamalla-
dēvam Kurugōḍa paṭṭa-
- 30 paḍoḷ sukha-saṁkathā-vinōdadim rājyam-geyyuttam-ire-yire tat-pāda-padma-ōpaḷvi
mahā-pradhānam vibudh-aika-bāṁdhavam śrīkaraṇam Rēchirājan-anvaya-ent-
emdaḍe || Vri || Svasti śrī-¹
- 31 Chandra-vaiś-ōdbhava-Harita-kuḷam Kamme-sat-kirtti-valli vistār-ā-tāra-tārachaḷa-
bhuvana-taḷam tān=enal sat-kavindra-prastutyaṁ Rēchirājam-anuvaśe guḷi
Rēkāmbikā-dēvigam saṁtra-
- 32 st-ārāti pradhānam sutan-udayisidam Sāyidēva-pradhānam || [13*] Rāmaṅg-
ā Rāmey-ent-amt-Amara-patige Paulōmiy-ent-amte Lakshmi-dhāmaṅg-ā
Lakshmi(kahmi)y-ent-amt-Ātanu-ripug-U-
- 33 māḍeviy-ent-ante Tārā-rāmaṅge Rohiṇi-prēyasi sogayipaḷ-ent-amt-amāty-
[— ∪ —]²ōldāmaṁ śrī-Sāyidēvaṅg-ati-pati-hite Sāvitre(tri)y-amt-oppuṭ-irddaḷ ||
[14*] Ant-ā śrī-
- 34 Svāmidēvaṅgam Sāvitri-dēvige || Vri(vri) || Rājat śrī³-Svāmidēvaṅg-anuvaśe
guḷi Sāvitrigam paṭṭidam śrī-bhājam tigmaṁśu-tējam gata-bhaya-hṛidha(da)y-
āmbhōjan-ā pu-
- 35 aya-bijam bhārat-kāntā-Manōjam vibudha-vibudha-bhājam yaśaḷ-śrī-samājam
naij-ōnamātr-ābdi-rājam suvibhava-Sumanō-rājan-ī Rēchirājam || [15*]

TRANSLATION.

(Line 1.) To the blessed Udbhava-Rāchamallaśvara (*homage*) !

(Verse 1.) (Identical with v. 1 of inscription A.)

(Verse 2.) May the blest Lord of the Great Mountain's Daughter—he who is a mass of radiance,⁴ who has famous eternal birth, that most illustrious one who is glorious with the name of Rāchamallaśvara, whose name is boundless, whom all the bright Sāmans praise, lovely in his own nature, terrible, bearing the moon on the tip of his braided locks, beloved of the souls of renowned men, having a stately eye in his brow—fulfil for us the object of (*our*) desire !

(Verse 3.) Like a moving jewel-mine appears the Ocean, bearing the stamp of a king, as the lines of the waves in its waters are (*his*) two arms, the fair turtles (*his*) feet, the little fish (*his*) eyes, the brilliant pearls (*his*) teeth, the *kalīṣa* fish (*his*) nails, the shells (*his*) neck, the fine turquoises (*his*) bright hair-tips, the lustrous coral (*his*) mouth, the rubies forsooth (*his*) palms.

¹ After *śrī* is written the syllable *ci*, projecting beyond the line.


² The engraver has left out these three syllables without marking the omission.

³ Read *Rājach-chāri*.

⁴ Perhaps a reference to the revelation of Śiva in the form of a fiery Linga, the Lingōdbhava (*see above*, Vol. XIII, p. 158 n.).

- 10 Nāradana torade saradim tārā-pathad-amte rāja-hama-ānvitadim kshir-ābhdh
sayanan-urada vol-ārameyin-turugi pora-vojala sā(so)gayisugum || [5*]
Mattam-ā pur-āntarbbhāgam-emt-e-
- 11 [ndaḍe || Vri] || Bharadibh-Aurv-ānalam tamn-ojagaṇa jalamam pīrvan-end-
Abdhi-nātham pīrid-omd-āsāmkeyind-1 puradole nava-ratnāṅgalam baytan-emb-
amt-iral-irkkum kshatra-ratnam | chatura-yuvati-ratnam | sa-
- 12 [— — √ ra]tnam | vara-ratnam | vira-ratnam | sujana-purusha-ratnam | gaj-
śev-ādi-ratnam || [6*] Va || Ant-ā purakk-adhiśvaram mahāmaṇḍalēśvaram
Siṁda-kula-kamaḷa-mārttaṇḍam sitagara gaṇḍanum-enisi negaḷda śrīmad-
Rāchamalla-dēvana
- 13 mahimey-emt-emdaḍe || Vri(vri) || Vara-mārggam | śrī-nisarggam | vinaya-vinata-
Bharggam | jit-ārati-varggam | sthira-kāryam | Mēru-dhairyam | sujana-
vanaja-sūryyam | mahipāḷa-varyyam | Smara-rūpam | sa-
- 14 pratāpam kṛita-ripu-nṛpa-tāpam kaḷ-āḷi-kaḷāpam | dhareg-ellam Rāchamallam
kuḍutav-irale ballam yaśah-śṛige nallam || [7*] Ant-ā sukha-samkathā-
vinōḍadin-irutt-ire || Vri || Dhareg-āścha-
- 15 ryyade Rāchamalla-mahipa[m] gō-bhū-hirany-āmna-pāna-ras-ādy-ākṣiḷa-dānadim
taṇipi śisht-śaṣṭ-ārthha-sadu-bhaktaram pīridum mannisal-īśvaram varadan-āgaḷ
rājyaman-tāḷdi vistarisutt-opp-i-
- 16 re dēvar-omdu diva-am pratyakshadim be(ba)rppudhu(du)m || [8*] Va || Āgaḷ
Nāndinātha - Nāndi-Mahākāḷa(ja) - Virabhadra-pramukha-pramatha-yūtha-samētanum
Hari-Virimehi-sur-āsur-ōrag-ādi-prasiddh-ā-
- 17 mara-gaṇa-sēvitanum-enisi Pārvati-pati bānd-avatarisi nind-iral Rāchamallarassam
bhomikane kaṇḍu poḍa-vatt-ānamdadim kara-kamaḷa-mukujitan-āg-iral
Hara[m*] dara-hasita-vadan-āravindam Kailās-āva-
- 18 lōkan-ārthhav-abhaya-hast-āvalambakan-āge mahā-prasādam-emdu mahā-vibhūtiyam
gaṇ-āḍambaravam māḍi Śiv-ārchchēneyan-ādi || Vri || Dhareg-imt-atyantha-
chōdy-āvaham-ene Śiva-līng-ārchchanam māḍi
- 19 prithvi-bhara-rājya-śrīyuman samtatige nilisadam Rāchamallam śarīram beras-
uttumg-āśva-chamchach-chamara-ruhe(ha)-śi(si)ta-chohhatra-chiḥn-ānvitam Śam-
karanol-sālōkyaman porddiyum-avanige āyū-
- 20 jyadiṁ līngav-āḍe || [9*] Va || Amtu Kurugōḍa pottāṇada śrī-
Svayambhūḍēvara paśchim-ābhimukhadolū bāndu nimdu sakuḷa-lōkakke
kautukam-āgi līnga-mūrttiyind-udbhavisalū śrī-
- 21 mad-Udbhava-Rāchamallēśvara-dēvar-embā pesaram tāḷdi suprasiddham-āg-
ire || mattam tādya-samtatiy-āḍagumtiy-emt-emdaḍe || Vri || Madavad-
vairi-karindra-kēsarīy-enipp-ā Rāchamallamgav-āspa-
- 22 dadim Sōvela-dēvigan-tanujan-āg-irdd-ā Yirumgōḷa-bhū-viditamg-ēchala-dēvigam
tanayan-ādam kshatra-chāḷira-sampadan-int-Irmaḍi-Rāchamalla-mahipam śrī-
Siṁda-Nāśyanam || [10*]
- 23 Va || Ant-ātanolū bīlam-gomḍu kalita-Naḷa-balupim kādi gelal-ārggam-arid-
emt-ene || Vri || Pulī mole-vālan-āḍe | phapipam peḍeyam kōḍey-ette
siṁdhuraṁ sa-lalita-bhadra-viṣṭaram-ad-āge | cha-
- 24 mach-chamari-mṛig-āḷi-kōmaḷa-chāḷa-chāru-chāmaraman-ikkū | diṭam Kalidēvan-
āvagam kulad-adhidāivav-āge | gelal-ār-ddorey-Irmaḍi-Rāchamallanolū ||
[11*] Mattam || Vira-śrī-
- 25 Kalidēvadēvan-Abhavam nitya-prasād-ōdbhav-ōḍāra-śrīyan-anāratam kuḍut-iral Śrī-
chāru-vāk-śrī-lasad vira-śrī-ruchir-ēndu-kumḍa(da)-nibha-kīrtti-śrī-

Kurgod inscription B.



(Lines 5-6.) In the realm of Bharata (*forming part*) of Jambū-dvīpa, which is surrounded by the deep Ocean thus described, there is the province of Kuntala; in it—

(Lines 6-7.) Hail! when the reign of the asylum of the whole world, beloved of Fortune and Earth, the great Emperor, the *paramēśvara*, the *paramabhāṭāraka*, ornament of Satyāśraya's race, embellishment of the Chālukyas, the fortunate Tribhuvanamalla Vira-Sōmēśvara-dēva [IV], was advancing in increase, then—

(Verse 4.) The mid-county of Ballakunde is indeed conspicuous wherever it is seen, being perfect in beauty, as though it were a mirror held ever to the end of the lovely face of that lady the Kuntala-land, who is beauteous as a curling lock on the glorious brow of that dame the Bhārata-land thus described.

(Lines 8-9.) So as regards the beauty of the outer town of the mountain-fortress of Kurugōḍu in the midst of this county, which may be called a charming jewel-mirror of that lady the brilliant royal city, and which like the mountain of Bharga [Śiva] is for all impassable to foes :—

(Verse 5.) The outer town, thickly clothed with groves, is beautiful like the stars' path [the sky] when studded with royal swans (*as they fly*) ceaselessly amidst the noise of the clouds,¹ (*or*) like the (*dark blue*) breast of (Viṣṇu) lying in the Milk-Ocean.

(Lines 10-11.) Moreover, as regards the interior of this town—

(Verse 6.) As though the Lord of the Ocean, from a great fear lest the submarine fires should eagerly suck up the waters within him, had lodged in this town the nine (*kinds of*) jewels, there are (*here*) the jewels of chivalry, jewels of graceful damsels, jewels of . . . , choice jewels, jewels of warriors, jewels of good men and followers, jewels of elephants, horses, and other things.²

(Lines 12-13.) Now, as regards the greatness of Rāchamalla-dēva, who is renowned as the ruler of this town, the Mahāmaṇḍalēśvara, sun to the lotuses of the Sinda race, warrior to the wanton :

(Verse 7.) As Rāchamalla was dispensing gifts to the whole earth, a man of noble courses, blest of nature, who reverently did homage to Bharga [Śiva], victor over the companies of his foes, steady in duty, having the firmness of Mēru, a sun to the lotuses of good men, best of kings, comely as Cupid, majestic, consuming hostile monarchs, master of the whole series of arts, skilful, lover to the goddess Fame :—

(Line 14.) So as he was (*engaged*) in this enjoyment of pleasant conversations—

(Verse 8.) As amidst the wondering admiration of the earth king Rāchamalla, treating most bountifully the good votaries whose objects of desire are noble by gratifying them with all gifts of kine, land, gold, food, drink, etc., was acting as an Īśvara [Śiva] (*and*) a Boon-giver [Viṣṇu], and was brilliantly advancing in the course of his reign, the god [Śiva] one day appeared in revelation :—

(Lines 16-18.) Then the Lord of Pārvatī [Śiva], accompanied by Nandinātha, Nandi, Mahākāla, Virabhadra, and the rest of the goblin troop, and attended by Hari, Viriñchi [Brahman], the gods, the demons, the Nāgas, and the rest of the famous Immortals' company, came down; and king Rāchamalla, reverently gazing and offering salutation, with joy made the lotuses of his hands to form a bud³; and Hara, the lotus of his face gently smiling, held

¹ Cf. *Māgā-dūta* i. 12.

² With this list of nine *ratnas* may be compared the Buddhist list of the seven *ratnas* in *Dharma-saṅgraha*, §§ 65, with the references given there.

³ That is, he clasped his hands in the *añjali*.

out the hand of security, to the end that he should behold Kaiāsa¹; and (*the king*), deeming it a great act of grace, having with much magnificence entertained with pomp the goblins and performed worship of Śiva—

(Verse 9.) Having thus performed the worship of Śiva, so that it caused exceeding admiration to the world, Rāchamalla established for his descendants prosperity of rule (*in bearing*) the burden of earth, being while still in the body attended by the tokens (*of royalty, namely*) stately horses, brilliant yak-hair fans, and white umbrellas; (*and*) even after attaining a place in the world of Śiva, he formed a Liṅga for the earth by union therewith.

(Lines 20-21.) So having come and stood at the western side of (*the temple of*) the god Svayaṁbhū of the town of Kurugōḍu, and arisen in the form of a Liṅga so as to delight the whole world, he became very famous under the title of "The God Udbhava-Rāchamalla-śvara." Moreover, as regards the line of his descendants—

(Verse 10.) To this Rāchamalla, who was a lion to the mighty elephants his furious foes, and to Sōvala-dēvi was (*born*) in their estate a son, the world-renowned Iruṅgōla; and to him and to Echalā-dēvi was (*born*) a son perfect in chivalrous conduct, king Rāchamalla II, a blest Nārāyaṇa of the Sindas.

(Line 23.) So, if it be said: "why is it impossible for any to overcome (*him*) by finding weak points in him and warring with the might of a Naja?"—

(Verse 11.) As a tigress gave (*him*) to drink the milk of her breasts, a Lord of Snakes raised (*over him*) its hood as an umbrella, the elephant is (*his*) graceful seat of honour, a brilliant troop of yaks give soft quivering beautiful fans, (*and*) Kalidēva in sooth is ever the tutelary deity of his race, who are able to overcome Rāchamalla II?

(Line 24.) Moreover—

(Verse 12.) As the god Vira-Kalidēva, (*who is*) Abhava [Śiva], constantly grants (*to him*) noble fortune by the rise of continual boons; as Fortune places success of sweet speech, success of splendid warriors, and success of fame (*white*) like the radiant moon and jasmine, in (*various*) parts, (*namely*) in (*his*) resplendent mouth, in (*his*) two arms, (*and*) in the circle of space (*respectively*)²; can there come now any who are able to prevail against the warrior king Rāchamalla II?

(Lines 26-30.) Being thus a subject of glory and praise—Hail! Rāchamalla-dēva II, renowned as "the Mahāmaṇḍalēśvara who has attained the five *mahā-sabdas*, lord of the Ballakundā land, lord of Bhōgāvati best of towns, sun to the lotuses of the Sinda race, warrior to the wanton, having the victorious banner (*with the device*) of a tiger and a host of four divisions³ inspiring fear in arrogant feudatory princes, he whose white fame travels through the ten regions of space, the emperor of Pātāla, he who has attained his power by the constant grace of Vira-Kalidēva's lotus-feet, who guards the heads of attendant feudatory princes, who gives without saying nay to suppliants," being in control of the kingdom at the town of Kurugōḍu with enjoyment of pleasant conversations,—

(Line 30.) as regards the lineage of the one who lives upon his lotus-feet, the high minister, the especial kinsman of sages, the treasurer Rēchirāja:—

(Verse 13.) Hail! To Rēchirāja, who was sprung from the blest Lunar race and belonged to the Harita family, a creeping-plant of goodly fame to the Kamme caste, celebrated by the

¹ That is, Śiva held out a hand in the *abhaya-mudrā* or gesture indicating protection and security, as a promise that the king should be translated to Kaiāsa, Śiva's paradise.

² An instance of the rhetorical figure *yathā-samāhāya*.

³ Namely, infantry, cavalry, horse, and elephants.

best of good poets as being the ground (*supporting*) a star-high Tārā's Mountain¹ of dignity, and to the devoted virtuous Rēkāmbikā-dēvi was born a son, the minister Sāyidēva, a minister who terrified foes.

(Verse 14.) As with Rāma Rāmā [Sītā] is radiantly present, as with the Lord of the Gods [Indra] Paulōmi, as with the Home of Fortune [Vishnu] Lakshmi, as with the Disembodied One's Foe [Śiva] Umā-dēvi, as with the Stars' Lover [Chandra] the lady Rōhini, so with the blest Savidēva, majestic among ministers (?) was Sāvitrī, exceedingly faithful to her lord, conspicuous.

(Lines 33-34.) So to this Svāmīdēva and Sāvitrī-dēvi—

(Verse 15.) To the brilliant blest Svāmīdēva and to the devoted virtuous Sāvitrī was born one enjoying fortune, having the radiance of the sun, the lotus of whose heart was void of fear, that seed of righteousness, a Cupid to radiant ladies, a celestial tree to sages, a meeting-place for the goddess Fame, a lord of the ocean of his own high verses of prayer, a most magnificent king of the *sumanas*,² this Rēchirāja.

No. 20.—TAXILA INSCRIPTION OF THE YEAR 136.

By STEN KONOW.

This inscription was discovered by Sir John Marshall in the course of his excavations at Ancient Taxila during the winter 1912-13, and published by him in the *Journal of the Royal Asiatic Society* for 1914,³ with additions and a plate in the same *Journal* for 1915.⁴ Valuable remarks have further been published by Messrs. Thomas,⁵ Fleet,⁶ Boyer,⁷ and Bhandarkar,⁸ and the record has been utilised in my *Indo-Scythian Contributions*.⁹ It is of such importance that it is advisable to record it in the pages of the *Epigraphia*.

Concerning the discovery of the inscription Sir John states that it was "made in a small chapel immediately west of the so-called 'Chir' *stūpa*. The chapel in question is built in a small diaper type of masonry, which came into vogue at Taxila about the middle of the first century A.D. and lasted for about a hundred years. Its entrance faced the main *stūpa*, and near the back wall opposite this entrance, and about a foot below the floor, I found a deposit consisting of a steatite vessel with a silver vase inside, and in the vase an inscribed scroll and a small gold casket containing some minute bone relics. A heavy stone placed over the deposit had, unfortunately, been crushed down by the fall of the roof and had broken both the steatite vessel and the silver vase, but had left the gold casket uninjured and chipped only a few fragments from the edge of the scroll, nearly all of which I was, happily, able to recover by carefully sifting and washing the earth in the vicinity. The cleaning and transcription of the record was a matter of exceptional difficulty, as the scroll, which is only $6\frac{1}{4}$ inches long by $1\frac{1}{2}$ inches wide and of very thin metal, had been rolled up tightly, face inwards, in order that it might be enclosed in the silver vase; moreover, the metal of which it is composed is silver alloyed

¹ This seems to be the Kishkindha-parvata in Ōdra-dēśa, on which Dēvi was worshipped by the name of Tārā (*Matayo Purāṇa*, xiii. 46), being apparently identified with the epic heroine Tārā, the wife of Vālin (*Rāmāyaṇa*, IV. 15 ff.; *Mahābhārata*, Prat. Bay's edn. III. 279).

² Meaning either "king of sages" or "king of gods" (Indra), according as we translate *sumanas*.

³ Pp. 973 ff.

⁴ Pp. 191 ff.; compare also *Archaeological Survey of India, Annual Report*, 1912-13, pp. 18 ff.

⁵ *JRAS.*, 1914, pp. 987 ff. 1915, pp. 155 ff.

⁶ *JRAS.*, 1914, pp. 992 ff.; 1915, pp. 314 ff.

⁷ *Jo. Asiat.*, XI, v, pp. 281 ff.

⁸ *Ind. Ant.*, 1916, pp. 120 ff.

⁹ *SBW.*, 1916, pp. 787 ff.

with a small percentage of copper, which had formed an efflorescence on the surface of the extremely brittle band, with the result that I could neither unroll it without breaking it, nor subject it to the usual chemical treatment. By the use of strong acid, however, applied with a zinc pencil, I was able to remove the copper efflorescence and expose, one by one, the punctured dots of the lettering on the back of the scroll, and then, having transcribed these with the aid of a mirror, to break off a section of the scroll and so continue the process of cleaning and transcription. In this way I succeeded in making a complete copy of the record from the back of the scroll, while the letters were yet intact. Afterwards I cleaned in like manner and copied the face of each of the broken sections, and was gratified to find that my second transcript was in accurate agreement with the first." Later on Sir John, by means of other methods, was able to clean the scroll more effectively, and succeeded in presenting a photographic reproduction of practically the whole inscription.

The characters are Kharoṣṭhī of the early Kushana type. As in other Kharoṣṭhī inscriptions, the length of vowels and diphthongs has not been marked. In the case of *a*, *i*, and *u* it is usual to retain this peculiarity in transliterating, while *e* and *o* are often marked as long, if we have no special reasons for assuming that they are short. The only consistent transliteration is, however, not to use the sign of length in the case of *e* and *o* any more than in the case of *a*, *i*, and *u*. *E* and *o* are, of course, always long in Sanskrit; in the Prakrits, on the other hand, they are sometimes long and sometimes short, just like other vowels. I shall therefore write *e* and *o* throughout, though most of the *o*-s and all the *e*-s occurring in the inscription are probably long. With regard to individual letters we may note the sign for *ṣa* in *-ṣati*, l. 4, and *f* in *Imdāfria*, l. 2. The voiced and voiceless dentals are carefully distinguished; compare *pradistharita*, ll. 1 and 2; *raṣṭirajasa*, l. 3, etc. The compound letter *tva* occurs in *bodhisatva*, l. 3. The same sign has hitherto been transliterated *tm* in *atmano*, l. 5. The only reason for this latter writing is that the corresponding Sanskrit word *ātmanah* contains a *tma*. If that had not been the case, nobody would have thought of reading otherwise than *tva*. Prakrit is not, however, Sanskrit, and I have no doubt that the correct reading is *atvano*. In the first place we know from the Ara inscription¹ that there was another compound *tma*, and it is not at all likely that there should be on the one side two different compounds for *tma*, and on the other two different meanings of one of them. Moreover the usual Prakrit forms *atta* and *appa* cannot well be derived from Sanskrit *ātman*, but both seem to go back to an intermediate form *atvan*, just as *sattva* becomes *satta* as well as *sappa*. Another compound occurs in *pradistharita*, ll. 1 and 2; *vasthavana*, l. 2. It will be seen that it is used both instead of Sanskrit *sta* and of Sanskrit *stha*. As a rule, it can be stated that the compound is rarely used in Kharoṣṭhī inscriptions except in foreign words and such as can be considered as Sanskrit loanwords.² *St* as well as *sth* regularly became *tth* in the dialect. It is a well known feature of the Prakrits that an *s* causes aspiration of a neighbouring consonant, and the necessary link between *st* as well as *sth* and *tth* is *sth*. Similarly we find *shih* in the Iranian name *Hashthana* in the Wardak vase inscription.³ It is therefore just as natural to transliterate the compound *stha* as *sta*; and, if we consider its shape, it is evident that the lower portion is identical with the letter *tha* and has nothing to do with *ta*. I therefore write *stha* and consider this as a semi-learned writing which does not represent the phonetical features of the dialect.

With regard to orthography, we may note, in addition to the use of the compound *stha*, that *ya* represents a Sanskrit *ja* in *puyae*, ll. 4 and 5. The writing is not over careful. Thus we find *a* for *e* in *putraṇa*, l. 2, *prachaga*, l. 4, and perhaps in *ma*, l. 5. Syllables have been left out in *Tachhasis*, for *Tachhatilae*, l. 3; *arahana*, for *arahantana*, l. 4; *sarvasana*, for *sarvasatana*, l. 4, and *-salohipa*, for *-salohidapa*, l. 4.

¹ Above, p. 143.

² Cf. Lüders, *SBAN*, 1914, p. 416.

³ Cf. Senart, *Je. Asiat*, XI, iv, p. 574. Kenow, *SBAN*, 1916, p. 806. Mr. Pargiter reads *Hashthana*.

The greatest difficulty connected with the interpretation of the inscription rests with the word *ayasa*, l. 1. Sir John considered it as the gen. of *Aya*, or *Azes*, and explained it to mean that the record was dated in an era founded by *Azes*, and this era he identified with the *Vikrama* era. Messrs. Thomas and Fleet were of opinion that the word could hardly be the name of a king, because no royal title is used. They further maintained that, if *ayasa* were really the name of a king, it would place the inscription in the reign of this king, who would then most likely have to be identified with the *Khushana* mentioned in l. 3. Dr. Thomas propounded the possibility of considering *ayasa* as the gen. of a demonstrative pronoun, and Dr. Fleet adopted the explanation and translated: "In the year 136: on the day 15 of this (present) month *Āshāḍha*," or "In the year 136: on the day 15 of the month *Āshāḍha* of this (year)."

A form *ayasa* of the base which we know from Sanskrit *ayam* is, of course, possible, though I do not think it a likely one. But the use of such a pronoun in this place is not in agreement with the practice in other old inscriptions. The use of *atra*, *etaye*, etc., in *atra divase* in the Sui Vihar inscription, *etaye purvaye* in the Patika plate, and so forth, cannot be compared, because such expressions always follow after the mention of the month and the day and recapitulate the whole dating, just as *isa divase* in the present record.

M. Boyer agrees with Messrs. Fleet and Thomas in thinking that *ayasa* is not the genitive of *Aya*, *Azes*. He explains *ayasa* as standing for *ayyasa* and this further as corresponding to Sanskrit *ādyasya*. The month *Āshāḍha* he thinks may have been called *ādya* because the year was *āshāḍhadi*. I do not know any old date which might be compared. Mr. Bhandarkar likewise explains *ayasa* as a Prakrit form corresponding to Sanskrit *ādyasya*, but thinks that it has been added because there was, in that year, a second, intercalated, *Āshāḍha*.²

Sir John Marshall is quite right in comparing the wording of the Taxila copper-plate where we read *samvatsaraye ahasatattimas 78 maharayasa mahamtasa Mogasa Panemasa masasa divase pañchame 5*. I do not know of any other old inscription where we find a similar addition between the mention of the year and the month. If, however, *Ayasa* is the name of a ruler, the inscription must, as urged by Messrs. Thomas and Fleet, be dated during the reign of this king.

Dr. Fleet further remarks that, if *Ayasa* were the name of the king ruling when the inscription was deposited, this would tend to mark him as the *Kushana* king referred to in line 3. Such an inference is not, however, necessary. The so-called Takht-i-Bahi inscription is dated during the reign of Gudufara, but in honour of another prince, and the same can very well be the case in the Taxila record.

The chief difficulty in explaining *Ayasa* as the name of a king rests with the fact that no royal title is used in connexion with the name. I have thought of the possibility of explaining this anomaly by assuming that *Aya* was the ruler, not of Taxila, but of the donor's home *Noacha*, and that *Azes II* might have spent his last days as a local ruler of *Noacha*. Such an assumption cannot, however, be substantiated by any fact, and the absence of every royal designation is so extraordinary that I think we must abandon Sir John's explanation of the word *ayasa* altogether.

Provisionally, therefore, I am inclined to adopt the explanation of Mr. Bhandarkar. We do not know how *dy* was regularly treated in the old dialect of the North-Western frontier. In the *Shābāzgarhi* and *Mansehra* versions of the *Aśoka* edicts *dy* becomes *j* in *aḥa*, Skr. *adya*, but in *uyana*, Skr. *udyāna*, it becomes *y* as in Pāli. It is possible that the same development

¹ *JRAS.*, 1915, pp. 317 f.

² Cf. Fleet, *JRAS.*, 1914, p. 998.

has taken place in *ādyā*, and I think this explanation, for the time being, the most likely one, though I am far from feeling certain about it.

Urasakena I take to be the name of the donor. The correct reading of this word is due to Dr. Thomas, who explains it as meaning "of Uraśa" and indicating the nationality, not the name, of the donor. Though M. Boyer is of the same opinion, I prefer to explain *Bahaliēna* as the national name, Sanskrit *Bahlīkēna*. In the North-Western dialect in which the inscription is composed, the general rule seems to be that intervocalic *k* became a soft spirant and was eventually dropped in Indian and Indianised words, while it was commonly retained in foreign names and loan words which had not become naturalised. Thus in the Mathurā lion capital we find *samanumotakra*, *nakraraśa*,¹ *mahasaghiana*, *kusulaśa*, but *Padika*, *Miyika*, *koraka*; in the record under discussion we have *prachaga* and *Bahaliēna*, but *Urasakēna*. *Urasaka* is, moreover, a very likely name, containing the element *sāka*, strength, which is rather common in Iranian.²

The reading of the word after *Urasakēna* is not certain. Sir John, who originally read *Dhitaphria*, has finally adopted the reading *Lotaphria*. Dr. Thomas suggests *Imtaphria* or *Ymtaphria* and sees in this name a variant of *Vindapharna*, *Undopherres*, *Gondopherres*, etc. So far as I can judge from the photograph the reading *Imtaphria*, or, as remarked by M. Boyer, rather *Imtafria* is the most likely one. The second *akshara* is not, however, to judge from a photograph which I owe to the kindness of Sir John Marshall, *ta* but *da*. The anusvāra at the bottom of the letter seems to be certain, and the top is also different from *lo*, *l*, *5*. I would therefore provisionally read *Imdafria*, though I admit that *Lomdafria* is also possible. At all events the form is certainly the genitive sing. of a name ending in *fri*. Compare *Ayasia* in the Mathurā lion capital; *Datia* in the Kaldarra inscription; *Kavīśia* in the Mānikīśā bronze inscription³; *Kamagulya* in the Wardak vase inscription.

Dhamaraie may be the oblique form of a *dhamarāi*, which would represent a Sanskrit *dharmarājī*. This again might be a shorter form of the word *dharmarājikā*, a stūpa. M. Boyer has, however, drawn attention to the fact that in another Taxila inscription we find *Tachhaila agadhamaiaie*, which seems to represent a Sanskrit *Tākshatīlā agra-dharmarājikā*. It is, therefore, more probable that we have to assume a form *dharmarājika* with the same meaning as *dharmarājikā*, though it is impossible to make any definite statement.

According to Professor Vogel⁴ *dharmarājikā* is more especially a stūpa the erection of which was ascribed to king Aśoka, the *dharmarāja*. M. Boyer⁵ has, however, shown that this explanation is not quite certain, and I think the word can also be explained as meaning a stūpa containing relics of the Buddha, the real *dharmarāja*. At all events *dhamaraie* must denote the Chir stūpa itself, and this stūpa M. Boyer is inclined to identify with the Kunāla stūpa mentioned by Hsüan-tsang.

Tachhasie is, of course, miswritten for *Tachhasīlā*, the oblique form of *Tachhasīla*, Sanskrit *Takshatīlā*.

Tagnuae was explained by Sir John as the name of some locality at Taxila. M. Boyer thinks that the word represents a Sanskrit *tanuśyaya*, "sacrifice of the body," and is the name of the Bōddhisattva chapel mentioned in the next word. He compares the *Vyāghriyātaka*. To me the dropping of the *ya* makes some difficulty. Though I admit the ingenuity of the explana-

¹ The compound *kra* in these words certainly denotes a guttural spirant.

² See Justi, *Iranisches Namenbuch*, p. 509.

³ Mr. Pargiter reads *kapōśia* and does not consider the form as a genitive. I read *Kavīśia cāhatrapasa G(r)anāfryaka cāhatrapa-putrasa dānamukhō*, "gift of the Kshatrapa Kavīśi, the son of the Kshatrapa Granāfryaka." Cf. *SBAW.*, 1916, p. 798.

⁴ *Archaeological Survey of India, Annual Report, 1903-04*, p. 223.

⁵ *loc. cit.*, p. 294.

tion, I prefer to see in *taṇuvas* the genitive of a female name *Taṇuva* which would then signify the founder of the Bōdhisattva chapel.

The various forms of the name which is here written *khushanasa* have been discussed by Dr. Fleet,¹ who did not then know the present record. The initial aspirate reminds us of the *χ* in the Greek legend of some of the coins of Kujula-Kadphises; and, if we compare these two writings, it becomes probable that the first letter of the name was originally a guttural spirant, and, to judge from the *g* in *gushanasa* in the Panjtār inscription and *gushana-* in the Māpikāla record, a voiced one. I have no doubt that Count Staël Holstein² is right in combining the name *kushana* with Chinese *yü-chi*, older *güt-shi* or *gür-shi*. I am further convinced that a short form *kushi*, corresponding to *yü-chi*, occurs in *koshano*, which is used in the coin legends of Kanishka and his successors. Dr. Fleet³ considers this *koshano* as an adjective in the nom. sing. I hope, however, to have proved⁴ that the whole legend is composed in a language which is, to all practical purposes, identical with ancient Khotant. The only exception would, if Dr. Fleet were right, be the word *koshano*. In old Khotant this form can only be the genitive plural of a *koshi*; it cannot by any means be explained as a nominative singular of an old *a*-base. In that case it would have sounded *koshani*. Dr. Fleet thinks that, if we explain *koshano* as a genitive plural, we must arrange the words of the legend "in an order in which they were not intended to be taken." In two Junnar inscriptions, however, we find a genitive plural denoting nationality after a personal name exactly in the same way as in the Kanishka coin legends. Compare No. 1154 in Professor Lüders' List, *Yavanasa Irilasa Gatāna*, "of the Yavana Irila, of the Goths," and No. 1182, *Yavanasa Chitasa Gatāna*, "of the Yavana Chitā, of the Goths," where the Yavanas (i.e. Europeans) Irila and Chitā are evidently described as belonging to the people of the Gatas, i.e. Goths.⁵

Though I agree with the Count in assuming the existence of a short base *koshi* in such forms as *koshano*, I am unable to understand how he came to deny the existence of another form *kushana* or *kushāna*. The new Taxila inscription proves, as remarked by Dr. Thomas,⁶ the existence of such a word, which is in itself a very likely one. Compare the two forms *a-she* and *a-she-na* which the Chinese used to denote the ancient royal family of the Turks. The only difficulty is whether the first *a* of this word is short or long. This question would be solved if the reading *kushānaputrō* in the Māt inscription were certain. There is, however, a mark above the *na* in this word, and Count Staël Holstein reads *kushānaṃ putrō*. I therefore prefer to read *kushana*, leaving the question as to the length of the *a* open.

In the last line the photograph favours the reading *niṇaṇas*, as stated by Dr. Thomas. M. Boyer explains *a-de* as Sanskrit *agrataḥ*, principally, and *samaparichago* as Pāli *sammāparichāgō*. Instead of the latter it would be possible to assume *sa me parichago*, "this my gift."

The most important questions connected with this record are its date and the identity of the Kushana ruler mentioned in it.

Sir John Marshall has shown that the record was found in strata which belong to the Kadphises kings and are deeper, i.e. older, than those of the Kanishka group. So far as I can see, his excavations have finally established the priority of the two Kadphises kings to the Kanishka group. On the other hand, Sir John has left the question open which of the two Kadphises kings is meant. He says,⁷ "The next important point is to determine which of the Kushan kings is referred to as reigning in that year. That he is identical with the nameless Kushan ruler mentioned in the Panjtār record of fourteen years earlier, is probable;

¹ *JRAS.*, 1914, pp. 389 ff.

² *loc. cit.*, p. 379.

³ See Konow, *JRAS.*, 1912, pp. 380 ff.

⁴ *JRAS.*, 1914, pp. 977 f.

⁵ *SBZW.*, 1914, pp. 645 ff.

⁶ *ZDMG.*, 68, pp. 93 ff.

⁷ *JRAS.*, 1914, p. 990.

and here, again, I think Dr. Fleet may be correct in identifying the latter with Vima-Kadphises.¹ On the other hand, it is also possible that Kujula-Kadphises may be meant. The monogram on the scroll is characteristic of coins of Vima-Kadphises, but is also found on coins of his predecessor. Again, the title *maharajasa rajatirajasa* also suggests Vima-Kadphises; indeed, it was stated by several speakers during the discussion on the date of Kanishka that Kujula-Kadphises was only a petty local chief (*yavuga-jabgon*), never 'a king of kings,' like his successor. But this assertion is erroneous. On some of his coins Kujula-Kadphises styles himself *maharaja rajadira*, and, according to Cunningham, *devaputra* also. That he ruled, moreover, at Taxila, and consequently over the north-west of the Punjab and Frontier generally, is abundantly clear from his coins, which are found there in larger numbers than those of any other king except Azes I and Azes II. Other considerations, too, favour the identification with Kujula-, rather than Vima- Kadphises. For, in the first place, it would be natural for the first emperor of the dynasty to be styled 'the Kushan emperor' without any further appellation, while it would be equally natural for his successors to be distinguished from him by the addition of their individual names. Secondly, the stratification of coins at Taxila shows that Kujula-Kadphises succeeded the Pahlava kings there, and consequently he can hardly have conquered the country before *circa* A.D. 50; and, inasmuch as his coins betoken a fairly long reign there, and he is known from other sources to have lived to a great age, he may well have been ruling in the 122nd and 136th years of the era of Azes, i.e., approximately, in A.D. 65 and 79."

Dr. Thomas seems inclined to ascribe the Taxila record to the reign of Vima-Kadphises. The era is, he maintains,² the same as in the Takht-i-Bahi and Panjtār records and probably an old Śaka era, which was continued by the first Kushana rulers, at least as late as the years 122 and 136. He goes on to remark: "If Gondophernes died about A.D. 50 after forty years of rule, the year 136 would correspond to A.D. 50 + 33 + 14 = *circa* A.D. 70, which approximates to A.D. 78, the beginning of the so-called Śaka era. And A.D. 78—twenty-eight years after Gondophernes—will be a very suitable date for the death of Vima-Kadphises, who succeeded an octogenarian probably soon after the death of Gondophernes. This would fit the commencement of Kanishka's reign . . . in A.D. 78. We may urge further (1) that the era of the Śakas, having been actually employed by the early Kushans, can have been overthrown only by the definite institution of a new era, which will naturally be the known era of Kanishka; (2) that the so-called Śaka era must have owed its institution to the intentional abolition of a real Śaka era, that is, to the new epoch of Kanishka. On the other hand, if 136 + = A.D. 78, the commencement of the era is not B.C. 58, but a few years earlier. If, however, the + = 0, we arrive actually at B.C. 58. Although the era which we know as the Mālava and Vikrama era is dated, as I have endeavoured to show above (pp. 413-14), from the institution of non-kingly (oligarchical) rule in Ujjain, it is quite conceivable that it was a consequence of the foundation of the real Śaka era and followed after only a short interval; for the Sakas in question may have overturned a ruling dynasty in Ujjain."

So far as I can see, there cannot be much doubt that the Kushana emperor of the Panjtār and Taxila records was Kujula-Kadphises, and not Vima-Kadphises, who does not on his coins style himself a Kushana.

We learn from Chinese sources that the Yüeh-chi, after their defeat by the Hiung-nu in the second century B.C., proceeded westwards, and that, on the southern slopes of T'ien-shan, they came into contact with the Sai-wang, who in their turn migrated southwards and made themselves masters of Ki-pin. Later on, about 160 B.C., the Yüeh-chi were attacked by the

¹ See, however, Dr. Fleet's remarks, *JRAS.*, 1914, p. 293 and note 1.

² *JRAS.*, 1914, pp. 289 ff.

Wu-sun and continued their march towards the west. In Bactria they settled down under the rule of several *hi-hou*. More than hundred years later the *hi-hou* of Kuei-shuang K'in-tsin-k'io conquered the other *hi-hou*, established himself as king and adopted the dynastic title "King of Kuei-shuang." He invaded An-si (Parthia), conquered Kao-fu and annihilated P'u-ta and Ki-pin. He died at the age of eighty years and was succeeded by his son Yen-kao-chên, who "again" conquered India and appointed a governor of that country.

It is now generally recognised that K'in-tsin-k'io is identical with Kujula-Kadphises and Yen-kao-chên with Vima-Kadphises, and that the Sai-wangs were the people who in India were known as Śakas or Śaka-murundas.¹ The information which can be gathered from Chinese tradition is accordingly to the following effect :—

The Śakas conquered the country which the Chinese called Ki-pin. Here they were later on replaced by the Kushana chief Kujula-Kadphises, who also invaded Parthia, and whose son Vima-Kadphises "again" conquered India. We are not told whether the Śakas extended their conquest beyond Ki-pin. The remark, however, that Vima-Kadphises' conquest of India was a re-conquest would naturally lead to the conclusion that India had formerly been subjected to the rule of the Śakas.

Sinologists seem to agree that Ki-pin in the times of the Han and the Wei denoted Kashmir, while in the T'ang period it was identified with Kapiśa, i.e. the country drained by the northern tributaries of the Kabul river.² There cannot be any doubt about the correctness of the latter statement that the terms Ki-pin and Kapiśa were often in the times of the T'ang dynasty used to denote the same locality. The principal reasons on which it is based have been ably summarised by M. Chavannes,³ as follows,—

(1) In the Chinese-Sanskrit dictionary Fan-yü-tsa-ming by Li-yan *Kie-pi-sho-ye*, i.e. Kapiśa, is given as a synonym of Ki-pin ;

(2) Hsuan-tsang states that the kings of those parts were in the habit of spending the summer in *Kia-pi-shi*, i.e. Kapiśa, and the winter in Gandhāra. A century later Wu-k'ung gives the same information, but substitutes *Ki-pin* for *Kia-pi-shi* ;

(3) From the T'ang-shu we learn that in the days of Hsuan-tsang the dominions of the Tu-kü extended as far as Ki-pin, and the Turkish Kagan gave the Chinese pilgrim an escort to *Kia-pi-shi*, i.e. to the southern limit of his empire.

That Ki-pin was, in the T'ang period, different from Kashmir can also be inferred from the fact that Wu-k'ung came to Kashmir after having visited Ki-pin. According to him Gandhāra was the eastern capital of Ki-pin, and, as Gandhāra was the lower Kabul valley, Ki-pin must have comprised the central part of that valley.⁴

Finally *Ki-pin* can be considered as a Chinese rendering of the word Kapiśa,⁵ though it is by no means certain that such be the case.

Kapiśa seems to have been an old country. Lassen⁶ has identified it with *Kapissa* which, according to Pliny VI. 25, was conquered by Kyros, and, if this identification can be upheld, we should be able to trace the name back to the 6th century B.C.

¹ Cf. *SBAW.*, 1916, pp. 787 ff.

² Franke, *Beiträge aus chinesischen Quellen zur Kenntnis der Türkvölker und Skythen Zentralasiens*. Berlin, 1904, p. 80.

³ *Documents sur les Tou-kue (Turcs) occidentaux*. St. Pétersbourg, 1903, p. 52¹.

⁴ Lévi, *Jo. As.*, IX, vi, pp. 371 ff.

⁵ Lévi, *Jo. As.*, IX, vii, pp. 161 ff. According to a note added to the Ming edition of the *Na-tien-king* (*Milindapañna*), Ki-pin is a *fa*, i.e. Indian word, meaning "mean fellow." Cf. Lévi, *Jo. As.*, IX, x, p. 529²; Schlegel, *Toung-pao*, II, i, pp. 329 f. Perhaps this means that Kapiśa was explained as *ka* (or *ku*)-*pīśa*.

⁶ *Indische Alterthumskunde*, Vol. I, pp. 859 f.

In the T'ang period Kapiśa was a considerable power. In Hsuan-tsang's time Gandhāra had fallen under its domination, and Wu-ta-kia-han-ch'a, i.e. Udbhāṇḍa on the Indus, was one of the residence towns of its king. Nagarāhāra, Lampāka, and other countries belonged to their dominions, which later on also comprised Udyāna. Takahāṣilā, which had formerly belonged to Kapiśa, on the other hand, had recently passed into the possession of the Kashmir kings.¹

The arguments in favour of the identity of Ki-pin and Kashmir in the Han and Wei periods are far less convincing. According to M. Lévi² they are,—

In Chinese works such as the Pien-yi-tien section of the T'u-shu-tai-ch'eng and the Hsin-k'uei-t'u-chi, Ki-pin and Kashmir are identified ;

The old annals distinguish Ki-pin from Kao-fu, which latter name must signify Kabul ;

The Wei annals state that the country was surrounded by four mountain ranges, and that it extended 800 li from east to west and 300 li from north to south ;

Finally Ki-pin can very well be a rendering of an Indian word *Kapira* ; cf. the transliteration of *Rāhula* as *Lo-yun*. This *Kapira* can be compared with Ptolemy's *Kaspēria*, *Kaspeiraioi*, and may represent a Sanskrit *Kāspira-Kāsmira*. Paramārtha, a native of Ujjayini, who lived in the second half of the 6th century, in his translation of the *Abhidharma-kōśa* always renders *Kāsmira* by *Ki-pin*,³ while Hsuan-tsang, a century later, in his translation of the same work, renders the Indian name as *Kia-shi-mi-lo*.

These reasons are far from being conclusive. The identification of Ki-pin and Kashmir in some Chinese sources does not prove much, if we remember that Kashmir became part of the empire of the Kushanas, of whom we know that they made themselves masters of Ki-pin after the Śakas. Mountain ranges are found everywhere in Afghanistan as well as in Kashmir, and the fact that Ki-pin may be a rendering of *Kāsmira* does not prove that such is actually the case. Ptolemy's *Kaspeiraioi* are located between the country of the Pāṇḍavas and the Vindhya hills,⁴ and Paramārtha's rendering would, at the utmost, prove the identity of Ki-pin and Kashmir in his time, and we have already seen that such cannot be the case.

It will accordingly be necessary again to examine the information which can be gathered from the oldest Chinese sources.⁵

The Chinese first heard about Ki-pin during the rule of the emperor Wu-ti (140-87 B.C.). The country was then in the possession of the Sai, i.e. the Śakas. Later on it was conquered by the Kushanas, and the first Kushana ruler does not seem to have extended his power beyond Ki-pin into India proper. In the time of Yuan-ti (48-33 B.C.) ambassadors from Ki-pin arrived in China and were escorted back as far as Hien-tu, which was accordingly on the way to Ki-pin. Also the Sai, i.e. the Śakas, passed Hien-tu on their way to Ki-pin.

According to M. Specht, Hien-tu was situated to the east of Badakshan. Professor Franke,⁶ on the other hand locates it at a short distance to the west of Skardu. He bases his conclusions on Fa-hian's description of his route from Turkistan to Udyāna. After crossing the passes he arrived at Kie-cha, and thence proceeded along the hills towards the south-west and arrived at a gorge where one had to descend and cross (*tu*) by means of hanging (*hien*) ropes. This description seems to suit the famous gorge near Skardu. From Hien-tu Fa-hian then arrived in Udyāna, i.e. the Swat valley. He did not accordingly

¹ Chavannes, *loc. cit.*, p. 174 ; Lévi, *Jo. As.*, IX, 1, p. 529.

² *Jo. As.*, IX, vi, pp. 371 ff.

³ *Ibidem*, p. 384.

⁴ Lassen, *loc. cit.*, Vol. III, p. 146.

⁵ Cf. Franke, pp. 59 ff. ; Specht, *Jo. As.* VIII, ii, pp. 323 ff. ; IX, 1, pp. 162 ff. ; Lévi, *Jo. As.*, IX, vi, pp. 371 ff.

⁶ *Loc. cit.*, pp. 56 ff.

proceed from Hien-tu to Kashmir, but towards the west, whereby he would have to cross the Indus a second time. His description would accordingly lead us to infer that Ki-pin was situated to the west of Kashmir.

This well agrees with the information which can be gleaned from older Chinese sources. According to the Han annals Ki-pin was bounded towards the south-west by Wu-i-shan-li, towards the north-west by the Bactrian empire of the Yüe-chi, while towards the north-east it was eight days' journey distant from Nan-tun, and towards the east 2250 li distant from Wu-cha. In another place Ki-pin is mentioned between An-si, i.e. Parthia and Wu-i-shan. Wu-i-shan-li is, as shown by Professor Marquardt,¹ a rendering of the Greek Alexandria, i.e. Kandahar, or, according to M. Chavannes,² Herat, and according to Cunningham³ it comprised the whole of South-western Afghanistan. This description certainly seems to indicate parts of Afghanistan, to the south of the Hindukush. Of Kao-fu, to the south-west of the Ta Yüe-chi, we hear⁴ that it sometimes belonged to Ki-pin and sometimes to T'ien-chu. Kao-fu has been identified with Ptolemy's Kaboura, the present Kabul, and, if we consider Kao-fu as the border land between Parthia and Ki-pin,⁵ to which latter country it sometimes belonged, we are led to think of parts of the Kabul valley and neighbouring districts, i.e. territories which we have found formed part of Kapiśa. Professor Franke therefore arrives at the conclusion that Ki-pin comprised the north-western portion of the present Kashmir state, the Indus country down to the Kabul river, the country between the lower Kabul river and the Swat river, and further parts of the Panjāb. These must be added, because we learn about Ki-pin that it was a flat and hot country, a designation which does not at all suit Kashmir. I think that we cannot get nearer at the truth. The only territories mentioned by Professor Franke which I do not think can be proved to have belonged to Ki-pin are the north-western districts of Kashmir. On the other hand it is possible that it extended a little further towards the west and the south-west.

Ancient Ki-pin thus included districts which were later on known as Kapiśa, and I do not see why it should be necessary to assume that the Chinese at different periods used the designation Ki-pin in two different senses. It seems to me that we shall have to return to the old explanation of Ki-pin as a rendering of the same word which the Greeks made into Kōphēn, whereby we must bear in mind that the Greek *ph* was an aspirated labial and not a spirant. The reasons brought forward against this identification are little convincing. M. Lévi⁶ thinks that the name Kōphēn had probably already become obsolete when Megasthenes picked it up. Ptolemy ignores it and calls the principal river of Afghanistan Koas, and finally Strabo has another form of the name, viz. Kōphās. I cannot find anything in these arguments which disproves the old identification of the names Kōphēn and Ki-pin, which is in itself much more likely than the supposed renderings of Kapiśa and Kāśmīra by Ki-pin. The fact remains that the Greek knew a name which they thought sounded like Kōphēn, that this name sounds much more like Ki-pin than any other name which has been suggested, and that we have every reason for looking for Ki-pin in the same neighbourhood where the ancient Greeks located Kōphēn, the country on the Kōphēn. The fact that the Chinese later on used the name Kapiśa of districts which others included in Ki-pin seems to be much more naturally explained by assuming that Kapiśa formed part of ancient Ki-pin and was sometimes designated by means of the wider name Ki-pin.

In support of my location of ancient Ki-pin I may mention a small detail. I hope to have proved in another place⁷ that the so-called Murundas who ruled in the Ganges valley in

¹ *Untersuchungen zur Geschichte von Eran*, H. 2, Leipzig, 1905, p. 176.

² *T'oung pao*, II, vi, p. 514.

³ *Specht, Jo. As.*, VIII, ii, p. 325.

⁴ *Jo. As.*, IX, vi, pp. 371 ff.

⁵ *Ancient Geography of India*, Vol. I, p. 39.

⁶ Franke, p. 77.

⁷ *SBZW*, 1916, pp. 790 ff.

the second and third centuries A.D. were in reality the Kushanas, and that the word *murunda* itself is not the name of a tribe, but a Śaka word meaning "lord," which was used as a title by the Śakas and after them by the Kushanas, while the Kshatrapas translated it by the corresponding Indian word *svāmin*. Wherever we meet with the designation *murunda*, we are justified in thinking of Śakas or tribes that can be considered as the heirs and successors of the Śakas. Now Lassen has long ago¹ drawn attention to the statement in Hēmachandra's *Abhidhānāchintāmaṇi*, v. 960, *Lampākās tu Murandāḥ syuḥ*, "the Lampākas would be (called) Murandās." Lassen inferred that the *Murandās*, who must be identical with the *Murundās*, should be located in the present Laghman. This, however, is impossible, when we consider the information about the *Murundās* which can be gleaned from Indian, Greek and Chinese sources, which unanimously locate the so-called people in the Ganges valley. If we examine the preceding stanza in Hēmachandra's work, we there find the remark, *Turushkās tu Śākayaḥ syuḥ*, "the Turushkas would be called Śākhis." It has long ago been recognised that this *śākhi* is nothing else than the title *śāhi*, and we are quite justified in looking for a title in *murunda* as well. Now that we know that *murunda* was actually a Śaka title, the natural inference is that the Lampākas had preserved this title from the time when they were ruled by Śakas, in other words that their country belonged to the dominion of the Śakas, of whom we know that they ruled in Ki-pin.

Finally, the location of ancient Ki-pin here attempted is the only one which suits what we know about the ancient history of the Śakas and the Kushanas. We have no traces of the Śakas or of Kadphises in Kashmir, and there is not the slightest indication that they ever ruled there. Numerous finds, on the other hand, prove that they held sway in Taxila and further to the west, at least as far as towards Jalalabad. Of Huvishka we have traces as far west as in Khawāt.

I have consulted Professor Franke about the results of my study of the question, and he kindly authorises me to state that he agrees with me. The support of his great authority makes me confident that I am right.

Taxila, the find-place of the present inscription, accordingly belonged to Ki-pin, and "India" which was reconquered by Vima-Kadphises was beyond Ki-pin, i.e. beyond the north-western Panjāb. We thus have an old tradition about a king who succeeded the Śakas in Ki-pin, and about his son, who reconquered India. Now I have shown in my *Indo-Scythian Contributions* that the Kushanas in India must be considered as the heirs and successors of the Śakas, that they were known under the Śaka title *murunda*, and that it would be nothing extraordinary if a Kushana ruler were designated as a Śaka. I have therefore compared the Chinese tales about the Sai-wang and the Kuei-shuang in India with an Indian tradition, which has been handed down in the Jain work *Kālakāchāryakathānaka*.²

We there learn how the king of Ujjayini, Gardabhilla, abducted the sister of Kālaka, who went to the country of the Śakas (*sagakūla*) and prevailed upon some of the *sāhis*, i.e. chiefs, to accompany him to India (*Hindugadśa*). They first proceeded to Surat (*Suratṭha*) and thence, in the autumn, to Ujjayini, where Gardabhilla was made prisoner. A *Sāhi* was made overking, and thus the dynasty of the Śaka-kings originated. After some time, however, Vikramāditya, the king of Mālava, ousted the Śakas and became king, whereafter he established his own era. After the lapse of 135 years his dynasty was overthrown by another Śaka, who in his turn introduced the Śaka era.

I have no doubt that this second Śaka king who reconquered India is identical with Vima-Kadphises, who "again" conquered India; and, if that is admitted, the Jain tale at once acquiesces

¹ *Loc. cit.*, I, p. 548¹.

² *ZDMG.*, 37, pp. 247 ff.

great importance. It must be a very old tradition, and we have no reason to reject any portion of it, unless it can be disproved. I know that most European scholars, though many of them speak with respect about Indian tradition, do not usually take any notice of it, but I am unable to see why. And with regard to the narrative of the *Kālakāchāryakathānaka* I see no reason whatever why we should disbelieve it. I have shown elsewhere¹ that there are good reasons for assuming the existence of a Mālava king Vikramāditya at an early date, and² that the oldest dates in the Mālava-Vikrama era are recorded according to a system which is quite different from that followed in old Kharōṣṭhī inscriptions, and which is probably the old national Indian one. I think the only sensible course is to abandon the idea that the Vikrama era was established by foreigners and return to the traditional theory that it dates back to an Indian ruler of Mālava, who upset the rule of Śaka conquerors. As remarked by Dr. Fleet, everything we know about Indian eras is to the effect that they were started by individual kings, and, though the Vikrama era was later on known as the era of the Mālava corporation, I do not think that Dr. Thomas has succeeded in making it probable that "it dates from the foundation of the tribal independence of the Mālavas."³

The oldest dates in the Śaka era are recorded in the same way as the ancient Kharōṣṭhī inscriptions, and this state of things makes it almost certain that Dr. Thomas was right in assuming⁴ that these latter ones were likewise dated in a Śaka era. The second Śaka era, of A.D. 78, was according to the *Kālakāchāryakathānaka* founded by the Śaka ruler who ousted the dynasty of Vikramāditya and "again" subjected India to the sway of the Śakas. I have already remarked that I identify this Śaka ruler with Vima-Kadphises, who "again" conquered India and appointed a governor to rule the country. If we remember that Surat and Mālava were the countries which the Śakas invaded at the invitation of Kālaka, when he asked them to accompany him to India, it becomes probable that the governor whom Vima-Kadphises appointed was the first of the Western Kshatrapas, i.e. in my opinion, Bhūmaka-Ysamōtika.⁵ It is thus easily explained why the inscriptions of the Western Kshatrapas are dated in the Śaka era.

If now Vima-Kadphises was the ruler who established the Śaka era, he can scarcely be the king alluded to in the Taxila inscription. His conquest of India did not probably take place in the first year of his reign, and we may roughly place his accession in A.D. 75. His father, who died as an octogenarian, would then have been born circa 5 B.C. According to Professor Franke⁶ the consolidation of the Kushana empire under Kujula-Kadphises had not taken place in A.D. 24, but did not happen long after that date. In l. 5 of the so-called Takht-i-Bahi inscription I read *erjhuna Kapśa puyae*, "in honour of prince Kapśa." This prince Kapśa can hardly be anybody else than Kujula-Kadphises, of whom we know that he invaded Parthia. The Takht-i-Bahi inscription is dated in the year 103 of the era which I follow Dr. Thomas in considering as an old Śaka institution. It can, of course, be anterior to A.D. 24, but scarcely much later. The initial date of the era would accordingly not fall later than about 75 B.C., but might fall some years earlier. At least there cannot be any question of the Vikrama era, which, I think, we must finally ascribe to Central India. With an initial date in or about 75 B.C., the year 136 would fall about A.D. 60, at a date when there can be no question of placing Vima-Kadphises; and, even if we were to assume that Kujula-Kadphises ascended the throne as much as 10-15 years after A.D. 24, the Taxila inscription would still have to be ascribed to Kujula-Kadphises. It should finally be borne in mind that we have the definite statement about him in Chinese sources that he assumed the title "King of Kuei-shuasog," i.e. Kushana king.

¹ *SBAN*, 1916, p. 812.

² *JRAS.*, 1914, p. 414.

³ *SBAN*, 1916, p. 814.


⁴ *Above*, pp. 135 ff.

⁵ *JRAS.*, 1913, p. 637.

⁶ *Beiträge*, p. 72.

Original.

Transcript.



TEXT.

- 1 Sa 100 20 10 4 1 1 ayasa Ashādasa masasa divase 10 4 1 iśa divase
 pradisthāvita bhagavato dhatu[o] Ura[sa]-
 2 keṇa Indafriya putr[e*]ṇa Bahaliṇa Noachae nagare vasthaveṇa Teṇa ime
 pradisthāvita bhagavato dhatuo dhamara-
 3 iśe Tachhaśi[la*]ṇe Tapuvae bosī(dhi)satva-gahamī maharajasa rājatirajasa
 devaputrāsa Khushapasa arogadachhipae
 4 sarvabudhāṇa puyae prach[e*]gabudhāṇa puyae araha[nta*]ṇa puyae
 sarvasa[iva*]ṇa puyae matapitu puyae mitr-amacha-ñati-sa-
 5 lohī[da*]ṇa puyae atvapo arogadachhipae ni[va]ṇae hotu a . . . de sama-
 parichago

TRANSLATION.

In the year 136, on the 15 day of the first month of Āshādha, on this day relics of the Venerable One were enshrined by Urasaka, the son of Indafri, a man from Balkh, a resident of the town Noacha. By him the relics of the Venerable One were enshrined in the Dharmarajika (*stūpa*) in Takshaśilā, in the Bōdhisattva-chapel of Tapuva, for the bestowal of health on the great king, the king of kings, the son of the gods (of heaven), the Khushana; in honour of all the Buddhas; in honour of the individual Buddhas; in honour of the Arhats; in honour of all beings; in honour of (*his*) parents; in honour of (*his*) friends, ministers, kinsmen and blood-relations; for the bestowal of health upon himself; to Nirvāṇa may this proper gift lead hereafter (?).

No. 21.—ARTHUNA INSCRIPTION OF THE PARAMARA CHAMUNDARAJA:
 VIKRAMA-SAMVAT 1136.

BY LIONEL D. BARNETT.

The village of Arthūṇa lies about 28 miles in a westerly direction from Bāṇswārā in Rājputānā; it is shown on the Indian Atlas quarter-sheet 36 (1905) as lying in lat. 23° 29½', long. 74° 9½'. About a mile to the east of Arthūṇa is a temple of Maṇḍalēśvara Mahādēva (Śiva); the present inscription, which records its foundation and endowment, is on a slab on the right side of its *śikhara*. According to local tradition, the place formerly bore the name of Amarāvati. An abstract of this record was published by Professor Kielhorn in *Ind. Ant.*, Vol. 22 (1893), p. 80. Recently Mr. Shyama Shankar Har Chaudhri, M.A., with great kindness obtained for me from the Antiquarian Department of His Highness the Maharaja of Jhalawar's Government the loan of an ink-impression of the stone, together with a transcript by the learned Curator of the Department, Pandit Gopal Lal Vyas, on the basis of which I now edit the text. Unfortunately the ink-impression in several places has been touched up with white paint, which somewhat lessens the value of its testimony; but in spite of this fact and of the frequent incorrectness of the original writing the greater part of the inscription can be determined with certainty.—The character is Northern, of a type common in Rājputānā during the period; the letters are on the average about ½" in height. They are for the most part fairly well preserved. The area covered by the writing is 2 ft. 6½" wide and 2 ft. 2" high.—The language is throughout Sanskrit, all verse, with the exception of the colophon on l. 53. The spelling throughout shews a tendency to confuse *ś* and *s* (I fear I may not have always succeeded in distinguishing what the engraver really put in this respect, owing to the touching up of the ink-impression), and sporadic doubling of consonants after *r*. In the somewhat ambitious *prastāvi* occupying ll. 1-45, which shews that the poet was a careful student of Kālidāsa, there is little of special linguistic interest; we may note the words *tōṇira* (for *tūṇira*, l. 5), *kamḍala* (l. 12), and *uchch[ra*]lumpichakāra* (l. 40). But in the business part of the record, comprising the articles of the endowment (l. 45 to end), there is a fair number of

rare words, mostly of a homely kind, viz. *prati* (ll. 45, 46), *haṭṭa* (l. 46), *māṭaka* (ll. 46, 50), *pālaka* (l. 47), *jāla* (ib.), *utthapanaka* (ib.), *vuśvaka* (l. 48), *lagaḍḍa* (ll. 48, 50), *saṁta* (l. 48), (?) *pāṇaka* (ib.), *viśha-viñśōpaka* (l. 49), *tavaṇi* (ib.), *araghaṭṭa* (ib.), *hāraka* (ib.), *chhaṅga* (l. 50), *rāpa* (ib.), and *āṭavika* (ib.).

The subject of the inscription is the foundation and endowment of the temple of Maṇḍalēśa (Śiva) at Arthūpā by the Paramāra king Chāmunḍarāja. After two Śaiva benedictory stanzas, it gives the familiar legend of the origin of the Paramāras. First Mount Arbuda (Ābū) is described (v. 3); here the saint Vasishṭha performed his holy rites (v. 4), in company with his wife Arundhati (v. 5) and the Cow of Desire (v. 6). Viśvāmitra, son of Gādhi, stole the cow (v. 7). To recover her Vasishṭha miraculously created a warrior, who defeated the enemy and brought her back (vv. 8-10). Vasishṭha blessed him and gave him the name Paramāra, "Destroyer of Foes" (v. 11). In his lineage was the warrior king Vairisimha (v. 12), who, despising common glory, became master of the earth (vv. 13, 14). Next his younger brother Dambarasimha, a valiant and charming prince, is introduced (vv. 15-16). In his lineage was Kakkadēva (probably an error for Kakkadēva), a brave warrior (vv. 17-18), who in a battle on the banks of the Narmadā overthrew the army of the king of Karpāṭa, and in fighting on the side of Śriharsha of Mālwa died a hero's death (v. 19). We are then told of the glories of his son Chaṇḍapa (vv. 20-21), Chaṇḍapa's son Satyarāja (vv. 22-24), Satyarāja's son Maṇḍanadēva (vv. 25-45), and Maṇḍanadēva's son Chāmunḍarāja (vv. 46-54). He (apparently Chāmunḍarāja) gloriously overcame Sindhurāja (v. 55); his splendours are further described (vv. 56-61). He established religion in an unprecedented degree (v. 62), and dispensed rich bounties to Brāhmins and others (vv. 63-65). He caused the temple of Maṇḍalēśa to be built (v. 66); may his fame endure for ever (v. 67). Then follow the details of the endowment (vv. 68-81), and comminatory stanzas (vv. 82-83). In the Sādhāra family was the learned poet Sumati-Sādhāra (v. 84); his son was Vijaya-Sādhāra (v. 85), whose younger brother was Chandra, the author of this poem (v. 86). The fair copy was written by Āsarāja, son of the Kāyastha Śrīdhara (v. 87).

The family of kings introduced to us by this *prastāvi* is a junior branch of the Paramāra dynasty. The point at which they branched off from the main stock (as represented by the family ruling Mālwa from Kṛishṇa-Upendra down to Arjunavarman: above, Vol. I, p. 224, *Ind. Ant.*, Vol. XIX, pp. 345 ff.) is not clear: it may be from Vairisimha and his brother Dambarasimha, for conceivably the former may be identical with the Vairisimha I of the Mālwa dynasty.¹ Some generations after these we find Kakkadēva fighting for the cause of "Śriharsha" of Mālwa against the "Lord of Karpāṭa." This "Śriharsha" is most probably Harshadēva-Siyaka II of Mālwa; and the "Lord of Karpāṭa" may be the Rāshtrakūṭa Khottiga, against whom Siyaka II waged a successful war about 970 A.D. Accordingly we may assign Chaṇḍapa to about 1000 A.D., Satyarāja to about 1025, Maṇḍanadēva to about 1050, and Chāmunḍarāja to 1080, which was the actual year in which the present inscription was set up. Some difficulty, however, arises from the obscurity of the verses 47 ff. To all appearance they refer to Chāmunḍarāja, and we should naturally gather from them that it was he who conquered Sindhurāja (v. 55), patronised religion (v. 62), and built the temple of Maṇḍalēśa (v. 66). But immediately afterwards we find a prayer for the continuance of the glory of Maṇḍanadēva (v. 67) and a statement that certain imposts for the benefit of the temple were established by the latter (v. 70). The most natural conclusion is that vv. 47-66 do refer to Chāmunḍarāja; that the temple of Maṇḍalēśa built by him was a new structure taking the place of an older sanctuary to which his father Maṇḍanadēva had

¹ Considerations of chronology forbid us to identify him with Vairisimha II of Mālwa.

previously granted an endowment¹; and that the present inscription was intended to record these facts and to amalgamate the endowments of the father and the son.

Who *Sindhurāja* (v. 55) can be is not clear. He cannot be the well-known *Sindhurāja* of *Mālwa*, whose period is about 990-1010 A.D.; for, even if we refer v. 55 to *Maṇḍanādēva*, the latter can hardly have been old enough to wage a victorious war before 1010; and as we saw, the probability is that the verse refers to his son, which will bring it still further down in time. Possibly *Sindhurāja* is to be understood as meaning "a king of *Sindh*."

The date as given on the ink-impression and read by Pandit Gopal Lal Vyas is: *Samvat* 1136;² *Phālguna śuddha*, the 3rd day; Friday. On this Mr. R. Sewell has kindly supplied to me the following remarks: "Since the month is *Phālguna*, the beginning of the year, whether *Chaitra*, *Kārttika*, or *Āshāḍha*, makes no difference in the year's number; and since the *tithi* was in the bright half, it makes no difference whether the months began with the new or full moon. Hence the only question is whether the year was current or expired. Take the *expired* case first. In that case *Samvat* 1136=A.D. 1079-80. The lunar year began 7 March 1079, and 3 *śukla Phālguna* corresponded with Tuesday, 28 January, A.D. 1080. This, therefore, does not fit. Now take the *current* *Samvat* 1136. This=A.D. 1078-79, which began in lunar reckoning on 17 March 1078. 3 *śukla Phālguna* of that year must have been coupled with a civil day 327 days later, viz. with Thursday, 7 February, A.D. 1078. On that day, 3 *śukla Phālguna* ended about 11 h. 24 m. before mean sunrise on the Friday next day, and it could not be coupled with that Friday. However, this is nearer than the Tuesday of the former case."

On the other hand, Professor Kielhorn, in his notice of the inscription, read the number of the *tithi* as *seven*, and accordingly calculated the date as Friday, 31 January, A.D. 1080, when, according to his reckoning, the seventh *tithi* of the bright half ended 20 h. 3 m. after mean sunrise. Mr. Sewell has pointed out to me that this is a satisfactory solution. "Only," he adds, "Kielhorn made a slip about the end of the *tithi*, so it seems to me. My work shows that the 7th *śukla tithi* of *Phālguna* in *Samvat* 1136 *expired* was current at mean sunrise on Friday, 31 January, A.D. 1080. It had begun 2 h. 25 m. before that mean sunrise, and was coupled with the civil day Friday. . . . Supposing that the calculation for the given date had been made for the moment of true sunrise, not mean, would the results be different? I think not. In Northern India true sunrise on Jan. 31 would take place *after*, not *before*, mean sunrise. Hence, since the 7th *śukla tithi* had begun 2 h. 25 m. before mean sunrise, it would have run a still longer time at the moment of true sunrise." Accordingly it would seem most probable that the numeral representing the *tithi* on our inscription was really 7, and has been wrongly altered by the preparer of the ink-impression to 3.

The only places mentioned are: Mount *Arbuda*, now *Ābū* (v. 3), *Karṇāṭa*, the *Narmadā*, and *Mālava* (v. 19).

TEXT.³

[Metres: vv. 1, 3, 4, 13, 19, 24, 28-9, 31, 37, 39, 40-1, 43, 45-6, 49, 58, 63-4, 67, *Śārdā-lavikṛīḍita*; vv. 2, 5-7, 14, 16, 18, 21, 23, 26-7, 30, 32-5, 42, 44, 47, 52-3, 57, 61-2, 65, 68-70, 72-84, 87, *Anuṣṭubh*; vv. 8, 48, *Drutavilambita*; vv. 9, 10, 38, 51, 56, *Sragdhara*; vv. 11, 36, 71, *Śoḍaśatī*; vv. 12, 15, 17, 22, 25, *Vasantatilaka*; vv. 20, 86, *Triṣṭubh*; vv. 50, 59, 60, *Māṇḍākrāntā*; vv. 54, 66, *Mālinī*; v. 85, *Āryā*. V. 55 is compounded of a *Rathōddhatā* (pāda 1) and *Śoḍaśatī* (pādas 2-4).]

1 Om⁴ Om Namaḥ Si(śi)vāya | Pāpau va(ba)ddha-bhujamga-phātākṛiti-bhayāt-
sankōchayatyaḥ karam vyākṛiṣṭam jaratī-janēna rabhasa(ch)-Chhambhōr-

¹ Possibly the name *Maṇḍalāśa* was intentionally chosen to commemorate the name of *Maṇḍanādēva* by likeness of sound.

² Curiously enough, the poet in v. 86 gives the year as *Śaka* 1136; chronological considerations prove this to be an error.

³ From the ink-impression

⁴ Denoted by a symbol.

- dr̥iḡham grihna(hpa)taḥ | bh̥r̥m̥t̥āḥ sambh̥ramataḥ sukh̥ān-mukulitā visph̥aritāḥ
kantukūta(d) vrid̥h-mamv̥ratā¹ viv̥ha-samayē Dēvyā dr̥iḡa[h*]²
- 2 pāntu vah || [1*] Indum m̥rddh̥nī dad̥ba[t*] ksh̥iṇam p̥āta vah Sasi-
s̥kbarah³ | kh̥ēdād-iva sad-āsanna-Gauri-mukha-par̥j̥yāt || [2*] Asty-
uchohair-gagan-āvalam̥iva(ba[bi?—Ed.])-si(śi)kharah ksh̥ōṇibh̥rid-asyām bh̥uvi
khyātō Mēru-mukh-ochchhrit-ād[r*]ishu p̥ārām kōṭīm gatō-py-Arvvu(rbbu)daḥ |
yatra sph̥āṭika-pushpa-rāga-kira-
- 3 n-āld̥h-ārka-chamdrau ksh̥apam̥ dr̥ishṭvā siddha-janair-amanyata divā r̥ātris(ś)-cha
naktam̥ dīnam̥ || [3*] Tasmims-tyakta-bhavas(ś)-charitra-vibhavas-tathyam tapo-
tapyata vra(bra)hma-jñāna-nidhir-guṇē(gai)r-niravadh̥iḥ s̥rē(ērē)sh̥thō Vasish̥thō
munīḥ | yasya prajvalit-āgni-hōtra-jvalitair-dhūmair-iva vyōma-gē(gai)r-j̥tāḥ
sam̥militās(ś)-chirēṇa haritās-tē
- 4 H̥āridasvā(śvā) hayāḥ | (||) [4*] Munēs=tasy-āntikē r̥ēḥ nirmmalā dēvy-
Arum̥dhati | sthira-vasy(śy)-ēndriya-grāmā tapaḥ-śrīr-iva jaṅgamā || [5*]
Ananya-sulabhā dhēnuḥ kāmā-pūrvv-āya sam̥nidhan | dadati v̥m̥chchhitān-
kāmā[m*]s=tapaḥ-siddhir-iva sthitā || [6*] Tataḥ ksh̥atra-mad-ōdvritō Gādhi-
rāja-suta-
- 5 ch(ś)-chhalit | dhēnum̥ jar(ja)br̥ē-sya duh̥prāpyām⁴ vighnam̥ siddhim-iv-
ōdyatām || [7*] Atha par̥ābhava-sambhava-manyunā jvalana-cham̥da-ruchā
munin-āmunā | ripa-vadham̥ prati vira-vidhitesyā hutabhujī sph̥uṭa-mantra-
yutam̥ hutam̥ || [8*] Prish̥thē topira-yugmam̥ dadhad-atha cha karē
cham̥da-kō-
- 6 daṇḍa-daṇḍam̥ va(ba)dhnan-jūṭam̥ jaṭānām-atinivīdataram̥ pāṇinā daksh̥iṇēna |
kruddhō yajñōpavitī nija-vishama-dr̥iḡa bh̥āyayāṇ-jiva-lōkam̥ tasmād-uddāma-
dhāmā prativa(ba)la-dalanō nirggataḥ kō-pi virah || [9*] Ādis̥ṭṭas-tēna yātō
raṇam̥-amara-gaṇair-mmam̥-
- 7 galē gtyamānē vā(bā)ḍham̥ vyāpt-ām̥taralair-dinakara-kiraṇa-chh̥āḍakair-vvā(bbā)ṇa-
varshē(rshai)ḥ || (||) k̥ritvā bh̥am̥gam̥ rip̥ṇām̥ prava(ba)la-bhuja-va(ba)lah
kāma-dhēnum̥ grihitvā bhaktyā tasy-ām̥hri(ghri)-padma-dvaya-lulita-si(śi)rāḥ
sō=vatasthau purastāt || [10*] Ānatasya jayinah̥ paritus̥ṭhō v̥m̥-
- 8 chchhit-āsisham-asāv-abhidhāya | tasya nāma Param̥āra it-ittham̥ tathyam-ēva
munir-āsu(su) chakāra || [11*] Tasy-ānvayē krama-vasād-udap̥ādī virah
śrī-Vairisim̥ha⁵ iti sambh̥ritāsanha⁶-nādaḥ | durvvāra-vairi-vara-vāraṇa-kumbha-
kūṭa-bh̥ēd-ōdyat-āsi-nakha-
- 9 r-ōḍḍamarah̥ ksh̥it̥lodrah || [12*] Kirttīm̥ tāvad-avēkshā(kshya) bh̥āva-chapalām̥
sambh̥oga-vrid̥dh-āpriyam̥ n[i*]tyam̥ māṅgala-sadmanā su(su)bha-chatur-ddik-
kumbhi-kumbha-prabhē(hau) | dōr-ddaṇḍa-dvaya-śālinā ksh̥itibhujām-āsā(ās)-
chatushk-āntarē yēu-ākāri kara-grahō vasudhayā gāḍa(dha)m̥ guṇ-āsa(sa)-
- 10 ktayā || [13*] Gata-śrīḥ śrī-nidhānēna sa-va(ba)m̥dhab̥ sam̥yat-āriṇā | na yēna
sam̥atām̥ dhattē jadadhib̥ paṭu-vu(bu)d̥hina || [14*] ⁷Tasy-ānujō
Dam̥va(mba)rasim̥⁸ha iti prachap̥ḍa-dōr-ddam̥da-cham̥ḍima-vas̥k̥rita-vairi-v̥rim̥-
daḥ [1*] s̥ri(śrī)ṅgāra-sāra-tarupī-jana-lōchan-āsi(li)-pum̥j-ōpara-
- 11 ddha-vadan-ānvu(bu)rah̥ va(ba)bh̥āva || [15*] Cham̥drik-āpi katham̥-kāram̥
yasya kirit̥yā samam̥ samā | ēkē dōsh[a*]kar-ōḍbh̥ūtē guṇ-ōṭkara-bhav-āparā ||

¹ Read *mantharita*.² Read *Sasi-s̥kharah*.³ Read *duh̥prāpyām*.⁴ Read *sambh̥rita-sim̥ha*.⁵ Metre: Vasantatilaka; the metre of pāda 1 is wrong. [The reading *Damara* would make it right.—

- [16*] Tasy-ānvayē kari-kar-oddhura-vā(bā)hu-dapḍaḥ śri-Kaṁkadēva¹ iti
lavdha(bāha)-jayō va(ba)bhūva darpp-āmdha-vairi-vanitā-kucha-patra-valli- ||²
12 saṁdoha-dāha-dahana-jvalita-pratāpaḥ || [17*] Yuddha-kamḍola-dor-ddamḍa-dvayē
yaḥ samaram prati | mēnē ripu-sa(śa)r-āghāta-nakha-kamḍūyanaḥ sukham ||
[18*] Ārādhō gaja-priṣṭha vāhuta(āhata?)-sa(śa)r-āśarai ranē sarvvataḥ
Karuṇāt-ādhipatēr-vva(bba)lam³ vidalayams-tan-Narmmadāyās-ta-
13 tē⁴ [19*] śri-Śriharsha-nripasya Mālava-patēḥ kritvā tath-āri-kshayam yaḥ
svarggam subhātō yayau sara-vadhū-nētr-ōtpalair-aroḥchitah || [19*] Tasy-
atmajas(ā)-Chamḍapa-nāmadhēyo vra(bra)hmāmda-vē(vi)bhrānta-yasā(śā) va(ba)-
bhūva [20*] sāmanta-kāntā-jana-hāsa-hamsa-śrēṇi-pravās-aika-payōda-kā-
14 lah | (||) [20*] Vra(bra)hma-staniva(ba)syā yat-kirttir-mmamjar-iv-ōpari
śhitā | sasvat⁵-kinnara-bhṛing-ō(au)ghair-upagīt-ādhiḥkām va(ba)bhan || [21*]
Saty-āspadam dahana-duḥsaha-vāma-dhāmā śri-Satyarāja iti tasya suto
va(ba)bhūva | sāmanta-dūra-nati-saṁgi-lalāṭa-paṭṭa-lagn-ōllasat-tilaka-pāda-na-
15 kh-āmsu-jālah || [22*] Vana-mālā-dharā nityam hi(bhi)yā yasy-āchyasā⁶ api |
ripavō na cha vijñām(jñā)tā na lakshmi-patayaḥ katham || [23*] Nirvyā-
jam karuṇ-ārdritō-pi satasō⁷ nistri(ētri)mśa-karm-ōdyataḥ saṁjāta-prasarō-pi
vikrama-śatair-amtaḥ sadā samyataḥ | ā-mūlam guṇa-varddhitō-
16 pi va(ba)hudhā dōḥ-ārijita-śri-harō yō-py-ēvam niyatam viruddha-charitō lok-
āviruddō(ddhō)-bhavat ||⁸ [24*] Tasmād-abhūd-īha payād-iva vpiddhi-yōgaḥ
punyas-triloka-tilakō vipul-ōnnat-āmsa(sa)ḥ | girvāṇa-chāru-charit-ārpita-karṇa-
pārah śri-mamdiram jagati Maṇḍana-dēva- ||⁹
17 nāmā || [25*] Viśāl-ora[h*]-sthalaṁ kā[m*]tam manyē Śrīr-utthit-ōditam | na
vavandha¹⁰ yam-āsādyā purāṇa-purushē ratim | (||) [26*] Anavaohohhinna-
dān-anghō yaḥ pralaṁva(ba)-kar-ōddhuraḥ | kul-aika-dhavalō bhadrāḥ sura-
dvipa iv-āvahau¹¹ || [27*] Viśphūrjan-nakha-chandra-dīdhitī lasal-lāvanya-
18 ntr-ōchchayam suznigdha-sphuṭa-dīrgha-rāji-ruchi-bhṛit sat-sa(śa)mkha-mūn-āmkitam |
vāhinīya[h*] prapattiva-yōgyam-atulam khyāva(ta)m śriyaḥ kārṇam yasy-
ādhatta kar-āmhri(ghri)-padma-yugalam sāmudrikam lakṣaṇam || [28*]
Va(ba)ddhvā kantukam-anvay-ōttha-ruchirā sarvv-āṁga-pārṇ-ādhiḥkām yēn-ātra
Smara-rū-
19 pipā dṛiḍha-bhujā-damḍ-ōllasan-mamḍapō | vairi-śrīr-nri-varēṇa bhavya-dīvas-
āvāptau parair-ihivē(tā) datt-ēyam nija-vikramēṇa mahav(t)-ē(ai)v-ōchchair-
ndāna¹² svayam || [29*] Dhṛita-viśvam-bharā-bhārah khamḍi[t-a*]rāti-vigrahaḥ
| asi[r*]-mmamtr-iva satatam yasy-āvarddhasyataḥ(ta) śriyam || [30*] Yasy-
ārā-
20 ti-vadhō-janasya saralāḥ svā(śvā)s-ānilāḥ sō(śō)ka-jair-ushṇ-ōshpāḥ paritō yug-
ānta-pavana-prasparddhiri(bhi)ḥ kēnanē | dagdhē nīla-triṇ-āmkur-ōtkara-bharō
nirē-dhikam sōahitē¹³ kriḥchbhṛēṇ-āsana-pāna-vṛitti-rahitāḥ khinnair-mṛigaiḥ
sthlyatē || [31*] Dīpyamānāḥ sadā sarvva-vāhin-lā-

¹ Read -Kakkadēva.² This syllable is engraved outside the line, in front of śri.³ Corrupt. The transcription of Pandit Gopal Lal Vyas gives acāyātā, which suits well the sense (see translation and note), but does not seem to be the reading of the ink-impression.⁴ Read safasō.⁵ The dāḍḍa is followed by a rosette and another dāḍḍa.⁶ Read babāḍḍa.⁷ Apparently a mistake for udāḍḍa.⁸ Delete this dāḍḍa.⁹ Read safasat.¹⁰ Delete this dāḍḍa.¹¹ Read -āḍḍahau.¹² Delete this dāḍḍa.

- 21 kshay-ōlla(lba)ṇaḥ | pratāpō yasya jajvāla Vā(bā)ḍavō-guir-iv-āparah || [32*]
Kirtti-nirggamanāth(d)-ēva śrīmkhal-ēva ripu-śrīyām | yasy-āsīḥ samarō bhām-
(bhā)ti vēpik-ēva jaya-śrīyāḥ || [33*] Valabbid-va(ba)la-yuktēna Gōtrahā
gōtra-namdinā | na yēna kṛitnā dhattē sō-pi sāmyam Parāmdarah || [34*]
- 22 Tasy-āsti hridayō Lakshmiḥ sa cha Śrī-hridayam-gamaḥ . sparddhā[m*]
pē(tē)na katham-kāram karōti¹ Garuḍa-dhvajaḥ || [35*] Yam pratāpa-
nava-pallava-kāntam kirtti-nirmala-dhṛit-ākshata-dēham [*] Śrīḥ sadā na hi
mumōcha day-āmbhaḥ-pūritam vijaya-maṅgala-kumbham || [36*] Nirvyājam
sura-māmdirō-tivima-
- 23 lair-vṛiddhair-gupaiḥ sthāpitā muktānām ruchi-dhāriṇi su-mahitā loka-traya-
vyāpini | praty-āśam prati-kānanam prati-puram gēham prati prastutām(tā)
yasy-aish-ādbhuta-dēvat-ēva satatam kirttir-ijanaib * sta(stā)yatō || [37*]
Lakshmyā yasminn-upātām jananam-atha yaśaḥ-pāṇḍu-piyāsha-pūrir-yatr-
ōdbhūtam
- 24 samantād-akhila-bhṛita-lasad-bhūtal-ās(ā)-āntarālah | kshir-āmbhōdhir-guṇ-anghō
niravadhir-abhavad-yasya chāritra-simuaḥ sītāmsu²-śrīr-yad-utth-āschchurayati
gaganam kirtti-kallōla-mālā || [38*] Kharvā kv-āpi na³ kuttra-chin-na
hi tathā lōkō gatā śēshatām na prāptā viratīm sphuṭam na hi
- 25 vṛisha-dhvams-ōday-āviḥ(ah)kṛitā | nō pūrṇa-aika-pad-ālpaka-tribhuvau-ākrodikṛitā
na kva-chid-yat-kirttir-vvīsi(śi)naḥ⁴ti kumda-dhavalā krishṇām tanum Śrī-patēḥ
|| [39*] Yasy-ōddāna(ma)ra-vā(bā)hu-daṇḍa-yugalasy-ōdyad-va(ba)lēn-ādhikam
samchchannēna rajo-bharaiḥ prachalataḥ pratyarthi-vṛindam prati | tē-
- 26 jas-tyaktam-abō svakam bhagavatām(tā) Chamḍ-āmsun-āpi sphuṭam praty-āśam
bhaya-sā(sa)dma sā(śā)titravajanasy⁵-ānyasya tat-kā kathā || [40*] Yasy-
āsā(śā)-vijay-ōdyatasya nikhila-kshmapāla-chōḍāmapēr-vvairi-śrī-hṛiti-lampāṭasya
chalatas-tir[ē*]shu vārām-nidhēḥ | kṛaddh-ādbhōraṇa-tarjīṭair-api muhur-mā-
- 27 n-ōnnataiḥ piyatē majja[d*]-dig-gaja-dāna-gandhi salilam duḥkheṇa sōṇ-gajaiḥ ||
[41*] Uchchair-dhṛita-vṛishō nityam sama-darśi gat-āhitaḥ | jin(t)-a(ā)sam-
khyā-puraḥ pōjyō yō-parah Paramēśvarah || [42*] Vikhyāt-āchapaḥ-ēti [—]⁶
priyatam-āsau śamkit-ēva Śrīyā gatv-Ādi-
- 28 tya-bhuvam surair-api nutā nityam visu(su)ddhā sati | mānēn-ō(ai)va tath-āpi
kirttir-amalēn-āmgikrit-āpi svayam |⁷ yōn-āyam yaśasā sah-aiva sahajēn-
ōttham jagad-bhṛāmyati || [43*] Dhanur-vvidyā-vidā yēna sat[t*]va-saty-aika-
śadmanā | rapō samvā(dhā)nam-āniya katham nu ripavō hatāḥ || [44*]
- 29 Ālānō vijaya-dvipasya ruchirā vēṇi nu kirtti-striyō dōr-ddaṇḍa-priya-nirbhar-
aika-vasatēs-chhāyā sphuranti Śrīyāḥ | vā(bā)ḍham vairi-vadh-ōdyataḥ prati-
raṇam Kāl-ōgra-damḍō gurur-yasy-āsīḥ susubhē⁷ parākrama-bhṛitō dṛipt-śrī-
darppa-chchhidat || [45*] Śūrah prauḍha-va(ba)lah
- 30 kul-aika-tilakō durvvāra-vir-āmtakō vairi-śrī-haran-aika-lampāṭa-lasach-chamḍ-āsi-
damḍ-ōlva(lba)ṇaḥ | kāmā-lōla-kaṭākeha-pūmja-nilayaḥ śrīṅgāra-Mina-dhvajō
jātō yasya ravi-dyutēr-ggūṇa-nidhiś-Chāmumḍarājah sutah || [46*] Guru-
duḥkh-ōshpa-nisya(śvā)sair-aśru-pūrai-

¹ The ō is wrongly formed, an i being written for the first mātrā and an ā for the second.

² Read sītāmsu.

³ Written na, with the u erased.

⁴ The corrections here are suggested by the Editor.

⁵ This syllable appears to be illegible on the stone.

⁶ Delete this dōḍa. [In what precedes I should prefer to retain mānēn-ōca.—Ed.]

⁷ Read susubhā.

- 31 ś-cha saṁtatam | kritam yasy-śri-kāntābhīr-ddagdha-pallavitam vanam ||
[47*] Ahita-dōsha-gu(ga)ṇair-udit-ōditair-jagati lavdha(bdha)-jayair-iva
vihṛitāḥ | sakala-loka-nikāya-nirākṛitā yam-iha sarvva-guṇāḥ śaraṇam yayuḥ ||
[48*] Durvvār-āri-vē(vi)dāriṇā hari-khura-kshunn(ṇṇ)-āntarā-
- 32 lē bhṛisam tīkshṇ-āstra-kshata-vānta-śōṇita-payab-pūra-plutē sarvvataḥ | nistṛi-
(stri)mś-āhata-kumbhi-kumbha-vigalan-muktāphalānām gaṇāḥ kshiptā vira-varēṇa
yēna samara-kshētrē yaśō-vi(bi)javat || [49*] ¹Vāram vāram prakṛiti-sambha-
gām² vau(dhau)ta-nistṛi(stri)mśa-pāṇim yuddhē yuddhē satata-
- 33 vijaya-śri-priyam khēchariṇām | tat-kāl-ōttha-smara-bhaya-vaśād-yam prati sparddhay-
aitā maṁdam maṁdam chakita-chakitam dṛiṣṭayāḥ saṁpatamiti || [50*]
Krōdhād-yasy-ātibhītā diśi diśi vihat-ānamta-sāmanā-kāntāḥ kāmāntārēṣu
pravāṣṭāḥ śrama-vaśa-vivaśāḥ saṁsri(śri)tā duḥkha-nidrām || [51*]
- 34 svapuḥ daivād-upāttān-nija-nija-ramaṇān-prāpya sambhogam-ētā(tya) jāgratyē(tyo)-
py-āsu(su) n-ēttham rati-rasa-rasikās(ś)-chakshur-unmilayamti || [51*] Śatrasa-
chamḍa-kōpēna yēna sva-sthāna-chālītāḥ | ³nija-kāntā-manō muktvā sthitim-
anyatra nō gatāḥ | (||) [52*] Sasvatannaḍako⁴ vā(bā)ḍham Va(ba)li-
va(ba)mḍh-ōdit-ōdi-
- 35 taḥ | Trivikrama iv-ōḍārām yā(yō) Lakshmiṁ satatam davan(dhau) || [53*]
Dṛiḍhataram-abhisa(sha)ktyā bhayya-sambhoga-ramyā vidhṛita-vimāla-paksha-
dvamdvam-ānamda-hētuḥ | kṣaṇam-api na mumōcha prāpya yam rāja-
hamsam kuvalaya-rati-pātram rāja-hams-iva Lakshmiḥ || [54*] Simdhurājam-
ati-
- 36 mathya hēlayā khaḍga-Maṁdara-bhṛitā yudhi yēna | uttamēna puruṣēṣu vi⁵
lēbhē śrīr-yaśō(śō)-bhuvana-pāvana-samkhaḥ || [55*] Viśvam vāri-pratāpam
jhaṭiti kavalayan līlayā jāṁgal-ābham chamḍ-āmsōs-tivra-śōchir-mulilana-kapilit-
ārechiś-chhaṭā-kēsara-śrīḥ | dhārā-dam-
- 37 śhṛā-karālō vilasati samarē jāta-ghāt-ōchcha-nāḍo yasy-ārāt-ibha-kumbha-sthala-
dalana-paṭuḥ prauḍha-nistṛi(stri)mśa-simhaḥ || ⁶[56*] Yasya sarvv-āṅga-
saṁdarya-prativimvam⁷-apaśyātā | praśamsitā Smarēṇ-āpi vijā chiram-
ana[m*]gatā || [57*] Stribhir-yatra griham pratipravi-
- 38 ēati svasthē sva-bṛin-maṁḍalē harsh-ōttālatay-aiva hāra-kiraṇān sambhāvya sa-
svastikam | uttūṅga-stana-kumbha-saṅga-ruchira-śri-kapṭha-kamva(ba)-sphurad-
vak[ī*]r-āmbhōja-vibhūṣitam nija-vapuḥ-chakrē svayam maṁgalam || [58*]
Dātīm dṛiṣṭv-ōtsukānām vadanam-abhibhavat-[-?—Ed.]saurabhāt-kāmi-
- 39 nīnām n-ēyāty-ēyāti v-ēti sva-vachana uditē yat-kṛitē duḥkha-saukhyaiḥ | jāt-
ōchṇam(shṇa)-svā(śvā)sa-dāhān-madhukara-paṭalāny-sēru-saṁpāta-sēkāta(d) vai-
kalpya-svāsthya-bhāmji tvaritana(ta)ram-adhaḥ saṁprataty-ā(ō)tpatamti⁸ || [59*]
Gēhē gēhē-nurāgāt-pathi pathi suhiraṁ prām-
- 40 gaṇē prāṅgaṇē vā vāram vāram nīlām tam yuta-yuvati-janō jāta-trishṇā-bhar-
ārtāḥ | utkallolam samantād-abamahamikayā yasya Kamdarppa-kāntē[r*]-lāvapy-
āmbhas-tanu-stham sva-nayana-chulukair-uchch[u*]lūmpichakāra || [60*]
Anāṅgaḥ sa Smarō yuktam viraba-jvalitē hṛidi |

¹ The verse imitates the style of the Mēgha-dūta.² Read -sūbhagā, or (less probably) -sūbhagam.³ The engraver has put this daṇḍa before the final ḥ of chālītāḥ.⁴ Apparently to be corrected to sa-Śatānandaḥ [śatad-unnati-gō (?)—H. K. S.].⁵ Apparently to be emended to puruṣāṅga-īca.⁶ After this daṇḍa is a four-armed figure and another daṇḍa.⁷ Read -pratibimbam.⁸ [Read saṁpatamti-utpatamti ?—Ed.]

- 41 tasthan yad-iha kāmānām chitram yō vasat-iti mō || [61*] Yēna dharmmo mahi-prishthō kō-py-apūrvah prakāśitah | yasy-ōnnama[ya*]tō-py-ēva guṇa[h] kōṭim parām gatah || [62*] Dattvā kāmchana-ratna-dānam-atulan dharm-aika-rāgān(t)-tathā yēn-aśvāyam-atiprapaṇchitam-abō paṇya-dvijāh
- 42 prāpitāh | jātam māndira-mālikāsu timiram dīpāir-vio-ō[j*]jimbhitam jiv-ō[d*]dyōtana-ahar-nisum vidadhātō ratnah(tna)-pradīp-āmkurāh || [63*] Yēna Svaranagiri[—]r-virāchatah¹ s[v*]arapōna sapt-ānvayah svarapāh kalpa-taruḥ samasta-vasudhā svarapayām sahasram gavām | ity-ādi dvi-
- 43 ja-samchayāya dadatā sphūrijad-yasā(śo)-hāsatah s-ollāsam hāsata vāla-prabhritayah² sarvvō-py-amī pārthivāh || [64*] Kāma-dh[ā*]nur-akām-ābhūch-chi * * * *³ pi | vikalpah kalpa-vrikahasya śratvā yad-dānam=adbhuta[m*] || [65*] Nata-ripu-dhrita-chūḍā-lagna-nīl-ēddha-sō(śo)chi[r*]-madhukara-
- 44 nikurāva(ba)-chchhauna-pād-āmva(bu)jēna [i*] ruchiram=idam-udāram kārītam dharmma-dhāmā vi(tri)daśa-griham-iha śrī-Maṇḍalēśasya tēna || [66*] Yāval-lō[cha*]na-dhāma-daṇḍa-militam chohhatra-chchhav-ī[m*]dum davau(dhau) bhōg-ī(m)ndram nava-yōga-paṭṭa-saḍṣam yāvach-cha maulau Haraḥ | yāvat-kaustubha ē-
- 45 sha bhāti hridayō Vishṇōh Śrīyō⁴ rāgavat (l) śrīman-Maṇḍana-kīrttanam kshiti-talē tāvat-sthiram tishṭhatu ||⁵ [67*] Atha Chaitra-chaturddāsyām Yasō(śo)dēv-ādī-k[i*]mkarāh | Kīrttirāja-mukhair-anyair-dēvasy-aishā kṛtā pratiḥ || [68*] Vajjām khaṇḍa-guḍayōr-bhamakam prati varṇi-
- 46 kā | mānjishṭhā-sūtra-karppāsa-bharakēshu cha rūpakah || [69*] Tathā śrī-Maṇḍanēn-ēyam ēśānēna mahātmanā | haṭṭē vikriyatē yat-tu t[asy-ā]pi rachitē pratiḥ || [70*] Nālikēra-bharakē phalam-ēkam mānakam lavapa-mṭṭaka-mathā⁷ [i*] pām(pū)gam-ēkam-āpi pūga-sahasrā-
- 47 d-ājya-taila-ghaṭakē palik-aikā | (ll) [71*] Dāpitō rūpakah s-ēddhah prati karppāsa-kōṭikām | pūlaka-dvitayam jālād-anna-chchhadmō cha pā iti⁸ || [72*] Tatth-otthapanakē tēna vajjām prati māndiram | Chaitryām drammah pavitryām cha dramma, ēkah pradāpitah || [73*] Sā(śā)lāsu kām-
- 48 syakārāpām māsō drammah kṛtas-tathā | vumvakē kalyapālānām rūpakāpām chatuṣṭayam || [74*] Prakṛitā(tī)nām m(cha) sarvvāsām tayā sthity-ānu-māndiram | dāpitō dramma ēkaikō dyūtē-smim(n) rūpaka-dvayam || [75*] Laguḍē yatra samitō dvō taila-karshō(reshō) nu pāpakam⁹ | dāpitā¹⁰ pashu(śu)-śākē
- 49 chchhā¹¹ vṛisha-vimśopakas-tathā || [76*] Drammas-tēna tathā dattō vajig-maṇḍalikām prati | sa[r*]vv-āvarita-yutā māsam prati su(śu)klā chaturddāsi

¹ Read *virachitāh*; the next words are more or less corrupt.

² Read *hastā Vā(ba)li-prabhritayaḥ*.

³ These six syllables are illegible on the ink-impression; the transcription of Paudīt Gopal Lal Vyas suggests the reading *chintā chintāmaṇḍar-āpi*.

⁴ See further the translation below, p. 309 and note.

⁵ Perhaps to be corrected to *Śrīyō*.

⁶ After this *daṇḍa* there is a four-armed ornament and another *daṇḍa*.

⁷ Corrupt; perhaps *-madhyāt*.

⁸ Uncertain; perhaps we should read *pālī* or *pālā* (i.e. *pāyālī*, *pāyālā*), or we may take *pā* as an abbreviation of one of these words: cf. above, Vol. XI, pp. 41, 56.

⁹ Possibly a mistake for *māpakam*.

¹⁰ The ending *ā* is wrong.

¹¹ Corrupt; possibly *chā*.

- || [77*] Arddhā¹ ma-satē diśe vyārgha-dōraka-sambhavē | tath-ākahu-
tavanim drammō-raghatē yava-hārakah || [78*] Dānē cha bhāṇḍa-
vā(dhā)nyānām bharaka[h*] su(su)ddha-
- 50 vi[rn*]śatau | tēna datta[h*] ava-dharmmēṇa bharakaś²-ohhaṅga śva cha ||
[79*] Sa-vāṭikam tathā tēna puram dhavala-maṇḍiram | kṛitam bhūḥ
pradattā cha dēvāy-āghāṭa-sammitē || [80*] Vi(bi)japūrakam-ākam tu
lagadāyāś=cha dāpitam [i*] yavānām mūṭakē(ka)śy-aisha vāpaś=ch-āṭavikē
tathā || [81*] Śrāyatām bhu-
- 51 vi bhūpālāḥ pradattam śāsanam mayā | pālyatām-anyathā n-ātra maulau
va(ba)ddhō-yam-samjalih || [82*] Prithu-prabhṛtibhir-bhūpair-bhuktōkaiḥkēna³
mēdini | tair=apy-āśhā punaḥ sārddham yatō n-aika-padam gatē || [83*]
Kaviḥ Sumati-Sādhārō vāmśē Sādhāra-sambhavē | va(ba)bhūva kramaśō
vidv[ā]-
- 52 n Bhārati-karṇa-kumḍalam || [84*] Tasya sut[ō*] guṇa-chamdana-sundara-
samjāta-dig-vadhū-tilakah | kavi-jana-mukha-kumuda-sasi⁴ jayatā[m*] śrī-Vijaya-
Sādhārāḥ || [85*] Tasy-ānujān-ābhīhitā prasastiś-Chamdrēṇa chamdr-
o[j*]jvala-kirtti-bhājā | Sa(śa)kā[t*] sahasr-aika-sa(śa)tē prayātē
śhaḍ-u]-
- 53 [tta]rē trimśa(śa)ti yāti kālē || [86*] Vā(bā)lasya jāti-kāyastha-Śrīdharasy-
śha sūnūnā | likhitā Āsarājēna prasastiḥ svastha-chētasā || [87*]
Utkirṇā vijñ * * * mūḍakēna | sūtradhārō * * * * *
* * * Samvat 1136 Phālguna śu di 3 Sukrē || māṅgalaḥ⁵

TRANSLATION.⁶

(Line 1.) Om ! Om ! homage to Śiva !

(Verse 1.) May the glances of Dēvi at the time of her marriage protect you—(*glances*) confused with excitement, budding forth with pleasure, quivering with delight, made slow by modesty, as in terror at the hissing of the snakes clinging to his arm she clenched her hand, which was drawn back by the old ladies for Śambhu, who seized it eagerly in firm grasp !

(Verse 2.) May the moon-crested one [Śiva] protect you, who bears on his head the moon that is wasted away as if from annoyance at the superiority of Gauri's face that is ever present !

(Verse 3.) There is in this land a famous mountain, Arbuda, the summit of which supports the heaven on high, (and) which stands in the highest rank among the lofty mountains beginning with Mēru; upon which for a moment night has been imagined by Siddhas to be day and day to be night, as they beheld the sun and moon licked by rays (*respectively*) of crystals and topazes.

(Verse 4.) Upon it the excellent saint Vasishṭha, freed from embodied life, magnificent in his conduct, a treasure of divine knowledge, boundless in merits, performed labours of true mortification; through being long in contact with the smoke flaring up from his *agni-hōtra* rites, (and) passing through the sky, as it were, the horses of the Sun were coloured bay.⁷

¹ For this missing syllable the transcription of Pandit Gopal Lal Vyas gives *śhū*. Much of the rest of the verse is corrupt.

² Apparently corrupt; should we read *bharakāś* ?

³ Read *bhukt-aiḥkaiḥkēna*.

⁴ One *akṣara* is here illegible.

⁵ About 12 *akṣaras* here are almost illegible, of which pos. 8-10 look like *Gaṇḍāka-sūtradhārāḥ*.

⁶ The transcription of Pandit Gopal Lal Vyas adds here *makā-śrī* ||.

⁷ [In a number of unspecified points I should dissent from the subjoined rendering of this elaborate composition. But it is not necessary to discuss them, as the historical facts are not affected.—Ed.]

⁸ The meaning of this *uprīkṣā* is that the Sun's horses got their bay colour because of their regularly passing through the sky, which was full of the smoke of his constant sacrifices.

(Verse 5.) In company with this saint shone the stainless lady Arundhati, having the whole of her organs strictly under control; like the embodied spirit of mortification.

(Verse 6.) With him dwelt the Cow of Plenty, obtainable by no others, bestowing objects of desire, like success in mortification.

(Verse 7.) Then the son of king Gadhi [Viśvāmītra], inflated with the arrogance of the warrior caste, by fraud carried off his precious cow, as an impediment (*to a religious act removes its*) success when ready.

(Verse 8.) Thereupon that saint, wroth at the occurrence of the insult, like a blazing sun, offered in the fire an oblation attended with clear spells, because he wished to create a warrior to slay (*his*) foes.

(Verse 9.) There issued thence a certain warrior, bearing on his back a pair of quivers and in (*his*) hand a terrible bow, fastening exceedingly tightly the mass of (*his*) braided locks with (*his*) right hand, wrathful, wearing the sacred cord, with awry glances terrifying the world of living beings, magnificent in splendour, crushing opponents.

(Verse 10.) He, who had most puissant strength of arm, being instructed by that (*saint*), entered the fray, while an auspicious song was sung by troops of celestials, routed his foes with showers of arrows forsooth filling the regions of space (*and*) covering up the sun's rays, seized the Cow of Plenty, and presented himself devoutly before (*the saint*), with head quivering upon the pair of lotuses that were his feet.

(Verse 11.) The delighted saint, having pronounced over the bowing conqueror the desired blessing, at once gave him the appropriate name of Paramāra [Destroyer of Foes].

(Verse 12.) In his lineage in due course arose a warrior named the blest Vairisimha because he was able to utter a lion's roar, a monarch terrible with claws consisting of the sword uplifted to cleave the frontal globes of the noble elephants' potent foes.

(Verse 13.) Observing now that Glory was fickle of nature, worn by enjoyment and unpleasing, he, puissant with a pair of long arms (*and*) having ever a festal residence on the periphery (P) of the frontal globes of the brilliant elephants of the four regions of space, held his espousals with [*or*, levied tribute upon] the earth of (*other*) kings, who was deeply enamoured of his virtues, within the area of the four regions of space.¹

(Verse 14.) The Ocean is not equal to him; for it has lost Fortune, and he was a treasure of fortune; it is in confinement, and he held foes in restraint; it is unintelligent,² and he was shrewd of wit.

(Verse 15.) His younger brother Dambarasimha subdued multitudes of foes by the awfulness of his terrible long arms, (*and*) the lotus of his face was obstructed by the mass of bees that were the eyes of damsels who were the very essence of amorous sentiment.

(Verse 16.) How could even moonlight be compared to his glory? The one arises from *śāśākara* [the moon, or a mine of faults], the other is produced from a multitude of virtues.

(Verse 17.) In his lineage was the blest Kakkadēva, whose long arms were solid as an elephant's trunk, (*and*) whose blazing splendour was a consuming fire to the multitudes of *patra-vāṇs*³ on the breasts of the wives of his pride-blinded foes.

(Verse 18.) In (*his*) two long arms itching for the fray so as to join battle he felt pleasure at the nail-scratchings that were the assaults of foemen's arrows.

(Verse 19.) Mounted upon his elephant's back in battle, on every side with showers of arrows shattering the host of the Lord of Karpāṣa upon the banks of the Narmadā.

¹ Despising ordinary glory, he aspired to and quickly won the earth. [*kumbha* also = 'bowl' of water, an auspicious object in the wedding marriage.—Ed.]

² There is a play on the double meaning of *jaḍadhi*, "ocean" (= *jaḍadhi*) and "dull-witted" (*jaḍa-dhi*: cf. Whitney's Grammar, § 354a).

³ Lions drawn with fragrant pigments.

slaying thus the foes of the blest king Śrīharsha the lord of Mālwa, he went to heaven, a valiant warrior, worshipped with the lotuses of the eyes of the ladies of the gods.

(Verse 20.) His son, Chandaṇa by name, had fame wandering free through the universe, (and) was a peculiar cloudy season (causing) the departure of the swans that are the smiles of princes' mistresses.

(Verse 21.) Exceedingly brilliant was his fame, standing like a flower-bunch over (the universe comprising everything from) Brahman to grass and constantly attended with song from crowds of Kinnaras like bees.

(Verse 22.) His son was Satyarāja, a seat of truth, having lovely splendour irresistible as fire, (who made) the mass of radiance from his toenails a bright forehead-ornament clinging to princes' brows delighting in deep obeisances.

(Verse 23.) From dread of him his enemies, though . . . constantly wore wild flowers: how surely are the lords of fortune known!¹

(Verse 24.) Being in a hundred ways active in the works of the sword, yet withal sincerely tender² with mercy; always controlled inwardly, though obtaining extension³ by hundreds of valiant deeds; in many ways winning fortune earned by his arms [or, without guilt]⁴ though nourished in virtue down to his very roots,—he was thus certainly *viruddha* [discrepant] in his conduct, but not *viruddha* [inimical] to the world.

(Verse 25.) From him arose, like a conjunction of prosperity from policy in this world, a holy ornament of the triple universe, broad and lofty of shoulders, an ear-jewel attached to the beautiful deeds of the gods, a palace of Fortune, (a son) named Maṇḍanadēva.

(Verse 26.) Finding him arisen in his career, broad of breast, charming, Fortune, as I imagine, held no (more) amorous commerce with her ancient husband.

(Verse 27.) Giving out constant streams of *dāna* [largesse, or rutting ichor], stout in his long arm [or, trunk], uniquely *dhavala* [white with fame, or a bull] in his race, *bhadrā* [brilliant, or a high-bred elephant], he was resplendent as the Elephant of the Gods [Airāvata].

(Verse 28.) The pairs of lotuses that were his hands and feet bore the tokens of cheiromancy, having moonbeams from the glittering nails, (being surrounded by) a mass of water of brilliant beauty, bearing a radiance of most graceful clear long lines, being marked with the goodly conch and fish, suitable for the lordship of an army, peerless, famous, a cause of fortune.⁵

(Verse 29.) This excellent king, having the form of the Love-god, binding the marriage-thread here in the brilliant pavilion (formed) of the pole of his stout arm, on the arrival of an auspicious day, espoused his foes' fortune, (as a bride) who was charming in high descent, exceedingly perfect in all members, desired by rivals, and gloriously given as his wife by his own great prowess.

(Verse 30.) His sword, like a minister, supporting the burden of the earth, shattering the hostile action of foes, constantly fostered his fortunes.

(Verse 31.) As the forest, full of masses of green grass-sprouts, is burned up by the earnest hot grief-born winds of the sighs of his foes' mistresses, which vie everywhere with the

¹ There is a play on words, designed to suggest that the king was the equal of Viṣṇu (Lakṣmīpati) or Kṛiṣṇa (Vanamālīn); it would be improved if we adopted Pandit Gopal Lal Vyas's reading *achyutā*. [¹How are his enemies neither recognized, nor lords of Fortune?—Ed.]

² Literally, "moistened." [*nīdrīkṣā* also—"cruel."—Ed.]

³ Scil. of territory or of fame.

⁴ If we take *dōṣa* in the sense of "arm," we must divide *caḥudā dōṣa*²; if in the sense of "guilt," we must divide *caḥudā-ādōṣa*².

⁵ For the full understanding of this verse the reader must refer to the text-books of palmistry. The figure of a fish in the palm usually portends wealth, progeny, and general success; that of a conch, lordship over millions of men. [*śāmundrikāṃ lakṣaṇam*, as also *vākyādā*, contains a punning reference to the sea, the source of the moon, etc. etc.—Ed.]

blasts of the end of the moon, (and) the water is utterly dried up (by them), the worn deer exist with difficulty, deprived of their sustenance of food and drink.

(Verse 32.) His splendour, ever brilliant, blazed like a second submarine fire, potent in the destruction of all lords of hosts [or, of the Ocean].

(Verse 33.) His sword in battle seems like a fetter for foemen's fortunes after the departure of (their) glory, like a braided lock of the goddess of victory.

(Verse 34.) Parandara [Indra] himself does not bear a resemblance to this skilful man—(the former being) a destroyer of (the demon) Vala, (the latter) a possessor of *vala* [strength]; (the former being) a smiter of the Gōtras [stalls of mythical kine] [mountains (?)]—H. K. S., (the latter) a gladdener of his Gōtra [family].

(Verse 35.) In his heart is Fortune, and he is dear to the heart of Fortune: how can he whose device is Garuḍa [Vishṇu] rival him?

(Verse 36.) As he was lovely with fresh sprouts of majesty, stainless of glory and bearing an unscathed body, a festal pitcher of victory filled with the water of mercy, Fortune never abandoned him.

(Verse 37.) This his fame, like a miraculous deity, truly established in a temple because of its ancient exceedingly pure virtues, bearing the radiance of pearl-strings, greatly admired, pervading the three worlds, present in every region, in every forest, in every town, in every house, is everlastingly extolled by men.

(Verse 38.) The boundless stream of the virtues of this man, who was a seat¹ of righteous conduct, was a Milk Ocean entirely filling the bright spaces of earth and sky on every side, in which Fortune found birth, and in which arose floods of the pale yellow nectar of fame; whence arising, the garlanded waves of (his) glory, radiant as the moon, spread over the heavens.

(Verse 39.) His glory, nowhere insignificant, nowhere in the world becoming a thing of secondary importance, certainly not ceasing, not arising from the occurrence of a failure of righteousness, nowhere finding a lodging in the triple world, which is too small to contain its full single stage, is marking, white as jasmine, the swart body of Fortune's Lord [Vishṇu].

(Verse 40.) Wholly covered up by the masses of dust (caused) by the mighty host of this (king), who had an awful pair of long arms, as he advanced against the foemen's host, even the lord Sun forsooth plainly surrendered his own radiance in every region of space in an access of terror . . . what need then to speak of other beings?

(Verse 41.) When this crest-jewel of all monarchs, ready to conquer the (various) regions, eager to ravish foemen's fortune, advances on the shores of the ocean, the water, scented with the rutting ichor of the plunging elephants of the quarters of space, is scarcely drunk by the elephants of (his) army, lofty in pride, although they are threatened again and again by the angry drivers.²

(Verse 42.) Bearing aloft the *vrishā* [rule of righteousness, or bull], always having even vision, being free from foes, conquering countless cities, he is another worshipful Paramēśvara [emperor, or Śiva].³

¹ Literally, "bound."

² The king's elephants feel themselves superior to the elephants of the Quarters, because the king is the conqueror of the Quarters; hence they scorn to drink the water of the ocean.

³ The king is greater than Śiva. For he bears the *vrishā* ("righteousness," or "bull"), while Śiva is borne on it; he is *sama-dṛiṣṭi* ("impartial"), but Śiva is a *sama-dṛiṣṭi* ("three-eyed"); he has no foes, but Śiva has the foe Kāma; he conquers innumerable cities, but Śiva conquered only the Three Cities. The figure is an *adāḥ-ābhāṣa*.

(Verse 43.) Though espoused by him personally from stainless high spirit, that dear mistress Fame wanders thus in company with his native glory through the world, renowned under the title of "The Unfickle" (*and therefore*) regarded with jealousy by Fortune, penetrating to the realm of the sun, praised even by the gods, everlastingly pure.¹

(Verse 44.) Learned in the science of the bow, a unique seat of high spirit and truth, when he applied his energy to battle, how were his foes smitten by him!

(Verse 45.) His weighty sword, a tethering-post for the elephant of victory, a bright tress of the lady Fame, a glittering reflection of Fortune, who had her dear and constant peculiar abode on (*his*) long arm, an awful mace of Kāla uplifted to destroy foes in battle after battle, was assuredly radiant, wielded with valour, as he cut down the pride of haughty enemies.

(Verse 46.) To him, who had the radiance of the sun, was born a son, a hero magnificent in might, a peculiar ornament of his race, a destroyer of irresistible warriors, potent with a bright and awful long sword lusting to ravish foemen's fortunes, a site of a mass of lovely women's wanton glances, a Cupid of amorous sentiment, a treasure of virtues, Chāmunda-rāja.

(Verse 47.) His foes' mistresses constantly by hot sighs of deep sorrow caused the forest to be burnt up, and by floods of tears made it sprout into bud.

(Verse 48.) To him all the virtues, as if dislodged by the multitudes of enemies' vices which had unhappily risen up² and attained victory in this world, (*and as if*) rejected by all classes of beings in the universe, came for refuge.

(Verse 49.) He, best of warriors, cut to pieces troublesome foes, scattered like seeds of fame multitudes of strings of pearls falling out of the frontal globes of elephants smitten by his sword on the field of battle, the spaces whereof were intensely pounded by his horses' hoofs, and which were on all sides flooded with streams of blood vomited forth from wounds made by sharp missiles.

(Verse 50.) Upon him, who wielded again and again a washed sword and was beloved of the goddess of constant victory in battle after battle, fall ever gently, ever timidly, these naturally charming glances of the sky-traversing (*goddesses*), (*inspired*) by immediate love and fear, in mutual rivalry.

(Verse 51.) Sorely fearing his wrath, the mistresses of countless smitten princes in every region, having entered the forests, overcome by the influence of weariness, (*and*) falling into the sleep of sorrow, in dreams meet and are embraced by their respective lovers, and thus on their waking, imbued with amorous emotion, they do not quickly open (*their*) eyes.

(Verse 52.) Enemies, expelled from their seats by him, who is terrible in his wrath, have found no resting-place anywhere except in their mistresses' hearts.

(Verse 53.) Verily endowed with a hundred delights [*or*, attended by Brahman], succeeding again and again in imprisoning the mighty [*or*, arising to his dismay³ from Balin's prison], like Trivikrama, he always has been in possession of exalted fortune [*or*, Lakshmi].

(Verse 54.) Having found him, Fortune, who is charming in the embrace of the righteous, a cause of delight, has never quitted him even for a moment, as a female swan (*quits not*) the

¹ The idea of this is that though the king's adscititious fame was acquired lawfully by him and became as it were his lawful wife, yet it spreads freely all over the earth like a common woman. He and his fame are paralleled with Viahnu and Sri (Fortune), but they have a point of superiority: Fortune is sickle, the king's fame is not. [I would take *amañśa* not with *māñśa* 'as if through temper,' but with *yāsa* and *gataśa* *sañśa* *sañśa* as—'with her brother, prestige.' In the next verse *sañśānaṁ āñśa* *ripaśa* *ātāśa*—his enemies were annihilated by his making friends with them.—Ed.]

² I understand the reduplication in *uḍit-pḍitair* in accordance with Pāṇini VIII. 1. 10 (*Siddhānta-kaumudī* 2145).

³ For this meaning of the reduplication, see the previous note.

male swan, for he is most firm in (*his*) attachment, possessed of a stainless double lineage¹ [*or, bearing a stainless pair of wings*], an object of the love of the encircling earth [*or, a performer of amorous sport amidst the lotuses*].

(Verse 55.) He, who in battle bears a sword like Mandara, with which he has utterly shattered Sindhurāja [*or, has completely churned the ocean*] in sport, has found like Parushōtama Fortune (*and*) a world-purifying conch-shell (*consisting*) of fame.

(Verse 56.) That lion his mighty sword, instantly devouring in sport all majesty of foemen as if it were a partridge, having a splendid mane of rays reddened by commixture of the intense radiance of the sun, awful with fangs (*consisting*) of its edge, displays itself in battle, making a loud noise with (*its*) blows, skilful in shattering the frontal globes of enemies' elephants.

(Verse 57.) Seeing not the likeness of his beauty of every member, the Love-god himself has long praised his own *anaṅga* [bodilessness, *or* character of Cupid].²

(Verse 58.) When he returns to the house, the women in the intensity of their joy, conceiving in imagination gleams of jewel-strings upon their happy bosoms, have made a festal scene of their own bodies, which are marked with *svastikas*, adorned both by shells (*consisting*) of (*their*) throats brilliantly beautiful by union with high pitcher-like breasts and by the lotuses of (*their*) bright faces.

(Verse 59.) When they see the faces of love-lorn damsels surpassing in fragrance their messenger,³ the troops of bees fly down very hastily in a swarm, enjoying alternative good fortune from (*either the damsels'*) fever of hot sighs (*or*) from the dripping of their falling tears because of sorrow (*in the one case*) or joy (*in the other*) on his account when it is reported of him either that he is not coming or that he is coming.

(Verse 60.) With affection in every house, constantly on every road, and repeatedly, perpetually, in every court, attendant damsels, worn with intensity of desire, on all sides in emulation have stirred up into high waves [*stole* (?)—H. K. S.] by the scoops of their eyes the water of beauty lying in the person of this (*king*) who is lovely as the Love-god.

(Verse 61.) The Love-god is naturally *Anaṅga* ["Bodiless"] when he has dwelt here in the heart of lovers which is ablaze with (*the agony of*) separation.⁴

(Verse 62.) By him a certain unprecedented religion has been displayed on the face of the earth; his merit in maintaining it has reached the highest degree.

(Verse 63.) By bestowing unparalleled largesse of gold and jewels in unique affection for religion, he thus forsooth has raised holy Brāhmanas to most abounding dignity; overcoming without lamps the gathered gloom that had arisen in the upper chambers of their dwellings, rays from lamps (*consisting*) of jewels create radiance by day and night.

(Verse 64.) ⁵ as he gave largesse of such degree to the multitude of Brāhmanas, by the splendour of his brilliantly demonstrated *fāne* all those (*ancient*) kings such as Balin have been conspicuously outshone.

¹ Cf. above, Vol. XIII, p. 32 and note 1.

² The king is in the perfect beauty of his every limb an image of Cupid (*Kāma*, *Smara*, or *Anaṅga*). The jatter has hitherto boasted of being *Anaṅga* ("bodiless one"), but that was because he had not yet seen the king: he was "bodiless" only so long as the king, his image in beauty, was not yet visible. It is thus suggested that the king himself is the true Love-god. [Or does *prasthāpita* imply 'congratulated himself upon'?—Ed.]

³ *Dāṭṭya*: if this is correct (and the reading seems to be certain), it must mean the mango-tree; but possibly it should be emended to *śāḍṣam*. [But should we not render 'owing to the fragrance which overspreads their faces (they blush, in fact) on seeing a go-between' and later *śaṅkaraśāḍṣa* 'as their own lips pronounce the words'?—Ed.]

⁴ The latter half of this verse is unintelligible to me, and is perhaps corrupt. [I would translate the verse 'That the bodiless *Kāma* remained in a heart [*sc.* that of *Rati*] on fire with the pain of separation was meet: but when he dwells in the hearts of us who have a [living] lover ["are loved," *kāśāṁśa*] that is surprising to me.' The next verse refers (*gṛha*, *kōṭi*, etc.) to the bending of a bow: *dāṛma* = 'fashion.'—Ed.]

⁵ [The omitted passage seems to contain a list of *mahādānas*; cf. e.g. Vol. XIII, p. 128, v. 17.—Ed.]

(Verse 65.) Since men have heard of his marvellous bounty, the Cow of Plenty has been a thing not wanted, as also the idea of the wishing-stone¹ and the conception of the tree of desire.

(Verse 66.) He, the lotuses of whose feet are covered with masses of bees (*consisting*) of the kindled lustre of sapphires fixed in the hair-knots worn by bowing foes, a seat of godliness, has caused to be made here this splendid exalted temple of the blest Maṇḍalēśa.

(Verse 67.) As long as Hara bears on his coronet² the moon with the hue of a white umbrella joined to the fire³ of his (*frontal*) eye and as long as he bears the snake-king like a new *yōga-paṭṭa*,⁴ as long as that Kaustubha shines on Viṣṇu's breast like (*his*) love⁵ for Fortune, so long may the praise of the blest Maṇḍana abide on the face of the earth !

(Verse 68.) Now on the fourteenth of Chaitra this list of dues of the god was made by Yaśōdēva and other servants, (*likewise*) by others headed by Kirttirāja.

(Verse 69.) On each *bharaka* of candied sugar and jaggery belonging to the traders (*there was assigned*) one *varṇikā*; and on each *bharaka* of Bengal madder,⁶ thread, and cotton, one *rūpaka*.

(Verse 70.) Likewise the blest Maṇḍana, great of soul, by edict made out this list of dues on what is sold in the bazaar.

(Verse 71.) On every *bharaka* of cocoanuts, one fruit; on each *māṭaka*⁷ of salt, a *mānaka*; from every thousand areca-nuts, one nut; on every *ghaṭaka* of butter and sesam oil, one *palikā*.

(Verse 72.) On each *koṣikā* of clothing fabric were assigned one and a half *rūpakas*; on a *jāla*,⁸ two *pālakas*⁹

(Verse 73.) For each house of the traders in the local bazaar (?) was assigned by him a *dramma*¹⁰ on the Chaitra festival and the festival of the sacred thread.¹¹

(Verse 74.) On the shops of the braziers was likewise imposed a *dramma* for the month; on (*each*) *vuṃvaka* of the distillers four *rūpakas*.

(Verse 75.) Under this constitution there was assigned on every house of the whole population a *dramma*, on the gambling (*-house*) two *rūpakas*.

(Verse 76.) On each *lagaḍā*¹² were assigned two *santas*, on each *karaha* of oil a *pāṇaka*; and similarly on each load of cattle-fodder a *vrisha-viṃśōpaka*.¹³

¹ See above, p. 302, note 3.

² If *maṇḍana* is right, it is out of place, and should come in the first *pāda*, as I have implied in translation. Possibly, however, it should be corrected to *maṇḍ*.

³ *Dhūma-danḍa*, literally "smoke-staff." There is apparently a play on words: *danḍa* is suggested by *cāḍatra*.

⁴ The band used by Yōgins to keep their limbs in a position of rigidity.

⁵ A play on the primary meaning of *rāga*, "colour," is intended.

⁶ *Rubia munjista*, Roxb.

⁷ Apparently "bullock's load"; cf. Marathi *māṭa*, "bullock's pack-saddle," and Telugu *māṭa*, "bundle," "pack."

⁸ This is perhaps connected with Sanskrit *jālaḥ*, "bunch of buds."

⁹ This in Sanskrit usually means "bundle"; it is the Hindi *ḡulā*, "a small bundle of sticks or plants."

¹⁰ See on this particularly the *Progress Reports of Asst. Arch. Supt. for Epigr., Southern Circle*, 1909, p. 80, 1910, p. 97, 1915, p. 102.

¹¹ See *Ind. Ant.*, 1909, p. 52.

¹² This seems to be connected with Marathi *lagaḍ*, "a bar of gold, silver, or other metal; a frame of wood or iron in which pitchers are carried upon beasts," and the Gujarati *lagaḍu*, "a coarse bag put on an ass in which the burden is placed."

¹³ See above, Vol. I, p. 166; Vol. XI, pp. 41, 59.

(Verse 77.) He likewise gave a *dramma* on each traders' association; the fourteenth day of the bright fortnight in each month was attached to every recurrence.¹

(Verse 78.) and on a pile of sugar² a *dramma*, on a water-wheel³ a *hāraka*⁴ of barley.

(Verse 79.) In (*his*) bounty also he granted on a clear twenty (*packs*) of loaded grain one *bharaka* in his piety, and on a *bharaka* (*of the same*) one *chhaṅga* (?).

(Verse 80.) He likewise constructed a town with white houses and furnished with gardens, and bestowed on the god lands duly measured out with their sides of access.

(Verse 81.) He moreover assigned one citron from each *lagaḍa*, and the *oṣṭa*⁵ from a *mūṭaka* of barley and likewise on *āṭavika*.

(Verse 82.) O kings on earth, hearken to the edict granted by me: observe it: for no other purpose are these my hands clasped upon this coronet.

(Verse 83.) Prithu and other kings have severally enjoyed the earth; whence the latter together with them has again passed through various conditions.

(Verse 84.) There was born in due succession in the family sprung from Sādhāra the learned poet Sumati-Sādhāra, an ear-ring of the Muse.

(Verse 85.) Success be to his son the blest Vijaya-Sādhāra, by the sandal-paste of whose virtues there was made a beauteous forehead-ornament for the goddesses of the quarters of space,⁶ a moon to the lotuses of poets' faces!

(Verse 86.) His younger brother Chandra, having fame bright as the moon, pronounced this panegyric when a period of one thousand, one hundred, and thirty-six years was elapsing since the Śaka (*king*).

(Verse 87.) Āsarāja, son of the junior Śrīdhara of the Kāyastha race, happy of mind, wrote out here the panegyric.

(Line 53.) Engraved by Samvat 1138, on Friday, the 3rd day of the bright fortnight of Phālguna. Good luck!

No. 22.—KADALADI PLATES OF ACHYUTA-RAYA: SAKA 1451.

By PROF. S. V. VENKATESWARA, M.A., AND S. V. VISWANATHAN, M.A., KUMBAKONAM.

These plates belong to Mr. Yegnaswāmi Ayyar, son of Rāmachandra Dīkshitar, a direct descendant of the donee of our grant, whose name is also Rāmachandra Dīkshitar. He is the village munsiff of Kaḍalāḍi in North Arcot district and has still in his possession the land granted to his ancestor by Achyuta-Rāya. The plates were obtained from him through the kindness of His Holiness the Śaṅkarāchārya at Kumbakonam. They are in good preservation and are at present in the possession of the latter.

The grant is on five copper plates bored at the top and held together by a ring. The plates bear inscriptions on both sides, excepting the first and the last, which are engraved on one side only. They are numbered with Telugu-Kanarese numerals on the first side of each

¹ *Sarev-ācartta-yutā*, i.e. assigned as the date of payment as it falls due annually.

² *Taṇḍim* (the ending is perhaps wrong) is connected with Marathi *taṇḍā*, "the heap of sugarcane as cut for the mill" (Molesworth).

³ See above, Vol. XI, p. 29.

⁴ Ibid.

⁵ A hand-cast or handful: cf. above, Vol. I, p. 161 n. Compare *nireṣṭa*, above, Vol. XI, p. 56.

⁶ I understand *śundara-saṁjāta* . . . *śiṭākaḥ* as an irregular compound similar in structure to the Prakrit *dāvala-ka-ṣvavā* (i.e. *dāvala-krīṭ-ṣparīta*, for *krīṭa-dāval-ṣparīta*): Piechsl, *Gramm. d. Prakrit-Spr.*, 603.

plate. They measure 9.2 in. by 7.4 in. Including the arch at the top, the height is 11.7 in. The writing runs across the breadth of the plates and is quite legible. There are 216 lines in all. All the plates have raised rims. The ring with which the plates are fastened is .7 in. in diameter.

The characters are Nandināgari, excepting the words *Śrī-Virūpākṣa*, the signature at the bottom, which is in large Kanarese characters. The average height of the letters is .2 in., except in the signature. The language is Sanskrit, full of errors, and the whole inscription is in verse, except in *Śrī-Gaṇādhipataye namaḥ* at the beginning and *Śrī-Virūpākṣa* at the end.

The inscription contains some noteworthy orthographical peculiarities. The first is that punctuation marks are not supplied in their right places, all the lines of the verses being stopped with a vertical line. These have been pointed out in the footnotes to the text. Here and there we find instances of confusion between long and short *i* and *u*. In these plates, as in others, there is a redundant *anuvāra* before the double consonants *nya* and *ṣya*. Instances of these are: *°hiraṇya-payō-dhārā* for *°hiraṇya-payō-dhārā* (l. 126), *°amṇyāṣe-traya* in the place of *°anyāṣe-traya* in ll. 127-8, *°Sāmānyō-ānucaya* instead of *°Sāmānyō-ānucaya* (l. 159). *Sāmānyō-yaṁ* (l. 214) is a mistake for *Sāmānyō-yaṁ*. *Anuvāra* is wanting in some places, as it is superfluous in others, e.g. *chandra* for *chandra* (l. 1); *Kāṁchya* instead of *Kāṁchyāṁ* (l. 36). These, we think, are mostly to be attributed to want of care on the part of the engraver. Visargas are likewise redundant. Examples of this may be seen in l. 66, where we have *°gaṁḍaḥṣe-tōṣa* instead of *°gaṁḍaṣe-tōṣa*; ll. 119-20 *°saṁyuktāḥṁ-śkabhōgyaṁ* for *°saṁyuktāḥ-śkabhōgyaṁ*. The confusion between the sibilants, palatal, dental and lingual (ṣ, ś and ṣ), is as common here as in the other grants of the Vijayanagara kings. Instances of this are: *°śhe-apy-a-śēṣēṣu* in l. 39 instead of *°śhe-apy-a-śēṣēṣu*; *°śāṁśāṣya* in l. 54 for *°śāṁśāṣya*; *°śudhībhi* in l. 72 in the place of *°śudhībhi*; *a-śēṣa* in l. 104; *°kāṣṭi* in l. 128; *°śēṣa* in l. 129 and *°śāṁśāṣya* in l. 207 are written instead of *a-śēṣa*, *°kāṣṭi*, *°śēṣa* and *°śāṁśāṣya* respectively. A conjunct consonant is made up of the full form of the first consonant and the curtailed form of the second consonant. The *r* sign is inserted over the line, where necessary, except in a few instances of double consonants, e.g. *āvajya* in l. 34 and *chatubhuja* in l. 51. In certain cases instead of a double consonant only one of the consonants is written. As in the other inscriptions of the same dynasty, this one also contains the *birudas* attached to the kings—for example *Bhāṣhegetappuvarāyagandhā*, *Hindurāyasaratṛāḥ*, etc. *Rāya* and *Mahārāya* appear frequently in the place of *Rāja* and *Mahārāja*. There are instances also of Tamil usage. *Tāmbra-śāṁśāṣya* in ll. 208 and 209 is evidently the Tamil form of *tāmbra-śāṁśāṣya* and *varsha* is usually written in Tamil as *varuṣa*.

The inscription records the grant of the village of Kaḍalāḍi alias Paṭendal, by Achyuta-Rāya to Rāma-chandra-Dikṣita, son of Nāgā-Bhaṭṭa, who in his turn splits up the village granted into 110 *vr̥ttis* and distributes them among other Brāhmanas, who are 46 in number. The inscription naturally falls into 4 parts—(1) Vv. 1-3, benedictory verses; (2) Vv. 4-36, the genealogy of the dynasty as far down as Achyuta-Rāya; (3) Vv. 37-104, the terms of the grant, names of donees, etc. etc.; (4) Vv. 105-111, the names of the composer, the engraver and the imprecatory verses at the end. Vv. 1-3 invoke Śambhu, the Varāha incarnation of Viṣṇu and Gaṇānana. Vv. 4-8 trace the genealogy of the family as far as Narasa Nāyaka. Vv. 9-11 give an account of the gifts made by the king and his exploits; his victory over the kings of the South, Chēra, Chōla and Pāṇḍya. Vv. 12 and 13 mention the sons of Narasa, Vira Nṛi-simha and Kṛishṇa-Rāya by Tippāji and Nāgala. Vv. 14-18 contain the praise of Vira Nṛi-simha as king and his gifts at holy shrines; and the beneficent rule of Vira Nṛi-simha. Vv. 19-23 likewise describe the deeds of valour of, and the gifts made by, Kṛishṇa-dēva-Rāya. Vv. 24-27 describe how Achyuta succeeds Kṛishṇa-Rāya after the latter's death. We have in these a long

list of the *birudas* attached to the name of the king. Vv. 28-36 are in praise of Achyuta-Rāya, who succeeds his brother.

The verse stating that Achyuta was the son of Ōbāmbikā, a step-mother of Kṛishṇa-Rāya, and thus making Achyuta a step-brother of the latter, is not found in our inscription. Our record states, however, that Kṛishṇa-Rāya, after his death, was succeeded by Achyuta-Rāya, a younger brother of his (*anujanma*—v. 29). The genealogy thus stops with Vira Nṛ-siṃha; and Kṛishṇa-Rāya and Achyuta succeed the latter in due course.

Among the shrines to which Achyuta paid pilgrimage and at which he is said to have made gifts is Viriñchipuram, which is a locality in the Vellore *Taluk*, North Arcot district. It contains a Śiva temple, known as that of Mārgasahāyēśvara. The late Rai Bahadur V. Venkayya has identified Marataka-puri (mistake for Marakata-puri), appearing in the Satyamangalam plates of Dēva-Rāya III and in the Madras Museum plates of Śrīgiri-bhōpālā¹ with Viriñchipuram. He says that Marakata-puri is derived from Marakata-valli, the goddess of Viriñchipuram.² The city of Viriñchipuram is mentioned as the capital of the country ruled over by Śrīgiriśvara, a brother of Dēva-Rāya II. Of the grants of the second Vijayanagara dynasty so far published it is only in this that Viriñchipuram is mentioned among the shrines visited by Vijayanagara kings. Perhaps at the time of this grant Viriñchipuram, which a century before was ruled over by a branch of the Vijayanagara family, had been lost to them and had come to be classified with Kāñchi as a place of pilgrimage.

(Vv. 37-42) In the Śaka year 1451 according to the Śālivāhana reckoning, in the year Virōdhin, in the month Makara, on the trayōdaśī day of the dark half of the month and on Tuesday (was made the gift) on the banks of the river Tuṅgabhadra, in the vicinity of Virōpāksha, to the best of Brāhmins, Rāmachandra Dikshita, the son of Nāgā-Bhaṭṭa. Thus the necessary details as regards the date are given.

The date of the grant is of considerable interest to students of history. In the course of his introduction to the Ūnamāñjēri plates of Achyuta-Rāya⁴ Professor Kielhorn has remarked as follows:—“The latest date for Kṛishṇa-Rāya known to me from published inscriptions corresponds to Friday, 23rd April, A.D. 1529, and the earliest date for Achyuta-Rāya to Monday, 15th August 1530.” But the astronomical data given in our inscription unmistakably refer to the year 1451 Śaka, etc., i.e. Jan. 1530 A.D. Dr. Kielhorn's earliest date for Achyuta-Rāya has therefore to be revised in the light of this inscription. It is clear also that Achyuta-Rāya succeeded his brother after the natural death of the latter (V. 29 कृतवन्ति सुरभीं कण्ठरावि-निर्वासा ।⁵ तदनु तदनुजन्म पुण्यकर्मवृत्तेः etc.). So the death of Kṛishṇa-Rāya must be placed before January 1530 A.D.

The only inscription among those as yet discovered that may seem to raise some difficulty as regards our chronological result is No. 369 of 1912, copied by the Madras Epigraphical Survey. It belongs to the reign of Vira-pratāpa Kṛishṇa-dēva Mahārāya and is dated Śaka 1453, *Virōdhi Sittirai su di 10, Attam*. But another inscription in the same temple⁶ records a sale of land made in the reign of Achyutayya-dēva Mahārāya, son of Vira-pratāpa Narasa Nāyaka, dated Śaka 1452, *Vikṛiti, Makara su di 13, Monday, Pūṣam*. If 1452 Śaka year is *Vikṛiti*, then 1453 cannot be *Virōdhin*. It is therefore clear that the figure 1453 must be a mistake for 1451, as the figure nearest to ‘three’ in Tamil characters is ‘one’.⁹

¹ See *Ep. Ind.*, Vol. III, p. 35.

² *Ep. Ind.*, Vol. III, p. vii.

³ Read मतवन्ति.

⁴ Read “अन्ता पुण्यकर्मवृत्ते”.

⁵ *oanu* (one); cf. *mūnu* (three). [The inscription reads clearly 1453 and not 1451.—H. K. S.]

⁶ *Ep. Ind.*, Vol. VIII, p. 308.

⁷ *Ep. Ind.*, Vol. III, p. 148.

⁸ Read निजनि.

⁹ No. 373 of 1912, *Ep. Surv. Report*.

Vv. 42-48 record the name of the village granted with its boundaries and neighbouring villages. The village of Kaḍalāḍi, the object of the grant, is situated in Paḍaviḍu-mahārājya in Jayamkoṇḍa-chōḷa-maṇḍala, in Phalgunna-kōṭaka, in Paṅgala-nāḍu, on the outskirts of Kaṭṭagara. It is surrounded on the north by the village of Sennāripāḍi; on the east by the village of Pālapūr; on the south by the village of Chiyanēndil; and on the west by Skandanadi and the village named Haritālāmaṅgala. Besides the localities noted above there are others mentioned in the grant. Among these are Singaṇappāḍi; Kunnaturu; Mām-bākam, and Paṭēndal. Of these Paḍaviḍu mahārājya was probably called after a town bearing the name Paḍaviḍu in the North Arcot district. This town was very likely the centre round which the Mahārājya was situated. Pālapūr may be either Polur or Pollilur. The former is a Tāluk in the North Arcot district, in which the town Paḍaviḍu is; while the latter is the scene of a battle between the English and Haider Ali.

Vv. 48-53 describe the terms of the grant, such as are usually found in all Vijayanagara grants. The villages are given in perpetuity as sarva-mānya, to be enjoyed by the donee and his descendants. With the grant of the village go also the rights over the property therein. The king reserves to himself no right over the village granted. The village, as the inscription states, is given as ēka-bhōgya, which implies the exclusive ownership of the property and the rights over it by a single individual. In effect, however, it is found that the land is not ēka-bhōgya, as part of it is divided among others and a portion reserved for the gods. Land which is thus enjoyed by 2 or more parties goes by the name of gaṇa-bhōgya or tri-bhōgya. The word ēka-bhōgya in the particular context can be explained only by the fact that the grant was made in the first instance only to one individual, Rāmachandra-Dikshita, who divided the land among the Brāhmins of the sect to which he belonged. It is, moreover, not clear whether, as in the original grant, Rāmachandra-Dikshita gave to the Brāhmins along with the land allotted among them, rights over it also. Perhaps the rights over the property were reserved by the donor, the donees being allowed only the enjoyment of the fruits accruing from the land.

In vv. 54-104 the village granted to Rāmachandra-Dikshita is divided into 110 vṛittis, and the portions allotted among various Brāhmins. The donee takes 27 shares for himself (V. 54). He leaves one vṛitti for Vishnu and one likewise for Śiva (V. 55). The remaining 81 vṛittis are divided among 47 Brāhmins, the division ranging from $\frac{1}{2}$ vṛitti to 8 vṛittis. The donees belong to an important sect of Brāhmins, the Poysala Kannaḍa sect—judging from the names and from the fact that there are two of the Sāma śākhā (Nos. 14 and 29 below). The Poysala Kannaḍa are, I am told, the only sub-sect of the Kannaḍa Brāhmins where we find Sāma-vēdins. The exact amount given to each, the name of his father and the particulars of his gōtra, sūtra, and śākhā, the nature of the learning of each etc. are appended below in a table.

Donee's name.	Father's name.	Śākhā.	Gōtra.	Sūtra.	No. of shares.	REMARKS.
1. Rāmachandra-Dikshita.	Nāgā-Bhaṭṭa	Yajus	Kāśyapa	Āpastamba	27	Vēda-vēdānta purāṇa-āgama-vid, yajnasvin, gaṇa-śālin, dhimat, mahātman.
2 & 3. Hara and Hari		...		...	1+1	Yajvan.
4. Tirumala	Nāgā-Bhaṭṭa	Yajus	Kāśyapa	...	8	
5. Nārāyaṇa	Do.	Do.	Do.	...	5	
6. Nāgā-Bhaṭṭa	Do.	Do.	Do.	...	5	

Donce's name.	Father's name.	Sākha.	Gōtra.	Sūtra.	No. of shares.	REMARKS.
7. Manishī Rāma-chandra.	Gōpinātha .	...	Kāśyapa .	...	4	
8. Rāmā-Bhaṭṭa .	Saṅgā-Bhaṭṭa .	...	Do. .	...	2	
9. Timmā-Bhaṭṭa .	Bhānu-Bhaṭṭa .	Bahv-riṣa	Bharaḍvāja .	...	2	Mahāmati.
10. Chandra-Dikshita	Māṭha-Bhaṭṭa .	Do. .	Jāmadagnya-vata .	...	2	
11. Śrī-Virūpāksha .	Rodra-Bhaṭṭa .	Do. .	Harita .	...	2	
12. Kōṇḍu-Bhaṭṭa .	Akkā-Bhaṭṭa .	Do. .	Bhāradvāja .	...	2	Dhīmat.
13. Sōmanātha-Bhaṭṭa	Śrīkanṭhēśvara .	Do. .	Viśvāmitra .	...	2	
14. Śrī-Virūpāksha .	Chauḍi-Bhaṭṭa .	Sāmaga .	Ātrēya .	...	2	
15. Kālāhastī .	Māda-Bhaṭṭa .	Bahv-riṣa .	Jāmadagnya-vata .	...	1	Adhvarin.
16. Viṭṭa-Bhaṭṭa .	Rāmā-Bhaṭṭa .	Do. .	Mandgalya .	...	1	
17. Chauḍi-Bhaṭṭa .	Nāgā-Bhaṭṭa .	Do. .	Ātrēya .	...	1	Sudhī.
18. Tirumala .	Bhāskara-Bhaṭṭa	Do. .	Harita .	...	1	Yajvan.
19. Śrī-Virūpāksha .	Kāmā-Bhaṭṭa .	Do. .	Bhāradvāja .	...	1	
20. Tippayya .	Mahādēva .	Vājasaneyin (?)	Viśvāmitra .	Bōdhāyana .	1	
21. Tirumala .	Kōśava-Yajvan .	Yajus .	Śāṇḍilya .	...	1	Sūri.
22. Sāditya-Liṅga-Bhaṭṭa.	Kōśav-Ādhvarin	Do. .	Do. .	...	†	
23. Tirumala .	Tirumala .	Bahv-riṣa .	Ātrēya .	...	1	
24. Rāmā-Bhaṭṭa .	Chittī-Bhaṭṭa alias Bhūtanātha.	Do. .	Gautama .	...	2	
25. Timmā-Bhaṭṭa .	Dēvaru-Bhaṭṭa .	Do. .	Kāśyapa .	...	1	Mahāmati.
26. Vaidyanātha .	Nārasimha .	Do. .	Do. .	...	1	
27. Uppapa-Bhaṭṭa .	Nārasimh-Ādhva- rin.	Yajus (?)	Gautama .	Bōdhāyana .	†	
28. Dēvarē-Bhaṭṭa .	Nārasimh-Ādhvarin	...	Do. .	Do. .	1‡	Manishin.
29. Dēvarē-Bhaṭṭa .	Chauḍi-Bhaṭṭa .	Sāmaga .	Ātrēya .	...	1	
30. Subrahmanya .	Varada-Bhaṭṭa .	Bahv-riṣa	Bharaḍvāja .	...	1	
31. Nārasimha .	Tirumala .	Yajus .	Gautama .	Bōdhāyana .	†	
32. Viṭhala .	Timmā-Dikshita	Do. (?)	Do. .	Do. .	†	
33. Śaṅkara .	Nārāyaṇa .	Bahv-riṣa .	Jāmadagnya-vata .	...	†	Sudhī.
34. Timmaya .	Tippā-Bhaṭṭa .	...	Gārgya .	...	†	Dhīmatāṇa varah.
35. Alru-Bhaṭṭa .	Varada-Bhaṭṭa .	Yajus .	Bhāradvāja .	...	1	
36. Varada-Bhaṭṭa .	Timmāvajjala .	Do. .	Do. .	...	1	Dhīmat.

Donee's name.	Father's name.	Śākha.	Gōtra.	Sūtra.	No. of shares.	REMARKS.
37. Sūrā-Bhaṭṭa	Varada-Bhaṭṭa	Yajus	Śrīvateś	...	†	
38. Venkaṭeśvara	Mahalinga-Bhaṭṭa	Bahv-ṛicha	Viśvāmītra	...	†	
39. Jannaya	Māra-Bhaṭṭa	Do.	Do.	...	†	
40. Yāllā-Bhaṭṭa	Gauri-Bhaṭṭa	Yajus	Śāṇḍilya	...	†	
41. Sri - Virūpākaha-Bhaṭṭa	Tirumala	...	Kauśika	...	1	
42. Sāndi-Bhaṭṭa	Lingā-Bhaṭṭa	...	Gautama	Bōdhāyana	1	Dhīmat.
43. Kāmā-Bhaṭṭa	Maṅgā-Bhaṭṭa	Bahv-ṛicha	Kāśyapa	...	†	
44. Kōṇḍ[ri]-Bhaṭṭa	Chōḍi-Bhaṭṭa	Do.	Bhāradvāja	...	†	
45. Tirumala	Ananta-Bhaṭṭa	Do.	Kāśyapa	...	†	Sūri.
46. Timmā-Bhaṭṭa	Sri - Vidyānīdhi-Bhaṭṭa	Do.	Kauśika	...	†	
47. Nāgā-Bhaṭṭa	Akkā-Bhaṭṭa	Do.	Bhāradvāja	...	1	Sūri.
48. Vēdaya	Mādhava-Bhaṭṭa	Do.	Kapila	...	†	Vēda-śāstra-vid.
49. Ekāba	Divākara-Bhaṭṭa	Yajus	Parāśara	...	†	

It is clear from the list given above that of the 47 donees among whom the land was distributed 24 were R̥ig-vēdins (Bahv-ṛicha); 15 Yajur-vēdins and 2 Sāmāgas. It is not stated to which Vēda the remaining 6 donees belonged; 10 were of the Kāśyapa gōtra; 8 of the Bhāradvāja; 6 of the Gautama; 4 each of the Viśvāmītra and the Ātrēya; 3 each of the Śāṇḍilya and the Jāmādagnya-vatsa; 2 each of the Kauśika and the Harita; and one each of the gōtras Maudgalya, Śrīvateś, Gārgya, Kapila and Parāśara. 6 belonged to the Bōdhāyana sūtra, the rest belonged presumably to the Āpastamba sūtra, though this is distinctly stated only of Rāmachandra-Dīkshita, the main donee. As regards relationship of the other donees to Rāmachandra-Dīkshita, it appears probable that Nos. 4-6 were his brothers, and No. 7 a cousin of his. No. 21 was apparently a brother of No. 22, and No. 27 of No. 28. All the donees probably stood in agnate or cognate relationship to Rāmachandra.

As regards the distribution of land among the donees, the allotment among the 47 Brahmans, when totalled up, comes only to 65 vṛittis and not to 81, as it should according to the grant (see above). It is not known what became of the remaining 16 vṛittis.

After the names of the donees, etc., thus given the record mentions that Paṭṇḍal was another name by which Kaḍalāḍi was known (V. 103). [If it was a grāmagrāma it must be a separate village.—H. K. S.] Then comes the name of the person who composed the edict of the king. His name was Sabhāpati, the famous rhymester of the Court (V. 105). V. 106 gives the name of the engraver, Virap-śchārya, the son of Mallapa, whose family were the hereditary engravers of the grants of the Vijayanagara kings. Under all these is the signature at the bottom of the last plate, Śrī-Virūpākaha, written in bold Kanarese characters, after the concluding imprecatory verses common to all the Vijayanagara grants.

TEXT.¹

[Metres: vv. 1-4, 6-8, 12-14, 18, 19, 25-27, 35, 37-103, 105-110, Anuṣṭubh; vv. 5, 20, 29, 34, Śārdulavikṛīḍita; vv. 10, 11, 15, 16, 17, 21-23, 28, Sragdharā; v. 9, Harīṇī; v. 24, Dōdhaka; vv. 30 & 104, Āryā; vv. 31, 111, Śālīnī.]

¹ From the original plates.

[The first 28 verses of the grant are not printed here, as they are the same as those found in the other grants of the Vijayanagara dynasty that have been published by us. They appear in the Kāñchīpuram plates of Kṛishṇa-dēva-Rāya (Vol. XIII, pp. 126-9). The first 26 verses are found in the Kuḍiyāntaṇḍal grant of Vīra Nṛsiṃha (Vol. XIV, No. 17). The Bēvinahalli grant of Sadāśiva contains the first 29 verses of our grant (Vol. XIV, No. 16). Such slight variations as occur are apparently due to mistakes of the engraver, and are not of interest to students of history or epigraphy.]

- (77) तदनुजन्म¹ पुण्यकर्माच्युतेंद्रः प्रकटमवनिर्लोकं
 (78) "सांशमेत्यातिजेता विलसितचचिवेता विहृदिष्टप्रदा-
 (79) ता ।[। २८] यत्कीर्तिचंद्रचरति क्षमायां तिथिष्वशेषासु विव-
 (80) र्धते च । तनोति चक्रस्य मुदं समिधै³ दिवा च सायं कुसु-
 (81) दैर्विहंघे ।[। ३०*] मदं मवसि⁴ मारुतं शीथीलयं त्यमेयैर्यैर्-
 (82) दशपटलोत्सुरैः क्षितिचोभिरुत्थापितैः⁵ । अजोजनद⁶-
 (83) तिल्लया⁷ किमु विशेषयत्यंबुधीं बलप्रमथनस्य
 (84) नो "रंगविरोधीनं वाजिनं ।[। ३१*] कारागृहाकलितवा-
 (85) सविरोधिभूपदारावलीकरविचालितचामरस्य ।[*]
 (86) राजाधिराजपरराजभयंकरैकवीरादिकानि वि-
 (87) रुदानि वह्नि यस्य ।[। ३२*] गोकर्णसंगमवृत्तिसुवर्ण-
 (88) संसत्क्षोणाद्रि¹⁰पर्वतविरिंचपुरेषु कांक्षां । श्रीका-
 (89) लहस्तिनगरेपि च कुंभकोणे¹¹ दानानि षोडश बह्व-
 (90) नि कृतानि येन ।[। ३३*] अंभोदेन निर्पायमा¹²नसलिलोगस्ते-

Plate III; Side i.

- (91) न¹³ पीतोष्णि¹⁴तस्तप्तो राघवसायकान्निशिव्या स्तंता¹⁵-
 (92) प्यमान सदा¹⁶ । अंतस्त्रैर्वडवासुखानलशो¹⁷खाजालै-
 (93) वशष्को¹⁸ [धु]वं यद्वावां वधवांवरं वधि¹⁹रहो पणं स²⁰सु

¹ Read तदनुजन्मा.

² Read सांशमेत्यातिजेता विलसति हरिचेता.

³ Read समिधे.

⁴ Read मवसि.

⁵ Read क्षितिचोभिरुत्थापितैः.

⁶ The reading in other plates is क्षितिचोभिरुत्थापितैः.

⁷ & ⁸ Read अजोजनदि कुषा.

⁹ Read रंगविरोधीनं.

¹⁰ Read शोषादि.

¹¹ Read कुंभकोणे.

¹² Read निर्पायमान.

¹³ & ¹⁴ Read पीतोष्णेन पीतोष्णिमत.

¹⁵ Read स्तंता.

¹⁶ Read सदा अंतस्त्रैः.

¹⁷ Read शि.

¹⁸ Read विसृष्टो.

¹⁹ Read यद्वावां वधवांवरं वधि.

²⁰ Read पणं स.

- (94) द्योतते । [। ३४*] अंगेनापि कलिगीन वन^१ च परै नृपै^२ । जय जां-
 (95) व महाराजेल्यनद्रां^३ गीयते च यः[*] । [। ३५*] स जयति नरपालो
 (96) रत्नसिंहासनस्तो^४ विजयनगरवासी कीर्तिपूर्वा
 (97) विलासी^५ [।*] नृगनलनहुषादीन् नीकयन्^६ राजनीत्य^७
 (98) निरुपमभुजवीर्योदार्य^८भूरचाताख्यः^९ । [। ३६*] शकान्दे शालि-
 (99) वाहस्य सहस्रेण चतुःस्रतैः^{१०} । एकाम्यधिकया पंचाशता
 (100) च गणिते क्रमात् । [। ३७*] विरोधिवत्सरे पुण्यमासे मकरसंक्र-
 (101) मे । कृष्णपक्षे त्रयोदश्यां पुण्यायां^{११} भौमवासरे । [। ३८*] तुंग-
 (102) भद्रापगातीरे श्रीविरूपाक्षसनिधौ^{१२} श्रीमत्काश्य-
 (103) पगोत्राय वरापस्तंबसूत्रिणे । [। ३९*] यशस्विने यल्लुशाखा-
 (104) ध्ययिने^{१३} गुणशालिने । असे^{१४}षवेदवेदान्तपुराणाग-
 (105) मवेदिने । [। ४०*] नागाभट्टमहामोधिपूर्णचंद्राय भूणवे । भूदा-
 (106) नपात्रभूताय भूमिदेवायया[यि]ने । [। ४१*] धीमते रामचंद्राख्य-
 (107) दीक्षिताय महात्मने । विख्यातश्रीजयंकोडचालमं^{१५}
 (108) डलभूषणं । [। ४२*] पडवीडुमहाराज्ये प्राज्ये विरचितस्ति(स्त्रि)-
 (109) तं । पल्लुनकोडके रंभ्ये^{१६} विर्वज्रपत्तुकेपि च । [। ४३*] स्ति(स्त्रि)-
 (110) तं पंगलनाडौ च स्कन्दहाच^{१७} पश्चिमं । श्रीक[ट*]टगर-
 (111) सोमातभावं^{१८} चापि समाश्रितं । [। ४४*] पालपूराह्वया[द*] या-
 (112) मात् प्राचीमाशामुश्रितं^{१९} । चीयनेन्दिलितिशामा-
 (113) त् दक्षिण[।*]माश्रितं दिशं । [। ४५*] पश्चिमाशां हरीतालामं-
 (114) गलां समुपाश्रितं । ग्रामाच्छेन्नारिपाद्याख्यादुत्त-
 (115) रस्यां दिशि स्थितं । [। ४६*] पुरीशे सिंगणप्पाडिसोमांतर्व-
 (116) र्तिनाड(वु)भौ । श्रीकुर्णतुरुमांवाकौ^{२०} ग्रामयाससमा-
 (117) श्रितं । [। ४७*] कडलाडोति विख्यात^{२१}नामानं ग्राममुत्तमं । स-

^१ Read अंगेन.^२ Read परै नृपै.^३ Read राजेलनिच.^४ Read °स्त्री.

^५ This pāda appears in other Achyuta plates as विजयनगरराजद्वसिंहासनस्थः. This is not suited to the reading in this inscription, as रत्नसिंहासनस्थः appears in the previous pāda. But to style a king as विजयनगरवासी ("residing in the city of Vijayanagara") is unusual, and the poet seems to have been carried away by consideration of rhyme in विजयनगरवासी and कीर्तिपूर्वा विलासी.

^६ Read नीकयन्.^७ Read आ.^८ Read श्रीवीर्याव.^९ Read °भूरचाताख्यः.^{१०} Read चतुःस्रतैः.^{११} Read पुण्यायां.^{१२} Read °सनिधौ.^{१३} Read यल्लुशाखायिने.^{१४} Read श्री.^{१५} Read छा°; °चील°.^{१६} Read मे.^{१७} Read अदनयाच.^{१८} The right reading here seems to be सोमानभावं.^{१९} Read समुपाश्रितं.^{२०} Read °कुर्णतुरुमांवाकौ. [The original reads कुर्णतुरु.—H. K. S.]^{२१} Read ह.

Plate III; Side ii.

- (118) वंमान्यं चतुसी¹मासंयुतं च समंततः ।[1 ४८*] निर्धनिजेप-
 (119) पाषाणसिद्धसाक्षाज्जलान्वितं । अक्षिपयागामिसंयु-
 (120) त्तः²भक्तभोग्यं समूहं ।[1 ४९*] वापीकूपतटाकैश्च कळे-
 (121) नापि समन्वितं । पुत्रपौत्रादिभिर्भोग्यं कमादाचंद्र³-
 (122) तारकं ।[1 ५०*] दानस्वाधमनस्वापि विक्रयस्वापि चीचि⁴-
 (123) तः । परीतः प्रयतै स्निग्धैः पुरोहितपुरोगमै⁵ ।[1 ५१*] विवि-
 (124) धैर्विबुधै चैत⁶पयिकैरधिकैर्गिरा । अश्व्युतेद्रम-
 (125) हारायो माननीयो मनस्विनां ।[1 ५२*] सहिर⁷स्वपयोधारा-
 (126) पूर्वकं दत्तवान्मुदा । यजमानोऽत्र हस्तीनां शतं कृत्वा द-
 (127) स्वीत्तरं⁸ ।[1 ५३*] समविंशतिसंख्याता हस्ति(त्तीः) स्त्रीया विधाय च । चं⁹-
 (128) न्यास्त्रयाधिकासीति¹⁰हस्तिः पुण्याय भूयसे ।[1 ५४*] विप्रेभ्यो न्या-
 (129) कृतासेष्ट¹¹शास्त्रेभ्यो व्यतरन्मुदा । अमरैरर्चमानस्य हर-
 (130) स्वापि हरैरपि ।[1 ५५*] एकैका हस्तिरत्रैव सुधाहाराय कथि-
 (131) ता ॥ नागामहात्मजो धीमान् याजुषः काश्यपान्वयः । षष्टौ
 (132) हस्ति¹²रिहाप्रोति यज्वा तिरुमलाह्वयः ।[1 ५६*] काश्यपान्वय-
 (133) संभूतो नागामहत्स्य नंदनः । श्रीनारायणमहास्थो या-
 (134) जुषः पंचहस्तिकः ॥ [५७*] नागामहाह्वयो धीमान् नागामह-
 (135) तनूहवः । पंचहस्तिरिहाप्रोति याजुषः काश्यपान्वयः ॥ [५८*]
 (136) काश्यपान्वयजसुतः¹³ गोपिनाथस्य याजुषः । म-
 (137) नीषीरामचंद्रस्य¹⁴ चतुहस्ति¹⁵रिहाप्रोति ॥ [५९*] काश्यपा-
 (138) न्वयसंभूतः संगामहत्तनूहवः ।[१*] रामामहाह्वयो ह-
 (139) स्तिह्वयमवैति याजुषः ॥ [६०*] भारद्वाजान्वयः चतुर्भा¹⁶सु-
 (140) भट्टस्य बंधूचः¹⁷ ।[१*] हस्तिह्वयमिहाप्रोति तिमाभट्टो महा-
 (141) मतिः ।[1 ६१*] माठमहात्मजो जामदग्न¹⁸वत्सकुलोद्भवः ।[1] हस्ति-

¹ Read स्त्री.

Omit the visarga.

² Read कमा¹⁰.³ The right reading would here be चोदितः.⁴ Read चै.⁵ Read श्री.⁶ Omit anuvāda after र.⁷ Read द्वासीतरं.⁸ Omit anuvāda after च.⁹ Read चोदोतीति हस्ती.¹⁰ Read चैव.¹¹ Read चोदी here and passim.¹² Read चकुतु.¹³ Read च ?¹⁴ Read चकुतुसी.¹⁵ Read श्री.¹⁶ Throughout the inscription this word appears wrongly with an anuvāda at the end of the first syllable.¹⁷ Read चय.¹⁸ Read श्री.

- (142) इयमिहाप्नोति बंद्ध्यः चंद्रदीक्षितः ॥ [६२*] नंदनो रुद्रभ-
 (143) इत्य बंद्ध्यो हरितान्वयः [१*] वृत्तिद्वयमिहाप्नोति श्रीवि-
 (144) रूपाक्षदीक्षितः । [१ ६३*] अक्काभट्टात्मजो धोमान् भारद्वाजा-
 (145) न्वयोद्वयः । बंद्ध्यो कौडुभट्टाख्यो वृत्तिद्वयमिहाप्नुते ॥ [६४*]
 (146) विश्वामित्रान्वयोद्भूतश्रीकंनेश्वरभट्टजः । श्रीसोम-

Plate IV ; Side i.

- (147) श्रीसोम^१नाथभट्टाख्यो बंद्ध्योऽत्र द्विवृत्तिकः । [१ ६५*] आत्रे-
 (148) यगोत्रजसूनु^२ चौडिभट्टस्य सामगः [१*] श्रीविरूपाक्षभ-
 (149) ट्टाख्यो वृत्तिद्वयमिहाप्नुते ॥ [६६*] मादभट्टसुतो जामद-
 (150) द्न्यवसकुलोद्वयः । कालहस्त्याध्वरो वृत्तिमेकामत्रे-
 (151) ति बंद्ध्यः ॥ [६७*] मौडस्यगोत्रसंभूतो रामाभट्टस्य नंद-
 (152) नः [१*] वृत्तिमेकामवाप्नोति विट[ट*]टाभट्टोऽत्र बंद्ध्यः ॥ [६८*] आ-
 (153) त्रेयगोत्रजसूनुर्नागाभट्टस्य बंद्ध्यः । वृत्तिमेकामि-
 (154) हाप्नोति चौडिभट्टाद्वयसुधीः^३ ॥ [६९*] सुनुर्भा^४शकरभट्टस्य
 (155) बंद्ध्यो हरितान्वयः^५ । यज्वा तिरुमलाभिख्यो वृत्तिमे-
 (156) कामिहाप्नुते ॥ [७०*] भारद्वाजान्वयः सूनुः कामाभट्टस्य वं-
 (157) द्यः [१*] श्रीविरूपाक्षभट्टाख्यो वृत्तिमेकामिहाप्नुते ॥ [७१*] वो-
 (158) ध्वनो^६ वसंत्याजि^७महादेवस्य नंदनः । विश्वामित्रान्व-
 (159) योद्वैकां तिष्ययी^८ वृत्तिमप्नुते ॥ [७२*] सुरिस्त्रिरुमलाभिख्यो
 (160) सूनुः केशवयज्वनः । शांडिल्यगोत्रजोद्वैकां वृत्तिमाप्नो-
 (161) ति यालुषः ॥ [६३*] सादित्यलिंगभट्टाख्यो^९ केशवाध्वरिनंदनो [१*]
 (162) शांडिल्यगोत्रजोद्वैक^{१०}वृत्तिकावत्र यालुषः^{११} ॥ [७४*] सुरेस्त्रि-
 (163) रमलाख्यस्य सूनुः^{१२}स्त्रिरुमलाद्वयः । बंद्ध्योऽत्राप्नुते वृ-
 (164) त्तिमेका^{१३}आत्रेयगोत्रजः ॥ [७५*] बंद्ध्यो भूतनाथस्य चिद्विभट्ट-
 (165) स्य नंदनः । रामाभट्टा^{१४}प्नुते वृत्तिद्वयं गौतमगोत्रजः । [१ ७६*]
 (166) सूनु दे^{१५}वरुभट्टस्य बंद्ध्यः काम्यपान्वयः । आत्रेका-

^१ Read श्रीवसु^१हर^१, as the name in the text seems to have no meaning.

^२ Omit one श्रीसोम.

^३ Read °जसूनु^३.

^४ Read रत्न.

^५ Read संभूतो.

^६ Read स.

^७ Read °सूनु^७चोः.

^८ Read स.

^९ Read °आनवः.

^{१०} Read °आयनी.

^{११} Read राजसूनेयि (PP). [वसंत्याजि is correctly वसंत्याजिन्, the title of a Brahman; S. I. I., Vol. II, p. 512.—H. K. S.]

^{१२} Read तिष्ययी.

^{१३} Read श्री.

^{१४} Read °आयन.

^{१५} Read श्री.

^{१६} Omit v/sarga.

^{१७} Read °मेकाना^{१७}.

^{१८} Read श्री.

^{१९} Read ट.

- (167) मश्रुते वृत्ति¹ तिमाभटो महामतिः ॥ [७७*] श्रीनारसिंहभ-
 (168) दस्य नंदनः काश्वपान्वयः । [१*] वंहुचो वैद्यनाथाख्यो
 (169) वृत्तिमेकामिहाश्रुते ॥ [७८*] बोधायनोपनिषदो नारसिं-
 (170) ह्यध्वरोद्रजः² । अर्धवृत्तिमिहाप्रोति गौतमान्वयसंभवः ॥ [७९*]
 (171) मनोषो देवरेभट्टः³ श्रीनृसिंहध्वरोद्रजः⁴ । बोधायनोश्रुते
 (172) वृत्ति⁵ सार्धकां गौतमान्वयः । [८०*] सामकः⁶ शौडिभट्टस्य सूनुरा-
 (173) त्रेयगीवजः । अत्रैकामश्रुते वृत्ति देवरेभट्टनामकः । [८१*] सूनुरै-
 (174) रदभट्टस्य भारद्वाजान्वयोद्भवः । सुब्रह्मण्यान्वयोत्रैकां⁷
 (175) वृत्तिमाप्रोति वंहुचः । [८२*] सूनुस्तिरुमलाभिख्यायज्वनो गौत-

Plate IV; Side ii.

- (176) मान्वयः । नारसिंहहृदयो⁸ त्रार्धवृत्तिं बोधायनोश्रुते । [८३*] गौतमा-
 (177) न्वयसंभूतः⁹ स्तिमादीक्षितनंदनः । बोधायन¹⁰ श्रुते त्रार्धवृ-
 (178) त्तिं पिठ¹¹ लनामकः । [८४*] नारायणात्मजो जामदग्न्यवसकु-
 (179) लोद्भवः । अर्धवृत्तिमिहाप्रोति संखरो वंहुचः शुधिः¹² । [८५*] वंहु-
 (180) चो गार्ग्यगोचस्य तिष्ठाभट्टस्य नंदनः¹³ । अर्धवृत्तिमिहा-
 (181) प्रोति तिष्ठायो धीमतां वरः । [८६*] सूनुरैरदभट्टस्य भारद्वाजा-
 (182) न्वयोद्भवः । [८७*] याजुषो ऐरुभट्टाख्यो वृत्तिमेकामिहाश्रुते । [८८*]
 भार-
 (183) द्वाजान्वयोद्भूतस्तिमावज्जलुनंदनः । [८९*] धीमान् वरदभट्टा-
 (184) ख्यो याजुषोत्रैकवृत्तिकः । [९०*] सूनुरैरदभट्टस्य श्रीवत्सान्वय-
 (185) संभवः । अर्धवृत्तिमिहाप्रोति सूरामटोत्र याजुषः । [९१*] श्रीमहा-
 (186) लिंगभट्टस्य नंदनो वैकटेश्वरः । विश्वामित्रान्वयोत्रा-
 (187) र्धवृत्तिमाप्रोति वंहुचः । [९२*] नंदनो मारभट्टस्य विश्वामित्रान्वयो-
 (188) द्भवः । [९३*] अर्धवृत्तिमिहाप्रोति वंहुचो जंनयाद्वयः । [९४*] नंदनो
 गौरिभ-

¹ Read सि.

² Omit cisarga.

³ Omit cisarga.

⁴ Read द्य.

⁵ Read द.

⁶ Read नारसिंहध्वरोद्रजः.

⁷ Read °श्राद्धयो.

⁸ Read श्री.

⁹ Read श्रीकरी. . शुधी.

¹⁰ Read सि.

¹¹ Read °सिंहाद्वयो.

¹² Read हि.

¹³ Read नंदन.

- (189) दृश्यं शण्डिल्यान्वयशंभवः¹ । येनाभट्टाद्वयोत्तार्धवृत्तिमाप्नोति
 (190) यालुषः । [। ८३*] सूरिस्तिरुमलाख्यस्य स्रुः कौशिकगोत्रजः । [।*] श्रीविह²
 (191) पाचभट्टाख्यो वृत्तिमेकामिहाप्नुते । [। ८३*] लिंगाभट्टात्मजो धीमान् गो-
 (192) तमान्वयसंभवः । [।*] सादिभट्टाद्वयोत्तार्धकां वृत्तिं बोधायनोप्नुते ॥ [८४*]
 (193) काश्यपान्वयसंभूतो मंगाभट्टस्य नंदनः । [।*] कामाभट्टाद्वयोत्त-
 (194) र्धवृत्तिमाप्नोति बंद्दिचः [।] ॥ [८५*] नंदनः चोडिभट्टस्य³ भारद्वा[जा*]नयोत्-
 (195) भवः । कोनि[रि*]भट्टनामा च बंद्दी(हृ)चोत्तार्धवृत्तिकः[*] ॥ [८६*]
 नंदनोनंतभट्ट(हृ)-
 (196) स्य बंद्दुचः काश्यपान्वयः । अर्धवृत्तिमिहाप्नोति सूरिस्तिरुमलाह-
 (197) यः । [। ८७*] श्रीविद्यानिधिभट्टस्या⁴ नंदनः कौशिकान्वयः⁵ । तिस्रामभट्टाद्वयो-
 (198) त्त्वार्धवृत्तिमाप्नोति बंद्दिचः । [। ८८*] भारद्वाजान्वयश्र⁶रिराभट्टनूत्त-
 (199) वः । वृत्तिमेकामवाप्नोति नागाभट्टा⁷व बंद्दिचः । [। ८८*] स्रु⁸
 माधवभट्टस्य बंद्दि-
 (200) चः[*] कापिलान्वयः । अर्धवृत्तिमिहाप्नोति वेदयो वेदशास्त्रवित् । [। १००*]
 श्रीदी⁹वाक-
 (201) रभट्टस्य स्रुरेकावनामकः । प[र]ाशरान्वयो वृत्तिमेकामवेति या-
 (202) लुषः । [। १०१*]

Plate V; Side i.

- (203) ¹⁰पुरीशेशिंगणप्याडिमीमांतर्वृत्तितां श्रितं । श्रीकीलपुतीरे अग-
 (204) रनामानं ¹¹ग्रामवासं च संश्रितं । [। १०१*] अशु¹²तेद्रमहारायः क¹³डलाडिर्मही-
 (205) यसः । पट्टेदलाद्वयंमामां माममासमदानसु¹⁴दा । [। १०३*] ग्राशनस-

¹ Omit anuvāda after ८३ and read संभवः.² Read मन्दनचोडिभट्टस्य and श्रीदीहवः.³ Read ०५.⁴ Read दि.⁵ Read इय.⁶ Read हो.⁷ The sense is not clear.⁸ Read ह.⁹ Read श्रीविह^०.¹⁰ Read सुनुम^०.¹¹ The right reading here would be something like this: श्रीकीलपुतीरनामानं. The present reading makes no meaning. Nor does it agree with metrical requirements.¹² Read अशु.¹³ Read क^०.¹⁴ The latter part of the pāda is wrong and illegible. The right reading would be, judging from other plates of Vijayanagara kings, ग्रामवासमदानं सुदा. नाना at the end of the first half of the pāda is probably an attribute of the village granted [or stands for ०लाहव ग्रामं.—H. K. S.]

- (206) तिवल्लमायनं तरुकरदानस्य सापदानस्य । अचुतरायनृ-
 (207) पेंदोराननशोभाभिभूतपुनंदो¹ ।[१०४*] अचुतेद्रमहारायमायनेन²
 (208) सभापतः³ । अभाषो मद्दुसंदर्भं तदिदं तावमासनं⁴ ।[१०५*] अच-
 तेद्रमहारा-
 (209) यमासनां⁵ मल्लयातमजः । त्वष्टा श्रीवीरणाचार्या व्यलिखक तावमा-
 (210) शनं⁶ ।[१०६*] स्वदत्तादि(हि)गणं पुष्पं परदत्तानपालतं [१] परदत्ता-
 पहारण स्वदत्तं
 (211) निष्कलं भवेत् ।[१०७*] येकेव⁷ भगिनी लोके सर्वेषामेव भूभुजां ।
 न भोज्या म ग⁸.
 (212) रगाद्या विष्वदत्त वसुंदरा⁹ ।[१०८*] सदत्ता¹⁰ परदत्ता वा यो
 हरेति वसुंदरा¹¹ । वष्टि-
 (213) वंसव¹² सहासि विष्ठायां जायते क्षिप्रि¹³ ।[१०९*] दानपाकन-
 योर्मध्ये दानावे¹⁴.
 (214) योनुपालनं [१*] दानात्सगमवाप्नोति¹⁵ पालनाद्वर्त्त¹⁶ पदं ।[११०*]
 सामा¹⁷ न्योयं ध-
 (215) मंसतुं नृपाणाः¹⁸ काले काले पालनीयोत्¹⁹ भवत्भिः । सर्वान्(१)नेता²⁰-
 (216) त्²¹ भाविनः पार्थिवेद्रान् भूयो भूयो याचते रामचंद्रः ।[१११*]
 श्रीविरूपाक्ष

ABSTRACT OF CONTENTS.

Vv. 1-3. Invocation to Gaṇādhīpati, Śambhu and the boar incarnation of Viṣṇu.

¹ Read °मासन, मासनसु, अचुत and पुनंदी.

² Read अचुतेन्द्र and °मासनेन.

³ Read सभापति.

⁴ Read मद्दु.

⁵ Read ताव. ताव is the Dravidian form of the Sanskrit word ताव.

⁶ Read अचु.

⁷ Read नायकपामज.

⁸ Read न तानुमासन.

⁹ Read एकेव.

¹⁰ Read न च.

¹¹ Read विप्रदत्ता वसुंधरा.

¹² Read स्वदत्ता.

¹³ Read वसुंधरा.

¹⁴ Read वंस. The reading in the text is the Dravidian way of writing वंस.

¹⁵ Read क्षिप्रि; which is the Dravidian form of the Sans. क्षिप्रि.

¹⁶ Read दानावे.

¹⁷ Read दानात्सगम.

¹⁸ Read °द्वयुत.


¹⁹ Read मा.

²⁰ Read °सेतुर्.

²¹ Omit न.

²² & ²³ Omit न after सर्व and read °नेतान्.

Vv. 4-28. Trace the genealogy of the second Vijayanagara dynasty as far down as Achyuta which runs as follows :—



V. 29. After the departure to the other world of Krishna-Rāya his brother Achyuta-Rāya succeeded him on the throne.

Vv. 30-32. Describe the deeds of valour and greatness of Achyuta.

V. 33. The gifts of Achyuta at the holy shrines of Gokarna, Saṅgama, Chidambaram, Śopādrī, Viriñchi, Kāñchi, Kālahasti, and Kumbhaghōṣa.

Vv. 34-36. Praises of the king.

Vv. 37-39. In the Śaka year 1451 according to the Śālivāhana reckoning, in Virōdhin, in the Pushya month, on the Makara-Saṅkrānta, on the 13th day of the dark half of the month, on Tuesday, on the banks of the Tuṅgabhadra, in the vicinity of Śrī-Virūpākha, (the gift was made)

Vv. 40 and 41. To the great soul Rāmachandra-Dīkshita, the best of Brāhmana, who very well deserved the gift of land, the son of Nāga-Bhaṭṭa, of the Yajus-śākha,

Vv. 42-48. Of Kaḍalādi, the ornament of the province of Jayamkoṇḍachōla, situated in Paḍaviḍu-rājya, in Phalgunna-kōṭaka, in Virvaḷḷu-pattuka, in Paṅgala-nādu, on the west of Skandanadi, bordering on Kaṭṭagara, to the east of Pālapūr, to the south of Chiyanēndil, to the west of Haritalāmaṅgala and to the north of Sennāripādi.

Vv. 49-52. Describe the details of the contents in the village granted and also the terms of the grant, as generally occurring in other Vijayanagara grants.

Vv. 53 and 54. The village is divided into 110 *vittis* and allotted in small portions to Brāhmana of various *gōtras*, *sūtras*, etc.

Vv. 55-104. Give the names of the donees, their *gōtra*, *sūtra*, *śākha* and the number of shares allotted to each.

Vv. 105 and 106. Give the names of the composer of the decree of Achyuta-Rāya and the engraver of the inscription as Sabhāpati and Virūpachārya.

Vv. 107-111. The admonitory verses above the signature Śrī Virūpākha.

No. 23.—THE BANGARH GRANT OF MAHI-PALA I: THE 9TH YEAR.

By R. D. BANERJI, M.A., INDIAN MUSEUM, CALCUTTA.

This grant was discovered among some ruins called Ban Rājā's garh or Bangarh, in the Dinajpur District of the Presidency of Bengal, during the latter decades of the 19th century. It was kept for some time in the office of Bābū Nṛsiṃha Charaṇa Nandī, Zamindār of Nawābbāgar in the same district. In 1886 Mr. Giridhārī Basu sent several rubbings of this inscription to the Asiatic Society of Bengal. These rubbings were examined by the late Rāja Rājendra Lāla Mitra, who pronounced the find to be an important one, but was prevented by his failing eyesight from attempting a decipherment. The rubbings were then sent by Dr. A. F. R. Hoernle to the late Dr. F. Kielhorn, who published his reading of this important record in the Journal of the Asiatic Society of Bengal in 1892.¹ The subsequent history of the plate cannot be definitely traced. It appears to have been sent to the Baṅgiya Sāhitya Parishad by the late Mr. Nanda Kṛishṇa Basu, C.S., then Collector of Dinajpur. In the Bengali year 1305 (1898 A.D.) Bābū Nāgendra Nātha Vasu Prāchya-vidyā-mahārāja Siddhānta-vāridhi re-edited the record in the Journal of the Baṅgiya-sāhitya-parishad.²

The new edition of the text was in no way an improved one, but on the contrary was disfigured by mistakes, though the author had the original plate before him. A fresh edition of the record, accompanied by a translation, was published in 1912 by Mr. Akahayakumāra Maitrēya in a book entitled *Gaṇḍa-lēkha-mālā*, in which the author collected all published records of the Pāla kings of Bengal.³ Though Mr. Maitrēya's translation is an excellent one, yet his version of the text was no improvement. It was a very careless copy of the text published by the late Dr. Kielhorn. The corrections made by Mr. Maitrēya are conjectural in the majority of cases, and he has taken Dr. Kielhorn's cautious version of ill-preserved portions of the record to be the only version possible. In the winter of 1911-12, when the authorities of the Baṅgiya Sāhitya Parishad exhibited their collection of antiquities and literary relics, this grant was sent on loan to that exhibition by Bābū Nāgendra Nātha Vasu, who is the present owner of the plate. I obtained a loan of it from the same gentleman, and the now accompanying ink-impressions were prepared by Munshi Wāhid-ud-dīn Ahmad of the Archaeological Section, Indian Museum. On examining the original plate I found that it had never been properly cleaned and in many cases letters were still filled up with earth. The plate was very carefully cleaned before estampages were taken. In the subjoined edition Dr. Kielhorn's version of the text has been improved in some places, the most important of which is the reading of the date. Dr. Kielhorn could not read any part of it, as he had tried to decipher the record from pencil-rubbings which were taken when this part was full of impurities. Bābū Nāgendra Nātha Vasu, instead of cleaning the plate, stated that the numeral of the year and the name of the month had been scratched out. Mr. Maitrēya has simply copied this statement without attempting to verify it. After cleaning the plate I found that the portion bearing the date has suffered from corrosion only, but no one had ever scratched any part of it. The year, month and day are still legible, the numeral for the year having suffered most. The impressions published here are the first of this important record, no one having supplied a fac-simile, when editing it either in English or in Bengali.

Like all other Pāla grants, this record also is incised on a single plate of copper, measuring 14½" by 12½". It is surmounted by a highly wrought ornament, which was the seal of the Imperial Pālas. It is pointed at the top and bears in the centre a beaded circle with raised

¹ *Beng. Asiat. Soc.'s Jl.*, 1892, pt. 1, p. 77.² *Baṅgiya-sāhitya-parishat-patrikā*, Vol. V, p. 164.³ *Gaṇḍalēkhamālā*, Vol. I, p. 99.

rim, supported and surrounded by arabesque work. On the top of this circle is a conch (*śaṅkha*). Inside the area of the circle is divided into two equal parts, the upper half bearing a representation of the Buddhist wheel of law (*dharma-cakra*) on a pedestal, surmounted by an umbrella and with a deer couchant on each side, while the lower half bears the name of the king Śrī-Mahipāla-Devasya in raised letters, supported by arabesque work.

The plate bears sixty-two lines of writing, thirty-four on the first side and twenty-eight on the second. After the *Oṃ Svasti* in l. 1 the first twenty-four lines contain twelve verses, which describe the genealogy of the Pālas from Gō-pāla I. to Mahi-pāla I. The rest of the record, with the exception of the seven imprecatory verses and the two verses giving the name of the *dūtaka* and the account of the mason, is in prose. The text is generally correct, and the majority of the mistakes is to be found in the prose portion of the record. In addition to the usual employment of *va* for *ba*, we find that the mason or the author had a predilection for the palatal in the place of the dental *sa*. In one or two cases, on the other hand, *sa* is used in the place of *śa*; e.g. in *saila* and *sikhara* in l. 25. The doubling of consonants with a subscript or superscript *r* is rare, e.g. *Maṣṭrīm* (l. 1), *-ātapatrā* (l. 10), **taṣṭr=jjagatām* (l. 11), **yair=jjaladhī* (l. 15).

The characters of the inscription show well-developed Bengali forms in the initials of *a* and *u* among vowels and among consonants *ka*, *kha*, *ga*, *cha*, *dha*, *va*, and *ha*. The rest of the alphabet shows forms gradually advancing to the Bengali alphabet of the 12th century A.D. In one case at least the complete Bengali form of *ja* is used, i.e. in *jītvā* (l. 3). This is really the proto-Bengali alphabet, while the 12th century alphabet of the Deopārā inscription of Vijaya-sēva, which Bühler termed proto-Bengali, is in reality the fully developed Bengali alphabet. Final forms of *ma* and *na* are used, e.g. in *bhūbhṛtām* (l. 7) and *=guṇān* (l. 13). The sign of *avagraha* is inserted in the majority of cases. The language of the record is Sanskrit.

The inscription refers itself to the reign of the Emperor Mahi-pāla I. of Bengal, whose titles are *Paramēśvara*, *Parama-bhaṭṭāraka* and *Mahārājādhirāja*, and who mediated on the feet of the *Parama-saṅgata*, *Mahārājādhirāja Vighraha-pāla-dēva* (III.). It records the donation of the village of *Kuraṣa-pallikā*, with the exception of the *Chuṭa-pallikā*, in the *Gōkalikā maṇḍala* of the *Kōṭivaraha viśaya* of the *Puṇḍravardhana bhukti*, by the Emperor, after a bath in the Ganges on the occasion of the *Vishuva-samkrānti*, to a *Brāhmaṇa* named *Kṛishṇā-ditya-śarmman*, son of *Bhaṭṭa-putra Madhusūdana* and grandson of *Bhaṭṭa-putra Hrishikēśa*, who is an immigrant from the village of *Hastipada*, an inhabitant of the village of *Chāvaṭi*, of the *Parāśara gotra*, *Śakti*, *Vasishṭha* and *Parāśara pravara*, a student of *Vājasaneyin* branch of the *Yajur-vēda*, and well-versed in grammar (*vyākaraṇa*), logic (*tarka-vidyā*) and the sacred philosophy (*mīmāṃsā*). The grant was issued from the royal camp or residence of *Vilāsa-pura*, on the 12th day of *Phālguna* of the 9th year of the king's reign. The *dūtaka* of the grant was the minister (*mantrin*) *Bhaṭṭa Vāmana*. It was incised by the artisan (*śilpīn*) *Mahidhara*, son of *Vikramāditya*, an inhabitant of *Pōshalī*. The *Āmagachhi* grant was incised by *Śāsīdēva*, the son of this *Mahidhara*. The record is here re-edited from the original.

TEXT.¹

[Metres: v. 1, *Sragdharā*; vv. 2-3, *Śārdūlavikṛīḍita*; v. 4, *Vasantatilaka*; v. 5, *Āryā*; v. 6, *Śārdūlavikṛīḍita*; v. 7, *Vasantatilaka*; v. 8, *Sragdharā*; v. 9, *Indravajrā*; v. 10, *Vasantatilaka*; v. 11, *Maṇḍākrāntā*; v. 12, *Mālinī*.]

¹ From the plates and impressions.

First side.

- 1 Ni¹ Ōm² Svasti | Maittrim kārūya-ratna-pramudi-ni³
- 2 -tahṛidayah prēyasīm sandadhānah samyak-samvō(mbō)dhi-vi-
- 3 -dyā-sa(sa)rid-amala-jala-kshālīt-ājñāna-pāṇkah | Ji-
- 4 -tvā yah kāmakāri-prabhavam-abhībhamam sāsāvati-
- 5 -m-prāpa śāntim sa śrīmān-lōkanāthō⁴ jayati Da-
- 6 -sa-va(ba)lō śnyās-cha Gōpāla-dēvah ||[1*] Lakshmi-janma-ni-
- 7 -kētanam sa-makarō vōdhum kshamah kshamā-bharam paksha-chehḥṣḍa-bhayād-
- 8 -upasthitavatām-ēk-āśrayō bhū-bhṛitām | Maryādā-paripā-
- 9 -lan-aika-nirataḥ śaury-ālayō śamād-abhūd-dugdh-āmbhōdhi-vilāsa-hāsi-mahimā Śrī-
- 10 -Dharmmapālō nripah ||[2*] Rāmasy-ēva
- 9 grihita-satya-tapasas-tasy-ānurūpō guṇaiḥ Saumittre-udapādi tulya-mahimā
- 11 Vākpāla-nām-ānujah | Yah śrīmān-na-
- 10 -ya-vikram-aika-vasatir-bhṛatuh sthitah śāsanē śūnyāḥ śatru-patākinibhir-akarōd-
- 11 -ēk-ātapattrā diśah ||[3*] Tasmā-
- 11 -d-upēndra-charitair-jjagattim punānah putrō va(ba)bhūva vijayi Jayapāla-nāmā
- 12 -Dharmma-dviśāhām śamayitā yudhi Dēvapālō yah
- 12 pūrvvajē bhuvana-rājya-sukhāny-anaishit ||[4*] Śrīmān-Vigrahapālas-tat-sūnur-
- 13 -Ajātasatru-iva jātah | Śatru-vanitā-prasādha-
- 13 -na-vilōpi-vimal-āsi-jala-dhārah ||[5*] Dik-pālaih kshiti-pālanāya dadhata[m] dēhē
- 14 -vibhaktān-guṇān⁵ śrīmantañ-jana-
- 14 -yānva(ba)bhūva tanayam Nārāyaṇam sa prabham | Yah kshōṇi-patibhiḥ
- 15 -śiromaṇi-ruchā-śliṣṭ-āṅghri-piṭh-ōpalam nyāyō-
- 15 -pāttam-alañchakāra charitaih svair-ēva dharm-āśanam ||[6*] Tōy-āśayair-jjaladhī-
- 16 -mūla-gabbhira-garbbhair-ddēvālayais-cha
- 16 kula-bhūdhara-tulya-kakshaih | Vikhyāta-kīrttir-abhavat-tanayās-cha tasya Śrī-
- 17 -Rājyapāla iti madhyama-lōka-pālāḥ ||[7*] Tasmā-
- 17 -t-pūrvva-kshītīdhān-nidhir-iva mahasām Rāshṭrakūṭ-ānvay-ēndōs-Tuṅgasy-ōttuṅga-
- 18 -maulēr-ddubitari tanayō Bhāgya-dēvyām pra-
- 18 -sūtah | Śrīmān Gōpāla-dēvaś-chiratarām-a[vanē]r-ēka-patnyā iv-aikō bhart-
- 19 -ābhūn-n-aika-ratna-dyuti-khachita-chatuh-sindhu-
- 19 chitr-āmsukāyāḥ ||[8*] Yam svāminam rāja-guṇair-anūnam-āśēvatē chārutar-ānu-
- 20 -raktā | Utsāha-mantra-prabhu-śakti-lakshmiḥ prithvīm sa-
- 20 -patnīm-iva śilayanti ||[9*] Tasmād-va(ba)bhūva savitur-vvasu-kōṭi-varshi kālēna
- 21 -chandra iva Vigrahapāla-dēvah | Nētra-priy-
- 21 -pa vimalēna kalāmayēna yēn-ōditēna dalitō bhuvanasya tāpah ||[10*] Dās-
- 22 -prāchi prachura-payasi svachchham-āptya tō-
- 22 -yam svairam bhrāntvā tad-ann Malay-ōpatyakā-chandanēshu || Kri[tvā] sāndrai[r]-
- 23 -mmar⁶uahu ja[ḍa]tām śikarair-abhra-tulyāḥ prālōy-ādre-
- 23 -ḥ kaṭakam-abhajan yasya sēnā-gajēndrāḥ ||[11*] Hata-sa[ka]la-vipakshah saṅgarō
- 24 -vā(ba)hu-darppād-anadhikṛita-viluptam rājyam-ā-
- 24 -sādyā pitryam | Nihita-charaṇa-padmo bhū-[bhṛitām] mūrdhni [tasmād-a]bhavad-
- 25 -avani-pālāḥ Śrī-Mahipāla-dēvah ||[12*] Sa kha-

¹ The first syllable of the word "baddha," registered or recorded," referring to the registration of the grant in the Department of Land Records. See Kleinhorn, *Journal Beng. As. Soc.*, 1892, p. 92, note 14.

² Expressed by a symbol.

³ See note 1.

⁴ Read Śrīmāl-lōkanāthō.

⁵ Read "guṇān-śrī."

⁶ s-tarushu in other plates.

- 25 -lu Bhāgīrathi-patha-pravarttamāna - [nānā] - vidha - nau - vāṭaka - sampādi[ta] - sētu-
va(ba)ndha-mihita-sai(śai)la-si(śi)khara-śrēpi-vibhram[ā]-
26 -t | Niratīśaya-ghana-ghanāghana-ghaṭā-śyāmāyamāna-vāsara-lakṣmī-samāravdha(bdha)-
-santata-jalada-samaya-sandēhāt |
27 Udicin-ānēka-narapati-prābhritikṛit-āprā(a)mēya-haya-vāhīnī-khara-khur-ōikhāta - dhūhī-
dhūsarita-dig-antarā-
28 -lāt | Paramēśvara-sēvā-samāyāt-āśēsha-Jamvu(mbū)-dvīpa-bhūpāl-ānanta-pādāta-bhara-
namad-avanēh | Vils(P)sa-pura-samā-
29 -vāsita-śrīmaj-jaya-skandhāvārāt | Paramasugatō Mahārājādhirāja-Śrī-Vigrahapāla-
dēva-pād-ānudhyātāḥ para-
30 -mēśvaraḥ parama-bhāṭṭārakō Mahārājādhirājaḥ śrīman-Mahipāla-dēvaḥ kuśālī
śrī-Puṇḍravarddhana-bhuktau | Kōṭīva-
31 -rsha-vishayō | Gōkalikā-maṇḍal-āntaḥpāti-sva-samva(mba)ddh-āvachchhinna-
tal-ōpēta-Chūṭa-pallikā-varjīta-Kurāṭa-palli-
32 -kā-grāmē | samu[pa*]-gat-āśēsha-rāja-purushān | rāja-rājanyaka | rāja-putra |
rāj-āmātya | mahāsāndhivigrahi-
33 -ka | mahākṣhapāṭalika | mahāmātya | mahāsēnāpati | mahāpratihāra |
dauṣṣādhāsādhānika | mahā[da]ṇḍanā-
34 -[yaka] | mahākumārāmātya | rājasthānty-ōparika | dāśāparādhika
chaurōddharanika | dāṇḍika | dāṇḍapā-

Second side.

- 35 -si(śi)ka | sau(śau)lkika | gaulmika | kṣētrapa | prā-
36 -ntapāla | kōṭṭapāla | sōga[ra]kṣha | tadāyu-
37 -kta-viniyuktaka | hasty-asv-ōshṭra-nau-va(ba)la-vyā-
38 -pṛitaka | kiśōra-vaḍavā-gō-ma[b]ish-āj-āvi-
39 -k-ādhyakṣha | dātāprēshanika | gamāgamika |
40 abhitvaramāpa | vishayapati | grāmapati | Tarika | Gaṇḍa | Mālava | Khasa |
Hāpa | Kulika | Karṇāṭa | Lāṭa |
41 chāṭa | bhāṭa | sēvak-ādīn | anyāmś-oh-ākīrttitān | rāja-pād-ōpajivinaḥ
prativāsinō vrā(brā)hmaṇ-ōttarāmścha | mahatta-
42 -m-ōttama - kuṣumvi(mbi) - purōga - mēd - āndhra - chaṇḍālā - paryantān | yath - ārham
mānayati | vō(bō)dhayati | samādiśati cha | Vidita-
43 -m-astu bhavatām | yath-ōpari-likhitō-yam grāmāḥ sva-simā-tṛiṇa-pūtil-gōchāra-
paryantaḥ sa-talaḥ | s-ōddēśaḥ s-āmra-ma-
44 -dhūkaḥ | sa-jala-sthalaḥ | sa-gartī-ōsharaḥ | sa-das-ōpachāraḥ | sa-chaur-ōddharanāḥ |
parihṛita-sarva-piḍaḥ | a-chāṭa-
45 -bhāṭa-pravēśaḥ | akiūchid-grāhaḥ | samasta-bhāga-bhōga-kara-hirany-ādi-pratyāya-
samētaḥ | bhāmi-chchhidra-nyā-
46 -yēna | ā-chandr-ārka-kṣhiti-sama-kālam | mātā-pitrōr-ātmanas-cha punya-yasō(śō)-
bhivṛiddhaye | Bhagavanjam Vu(Bu)ddha-bhāṭṭāra-
47 -kam-uddiśya | Parās²ara-sagotrāya | Śakti | Vāsī(śi)shṭha | Parās²ara-pravarāya
Yayur²-vēda-savva(bra)hmachārinō | Vāja[sanē*]-
48 -ya-śākṣ-ādhyāyinō | mīmāṃsā⁴-vyākaraṇa-tarkka-vidyā-vidē | Hastipada-grāma-
vinirgatāya | Chāvaṭi-grāma-vāstavyā-

¹ May also be read *yūti.² Read sa.³ Read Yafer.⁴ Read mīmāṃsā.

- 49 -ya Bhaṭṭaputra-Rishikēśa¹-pantrāya | Bhaṭṭaputra-Madhusūdana²-putrāya
Bhaṭṭaputra-Krishṇāditya-sarmma³ | Viśuva⁴-saṅkrā-
- 50 -vantau⁵ vvidhivat⁶ | Gaṅgāyām snātvā śāsanikṛitya pradatto śmābbih | ato
bhavadbbih sarvvair-śv-ānumantavya-
- 51 -m | bhāvibhir-api bhū-patibhiḥ | bhūmēr-ddāna-phala-gauravāt | apaharaṇē cha
mahānaraka-pāta-bhayāt |
- 52 dānam-idam-anumōdy-ānupālantiyam | prativāsibhiḥ-cha kshētra-karaiḥ | ājñā-
śravaṇa-vidhēyibhūya yathā-kālam
- 53 samuchita-bhāga-bhōga-kara-hirany-ādi-pratyāy-ōpanayaḥ kārya iti || Samvat [9
Phā]lguna-dinē 12 bhavanti ch-ātra
- 54 dharmm-ānusaṁsainah ślōkāḥ || Va(ba)hubhir-vvasudhā dattā rājabbis-
Sagar-ādibhiḥ | Yasya ya[sya*] yadā bhūmis-tasya stasya⁷
- 55 tadā phalam ||[13*] Bhūmim yaḥ pratigrihōti yaś-cha bhūmim prayachchhati |
Ubhan tau punya-karmmapau niyataḥ svargga-gāminau ||[14*]
- 56 Gām-ōkām avarṇam-ōkañ-cha (1) bhūmēr-apy-arddham-aṅgulam | Haran-narakam-
ayāti⁸ yāvad-ā-bhūta-samplavam ||[15*] Shashṭim⁹-varsha-sahasrā-
- 57 -pi svarggō mōdati bhūmi-daḥ | Ākshēptā ch-ānumantā cha tāny-eva narakō
vasēt ||[16*] Sva-dattām mpar¹⁰-dattām vā yō harēta
- 58 vasundharām | Sa vishṭhāyām krimir¹¹-bhūtvā pītribhi[s*]-saha pachyatō ||[17*]
Sa[rvvā]n-ētān bhāvinah pāthiv-ēndrān bhūyō bhā-
- 59 -yaḥ prārthayaty-ēsha Rāmaḥ | Sāmānyō-yam dharmma-sō(sē)tur-nripāṇām
kāle kālē pālantiyō bhavadbbih ||[18*] Iti kamala-da-
- 60 -l-āmva(mbu)-vi(bi)ndu-lōlām śriyam-anuchintya manushya-jivitañ-cha | Sakalam-
idam-udābhṛtañ-cha vu(ba)ddhvā na hi purushaiḥ para-kīrtta-
- 61 -yō vilōpyaḥ ||[19*] Śrī-Mahipāla-dēvēna dvija-śrēṣṭh-ōpapādītē | Bhaṭṭa-Śrī-
Vāmanō mantri śāsanē dātakaḥ kṛtāḥ ||[20*]
- 62 Pōshali-grāma-niryāta-Vikramāditya-śununā¹² | Idam śāsanam-utkirṇam Śrī-
Mahidhara-śilpinā ||[21*]

TRANSLATION.

V. 1. Om Hail ! Victory to the illustrious Gopāla-dēva, who with his heart gladdened by the jewel of compassion, held love (for his subjects) higher (than any other thing), who had washed away the mud of ignorance (of the people) by the pure water of the stream of his perfect understanding and knowledge, who had obtained enduring peace (for his kingdom) by defeating the attacks (of princes) who were led by (their own) passions, (and who therefore was) like another Daśabala (Buddha), who with his heart expanded by the jewel of compassion held Maitri to be dearer than others, who washed away the mud of ignorance by the pure water of the stream of knowledge of the perfect enlightenment, (and) who had obtained eternal peace by having defeated the attacks made by the Kāmaka foe (i.e. Māra).

¹ Read *Hrishikēśa*.² Read *Viśuva*.³ Read *tasya*.⁴ Read *para*.⁵ Read *Madhusūdana*.⁶ The *va* is superfluous.⁷ Read *ayāti*.⁸ Read *krimir*.⁹ Read *sarmma*.¹⁰ Read *vidhivat*.¹¹ There is a superfluous *causēra* over the *m*.¹² Read *śununā*.



मन्त्रान्तरं यमद्विनि
नः यमा क्रमादिना
नेता जानयद्वादि
यत्तुमाद्यद्वादिना
नाकृताष्टादश्यादय
नायद्वादिना श्री कृष्ण

विष्णुस्त्रोत्रं श्रीकृष्ण
 चरितं यथावत् प्रदीयते
 साधुभिः कृतं मन्त्रं यथा
 गायत्री मन्त्रं यथा
 शिवोक्तं यथा

१
 २
 ३
 ४
 ५
 ६
 ७
 ८
 ९
 १०
 ११
 १२
 १३
 १४
 १५
 १६
 १७
 १८
 १९
 २०
 २१
 २२
 २३
 २४
 २५
 २६
 २७
 २८
 २९
 ३०
 ३१
 ३२
 ३३
 ३४

36 श्रीमन्मोक्षोक्तो
 38 श्रीमन्मोक्षोक्तो
 40 श्रीमन्मोक्षोक्तो
 42 श्रीमन्मोक्षोक्तो
 44 श्रीमन्मोक्षोक्तो
 46 श्रीमन्मोक्षोक्तो
 48 श्रीमन्मोक्षोक्तो
 50 श्रीमन्मोक्षोक्तो
 52 श्रीमन्मोक्षोक्तो
 54 श्रीमन्मोक्षोक्तो
 56 श्रीमन्मोक्षोक्तो
 58 श्रीमन्मोक्षोक्तो
 60 श्रीमन्मोक्षोक्तो
 62 श्रीमन्मोक्षोक्तो

V. 2. From him was born the king **Dharmmapāla**, whose grandeur mocked the charm of the Ocean of Milk, whose place of birth was the same as that of Lakshmi¹ (or who was the place of the birth of Lakshmi), who exacted the payment of revenue (*kara*) evenly, (or who was full of crocodiles, "makaras"), who was capable of bearing the weight of the world, (or who was capable of bearing the maintainer of the Earth, i.e. *Vishṇu*), who was the only refuge of kings that had sought protection out of fear of having the wings (of their armies) cut off (or who was the only refuge of mountains who had sought shelter out of fear of their wings being cut off by *Indra*), who was intently engaged in maintaining the dignity (of the social orders) (or which was intently engaged in maintaining boundaries) (and) who was the receptacle of valour (or who was the home of the rays of the sun).

V. 3. To him, who had taken the vow of truth like *Rāma*, was born a younger brother, like him in virtues, named **Vākpāla**, who was the equal of *Saumitri* (i.e. *Lakshmana*) in greatness, who, endowed with grandeur, was the only abode of policy and valour and who, remaining under the rule of his (elder) brother, made the (ten) cardinal points free of the banners of the enemies and brought them (i.e. the cardinal points) under a single umbrella.

V. 4. From him was born a victorious son, named **Jayapāla**, who, purifying the world by his deeds, which were like that of *Upendra* (*Vishṇu*) and vanquishing the enemies of religion in battle, made his elder brother **Dēvapāla** enjoy the happiness of having the world for his kingdom.

V. 5. His son, the illustrious **Vigrahapāla**, was born like *Ajātaśatru* (*Yudhishtira*), the keen edge of whose spotless sword, like a stream of pure water, wiped away the toilette marks of the wives of his enemies.

V. 6. He begot a son, the illustrious Lord **Nārāyaṇa**, who in (his own) body was possessed of the qualities divided by the guardians of the cardinal points for supporting the world, who adorned by his own deeds the throne of law obtained by righteousness (or by inheritance), the stone foot-stool of which was surrounded by kings with the lustre of their crest-jewels.

V. 7. His son was the illustrious **Rājyapāla**, a ruler of the middle world, who, by (excavating) tanks, the beds of which were as deep as the bed of the ocean, (and) by (erecting) temples whose sides were as high as the ridges of the principal mountains (*Kula-bhādhara*), had become famous.

V. 8. As from the eastern mountains the Sun, so from him, in the womb of **Bhāgya-dēvī**, the daughter of the high-crested *Tuṅga*, the moon of the **Rāshtrakūṭa** family, was born a son, the ocean of lustre, the illustrious **Gōpāla-dēva** (and) who became for a long time the only husband of the earth, who had only one husband (i.e. was the sole Lord of the earth), which (earth) was clad in the four oceans decorated by the rays of many jewels as its coloured garment.

V. 9. *Lakshmi*, being possessed of the powers of valour (*utsāha*), counsel (*mantra*) and rule (*prabhū-śakti*, i.e. *kṛpā*, *danḍa* and *balā*²), keeping the earth pleased (just as a good-natured lady keeps well-pleased) her co-wife served her husband (**Gōpāla**), who was not lacking in kingly virtues, with ever-increasing charm and devotion.

V. 10. As the moon, the scatterer of myriads of rays, from the Sun, so from him was born in course of time **Vigrahapāla-dēva**, the scatterer of innumerable riches. By his rise (or birth), who was pleasing to the eyes on account of personal beauty (or by his soft rays), who

¹ This refers to the descent of the *Pāla* kings from the Sea (cf. *Pālas of Bengal*, *Mem. B. A. S.*, Vol. I, p. 46). This fact is based on the *Rāmcharita* of *Sandhyākaranandin*, published by *Mahamahōpādhyāya Hara Prasad Sāstrī* (*Mem. B. A. S.*, Vol. III, I, 3-4).

² This explanation is based on *Amarakōśa* 2, VIII. 19, quoted by *Mr. Atshaya Kumāra Maitreya* in his *Gauḍalēkhamālā*, p. 99, note.

was pure, (or spotless), who was learned in the (sixty-four) arts (*kalās*) (or who was formed of sixteen parts, i.e. *kalās*), were annihilated the sufferings of the world (or the heat of the earth caused by sunshine).

V. 11. Whose war-elephants, like clouds, having drunk clear water in the eastern country, which abounds with water, after that having roamed according to their own wills in the sandal forests of the valleys of the Malaya (country), (and) having caused a coolness in the Maru lands by throwing dense sprays (of water emitted from their trunks), enjoyed the slopes of the Himālayas (*Prāśyādri*).

V. 12. From him was born, the protector of the earth, the illustrious Mahipāla-dēva, who, slaying all enemies, (and) having obtained his paternal kingdom, which had been snatched away through pride of prowess by people who had no claim to it, placed his lotus-like feet on the heads of kings.

Ll. 24-62. From the illustrious (and) victorious camp (pitched) at Vilāsapura, where the illusion of the Sētabandha (bridge built for Rāma between India and Ceylon) with a chain of mountain tops placed (in the sea) was produced by water-craft of various kinds proceeding along the path of the Bhāgrathi; where exceedingly dense arrays of rutting elephants darkened (i.e. obscured) the beauty of the day (and) caused the illusion of the beginning of a perpetual rainy season; where the cardinal points were made grey with the dust dug by the sharp hoofs of the countless army of horses (that were) presented by many kings of the North; where the (surface of) the Earth bent under the weight of the endless infantry of the kings, one and all, of Jambūdvīpa, (who had) come for serving (their) overlord; he, the Paramāśvara, Paramabhāṭṭāraka, great king of kings, the illustrious Mahipāla-dēva, who meditated on the feet of the illustrious Vigrahapāla-dēva, the devout worshipper of the Sagata, the great king of kings, being in good health, honours, informs and orders (the following persons), in the village of Kuraṣa-pallika with the exception of Chūṭa-pallikā with the low ground (*tala*) which belongs to the personal (royal) domain, in the maṇḍala of Gōkalikā, in the viśaya of Kōṭivarsha, in the Puṇḍravardhana bhukti, all royal officers assembled (here follows names of officers, ll. 22-41) and others, (who are) royal dependants, but not mentioned in the lists of superintendents (*adhyakṣas*), the neighbouring Brāhmaṇas and others, Mahattamas and other families down to Mēdas, Andhras and Chāṇḍālas, "Be it known unto you, that this village which has been mentioned above, as far as its boundaries, grass and pasture-lands, with low lands, with assignments, with mango and Madhūka trees, with land and water, with hollows and salt lands, with the ten offences, with the right of extirpation of robbers, with the exemption from all oppression, not to be entered by irregular or regular troops, not to be meddled with by anybody, with all revenues, shares, rights of easement, taxes, (rights of mining) gold, etc., by the law of bhūmi-cakṣhidra, as long as the Sun and the Moon will last, for the increase of the merit and fame of my father and mother as well as mine, in the name of Lord Buddha, has been granted by us by means of a copper-plate grant, after bathing in the Ganges, according to law, on the occasion of the Vishuva Saṁkrānti, to the Bhaṭṭaputra Kṛishṇāditya-śarman, son of the Bhaṭṭaputra Madhusūdana, grandson of the Bhaṭṭaputra Hṛishikēśa, an inhabitant of the village of Chāvaṭi, an emigrant from the village of Hastipada, (who is) well versed in religious law (*Mīmāṃsā*), grammar and logic, a Brahmachārin of the Yajur-veda, of the Parāśara gṛha, whose pravaraṣ are Śakti, Vasiṣṭha and Parāśara, (here follows a valedictory sentence in prose). In the year 9 on the 12th day of Phalguna (here follows 5 of the usual valedictory verses)" For this grant given to the best of the twice-born, by the illustrious Mahipāla-dēva, the counsellor Bhaṭṭa Śrī-Vāmana was selected as the *dātaka* (20). This grant was incised by the artisan, the illustrious Mahidhara, son of Vikramāditya of the village of Pōhali (21).

No. 24.—PENUKONDA PLATES OF MADHAVA II (III).

By LEWIS RICE, C.I.E.

These plates are of special interest as being an admittedly genuine record of the early Gaṅga kings of Gaṅgavāḍi, or Mysore. They were brought to notice by Rao Sahib H. Kṛishṇa Śāstri in his *Epigraphical Report* for 1913-4, and belong to a resident of Penukonda, or, more correctly, Penugonda, in the Anantapur District of Madras, which borders Mysore on the north-east. It was the seat of government of the Vijayanagar kings after the loss of their capital. The plates have been among the family records of a *purōhit* of Penugonda, named Ādem-Bhaṭṭa, for a very long time, his ancestors being hereditary *purōhīts* of the place. They were produced for examination by the Karpam Venkatarayappa of Kanchasamudram in the Hindupur taluq.

There are three plates, of which the two outer ones are engraved on the inner sides only. Four faces are thus inscribed, each containing five lines. The whole inscription is in a good state of preservation.¹ The characters are of an ornamental type and well formed, similar to those used in the best engraved Gaṅga grants, of which we have examples in Nos. 1, 18, 27, 28, 31 and others in the list below. The letters in the present case, measured by the single ones within the lines, are exactly $\frac{1}{4}$ " in height. Except for the partial omission of one step in the pedigree, the engraver's work is remarkably free from errors. But in the word *mati* (l. 4) the *ma* is formed like *che*; and in the word *dushkham* (l. 18) an *m* has been put for *sh* [or for the *jñāṣ-māliya*.—Ed.], but these two letters closely resemble one another. According to Mr. Kṛishṇa Śāstri—"The plates measure roughly $8\frac{1}{2}$ " by $2\frac{1}{2}$ ", and are strung on an oval ring, whose major and minor axes are $2\frac{1}{2}$ " and $2\frac{1}{4}$ " respectively. The edges of the ring are secured at the bottom of a circular seal, $1\frac{1}{4}$ " in diameter, which bears at its top, on a countersunk surface, a standing elephant, facing the proper left, with its trunk hanging down between its tusks. The ring was not out when the plates were placed in my hands. The plates, ring and seal weigh 88 *tolas*."

The record is in Sanskrit prose throughout, except for three of the usual imprecatory verses at the end. It contains the pedigree (to be noticed below) of four Gaṅga kings, from Koṅgaṇivarman (the first of the line), here spelt Koṅgaṇivarman, which is a Tamil form,² to Mādḥava II,³ and announces a grant by the latter, to a Brahman named Kumāraśarman, of 65 paddy fields, having a sowing capacity of 27 *khaṇḍukas*, below the big tank of Paruvi in the Paruvi *riṣaya*. The only date given is the full-moon day of the month Chaitra. The engraver was Apāpa, son of the goldsmith Ārya.

Paruvi is the modern Parigi, 7 miles north of Hindupur in the Anantapur District, still noted for its capacious tank. Paruvi is mentioned in early inscriptions as the capital of the Bāpas; and in the time of the Chōla king Rājaraṣa I it was the chief place of the Parivai *nāḍu* in the Nulambavāḍi (i.e. Nalambavāḍi) district.

Dr. Fleet's opinion of the plates was as follows:—"In the characters, language and orthography the record stands all the usual tests, and its execution is good throughout . . . My conclusions about it are that we have here at last a genuine early Gaṅga record, and that on the paleographic evidence . . . A.D. 475 seems a very good date for it."

¹ The impressions were sent to me by Mr. Kṛishṇa Śāstri, with a request that I should publish the inscription in the *Epigraphia Indica*. But, finding that the late Dr. Fleet had already made preparations for doing so, I left it to him. He issued a preliminary notice in the *Journal of the Royal Asiatic Society* for July 1915, but appears to have got no farther. Hence, by the courtesy of the Editor, I have undertaken the task.

² The Beḍḍigānhaḷḷi plates have both forms.

³ More properly Mādḥava III, as the original Koṅgaṇivarman was also named Mādḥava. But I retain II in order to be in conformity with the heading given to the facsimile.

In its description of the kings it follows, with slight variations, that given in the majority of the Gaṅga copper-plate inscriptions, of which as many as thirty-nine are known and have been published, ranging in date from c. 240 to 939 A.D. (see list herewith). From about the year 650 stone inscriptions preponderate. But the present record contains certain fresh statements of special importance not elsewhere met with.

The pedigree as here given is as follows:—

Koṅkaṇivarman *dharma-mahādhirāja*,
(of the Jāhnavya (Gaṅga) *kula*, and Kāṇvāyana *gōtra*).
|
Mādhava *mahādhirāja*.
|
Gaṅga-rāja Āryavarman,
(installed by Siṃhavarman *mahārāja*, the Indra of the Pallava *kula*).
|
Mādhava *mahādhirāja* (of the Gaṅgas).
|
Siṃhavarman,
(Banner of the Gāṅgēya-*vaṃśa*),
(installed by Skandavarman *mahārāja* of the Pallavas).

As regards the two first steps all the Gaṅga plates are in agreement. But a Nagar stone inscription¹ informs us that Koṅkaṇivarman's name was Mādhava (I), the younger of two brothers, Daḍiga and Mādhava,² and that Mādhava (II), Kiriya Mādhava, was the son of Daḍiga, with whom the succession continues. In some plates Mādhava appears as Mādhavarman. The third king is in all the plates named Harivarman, which in the Tanjore plates has the Tamil form Arivarmā. But in the Beḍigāhalli plates we have Kṛṣṇavarman (with the prefix Śrī-vijaya, apparently only complimentary); and here we have Āryavarman (equivalent to Āryavarman). These are all variants of the same name Harivarman; for Kṛṣṇa is synonymous with Hari, and Ārya or Āryya may be intended for an improvement on Ari. It is with the fourth king that a discrepancy arises, when compared with the whole run of plates. For they with one accord give his name as Viṣṇugōpa (in the Kaḍagattūr plates Viṣṇugōpa, and in the Ganjam plates³ Biṣṇugōpa) and then bring in his son as Mādhava (III). The testimony of all the records being uniform as to Viṣṇugōpa at this point, his omission in the present plates has to be accounted for. With regard to his successor being Mādhava, there is no dispute; but he is distinguished in some cases as Taḍaṅgāla Mādhava (perhaps owing to a limp in his gait), and one record⁴ makes him Viṣṇugōpa's grandson, which may be correct and indicate that his actual father did not reign.

The most conspicuous occurrence of the name Viṣṇugōpa is in the Samudra-gupta inscription on the pillar at Allahabad, where he is introduced among the conquered kings as Viṣṇugōpa of Kañchi. He was thus a Pallava, and contemporary with Samudra-gupta, who belongs to the latter part of the 4th century. In Pallava inscriptions⁵ Viṣṇugōpa is mentioned along with Skandavarman and Siṃhavarman, who appear in the present record as being connected in a special manner with the Gaṅgas. But we here get no help from this source to explain the exclusion of Viṣṇugōpa.

¹ *EC*, VIII, No. 35.

² Dr. Fleet was disposed to combine them into one, named Daḍiga-Mādhava; but the dual form—*taṭ-sataṭ Daḍiga-Mādhava-nāmadhāyau*—shows that they were two, said to be a Rāma and Lakṣmaṇa.

³ *EC*, VII, Sh. 4.

⁴ *IA*, V, 60, 154.

Now all the Gaṅga plates describe Viṣṇugōpa in the same way,—as 'devoted to the worship of the twice-born, gurus and gods,' or 'gurus, cows and Brāhmaṇas.' Taking this statement into consideration, it seems to me that a simple explanation can be given to account for the omission of Viṣṇugōpa in the present plates. At the end of line 8 and the beginning of line 9 we have the phrase 'devoted to the worship of gods, twice-born and gurus,' with which the inscription goes on as if it were an attribute of Mādhava. But this is nowhere stated of Mādhava; on the other hand, it is the distinctive characteristic of Viṣṇugōpa, and of no other. It is evident then, I think, that Viṣṇugōpa was intended by the composer of the inscription to come here, in connexion with this phrase. But the engraver, whether for the purpose of saving space for the rest, or out of pure carelessness or misunderstanding, went on with it as if part of the description of Mādhava. Viṣṇugōpa thus dropped out.

Having disposed of this difficulty, we have now to consider the character in which the Pallavas appear in relation to the Gaṅgas, which is the novel feature of this record. Of the first two kings nothing of the kind is stated; but the third and fourth are said to have been installed (*abhishikṭa*) by Pallava kings, and this function¹ is described as performed *yathārham*, which may merely mean 'in due form,' or it may perhaps be intended to imply that the sanction of the Pallavas was customary, and indispensable to confirm the Gaṅgas on their thrones. Though, occurring as it does in a Gaṅga grant, the act may be considered as a friendly one, yet the adoption by Mādhava of a second name which was that of the Pallava king would usually be a sign of subordination. On the other hand, it must be noted that the name he took was not that of the king who crowned him, but that of his son. The only instances in which we find anything of the kind in connexion with the Gaṅgas are in the Sirigunda stone,² which says that Nirvīṇa's (i.e. Avinīta's) younger son obtained the Koṅgaṇi crown from the Pallava and Rāṣṭrakūṭa kings (superseding the rightful heir)—this was in the latter half of the 5th century: and in the early part of the 9th century, Śivamāra-Saigoṭṭa, on his release from captivity, was crowned by the Rāṣṭrakūṭa and Pallava kings³ with their own hands. We gather, therefore, that the Pallavas laid claim to be overlords of the Gaṅgas; but, if so, they only asserted the claim on rare occasions. Certain it is that no such relation is mentioned in any other Gaṅga grants as it is in this. It may be noted that in the case of the Kadambas, although the Pallavas installed the founder of the line in his kingdom,⁴ they are not afterwards referred to as overlords. Perhaps, therefore, they pursued the liberal policy of letting the quasi-dependent kings ordinarily follow their own course unimpeded.

We are here told that Āryavarman was installed by the Pallava king Śimhavarman, and that Mādhava (III) was installed by the Pallava king Skandavarman and had another name Śimhavarman. Now in the Pallava inscriptions already mentioned above we have the same names. First Skandavarman, then his son Viravarman, his son Śkandavarman, and his son Viṣṇugōpavarman or Viṣṇugōpa. The latter, as *Yuvamahārāja* or *Yuvārāja*, makes a grant in the reign of Śimhavarman, who may have been his elder brother or his uncle and the ruling sovereign. The second grant goes on to Śimhavarman, the son of Viṣṇugōpa. He may be the Śimhavarman of this inscription. If so, the Skandavarman may be his son, as we have no Skandavarman following a Śimhavarman, as here required. There are no precise dates that can be given for these kings; but undoubtedly they belong to the 4th century.⁵

¹ Sprinkling with consecrated water. Goldstücker, in the Dictionary he began, has 25 columns on the subject.

² *EC*, VI, Cm 50.

³ *Id.* IV, Yd 60; IX, Nl 60.

⁴ *Id.* VII, Sk 176; *NI*, VIII, 24.

⁵ A somewhat similar sequence, but with variations, occurs in two later Pallava grants, of perhaps the 8th or 9th century. But this seems to be merely an echo of the earlier genealogy in the grants above referred to. See Kielhorn's remarks on the subject in *NI*, III, 144. Also the list in *IA*, VIII, 290.

We have seen already that the Pallava Vishnugōpa is mentioned on the Samudra-gupta pillar. It is likewise interesting to note that his father Skandavarman is also said,¹ like the Gaṅga Vishnugōpa, to have 'honoured the gods, twice-born, gurus and old men.' Moreover, the phrase that 'his fame was tasted by the water of the four oceans,' stated of Harivarman, the Gaṅga Vishnugōpa's father, is found applied to Samudra-gupta.² The prefix *Śrī-vijaya* to the name of Kṛishṇavarman, the equivalent of Harivarman, is chiefly used in connexion with the Gaṅga-Pallavas, who, though Pallavas, claimed descent from Koṅgaṇi, the first Gaṅga. Mādhava (III), again, married the sister of the Kadamba king whose name was Kṛishṇavarman, and she was probably a daughter of the Kadamba king Kākusthavarman, who is said to have given his daughters in marriage to Gupta and other kings, which, it is plain, refers to Samudra-gupta, the only Gupta king who made an expedition to the south. These various items point still farther to the end of the 4th century, or beginning of the 5th, as the period of our inscription.

But by a remarkable coincidence more exact evidence can be adduced in support of this. For the manuscript of a Digambara Jain work in Sanskrit, named *Lōkavibhāga*, has been discovered by the Mysore Archaeological Department (see the Reports for 1909 and 1910), treating of Jaina cosmography. The contents, it says, were first delivered by the Arhat Vardhamāna, and handed down through Sudharma and a succession of other teachers. The *Rishi* Simha-sūri (or Simha-sūra) produced the work in a translation (? from Prākṛit into Sanskrit). And the *Muni* Sarvanandin formerly (*purā*) made a copy of it in the village named Pāṭalika in the Pāṇa-rāshṭra. The interesting point is that the precise date is given when this task was completed, namely, the 22nd year of Simhavarman, the lord of Kāñchi, and in 80 beyond 300 of the Śaka years. Two other manuscripts of the work have since been discovered, which give the same information. It is unnecessary to point out the supreme importance of this record; but Śaka dates of such early period are looked upon with suspicion. Dr. Fleet has published his views in full about this date. Having detected a flaw in the calculations of Prof. Śaṣipāla Jhā of Benares, who made it the 1st of March 458, he has decided that the real date is the 25th of August 458. In either case the year is the same, and this Simhavarman began to reign in Kāñchi in 436. As regards the Simhavarman of our inscription, the latest date so far obtained for Mādhava (III) is ? 390; but he must have lived to c. 430, when his son was crowned, being then an infant on his mother's lap. The near approximation of the two dates is evident; and that of the literary work furnishes a limit beyond which we need not go, while it seems to show that the name Simhavarman was a recurring one among the Pallavas of the period. Pāṭalika, the village in which Sarvanandin made his copy, may be Pāṭalipura, in the South Arcot District. The *Periya-purāṇam* makes it the seat of a large Jaina monastery in the 7th century. Pāṇa-rāshṭra is no doubt the territory of the Bāṇa kings.

TEXT.

Ib

- 1 Jitam Bhagavatā gata-ghana-gagan-ābhena Padmanābhena śrīmaj-Jāhnaveya-kul-āmala-
vyōma-bhā-
- 2 sana-bhāskarasya sva-bhuja-java-jaya-janita-sujana-janapadasya dāruṇ-āri-gaṇa-vidā-
raṇ-ōpa-

Svasti

¹ *Id.*, V, 51.² *GI*, No. 4, p. 27; No. 13, p. 54. "One of the habitual expressions applied always and only to Samudra-gupta," p. 14.

[illegible][illegible]

3 labdha-vraṇa-bhūṣaṇasya Kāṇvāyana-sa-gōtrasya śrīmat-Koṅkaṇivarṇma-dharmma-mahādhīrājasya pu-

4 trasya pītur-anvāgata-guṇasya nānā-śāstr-ārttha-sadbhāv-ādhipāma-praṇīta-chōṭī¹-viśē-
śaṣya nīti-śāstra-

5 sya vaktṛi-prayōktṛi-kuśāṣya samyak-prajā-pālana-mātr-ādhipāma-rājya-prayōjanasya
śrīmat(n)-Mā

IIa

6 dhava-mahādhīrājasya tasya putrasya anēka-yuddh-ōpalabdha-vraṇa-vibhūṣita-
śarīrasya nānā-

7 śāstr-ōtīhāsa-purāṇa-tatva-jūṣasya śrī-Pallava-kul-ōndrēṇa Śīṃhavarmma-mahārājēna
yathārham-a-

8 bhishiktasya Gaṅga-rājasya Āyyavarṇmanah putrēṇa pīṭṛi-paitāmāḥ(ha)-guṇa-sah-
yuktēna dēva-

9 dvijāti-guṇa-pājana-tatparēṇa dharm-ābhīyāsa-kṛita-matinā sva-bāhu-vīryy-ārjjita-
rājya-vibhāvēna

10 Gāṅgēya-varṇśa-dhvajēna sva-varṇśa-kramāgata-rājya-praṇītēna Pallavānāḥ śrī-
Skandavarṇma-mahā-

IIb

11 rājēna yathārham-abhishiktēna Gaṅgānām-Mādhava-mahādhīrājēna śrī-Sīṃhavar-
mmanah Brāhma-

12 pāya Vatsa-sa-gōtrāya Taittirīya-charaṇāya Kumāraśarmmanah yama-niyama-tapa[s*]-

13 svāddhyāya-yajana-yājan-ādhyayan-ādhyāpana-śēp-ānugraha-sāmarthyāya ādāna-prati-
grahā-

14 ya Chaitra-māsyāḥ tithau paurnamāsyāḥ Paruvi-vishayē Paruvi-mahā-tatā
k-ādhasat Karṇmaṭuva-kehā-

15 trē pañcha-shaṣṭi-kēdārāḥ saptaviṃśat-khaṇḍuka rāpāḥ brahmaḍāya-kramēp-ādhibhī
pradātāḥ

IIIa

16 yo-sya hartā sa pañcha-mahāpātaka-samyuktō bhavati || api-ch-ātra Manu-
gitāḥ ślōkāḥ [1*]

17 bahubhīr-vvasudhā bhuktā rājābhis-Sagarādibhīḥ [1*] yasya yasya yadā bhūmis-
tasya tasya tadā phalam [|| 1*]

18 svan-dātum sumahachohhakyān-dushkham²-any-ārttha-pālanam [1*] dānam vā
pālanam vēti dānēch-ōhrōyo-nupālanam [|| 2*]

19 svadattām-paradattām vā yō harēta vasundharām [1*] shashtim varsha-sahasrāpi
ghōrē tamasi varittatē [|| 3*]

20 iti suvarṇnakār-Āryya-putrēṇa Apāpēna likhitēyan-tāmra-paṭṭikā

TRANSLATION.

(Line 1) Om.³ Be it well.⁴ Success through the adorable Padmanābha, resembling (in colour) the clondless sky.

¹ Read *maṭi*.

² Appears as *dushkham* [*duṣkham*?—Ed.] in the original.

³ The spiral symbol here is supposed to represent this sacred syllable.

⁴ This word *Seṣatī* is in the margin, midway between lines 2 and 3.

A sun illumining the clear firmament of the Jāhnavi (or Gaṅga) *kula*, possessed of a territory of good people which sprang from the swift victory of his own arm, adorned with wounds received in cutting down the hosts of his cruel enemies, of the Kāṇvāyana *gōtra*, was His Majesty Koṅkaṇivarman *dharma-mahādhirāja*.

(Line 4) His son, inheriting the qualities of his father, having developed a special intelligence, by acquiring the meaning and essence of many sciences, skilled in the exposition and practice of the science of politics, having obtained the honours of the kingdom only for the sake of the good government of his subjects, was His Majesty Mādhava *mahādhirāja*.

(Line 6) His son, his body adorned with wounds obtained in many wars, knowing the essence of many *Śāstras*, *Itihāsas* and *Purāṇas*, duly installed by the Indra of the Pallava *kula*, Simhavarman *mahārāja*,—was the Gaṅga-rāja Āyyavarman.

(Line 8) By his son, uniting the qualities of his father and grandfather, devoted to the worship of gods, Brāhmanas and gurus, knowing how to act by the practice of justice, having the glory of a kingdom won by the valour of his own arm, the banner of the Gāṅgōya-vamśa, having acquired the kingdom descended in his own family, being duly installed by śrī-Skandavarman *mahārāja* of the Pallavas—Mādhava *mahādhirāja* of the Gaṅgas, śrī-Sinhavarman—to the Brāhman, of the Vatsa *gōtra* and Taittirīya *charaṇa*, Kumāraśarman, proficient in penance, fasting, mortification, silent prayer, sacrificing, conducting sacrifice, studying and teaching the sacred books, cursing and blessing, an acceptor and receiver of gifts, —on the full-moon day in the month Chaitra, were given, in the form of a Brāhman gift in the Karmaṭuva *kaṭētra*, situated below the great Paruvi lake in the Paruvi *viśhaya*, sixty-five fields, sowing twenty-seven *khaṇḍuka* (of seed).

(Line 16) Whoso takes away this becomes guilty of the five great sins. As to this also there are the *ślokas* uttered by Manu :—By many kings has the earth been enjoyed, Sagara and others. Whosoever at any time is the land, his is then the fruit. To make a gift oneself is very easy ; difficult the protection of another's. Of giving or protecting, than giving more excellent is protecting. Whoso seizes on land given by himself or by another, abides in dreadful darkness for sixty thousand years.

(Line 20) Thus is this copper plate, written by the goldsmith Āryya's son Apāpa. Ōm.

LIST of GANGA copper-plate INSCRIPTIONS.

	Name.	No. of plates.	Reference.	DATE.			King or Ruler.	Donee.	Engraver.	REMARKS.
				Śaka.	Regnal.	A. D.				
1	Nandi (1)	3	MAB, 1914	...	...	c. 240	Madhava (II)	Brāhman	Śrīpāla	
2	Bepdighatalli	4	" 1915	...	1	...	Kṛṣṇavarman	"	Mātrivarmaṇ	
3	Tanjore	3	IA, viii, 212	169	...	247	Arivarmaṇ	"	Viśvakarma- Achārya.	
4	Tagaḍūr	3	EC, iii, Nj 123	188	...	? 266	Hacivarmaṇ	Gāvaṇḍa		Inscribed on back of Pl. 1 of this Bāga grant and effaced. Pl. 5 is blank.
5	(Madayanūr)	5	" x, Mb 157; IA, zv, 172.	201 (Bāga)	23	338	"		Nandivarma- Achārya.	At first called the Harbhara plates.
6	Tāgarti	3	" vii, Sk 52; IA, vii, 172.	? 279	...	? 367	Tadāṅga Madhava (III)	Gavaṇḍa		...
7	Nopamasgala (1)	3	" x, Mr 73	...	13	c. 370	Madhavavarman	Jain temple		Pl. 2 missing.
8	Melekoṭe	5	MAB, 1910	...	...	c. 390	"	Buddhist	Chārudatta	A genuine Gaṅga grant of ? c. 476 (Fiset).
9	Penugonda	3	MER, 1914; JRAS, 1916.	...	...	c. 400	Madhava (III); Sinha- varman.	Brāhman	Apāpa	
10	Nopamasgala (3)	4	EC, x, Mr 72	...	1	c. 430	Koṅṭapivarmaṇ (Avin- nīla).	Jain temple	Mārisheṇa	
11	Śrīgēri	5	MAB, 1916	...	2	431	Koṅṭapivarmaṇ (Avin- nīla).	Brāhman	Pāpāra	
12	"	...	" "	...	...	...	Senior Queen	"		Follows, on Pl. 5.
13	Bangalore Resi- dency.	6	" 1911	...	25	455	Koṅṭapī (Avinīla)	"	Mārgi	Pl. 2 missing: Pl. 5 may belong to an- other grant (see MAR, 1911, para. 72).
14	Malibhūḷi (1)	3	EC, ix, DB 67; IA, v, 186.	...	29	459	" (")	"		

LIST of GANGA copper-plate INSCRIPTIONS.

Name.	No. of plates.	Reference.	DATE.		-King or Ruler.	Donee.	Engraver.	REMARKS.
			Śaka.	Regnal. A.D.				
16 Merikāra . . .	3	EC, i, Cg 1; IA, i, 362	388	...	Koṅgaṇi (Avinīta)	Jain temple	Viśvakarma	Grant by Akalavaraha's <i>maṇḍir</i> (a).
16 Bangalore Museum	5	" ix, Bn 141	...	3	" (Duvvīnīta)	Brāhmaṇa .	...	Pl. 5 missing.
17 Kadagattūr . .	5	" xii, Ml 110	...	4	" (")	"	Chakkana	At first called the Madanagiri plates.
18 Uttanūr (1) . .	5	MAR, 1916	...	20	Duvvīnīta .	48 Brāhmaṇa	Koṅgaṇi Per- dattāra.	
19 Uttanūr (2) . .	5	" 1917	...	20	"	80 "	"	
20 Mallakallī (2)	5	EC, x, DB 68; IA, v, 138	...	35	Koṅgaṇividdha (Duvvīnīta).	Brāhmaṇa	...	
21 Gummareddipura .	5	MAR, 1912	...	40	Duvvīnīta .	"	Koṅgaṇi Per- dattāra.	
22 Hebbūr . . .	5	EC, xii, Tm 23	...	c. 680	Nava-Kāma (Śivamāra)	"	...	Pl. 3 and 5 missing.
23 Hallegere . . .	5	" iii, Md 113	635	34	Prithivī Koṅgaṇi Śivamāra.	Brāhmaṇa .	Viśvakarma- Acharya.	Grant by request of the two sons of the Pallava <i>yuvorāja</i> .
24 British Museum .	7	IA, xiv, 229	...	...	Nava-Kāma .	"		Grant by Erenganga.
25 Nandi (2) . . .	3	MAR, 1914	...	3	Prithivī Koṅgaṇi (Śrī-purusha).	"		King has the title of Bagabhaṇa.
26 Sargūr . . .	5	EC, iv, Hg 4	...	...	Prithivī Koṅgaṇi (Śrī-purusha).	12 Brāhmaṇa	Kuṇḍ-Acharya .	
27 Kondaḷḷi Agrahāra	5	MAR, 1907	...	7	Śrīpurusha .	Brāhmaṇa .	Viśvakarma- Acharya.	Ranavikramarasa (Vijayāditya), governing (? Kereḷ) <i>naḍa</i> .
28 Jāvali . . .	6	EC, vi, Mg 36	672	25	Prithivī Koṅgaṇi Śrī-purusha.	"	Viśvakarma- Acharya.	

EC, *Epigraphia Carnatica*; BI, *Epigraphia Indica*; IA, *Indian Antiquary*; JRAS, *Journal of the Royal Asiatic Society*; MAR, *Mysore Archaeological Report*; MEE, *Madras Epigraphical Report*.

LIST OF GANGA copper-plate INSCRIPTIONS.

Name.	No. of plates.	Reference.	Date.		King or Ruler.	Dosee.	Engraver.	REMARKS.
			Saka.	Regnal.				
29 Islāmpūr . . .	5	El, xii, 48 . . .	...	30	Prithivi Kōṅgaṇi Śrī-puraṇa.	Brāhman .		Grant by Vijayāditya when at Aṇandi.
30 Hoṣṭr . . .	5	EG, x, Gd 47; Mad. J60L, 1878.	684	...	" "	" "	Vivakarman .	
31 Dēvarhaji . . .	6	" iv, Ng 85; 1A, ii, 155, 370.	698	50	" "	Jain temple .	Vivakarman .	At first called the Nāgamaṅgala plates.
32 Maṇḍe (1) . . .	7	" ix, N1 60 . . .	719	...	Mārasinha Lōka-Trideva Yavarāja.	" "	Vivakarman .	
33 Gaṇjīm . . .	5	" iv, Sr 160 . . .	...	...	Mārasinga Kreyappa Lōka-Trideva Yavarāja.	Brāhman .		With his permission, grant by a Pallava.
34 Chik-Ballāpur . . .	3	MAR, 1914 . . .	...	17	Jayateja Dattiya .	Śiva temple .		The date is that of the Rāshtrakūṭa Prabhūlavarsha Jagat-tunga.
35 Maṇḍe (2) . . .	5	" 1910 . . .	720	12	Satyavākya Kōṅgaṇi-varman Rājamaṇa.	Brāhman .	Madhurōvajha .	
36 Gaṇḍekere . . .	5	BC, iv, Yd 60 . . .	...	...	Rapavikramayya (Nīlīmarga I).	" "	Marikēḷi .	
37 Narasipura . . .	7	" v, K1 90 . . .	824	...	Rājamaṇa Satyavākya .	Jain temple .		
38 Gaṭṭavāḍḍipura . . .	9	" xii, Nj 269 . . .	826	...	Rājamaṇa Satyavākya and Nīlīmarga (Ereyappa).	Brāhman .	Vivakarman .	Pl. 1 and 3 missing.
39 Saḍḍi . . .	5	El, iii, 164 . . .	860	...	Bātuga Nanniya Gaṅga .	Jain temple .		Date may be 988.

NO, *Epigraphia Carnatica*; EL, *Epigraphia Indica*; IA, *Indian Antiquary*; JHAS, *Journal of the Royal Asiatic Society*; MAR, *Mysore Archaeological Report*; MER, *Madras Epigraphical Report*.

This array of documents provides us with the inscriptional chronicles of the Gaṅga kings of Gaṅgavāḍi, or Mysore. They have been found in all parts of the country, and of various dates throughout the period to which they relate, a period for which but for them the local history is a blank. They present a consistent and consecutive account, not discredited by contradictory statements or anachronisms. They are supported and confirmed by scores of stone inscriptions of all periods, and by references in contemporary records of neighbouring and other dynasties. They are thus entitled to acceptance as credible and authentic, though it would be unreasonable to expect that chronicles for so extended a period of antiquity should be free from all difficulties.

Objections have been raised to them, by Dr. Fleet, who prefixed the epithet 'spurious' to the whole series, and this has been simply repeated by others, following his authority. But the grounds of his opposition mainly relate to faults that may be in some cases detected in style or orthography. These, however, are not such as to affect the veracity of their contents. The basis of his sweeping dictum that all the Gaṅga inscriptions on copper plates are 'spurious,' and only those on stone genuine, is on the face of it unsound and paradoxical. Why should a line of kings issue chronicles of their past which are true and to be accepted as such when on stone, but false and to be rejected when on metal? Especially when, as here, such stone inscriptions as have survived, even for the early periods, confirm, so far as they go, the accounts on the metal plates, which, being portable and indestructible, have more easily been concealed and preserved. In fact, it is not uncommon for a stone inscription to state that the grant recorded in it was also engraved on a copper plate.

Then a condemnation, perhaps for a discrepancy in the week day of the date, as sometimes happens, is not a sufficient reason for rejecting them as altogether false. Dr. Fleet has himself said that 'the fact that a date has been recorded accurately does not prove the authenticity of a record, any more than an incorrect date proves that the record in which it is put forward is spurious.' This completely cuts away the ground from under the feet of those who insist unduly upon the value of such testimony, though it is not to be disregarded.

As regards the palaeography, again, although changes have undeniably taken place in the forms of certain letters from time to time, it is impossible to draw a hard and fast line, as Dr. Fleet does at the year 804, for instance, and to lay it down that a particular form cannot occur before that, in which particular he has been shown to be incorrect. The standards, therefore, by which he proceeded to judge the Gaṅga copper plate grants and reject them as 'spurious' were themselves in need of revision and correction. Approaching these grants with preconceived ideas, if he found that the facts did not support his views,—well, so much the worse for the facts.¹

It might seem desirable here to recapitulate the history of the Gaṅgas, as derived from the numerous inscriptions on metal or stone which have been brought to notice. But for this information I may refer, for the present, to my work '*Mysore and Coorg from the Inscriptions*' and to my revised edition of *Coorg Inscriptions* in the New Imperial Series of the Archaeological Survey of India.

¹ There seemed to be a sense of some personal annoyance in the matter, for he says his difficulty was 'to put himself in the frame of mind from which they can be imagined to be genuine.' He even saw nothing strange in writing to me—'If you will only give up the Gaṅgas, I will do anything you like for you'!

A somewhat similar state of things is met with elsewhere. For Canon Isaac Taylor, in his book '*The Alphabet*,' refers to Prof. Mahaffy's complaint that even eminent English Hellenists are found to be helpless in face of a Greek inscription. Mr. Paley, on first becoming acquainted with the inscription at Abu Simbel, the cardinal monument of Greek epigraphy, finding he could not reconcile it with his Hellenic studies, pronounced the whole thing a bore!

No. 25.—THE KANUMA GRANT OF SADASIYA-RAYA : SAKA 1470.

By S. V. VISWANATHA, M.A., MANNARGUDI.

The inscription is on five copper-plates, which are bored at the top so as to admit a ring holding the plates together. The latter are in good preservation. They are now in the possession of the Collector of Anantapur. They were obtained and sent to me for publication by Rao Sahib H. Krishna Sastri, who has noticed these in his Report on Epigraphy for 1915, pp. 9 (No. 9) and 112.

The plates measure 10½ in. by 7½ in., except in the middle, where the height is greater on account of the arch at the top. The holes through which a ring is intended to pass have a diameter of 6 in. The rims of all the plates are slightly raised. The writing runs across the breadth of the plates, and is quite legible. The first and the last plate are engraved only on one side. The inscription contains 241 lines in all. The plates are numbered in Telugu numerals. I am supplied with the following further information about the plates from the office of the Assistant Archaeological Superintendent for Epigraphy, Madras:—

"The plates are strung together on a circular ring of the same metal, which is 3" in diameter and about 1½" in thickness. It bears on it a sliding signet ring to which is fixed a circular seal, whose diameter is about 1½". The seal bears on a countersunk surface the following, which are the prevailing features of all Vijayanagara seals: (1) *Top-row*: the crescent to the proper right and the sun to the left; (2) *Middle-row*: a boar standing on a platform and facing the proper right with a dagger in its front, pointing downwards; and (3) *bottom*: a floral device, probably a blown lotus, on which the platform of (2) rests. The plates with the ring and the seal weigh about 431 tolas."

The language of the inscription is Sanskrit, and the whole is in verse, except the Telugu portions in plates Nos. 3, 4 and 5, which give the distinguishing marks of the boundaries and the signature. The characters are Nandināgarī, except in the case of the signature, which is in Telugu. There are a few orthographical peculiarities worth noticing. Instances of unnecessary *anusvāra* and *visarga* have been noted in the footnotes to the text. As in other Vijayanagara grants, there is confusion here also between the use of *sa*, *śa* and *sha*. Instances of this are:—*Sambharā* for *Sambhavarā* (l. 2); *Kaṇḍalyā-śrī-Sumitra* in place of *Kaṇḍalyā-śrī-Sumitra*° (l. 19); °*situ* instead of °*śitu* (l. 27); °*rāsi* for °*rāśi* (l. 40); *śaṁśōya* instead of *śaṁśōsha* (l. 41); *śaṁśam-ātya* in place of *śaṁśam-āśya*° (l. 47), etc. The vernacular sound *r* is represented by an *r* sign added over the consonant *r*, e.g. *māru* in l. 75. Long *t* is represented in one place by a vertical stroke and a loop over short *i*, as if *i* were a consonant.

The inscription records the grant of the village of Kanuma by Sadāsiva-Mahārāya of the Second Vijayanagara dynasty to several learned Brahmans of various *gōtras* and *śākhās*. The grant was made at the request of Appalarāja, the son of Krishnarāya and grandson of Timmarāja, of the Kāśyapānvaya, i.e. the Solar race. It was made in the presence of the god Viṭṭhalēśvara, on the banks of the Tungabhadra river. Kanuma, we are told, is situated in Mundimadugu *śimā*, a division of the Gutti *calita*. The boundaries of the object of the grant and the marks of identification thereof are clearly described in Telugu, the *Dēśa-bhāṣā*, as it is called in the inscription. The terms of the grant are the same as those found in other grants of the Vijayanagara house. One peculiarity to be noted about this is that the village granted is divided equally between the god Chennakēśava and the Brahmans, one-half going to each. A half is thus left as the property of the temple, while the other portion is split up into 30 *vṛttis*, to be divided among Brahmans, 2 *vṛttis* being set apart for the daily worship of the god. The grant is made for the performance of 16 kinds of worship (*śhōḍaś-ōpachāra*) to the god Chennakēśava. Of all the kings of the Vijayanagara dynasty Sadāsiva seems to have favoured the Vaiṣṇavite religion most.

The date of the grant is given (ll. 82-83) in the numerical words *avatār-śāga-vēd-ēndu*, i.e. 1470. Thus the record is dated in the Śaka year 1470, corresponding to 1548 A.D., Kṛitika, the month Āṣāḍha; the bright fortnight; Prathama-dvādaśī and Sunday. The Śaka year 1470 is the earliest date for Sadāśiva that can be fixed from the copper-plate inscriptions known so far, though the earliest stone inscription of his time that has been examined is dated in the Śaka year 1467. Thus the grant is of importance, as it is the earliest of the copper-plate grants of Sadāśiva yet discovered.

Among the names of personages appearing in the grant the most important is that of Rāmarāja, the Karaṇṭha minister and brother-in-law of the king. Sadāśiva bears the usual titles, of which *Gaj-augha-gaṇḍa-bhēruṇḍa* deserves notice. In 'South Indian Images of Gods and Goddesses' by Rao Sahib H. Krishna Sastri (p. 268) there is an interesting picture of a mythological bird, with two heads. It is seen in the picture to carry elephants in its talons and beaks.

Appalarāja, the son of Kṛishnarāja and grandson of Timmarāja, at whose request the grant was made, is stated to be of the Kāśyapa *gōtra*, Āpa-tamba *sūtra* and the Solar race.

The names of the composer and the engraver appear as usual after the imprecatory verses at the end. It is interesting to note that the engraver and his father are known by the same name. It has been the custom among Hindus that the grandson is given the name of the grandfather. The names of the father and son are identical in rare instances. Mallāṇa appears as the father of Vīraṇa in the Unamañjēri Plates of Achyuta-Rāya (above, Vol. III, p. 151) and in the Conjeeveram Plates of Kṛishna-Rāya (*ibid.*, Vol. XIII, p. 126).

Table of Donees.

Verse.	Name.	Father's name.	Gōtra.	Vēda or Sūtra.	No. of epittis.
66	Vishṇu ¹		...	...	2
67	Śingari Dikshita	Munyaugy-Appalē-Bhaṭṭa	Kāśyapa	Yajus	1
68	Narasimha	Siddhi Timmā-Bhaṭṭa	Bhāradvāja	Do.	1
69	Akkalē-Bhaṭṭa	Vēdam Rāghava-Bhaṭṭa	Vādhūla	Do.	1½
70	Yāndāṭi Narasimha	Nāra-Avadhānin	Kauṇḍinya	Do.	1
71	Purushōttama-Bhaṭṭa	Siddhi Tirumalārya	Bhāradvāja	Do.	1
72	Jambā-Bhaṭṭa	Munnāngi-Appalē-Bhaṭṭa	Kāśyapa	Do.	1
73	Beavvā-Bhaṭṭa	Vasanta-Bhaṭṭa	Kauṇḍinya	Do.	1
74	Munnāngi Narahari	Śingari Yajvan	Kāśyapa	Do.	1
75	Sōma-Bhaṭṭa	Siddhi Timmā-Bhaṭṭa	Bhāradvāja	Do.	1
76	Narasimha	Śirikuppa Timmā-Bhaṭṭa	Kausika	Do.	1
77	Kṛishna-Bhaṭṭa	Uṭukūru Timmā-Bhaṭṭa	Ātrēya	Do.	2
78	Timmā-Bhaṭṭa	Śirukuppa Timmā-Bhaṭṭa	Kausika	Do.	1
79	Mallu-Bhaṭṭa	Vaddamāni Lingaṇ-Bhaṭṭa	Śrīvatsa	Do.	1

¹ [Probably Kṛṣṇanātha mentioned in l. 110 was the name of the priest in the temple of Cheppakṣāra.—H. E. S.]

Table of Donees—contd.

Vers.	Name.	Father's name.	Gōtra.	Vēda or Sūtra.	No. of <i>vr̥ttis</i> .
80	Gauru-Bhaṭṭa . . .	Timmāpuram Timmā-Bhaṭṭa .	Agastya .	Bahvricha .	1
81	Janārdanārya . . .	Vaddamāni Liṅgā-Bhaṭṭa .	Śrīvatsa .	Yajus .	1
82	Anbhalay[y]a . . .	Varidaḍu Narasayya . . .	Kauṣika .	Bahvricha .	1
83	Phaṇi-Bhaṭṭa . . .	Śiruguppa Timmā-Bhaṭṭa .	Do. . .	Yajus .	†
84	Timmā-Bhaṭṭa . . .	Dēvarakoṇḍa Sūri-Bhaṭṭa .	Harita .	Do. . .	1
85	Nārāyaṇa-Bhaṭṭa . . .	Chippagiri Rāghava-Bhaṭṭa .	Vaasiṣṭha .	Bahvricha .	1
86	Chakrapāṇi . . .	Timmāpuram Tirumalārya .	Agastya .	Do. . .	1
87	Timmā-Bhaṭṭa . . .	Rāchūri Timmā-Bhaṭṭa .	Kāśyapa .	Yajus .	1
88	Nigā-Bhaṭṭa . . .	Kūkaṭamkoṇḍa Dādi-Bhaṭṭa .	Kutas .	Do. . .	1
89	Giri-Bhaṭṭa . . .	Śiruguppa Timmā-Bhaṭṭa .	Kauṣika .	Do. . .	†
90	Koṇḍu-Bhaṭṭa . . .	Timmā-Bhaṭṭa . . .	Bhāradvāja .	Do. . .	1
91	Chikka-Purushōttama . . .	Siddhi Timmārya . . .	Do. . .	Do. . .	1
92	Pārvaṭinātha . . .	Mahidhara Bhairava . . .	Do. . .	Do. . .	1†
93	Kēśava-Bhaṭṭa . . .	Maṇimaṇi Anbhala-Bhaṭṭa .	Do. . .	Do. . .	†
94	Veṅkaṭay[y]a . . .	Bukkarāyasaṃmudram-Appa-Koṇḍa .	Do. . .	Dāhyāyana .	1
95	Śri-Koṇḍa Rāmā-Bhaṭṭa .	Brahmā-Bhaṭṭa . . .	Kauṇḍinya .	Yajus .	1
96	Mādhava . . .	Vāraṇāsi Koṇḍu-Bhaṭṭa . . .	Kāśyapa .	Do. . .	†
97	Anbhala-Bhaṭṭa . . .	Purāṇa Anbhala-Bhaṭṭa . . .	Harita .	Do. . .	†

TEXT.

[Metres : vv. 1-4, 6-8, 12, 13, 19, 20, 37-41, 43-98, 101-105, *Anuṣṭubh* ; vv. 5, 21, 25, 29, 30, 32, 33, 35, 42, *Śārdūlavikr̥tā* ; vv. 10, 11, 15, 16, 17, 18, 22, 23, 34, *Śragdharā* ; v. 9, *Hāriṇī* ; v. 36, *Dōdhaka* ; vv. 14, 28, *Upajāti* ; vv. 24, 26, 1-5, *Mālinī* ; vv. 27, 31, *Indravajrā* ; v. 99, *Giti* ; v. 100, *Pushpitāgrā* .]

(Verses 1-25, ll. 1-51, giving the genealogy, are omitted, since they repeat practically verbatim what is stated in another Vijayanagara grant, edited *supra*, Vol. IV, pp. 12-14.)

Plate I.

- 52 भुजवीर्योदायभूरचुतेंद्रः । [२६*] चितिप्रतिष्ठापितकोर्त्तिदेहे प्राप्ते पदं
वेणवमचु-
- 53 तेंद्रे । अध्यास्य भद्रासनमस्य सुमुखोरो वभौ वेंकटदेवरायः । [२७*]
प्रयास्य राज्य

- 54 प्रश(स)वास्तरूपे विह्वलिधौ वेंकटरायभूषे । अभागधेयादचिरात्प्रजानामाखं-
 55 डलावासमथाधिरुटे । [२८*] तिमांवावरगर्भमौक्तिकमणौ रंगक्षतीद्रात्मजः । ज-
 56 त्वालंकरणेन पालितमहाकर्णाटराज्यत्रया । शौर्यौदार्यदयावता स्वभगिनो-
 57 भर्त्ता जगन्नायिना^१ रामस्मापतिनाप्यमात्यतिलकैः कृपाभिषेकक्रमः । [२९*]

श्रीवि-

- 58 द्यानगरीललामनि महासां(सा)म्राज्यसिंहासने । संतानदुरिव स्फुरस्फुरगिरी
 59 संहृत्य विदेपिणः । आ सेतोरपि चाहिमाद्रि रचयन्नाज्ञो निजाज्ञात्करां ।
 न्मर्वा^२ पा-

- 60 लयते सदाशिवमहारायचिराय क्षमां । [३०*] विख्यातविक्रांतिनयस्य
 यस्य पट्टाभि-
 61 पेक्षे नियतं प्रजानां । आनंदबाष्पैरभिषिच्यमाना देवीपदं दर्शयते
 धरित्री । [३१*]
 62 गोत्रीहारविशारदं कुवलयपीडापहारोदुरं सत्यायत्तमर्ति समस्तसुमन-
 63 स्तोमावनेकायनं । संजातच्छृतिभूरुचिं सविजयं संनंदकन्धीभरं यं शंसंति
 64 यशोदयांचितगुणं कृष्णावतारं बुधाः । [३२*] विख्यातं बहुभोगशृंगविभवैरुहा-

Plate II, Side ii.

- 65 मदानोदुरं धर्मेण क्षृतिमात्रतोपि भुवने दत्तं प्रजारचणे । प्राप्तां यस्य
 66 भुजं भुजंगमहिभृद्दिग्दंतिकूर्मोपमं पातिव्रत्यपताकि[कि]ति धरणीं
 67 जानंतु सर्वे जनाः । [३३*] यस्ते^३नाधूलिपाली स^४कमशक[स]मुच्चाटनं^५
 धूमरेखा रो-
 68 माली कीर्तिवध्वा इव भुवनमिदं सर्वमंतर्वहत्याः । व^६णी नाणोयसीव प्रकटि-
 69 तविहृतवीरलक्ष्म्या रणाणे । शान्ति(त्वे) जौमूतपद्भिः^७ किल सकल[खल]^८स्तोम-
 दावानलानां । [३४*]
 70 तुंगामेव दयां पदांबुजयुगं शोणं च कृष्णां तनुं रक्तानीलशितां^९ त्रिवेणिमन-
 71 वा वीक्षां गिरं नर्मदां [१*] तीथा^{१०}नीति समावहत्त्वयवैः शेषाद्रिवासो
 विभुः (१) प्रा-
 72 यो यस्य विशेषभक्तिसुदितः पट्टाभिषेकत्रये । [३५*] वो^{११}धधिपत्युपमा-
 यितगंड-
 73 स्तोषणरूपजितासमकांडः । भाषेगेतप्यवरायरगंडः पोषणनिर्भर-
 74 भूनवखंडः । [३६*] राजाधिराजविरुदो राजराजसमा(मां)हतिः । स्वाराज(ज्य)राज-
 75 मानश्री[ः]^{१२} श्रीराजपरमेश्वरः । [३७*] मूर्धरायरगंडांको मेरुलंघियशोभरः । श-

^१ Read अ.

^२ Read म.

^३ Read "विद्मन्तौ."

^४ Read सा.

^५ Read निजाज्ञाकरात्करान्

^६ Read जे.

^७ Read जौमूतपद्भिः.

^८ Read तीथां.

^९ Read रवे.

^{१०} Read ये.

^{११} Read "सितां."

^{१२} Read श्री.

- 76 रणामतमंदार¹ परराजभयंकरः । [३८*] करदाखिलभूपासः परदारसहोदरः ।
 77 हिंदुरायसुरत्राणः इंदुवंश[श*]खामणिः² । [३८*] घञौघगंडमेरुंडो
 हरिभक्तिसु-
 78 धानिधिः । वर्धमानापदानत्रोरधनारीनटेश्वरः । [४०*] इत्यादिविरुदैर्वदि-
 79 त्व³ नित्यमभिष्टुतः । कांभोजभोजकालिंगकरहाटादिपार्थिवैः । सोविहं-
 80 क्षपदं प्राप्ते(सै)ः संदर्श⁴तनृपोपदः । [४१*] सोयं नीतिविशारदः सुरतरु-
 स्पर्धालवि-
 81 आणनः (i) सर्वोर्विशिनतः सदाशिवमहारायचमानायकः । बाह्वावंग-
 दर्विशेषम-
 82 खिलां सर्वसहामुहहन्विहतातंत्राण⁵परायणो विजयते वीरप्रतापोक्षतः । [४२*]
 83 अवतारांगवेदेदुगणिते शकवत्सरे । वत्सरे कीलकाभिख्ये भासि चाषाढना-
 84 मनि [४३*] पचे व[क]चे प्रथमद्वादश्यां भानुवासरे । तुंगभद्रानदीतीरे विठ्ठलेश्वर-
 85 संतिष्ठौ । [४४*] वंदारुमंदिराकिंदमंदारधरणीरुहं । वंदारकाकिरीटांशुसंदानि-
 86 तनखेंदवे । [४५*] इंदिराया जगन्नातुमं(मं)दिरायितवचसे । श्वं(कं)द-
 सामादिकंदाय चंप-
 87 कद्वि(द्यु)तिवाससे । [४६*] कैवल्यकल्पलतिकाकंदलोपप्लकोत्तये । कालचक्र-
 घटीयत्र(न्र)क-
 88 स्पर्नाशित्यकारिणे । [४७*] कौस्तुभारुणपाथोजपाश्व(र्ष)लीनालिमालया ।
 वनमालिकया
 89 चारुवचसे इतरचसे । [४८*] ओमुंडिमडुगुग्रामे सांनिह्यं समुपेयुषे ।
 चैनकेशव-
 90 देवाय चंद्रचंडांशुचक्षुषे । [४९*] विधातु¹⁰ षोडशविधैरुपचारैरुपासनां ।
 नानाशाखा-
 91 भिभागोवसूत्रेभ्यश्चास्त्रवित्तया । विख्यातेभ्यो हिजातिभ्यो वेदविद्भ्यो विशेषतः ।
 [५०*]¹¹श्री-
 92 गुत्तिवलिते मं(मुं)डिमु(म)डुगुख्यातसोमनि । पिनाकिनीस्त्रले चापि पावने
 विहितस्त्रि-
 93 तिं । [५१*] प्राचीं शिरिवराभिख्ययामकाहिशमाश्रितं । ख्यातात्कलमडि-
 यामाहृत्ति-
 94 णस्यां दिशि स्थितं । [५२*] ग्रामां¹²नागलगुह्या(ह्वा)ख्यादाश्रितं पश्चिमां
 दिशं । आकिलेरुव-

¹ Read मंदारः.² Read शिखामणिः.³ Read न^०.⁴ Read तया.⁵ Read कांभोज.⁶ Read सोविहं.⁷ Read शि^०.⁸ [This verse is made up of three half-verses since in l. 77 the plates omit विष्टपचयविख्यातो दुष्टग्राह्यलमर्दचः which we find, however, in the Krishnapuram Plates (above, Vol. IX, p. 335, text-line 97.—H. K. S.)]⁹ Read "सुपाव"¹⁰ Read तु.¹¹ V. 40 has three half-verses.¹² Read "नागा".

95 रघामादुत्तरां दिग्मात्रितं । [५३*] नरसंसु^१मुद्राख्यामपरां समुपात्रितं ।
ग्रामं

96 कनुमनामानं सर्वसंस्थोपशोभितं । [५४*] सर्वमान्यं चतुस्त्रीमासंयुतं च

Plate III, Side i.

97 समंततः । निधिनिक्षेपपाषाणसिद्धसाद्वज्रलान्वितं । [५५*] अक्षिखानामिसं-

98 युक्तं गणभोग्यं समूहं । वापीकूपतटाकैश्च कच्छा(च्छा)रामैश्च संयुतं ।
[५६*] आचंद्र-

99 तारकं भोग्यं(स्थ)मपि देवेन भूसुरैः । दानाधमनविक्रीतियोग्यं विनिमयोचि-
100 तं । [५७*] श्रीचैनकेशवायार्हमर्हं विप्रैश्च इत्यपि । प्रकल्पिता(त)व-
ता(तो) ग्राम(मं) पाकशास-

101 नतेजसः । [५८*] काश्यपान्वयदीपस्य काश्यपीकल्पशाखिनः ।
वैरिवारणसिंहस्य

102 वरापस्तवसूत्रिणः । [५९*] सूर्यजनवनसूर्यस्य सूर्यवंशशिखामणेः । सर्व-
धर्मरहस्या-

103 त्र्यंसारविज्ञानशालिने(न): । [६०*] ख्याताप्रतीकमन्त्रैरुविहृदस्य महस्विनः ।
श्रीतिम[राज*]-

104 पौत्रस्य चिन्तारत्नस्य धीमता । सूनोः कृष्णमराजस्य सूनृतालापशोभिनः ॥

105 श्रीमदप्यलराजस्य विश्रुतिमनुपालयन् । [६१*] परीतः प्रयतैः स्निग्धैः
पुरोहित-

106 पुरोगमैः । विविधैर्विबुधैः[*] श्रीतपयिकैरधिकैर्गिरा । [६२*] सदाशिवमहारायो

107 माननीयो मनस्विना । सच्चिरक्षपयोधारापूर्वकं दत्तवान्मुदा । [६३*]
ग्रामेक्षिन्विनु-

108 तेषारक्तपाकूपारचक्षुषः । चैनकेशवदेवस्य विष्णोरर्हं विनार्पितं [६४*] । वि-

109 प्राप्यते^२ विभक्त(क्ते)र्हं त्रिशद्वृत्तिसमसमश्रुते^३ । वृत्तिमंतो विलिख्यंते विप्रा

110 वेदांतपारगाः । [६५*] श्रीमत्केशवनाथाय ग्रामदेवाय विष्णवे । विधातुं
प्रत्य-

111 हं पूजां वृत्तिद्वयमिहार्पितं । [६६*] श्रीमुन्वंग्यपति^४भट्टसूनुः काश्यप-
गौत्रजः ।

112 अश्रुते याज्ञुषीवार्हवृत्तिं शिंगरिदौक्षितः । [६७*] भारद्वाजान्वयस्त्रि-
तिमाभट्ट-

^१ Read 'संसु'.

^२ Read 'पति'.

^३ [Read 'श्री' 'समश्रुते'—H. K. S.]

- 113 तनुद्वयः । नारसिंहसुधीरेकां वृत्तिमवैति याजुषः । [६८*] वेदंराघव-
भट्टस्य सू-
114 तुवाधूलगोत्रजः । याजुषोवाकलेभट्टसुधीस्त्रैकवृत्तिकः । [६९*] यांदाटिनर-
115 सिंहाख्यसुधीः कौडि(डि)न्यगोत्रजः । नारावधानिजोवैकां वृत्तिमाप्नोति या-
116 जुषः । [७०*] दारद्वान्वया(य)स्त्रिद्विभ्योमतिरुमलार्यजः । पुरुषोत्तमभट्ट-
स्यो^१ याजु-
117 पोवैर्क^२वृत्तिकः । [७१*] काश्यपान्वयोजो^३ मुनंम्यप्यलेभट्टनंदनः । जंवा-
भट्टो या-
118 जुषोत्वर्द^४वृत्तिमत्र समश्रुते । [७२*] सुनुर्वसंतभट्टस्य कौडि^५न्यान्वयसं-
भवः । मनी-
119 षो वश(स)वाभट्टो याजुषोवावृत्तिकः । [७३*] मुनंगिर्ग्रीचीनरहरिस्सुधीः
काश्यपगो-
120 वजः । याजुषोवाश्रुते वृत्तिमिकां शिंगरियज्वजः । [७४*] भारद्वाजा-
न्ययस्त्रिद्वि-
121 माभट्टस्य नंदनः । सो^६भट्टो भवत्वेकवृत्तिमानत्र याजुषः । [७५*]
याजुषश्शिरिकु-
122 प्यश्रोतिमाभट्टात्मसंभवः । नरसिंहसुधीचैकवृत्तिकः कौशिकान्व-
123 यः । [७६*] आत्मभृकुटुक्श्रीतिमाभट्टस्य याजुषः । कृष्णभट्टोश्रुते वृत्ति-
124 द्वयमात्रेयगोत्रजः । [७७*] याजुषश्शिरिकुप्यश्रोतिमाभट्टतनुद्वयः । तिमा-
125 भट्टोश्रुतेचार्धवृत्तिं कौशिकगोत्रजः । [७८*] याजुषो बहुमानिश्रीलिंगभट्टस्य
126 नंदनः । मनुभट्टोश्रुतेचैकां वृत्तिं श्रीवत्सगोत्रजः । [७९*] सुतुस्त्रिमापुरंति-
127 [आभ]ट्टस्यागस्त्यगोत्रजः । बहुचो^७ वृत्तिमचैकां गौरभट्टसमश्रुते ।
[८०*] न-
128 दनो बहुमानिश्रीलिंगभट्टस्य^८ याजुषः । जनार्दनार्यः[.] श्रीवत्सगोत्रलोचै-
129 कवृत्तिकः । [८१*] बहुचो^९ वरिदुश्रीनरसस्यतनुद्वयः । वृत्तिमौभ-

Plate III, Side ii.

- 130 लयोचैकौशिकाजोश्रुते^{११} । [८२*] याजुषश्शिरिकुप्यश्रोतिमा-
131 भट्टतनुद्वयः । फणिभट्टोश्रुतेचार्धवृत्तिं कौशिकगोत्रजः । [८३*]

^१ Read ग्रा.

^२ Read क.

^३ Read कौशिन्य,

^४ Read बहुचो.

^५ Read the whole line as वृत्तिमौभकवीवेकां कौशिकसमश्रुते.

^६ Read ति.

^७ Read यजो.

^८ Read सोम.

^९ Read 'भास्वी.

^{१०} Read 'सुषोड'.

^{११} Read 'भट्टस्य.

- 132 सुनुईवरकोडन्नीधरिभट्टस्य याजुषः । तिमा(भ)ट्टोद्युते-
 133 त्रैकां हत्तिं ह[रि]तगोचजः । [८४*] वसिष्ठ(ठ)गोचजचिप्पगिरिराघ-
 134 वभट्टजः । श्रीनाराय[ण*]भट्टाख्यो वट्ट(हु)चोचैकहत्तिकः । [८५*] चक्रपाणि-
 135 सुधीस्तिमापुरंतिरुमलार्यजः । हत्तिमेकामिहाप्रोति वट्ट(हु)चो-
 136 गस्त्यगोचजः । [८६*] राघूरितिमाभट्टस्य नंदनः काश्यपान्वयः । तिमा-
 137 भट्टो भवत्येकहत्तिमानच याजुषः । [८७*] सुनुः कूकटंकोडन्नीदादिभट्ट-
 138 स्य याजुषः । नागाभट्टाख्योलैकां हत्तिकः कुल्लगोचजः । [८८*] याजुषशिख-
 139 गुप्पय्यीतिमाभट्टस्य नंदनः । गिरिभट्टोद्युतेचार्द्धहत्ति(त्तिं) कौशिकगोच-
 140 जः । [८९*] भारद्वाजान्वयोचार्द्धतस्तिमाभट्टस्यनूद्वयः^१ । कौडुभट्टो भवत्येक-
 141 हत्तिमानच याजुषः । [९०*] भारद्वाजान्वयो(य)चिक्कपुरुषोत्तमकोविदः । याजु-
 142 योचायुते हत्तिं श्रीसिद्धितिमार्यनंदनः । [९१*] वट्ट(हु)चः पार्वतीनाथो
 भारद्वा-
 143 जान्वयसुधीः । महीधरय्यीभैरवसुनुस्मार्द्धैकहत्तिकः । [९२*] भारद्वाजो म-
 144 णिमरिंय्यीमदौभलभलभट्टजः । कृती केशवभट्टाख्यो याजुषोचार्द्धहत्ति-
 145 कः । [९३*] द्राह्मायण(णो) बुक्करायसमुद्रीयाप्पकोडजः । भारद्वाजान्वयोचैकां
 हत्ति(त्तिं)
 146 वेकटयोद्युते । [९४*] श्रीकौडरामाभट्टाख्यो ब्रह्माभट्टनूद्वयः । याजुषोचायु-
 147 ते हत्तिमेकां कौडिन्यगोचजः । [९५*] याजुषो वारणाशिय्यीकौडुभट्टस्य
 नंदनः ।
 148 मनीषो माधवोचार्द्धहत्तिकः काश्यपान्वयः । [९६*] पुराणीभलभट्टस्य नंदनो
 149 हरितान्वयः । सुधीरोभलभट्टाख्यो याजुषोचार्द्धहत्तिकः । [९७*] ग्राम-
 स्थास्यैव
 150 सीमानो दिक्षु प्राच्यादिषु क्रमात् । तत्रचिन्हसमायुक्ता लिख्यंत
 देशभाष-
 151 या । [९८*] कनुमग्रामानकु प्रतिनाममैन नरसंमसमुद्रं सर्वमान्यं अग्रहा-
 152 रं पोलमेर विवरं । तूर्पुकु मोड्कोन तिप्पमीदि कुप्पराकु गुरुतु ।
 चंदुकु
 153 विवरं तरुमिलि गोविंदपुरं गुरुगुंटु कनुम सुगुड । चंदुकु दक्षिणं
 154 चिनमो[ट्ट]कोन सागुतिप्प नडुसुगानु गुरुगुंटु कनुममेर लेमुलकी-
 155 ड पडुमटि मोरु गुरुतु । चंदुकु दक्षिणं गुरुगुंटु कनुममेर । यमुकल-

^१ Read क.^२ Omit श्री.^३ Read ०रवदीहूतक्षिपामरतनूद्वयः.^४ Read भल once only.

[illegible]

2	34	34
4	38	36
6	38	38
8	40	40
10	42	42
12	44	44
14	46	48
16	48	48
18	50	50
20	52	52
22	54	54
24	56	56
26	58	58
28	60	60
30	62	62
32	64	64

६६
 ६७
 ६८
 ६९
 ७०
 ७१
 ७२
 ७३
 ७४
 ७५
 ७६
 ७७
 ७८
 ७९
 ८०
 ८१
 ८२
 ८३
 ८४
 ८५
 ८६
 ८७
 ८८
 ८९
 ९०
 ९१
 ९२
 ९३
 ९४
 ९५
 ९६

[illegible]

- 156 वीयिनि तिप्य अर्धं तूर्णतद् गुरुतु । अकडनुंठि नैर(क)त्वं आ यमु-
कलवो- ।
157 यिनि तिप्य नहुसुगातु गुरुगु(गुं)टु कनुममेर । आ तिप्यकु पडुमर
मारुवे-
158 सुवंक गुरुतु । गुरुगु(गुं)टुनागुलगुडकनुमसु[गु*]इ । आ वंककु द-
159 क्षिणान नागुलगुड कनुममेर । आ मार(र)वेसुवंक मेडिता-

Plate IV, Side i.

- 160 पुगा तूर्णदिनि वीयिनि मूलतुनागुलगुड(इ) [आ]कुलेर कनुम
161 सुगु(गु)इ गुरुतु । अंदुकु दक्षिणं आकुलेटि कनुम मेर नलकटुव
गुरुतु ।
162 अंदुकु दक्षिणं आकुलेटि(ले?) कनुम(टि) मेर नर मैसै(य)दोडिक्कि पडुमटि
दिक्कुन
163 नलकटुव गुरुतु । अंदुकु मैर(क)त्वं पुटुगातु पडुमरगातु अकुलेटि कनु-
164 मेमर' । 'द्रंहुचोर तेत्तराकु गुरुतु । अंदुकु पडुमर माकुलेटिक्किनि क-
165 नुमकुंतु मेर आकुलेर जंजु[म](ल)दिक् कनुम सुगु(गु)इ गुरुतु ।
अंदुकु इ-
166 दुकु इ(उ)त्तरं जंजुलदिन कनुममेर अंदुकु पडुमर मेडि तापुगातु कौड-
167 'कूपोयो वीव गुरुतु । आवीवकु पडुमर जंजुलदिन कनुम मेर मीरीत्त-
168 गुड गुरुतु अंदुकु पडुमर जंजुलदिन कनुम मेर मेडि तापुगा' मूलल गु-
169 रतु अ'कडनुंठि उत्तरं जंजुलदिन कनुम मेर उत्तरपु रीगडि पंगुलली
170 वच्चिन वंक गुरुतु । अकडनुंठि पडुमर सा(आ) वायव्य मूल जंजुलदिन क-
171 नुम मेर कूटा[ल]वंक गुरुतु । अंदुकु [ज]ंजुलदिन[त]लगादेपत्थ कनुम
सुगु(गु)-
172 इ । अकडनुंठि उत्तरं कूटालवंक तलगादेपत्थ कनुम मीरतूरुप पडम-
173 रनेन नलकटुव गुरुतु । अकडनुंठि उत्तरं कूटालवंक(क) तलगादेपत्थ
कनु[म*]
174 मेर । अकडनुंठि उत्तराननुंठि पडुमरसुखंगातु पुटुकुडा लवंका त-
175 लगादेपत्थ कनुम मेर । चमडुचट्टकाड तेत्तरालकटुव गुरुतु । अकड-
176 नुंठि पडुमरसुखं वायव्य मूलगातु कूटालवंकनहुमध्यं तलगादेपत्थ

* Read मीर.

* Read इंदुवेव as in l. 207, below.

* Read कूपोये.

* Read perhaps तापुग.

* Read इ.

- 177 कनुम मेर रेडु वंकलु कूडिन मंगचहुतेकरालु गुरुत । अक'डनुंठि
कूटा-
178 र(ल) वायव्यगालु तलगादेपल्य कनुम मेर । आ वंक पडुमटि
दिक्कु(कु)न तलगा-
179 देपल्यलोनि राळदिन गुरुत । अक'डनुंठि^१ वायव्य तलगादेपल्य कनुम
मेर-
180 पडुमरमुखंगालु पोयिन मेर गुरुत । अकडनुंठि पडुमर तलगादेपल्य
181 कनुम मेर रेडु चिडिपिराळु गुरुत । अक'डनुंठि^२ पडुमर तलगादेपल्य
182 कनुम मेर मेडितापु गुरुत । अकडनुंठि^३ उत्तरगालु तलगादेपल्य कनु-
183 म मेर । पडुमरमुखंगालु मेडितापु गुरुत । अंदुक्कु तलगादेपल्य शिरिय-
184 वरं कनुम सुग्गुड । अकडनुंठि^४ उत्तरगालु वायव्य शिरियवरं कनुम मे-
185 र । तलगादेपल्य मंठि(डि)मडगुक्कु पोये तेरुवु । अकडनुंठि^५ आ
तेरुवुक्कु उत्तरं
186 शिरियवरं कनुम मेर । आ तेरुवुक्कु तूर्यं तेजराळ गुरुत । अकडनुंठि
उत्तर-
187 रं शिरियवरानक्कु कनुम मेर पेहगुंठु गुरुत । अंदुक्कु उत्तरं शिरियव-
188 रं मुंडिमडुगु चेचपालेकीड कनुम सुग्गुड तिप्पमीदि नौक्कु गुरुत । अं-
189 दुक्कु ईशान्यं आ कीडनौकुनडुमध्यंगालु चेचपालेकीड कनुममेर मंडि-

Plate IV, Side ii.

- 190 कनु[म*]गुरुत । आ मंडिकनुम ईशान्यं चेचपालेकीड कनुम मेर चिडि-
191 पिराळकडुव गुरुत । अंदुक्कु ईशान्यं चेचपालेकीड कनुम मेर तं(ते)ज-
192 राळकडुवकाड पेहगुंठु गुरुत । अंदुक्कु ईशान्यं चेचपालेकीड कनुम मेर
193 पेहराळकडुव मीदि दीच अरुगुंठु गुरुत । अंदुक्कु ईशान्यं चेचपालेकीड
कनु-
194 म मेर कीयकीडवंकवहि तेज कुप्पराळु गुरुत । अंदुक्कु चेचपालेकीडु(ड)
कलू-
195 र कनुम सुग्गु(गु)ड । अकडनुंठि ईशान्ये कलूरिकिंनि कनुममेर
यंपलि(दी)न
196 कनुमवहि नजराळकीड गुरुत । अकडनुंठि^६ ईशान्यं कलूर कनुम मेर
197 वलसुमानि तिप्प रेडु तिप्प(प्य)लसंदु गुरुत । अंदुक्कु तूर्यं कलूरिं कनुम
मेर वलसु-

^१ Read ड.

^२ Read डि.

^३ Read अकडनुंठि.

- 198 चेदु तिप्पवोहि पेह भटुडु गुंडु गुरुत । कज्जुर विज्जुर कनुम सुगु(गु)ड ।
अंदुडु तू-
- 199 पुं विज्जुर कनुम मेर अप्पज्जि दीन तिप्पडु उत्तरपु अंजुन पेहराक-
कटु(हु)वल्लोनि पो-
- 200 डवटिगुंडु गुरुत । अंदुडु तूपुं विल(ज्जु)रि कनुम मेर यरवंगतलपुन
मेरपु राळ
- 201 कटु(हु)वगुरुत । अंदुडु पाप्पेन्ने(यं) डुटु(हु)गानु तूपुं विज्जुर कनुम
मेर यरसागुडुतलपु-
- 202 न नज्जगुंडु गुरुत । अंदुडु ईशान्यं यरसागुडु दक्षिणपु अं जु विज्जुर
कनुम मेर
- 203 अंदुडु तूपुं डुडुगानु आ तिप्पडु दक्षिणपु अंच(जु)न पोडवा(व)टि
रेंडु राकुदीत सुपु रा-
- 204 कु वोकटि ई मंडुराकु गुरुत । अज्जडनंति तूपुं विज्जुरि कनुम मेर
यरसागुडुकीड
- 205 तूपुंकोननु चिडिपिरक्कालोनि तेज्जनि पोडिराकु गुरुत । अंदुडु तूपुं विज्जुरि
कनुम मेर
- 206 मंतदोनसागुड पेहकडुवतेरुवुन पु[हुं]वंडवोहि तेरुवल्लोनि गुंडु गुरुत ।
अंदुडु आ-
- 207 ज्ञेयं विज्जुर कनुम मेर दंडुचोवकु अहकटि(डि)न कटु(हु)वराकु गुरुत ।
अंदुडु तूपुं विज्जु-
- 208 क कनुम मेर कुरुवलकुंटदक्षिणपु दिक्कुरु कोनकडु गुरुत । अका(क)डनंति
ईशा-
- 209 न्यं विज्जुर कनुम मेर विज्जुर कज्जमडि कनुम सुगु(गु)ड गुरुत ।
अज्जडनंति तूपुं
- 210 कज्जमडि कनु[म*] मेर दक्षिणमुखंगानु पोयिन मेर मेडितापु मूल
इगुकवंक गु-
- 211 रुत । अज्जडनंति¹ दक्षिणं कज्जमडि कनुम मेर मेडितापुं गुरुत ।
अज्जडनंति
- 212 तूपुं कज्जमडि कनुम मेर मोतुकुलवंक गुरुत । अज्जडनंति दक्षिणं कज्ज-
- 213 मडि कनुम मेर मोतुकुलवंककाडनंति तूपुंगा पोयिन मेर मूलवंकलो-

¹ Read अज्जडनंति.

- 214 नि राकु गुरुत [1*] चंदुकु तूर्प कलमडि कनुम मेर मेडिताप मूल
गुरुत । अक'-
215 डनुंडि दक्षिणं कलमरिंकि कनुम मेर मूल मेडिताप गुरुत । चंदुकु
तूर्प
216 कलमडि कनुम मेर मूल मेडिताप गुरुत । चंदुकु आम्येयं कलमरि(डि)क
217 नुम मेर गगेरलकुंट नलकटु(डु)वमीदि कुप्पुराकु गुरुत । चंदुकु तूर्प क-
218 लमडि कनुम मेर नलकटु(डु)व नडुसुगानु मल्लिनायनि तिप्य दक्षिणं न-
219 लपपुननेरपुराकुलोनि चप्पटिवटुवुगुंडु गुरुत । चंदुकु इशान्यं
220 [त]टुगानु कलमडि कनुम मेर मल्लिनायनि तिप्य तूर्प कोनपोटु(डु)वटि
गुंडु गु-

Plate V.

- 221 रतु चंदुकु तूर्प कलमडि कनुम मेर । चलगर गेल'तिप्य प-
222 डुमटि चंडु तेजगुडु गुरुत । चंदुकु कलमडि गोविंदपुरं कनु-
223 म मेर सुगु(म्)ळ । चंदुकु तूर्प गोविंदपुरं कनुम मेर चलगरिगल
224 तिप्य कनुम नडुसुगानु ई तिप्यकु तूर्पदिक्कन कोडमीदनु पेद(ड)गुडु
225 गुरुत । चंदुकु तूर्प गोविंदपुरं कनुम मेरचंदु शुळ(कु)कोडमीद उत्त
226 रपु दिक्कन तेजगुरुत चंदुकु तूर्प गोविंदपुरानकु कनुममेरकु
227 चंदुगुळकोडकु नडुसुगानु आ कोडकु तूर्प पचालंकोन तिप्य गु-
228 रतु । अक'डनुंडि दक्षिणं पेदमोटु कोन तलपुन[कुडे]नु ॥ ओ ओ ओ
229 सरससदाशिवरायचित्तिपतिचर्यस्य कीर्त्तिधुर्यस्य । शासनमि-
230 दं सराशन'दाशरथेरमितहोमदानरतेः । [८८*] स्रदुपदमिति तांस्'शा-
231 सनार्थं मल्लितसदाशिवरायशासनेन । अभणदनुगुणं वचीमहि-
232 आ सरसतरेण सभापतिस्त्रयंभूः । [१००*] सदाशिवमहारायशासनाही-
233 रणात्मजः । त्वष्टा ओवीरणाचार्यो व्यलिच्छतांस्'शासनं । [१०१*] दानपालन-
234 योर्मध्ये दानाकळे(ष्टे)योनुपालनं । दानास्त्रगमवाप्नोति पालनादच्युतं प-
235 दं । [१०२*] स्रदत्ताहि(डि)गणं पुष्यं परदत्तानुपालनं । परदत्तापहारिण
स्वद-
236 तं निस्सलं¹⁰ भवेत् । [१०३] स्रदत्तां परदत्तां वा यो हरित वसुंधरां
यष्टिर्वय-

¹ Read अकडनुंडि.² Read अ.³ Read अ.¹⁰ Read निस्सलं.⁴ Read कलमडि.⁵ Omit the punctuation.⁶ Read सराशनं.⁷ Read इ.⁸ Read चलगरिगल as in line 223, below.⁹ Read 'ताम्'.

- 237 सहस्राणि विष्टा(ष्टा)यां जायते क्रिमिः । [१०४*] ऐकैव^१ भगिनी
लोके सर्वेषामेव
238 भूभजां । न भोज्या न करप्राज्ञा विप्रदत्ता वसुंधरा । [१०५*] सामा-
न्यीयं
239 धर्मसंतुष्टपाणां काले काले पाक्षनीयो भवद्भिः । सवा(र्वा)नेताम्भा-
240 विनः पार्थिवेन्द्राभूयो भूयो याचते रामचंद्रः ॥१०६॥ श्री श्री श्री
241 श्रीविरूपाक्ष^२

ABSTRACT OF CONTENTS.

Vv. 27 & 28. After the death of Achyuta, Venkaṭa-dēva-Rāya succeeded to the throne. On his death,

Vv. 29 & 30. Sadāśiva-Mahārāya, the son of Raṅga by Timmāmbā, was anointed as king of Vidyānagara by Rāmarāja, the protector of the Karpāta kingdom, and other ministers.

Vv. 31-35. The praises of Sadāśiva-Mahārāya, who was a devotee of the god residing on Śēṣhādri (i.e. the god Venkaṭeśa).

Vv. 36-42. The other titles of king Sadāśiva.

Vv. 43-57. In the vicinity of the god Viṭṭhaleśvara, on the banks of the Tūṅgabhadra river, in the Śaka year counted by the numerical words *avatār-āṅga-vēd-ēndu* (=1470)³; in the year Kilaka; the month Āṣhāḍha; in the bright fortnight; and on Sunday, the day of Pramatha-Dvādaśī; for the worship of the god Chenna-Kēśava enshrined in the village Muṇḍimaḍugu, by the 16 methods prescribed and for Brāhmaṇas of various Śākhās, names, *gōtras* and *sūtras*, famous for their Vedic knowledge and learned in the *śāstras*; the king gave the village of Kanuma, otherwise known as Narasammasamudra, situated in the Gutti *valita* in Muṇḍimaḍugu *śimā*, on the banks of the Pinākinī (Pennar) river to the east of the village Śirivara, to the south of Kallamaḍi, to the north of Ākilēru and to the west of Nāgalaguḍḍa.

V. 58. The god Chenna-Kēśava and the Brāhmaṇas hold equal divisions in the village.

Vv. 59-97 contain the names of the donees and the number of shares that went to each.

V. 98 & ll. 151 to 228. The details of the boundaries and the marks of identification are set forth.

Vv. 99 & 100. The grant was composed on the order of the king by Sabhāpati-Svayambhū.

V. 101. The engraver of the grant was Virāṇa-āchārya, son of Virāṇa.

Vv. 102-106. The usual admonitory verses.

L. 241. *Śrī-Vīrūpakṣa* (the sign manual of the king).

No. 26.—THE MELUPAKA GRANT OF MAHADEVENDRA-SARASVATI: SAKA 1608.

By S. V. VISWANATHA, M.A., TRICHINOPOLY.

The grant is recorded on a single copper-plate inscribed on both sides. It is now in possession of the Śāhkarāchārya of the Kumbhaghōṣam *maḥā*, who kindly lent the plate for examination. I edit the inscription from inked impressions prepared by me.

¹ Read ऐकैव.

² In Telugu characters.

³ [The number 70 is obtained by adding *avatāra* (10) to *āṅga* (6) the latter of which, as it stands in the place of tens, is equal to sixty.—H. K. S.]

The plate is 8·8 in. high and 8·4 in. broad, except in the middle, where it is 12·3 in. high. There is a hole at the top of the plate to let in a ring. The inscription, which is in large Nāgarī characters and which runs across the breadth of the plate, is legible enough. The plate is in good preservation. There are in all 31 lines of writing.

Two languages are used in the inscription. The first three lines are in Telugu and give the details of the date of the grant. The rest of the first side from l. 3 to l. 15 is in Sanskrit and describes the religious qualities and attributes of Mahādēvendra-Sarasvatī, the disciple of Chandrasēkhara-Sarasvatī of the Conjeeveram Śārādā maṭha. The whole of the second side again is in Telugu, mostly of a corrupt kind, except the usual admonitory verses.

The characters of the inscription are a carelessly written form of Dēvanāgarī. The whole inscription is in these characters, excepting the last line, which is in Telugu.

The inscription records the grant of certain rights in the village of Mēlupāka by the then presiding teacher (ācārya) of the Śārādā maṭha at Conjeeveram, Mahādēva-Sarasvatī, disciple of Chandrasēkhara-Sarasvatī, to Rāmā Śāstrin, follower of the Āśvalāyana sūtra, of the Kāmākṣyana Viśvāmitra gōtra, a member of the Hōyāsāna Kanneḍi community. The village of Mēlupāka was once granted to the maṭha by the Golkonda ministers Akkanna and Mādanna. These rights included certain taxes of 3 maṇas (maṇakkāl) for every kalam or paddy, which gives us the ratio of $\frac{1}{4}$ for kṣanukoyi-dāsamukhi. It is interesting to compare the term kṣanukoyi with the similar form Kanungo, which is the name given to the village accountant in Muhammadan India. Dāsamukhi is the tax customarily paid by the subjects to the 'lord,' and this is given as a definite proportion of the produce raised, generally $\frac{1}{10}$. It also included the gift of two varāhas (=Rs. 7-0-0) per annum from the maṭha and two house sites.¹

The grant is dated Śaka 1608, Prabhava, Vaiśākha, Śu. di. 15, Saturday, lunar eclipse. On these details Diwan Bahadur L. D. Swamikkannu Pillay writes as follows:—"Śaka 1608, Prabhava, Vaiśākha, Śu. di. 15 Saturday, lunar eclipse. Śaka 1608=A.D. 1686-87. But Prabhava was A.D. 1687-88. The day intended was Saturday 16th April, A.D. 1687. The tithi commenced at .58 of the day and ended at .55 of the following day. There was no lunar eclipse on the day in question." One thing has to be remembered against the above verification of the date. The occurrence of the lunar eclipse on the day on which the grant was made must have been an unmistakable fact. We have to take this as a certain and known fact and with this as our basis work out the other details to suit it. Eclipses are of immense significance to the Hindu, and could not be easily forgotten by him, whether the other details of a date are correctly stated or not. Hence the right method of verification of the date would seem to be to find out on what days in the year 1686 or 1687 there were lunar eclipses and to see if the other data fit in with the date on which the eclipse occurred.²

Regarding the names of persons occurring in the grant, special mention has to be made of Akkanna and Mādanna of Golkonda, as they appear in our inscription. Akkanna and Mādanna were the ministers of one of the Nawabs of Golkonda. They appear in Indian tradition as the disciples of the Vaiṣṇava saint Rāmadas of Bhadrāchalam.

Concerning the two brothers Rao Sahib H. Krishna Sastri writes thus in the *Madras Ep. Rev.*, 1915, pp. 117 f., quoting from the Dutch journal of *Havart*:—

"These donors must be identical with the two famous persons of those names frequently mentioned in the popular story of Rāmadas. They were the ministers of Tānisha, one of the

¹ See below, p. 359, note 7.

² [The non-coincidence of the most important item of the date, viz. the lunar eclipse, reflects upon the genuineness of the grant itself.—H. K. S.]

kings of Golkonda. Rāmadās, the nephew of these ministers, was put to extreme torture on account of certain misappropriation of revenue."

"They were two brothers, born of a very poor family, who entered service as shroffs in A.D. 1666 on a pay of 10 *gilders* per mensem under Saiyyad Mustapha, a nobleman of Golkonda known to fame as Mir Zumla. Mādanna *alias* Sūryaprakāśa Rao is stated by the Dutch journalist to have been an intelligent man, whereas his brother Akkanna was a man of cunning and roguery with very little of understanding. The brothers rose in rank by an apparent act of treachery, which cost Mir Zumla his high office under the Nawabs of Golkonda. Mādanna became a very prominent figure in the administration of the kingdom, so much so that the Sultan left everything to his care and was satisfied with receiving 75,000 dollars for his personal use. Mādanna was well versed in Persian, Hindustani, and the vernaculars of the country, and lived in a kingly style."

"Having served under Abdulla Qutb Shah (A.D. 1611-1672), the two brothers seem to have maintained the same high position also under the reign of Abdul Hassan, the successor of Abdulla Qutb Shah. But they were not to maintain this long. In A.D. 1685 the Mughal king Aurangzeb marched with his army into Golkonda and plundered first the house of Mādanna. The people were in a state of panic and accused Mādanna of high treason. Under orders from the Sultan they murdered the two brothers, who were once the bosom friends of the king, in a most ignominious way. Akkanna and Mādanna were dragged along the streets in the presence of the people. The head of Mādanna was severed from his body and sent to Aurangzeb, while that of Akkanna was trampled under the foot of an elephant. The death of the two brothers must have happened after the 29th of Oct. 1685, when the Mughal army entered Golkonda, and perhaps before the end of that month."

The Dutch journal contains four interesting pictures, which have been reproduced in the *Madr. Ep. Rep.*, 1915, plate II, regarding the story of Akkanna and Mādanna. One of them is a figure of the king of Golkonda "*Sultaan Aboe-il-Hassan Kotbshah Koning van Golkonda*." Two others are those of Akkanna and Mādanna. The former is styled "*Opper Boekhouder en Generalissimus van het Golcondase leger*," while concerning Mādanna we have "*Madoena Suraparkas Bouw Albestierder van het Golcondase ryk*." The fourth picture illustrates how the two brothers are drawn through the streets by the disaffected populace. Under each of these we find an inscription by Havart as follows :—

I. *Aboe-il-Hassan.*

Nemo felix ante obitum.

L. 1. Hy was een Koning in de naam,
niet in der daad,

L. 2. Quam tot die waardigheyd van de
alderlaagste staat,

L. 3. En liet door andere zig zelf, ent Ryk
bestieren,

L. 4. Een dom onnozel Mensch, niet
Vorstlyk in manieren.

L. 5. Toen nu't geluk met hem een tyd
lang had gefopt,

L. 6. Wierd hy door eygen Schuld van
Kroon en Throon geschopt,

L. 7. Kroep in het sant, vrat stof, moest
zig als slaaf verminderen.

L. 8. Wee zulken land, alwaar de
Koningen syn kindren.

Translation.

None is happy before death.

He was a king in name, not in deed. From a very low state he rose to high dignity. He let others rule himself and his kingdom. He was a stupid man, not kinglike in manners. When fortune had played with him for a long time, he was kicked from crown and throne through his own fault; crept in sand, ate dust and was humbled like a slave. Woe to the land where kings are children.

II.

Tollantur in altum, ut lapsu graviore ruant.

L. 1. Hier ziet men Madoena naar't leven afgetekend,

L. 2. Die van den eersten tyd zyns Ionkheys afgerekend,

L. 3. Tot aan zyn dood toe was een speel-kind vant geluk :

L. 4. Hy is van niet tot zoo een hoogen trap verheven,

L. 5. Dat zelf de Konink naar zyn wenk beest moeten leven.

L. 6. Hy heeft zyn eygen Heer (O hsy-loos schelemstek)

L. 7. Van ampt en staat gezet, ja alles derven wagen.

L. 8. Maar trag tende zyn Vorst te levren in de hand

L. 9. Des vyands, raakte hy toen't uyt quam aan een kant,

L. 10. Door Sidemaktas swaard, teynd moet de last tog dragen.

III.

Alter Idem.

L. 1. Hier ziet men in het kleyn de schets van Akkana,

L. 2. Een beest in menschen schyn : wiers loze loze streken,

L. 3. Wiens schelmery en trots niet syn om uyt te spreken.

L. 4. Geen groter booswicht droeg de stad van Golconda.

L. 5. Deelaghtig aan verraad zyno broers nooit wel te vreden,

L. 6. Heest hy de zelve straf op eenen tyt geleden.

Let them be raised on high that they may be led to graver fall.

Here we see Madanna drawn from life ; a plaything of fortune from the beginning of his youth till his death ; he had risen from nothing to such good luck that even the king must live according to his direction. He removed his own master from office and state. Oh hellish scoundrelism, nay, he dared to do anything. Trying to deliver the king into the enemy's hands, he was discovered in the act and had to give up his life through Sayyad Makhta's sword. After all the burden has to be borne.

A second just the same.

There we see the picture of Akkana in miniature. A beast in human skin : his cunning and wily tricks, his roguery and pride are not fit to be spoken. No greater villain Golkonda ever produced. Partaking in his brother's treason, he was not content. He had the same penalty at the same time.

Madoena en Akkana. Twee Gebroeders vermoord en schandeluk ten toon Gestellt.
(Madanna and Akkana. Two brothers murdered and exhibited scandalously.)

The donor of our grant is Mahādevendra-Sarasvati, disciple of Chandrasekhara-Sarasvati of the Śārada pīṭha of Kāñcīpuram. This grant, taken with the other Vijayanagara record

examined and published by myself and Mr. Venkateswara in Vols. XIII and XIV of this Journal, discloses to us the names of four Āchāryas of the Conjeeveram *maṭha*—

Name.	Grant.	Date.
1. Mahādēva-Sarasvatī, disciple of Sadāśiva-Sarasvatī.	Kuḍiyāntaṇḍal grant of Vira-Nṛsiṃha	S. 1429.
2. Chandrasekhara-Sarasvatī, disciple of Mahādēva-Sarasvatī.	Conjeeveram plates of Kṛishṇa-dēva-Rāya.	S. 1444.
3. Sadāśiva-Sarasvatī, disciple of Chandrasekhara-Sarasvatī.	Udayambākam grant of ditto	S. 1450.
4. Mahādēvendra-Sarasvatī, disciple of Chandrasekhara-Sarasvatī.	The present grant	S. 1608.

For the relation in time of these and their descent from the first Śaṅkarāchārya see Mr. Venkateswara's article in the *Journal of the Royal Asiatic Society*, October, 1916, pp. 161 f.

Chandrasekhara-Sarasvatī we find residing in the Śārada *maṭha* of Kāñchi, surrounded by his disciples, to whom he imparts nectar-like instruction in Advaita, crushing the heretic faiths and setting up the religion of the Vēda and Vēlānta. The heretic faiths referred to are probably Jainism and Buddhism, vestiges of which are still to be found in South India, especially in Conjeeveram.

As regards Rāmā Śāstrin, the donee, we are told that he belonged to the Hōyāsāna Kannaḍi community, was of the Āśvalāyana *sūtra* and Kāmākāyana Viśvāmitra *gōtra*. We find no more particulars about him. But the fact that he was of the Kannaḍi community is of some importance. It shows probably the encouragement given to this sect by the then presiding āchārya. This in a way continues to be the practice in the Kumbhaghōṣam *maṭha*, where the Āchārya for some generations past at least has been chosen from among the Hōyāsāna-Karṇāṭaka community.

It is clear to us that Chingleput was included in the territory of Golkonda and that in the 17th century it was held as a *jāgīr* under Golkonda. This record makes it clear to us that the Kāmakoṭi *pīṭha*, as at present it is known to be the seat of the Śaṅkarāchārya of Kumbhaghōṣam, must have been in the Śārada *pīṭha* at Kāñchi, at least till the date of this grant (1686-1687). We know from another grant to an earlier Śaṅkara-Yōgin of probably this same *maṭha*, by Vijayagandagopāla-dēva, the Telugu chieftain, that this line of teachers must have been in existence in Kāñchi at least from the 13th century.¹ Thus the Śārada *pīṭha* or the Kāmakoṭi *pīṭha* must have been in Kāñchi between the 13th and 17th centuries of the Christian era. The tradition of the *maṭha* tells us that it was at the invitation of King Śarabhoji of Tanjore that the Āchārya removed to Kumbhaghōṣam.

The inscription ends with the usual admonitory verses. We do not find at the end, where there is the line '*Śrī-Chandramauṣīvara-Svāmī sahāyam*,' the signature of Mahādēvendra-Sarasvatī, who made the gift, and it is interesting to note that to this day the Āchāryas on no occasion affix their signature to any letters or correspondence proceeding from the *maṭha*.

¹ [The date of this grant has been disputed. See above, Vol. XII, p. 195.—H. E. S.]

TEXT.¹

First Side.

श्रीमहादेव


- 1 खं(स्त्र)स्ति श्रीविजयाभ्युदय शा[लो]वाहनशकवर्ष²सुतु १६०८
- 2 अगुनेटि प्रभवा³[न]मसंब[त्स]रं वशाख⁴ शुद्ध १५ स्थिरवारं
- 3 चंद्रा⁵परागपुष्पकालमदु⁶ [स्त्र]स्ति श्री[म]दखिलभ⁷मंडलाज्ञ(लं)-
- 4 कारत्रयस्त्रिंशत्कोटिदेवतारावि(धि)तश्रीकामाक्षीदेवीसनाथ-
- 5 श्रीमदेका⁸सनाथश्रीमहादेवा(व)स[न]ायश्री⁹हस्तगिरिनाथसाचा-
- 6 त्कारपरमाधिष्ठा¹⁰नसत्त्वव्रतनामांकितकांचीदिव्यलेखे शा-
- 7 रदाप(पो)ठसंस्थितानामतुलितसुधारसमाधुर्यकमलासन-
- 8 कामिनीधम्मिल्लसंपुल्लमलि¹¹कामालिकानिधं दमक-
- 9 रंद[भ]रोसौवर्णि(स्ति)कवाग्निगुंभ(फ)विजृम्भणानंदतुंदिलित-
- 10 मनीषी(धि)मंडलानामनवरताडे(दै)तविद्याविनोदरसिकानां
- 11 निरंतरालंकृतीकृतशान्तिदांतिभूषां सकलभुवनच[क्र]¹²प्रतिष्ठा-
- 12 पकविख्यातयशोलंकृतानां निखिल¹³[ल*]पाण्डवपंडकटकोट्टाटनेन
- 13 विशदीकृतवेदवेदांतमार्गप्रतिष्ठापना[ना*]चार्याणां श्रीमत्परमहं-
- 14 सपरिव्राजकाचार्य¹⁴*श्रीमच्छंकरभगवत्पादाचार्याणामधि[ष्ठा]-
- 15 ने सिंहासनाभिषिक्तश्रीमच्चन्द्रशेखरेन्द्रसरस्वतीसंयमां¹⁵
- 16 द्वाणामंतेवासिवर्यश्रीमच्छाहादेवेन्द्रसरस्वतुलचा(वा)रु शा¹⁶


Second Side.

- 17 आश्वलायनसूत्रले¹⁷न वा(का)मकायनविज्ञामित्रगा¹⁸तुलैन
- 18 श्रौयासानकवेडिवार¹⁹ रामाशास्तुर्नवारिकि गोलको²⁰ड अह-
- 19 क्षमादं(द)[क]वारु यिच्छिन तम सुसा²¹ग्रामंलो चंगलपट्ट्यागीर-
- 20 श्रीमल(लो) अजूर दगोर मेलुपाकलोतु अग्रहारं चसि²² पनमा-
- 21 नसास्थं²³ करिकि उत्तरं चरुतकु दक्षिणपु[न*]पार्श्व छिमिका-[ल]-

¹ From the original plate and from ink-impressions.² Not very clearly inscribed. Read ग्रमवनाम संवत्सरं.³ Read नो.⁴ Read वा.⁵ Read हा.⁶ Read हा.⁷ Read हा.⁸ Read हा.⁹ Read हा.¹⁰ Read हा.¹¹ Read हा.¹² Read हा.¹³ Read हा.¹⁴ Read हा.¹⁵ Read हा.¹⁶ Read हा.¹⁷ Read हा.¹⁸ Read हा.¹⁹ Read हा.²⁰ Read हा.²¹ Read हा.²² Read हा.²³ Read हा.² Read सुतु.⁴ Read वशाख.⁵ Read म.¹⁰ Read श्रीहस्तगिरि.¹¹ Read श्री.¹⁴ Read श्री.¹⁵ Read श्री.¹⁶ Read श्री.²⁰ Read मोक्षासा.²³ [The unexplained words अग्रहारं चसि पनमानसास्थं appear to me to stand for अग्रहारं चसि पनमानसास्थं, i.e. "The tax-free Brāhman's share declared as such is."—H. K. S.]

First Side





- 22 वक्रंणारुल¹ तिलयोडुकांडु आयदु(सु*)कांडु मान्यमुं(मृ)नु संवत्-
 23 रानकु मठमुलोतु वरषाशनं २ रेडु वरञ्जालुं(लु)नु निवश²तरेडुं(डु)-
 24 नु या ग्रामली(लो) कनुवडि कलानिकि कानुगोयिदेशमुखि मर ३
 25 मूडु अडुलुनु³ श्रीचंद्रमौलीश्वरस्वामिकि मर अ[डु]डुनु यी ता(ना)-
 26 लुगु अडुल मानुनु⁴ श्रीचंद्रमौलीश्वरस्वामिकि अ[पि]तंगा-
 27 नु दत्तं व(चि)सि दानशासनं त्रासि यिच्चिनासु ॥ श्रीरामा ॥ श्री ॥
 28 दानपालनयोर्मध्ये दा[न]ा[व्हे](व्हे)यीनुपालनं [१*] दानात्स्वर्गमवा-
 29 प्रोमि(ति) पालनादच्युतपद⁵ ॥ [१*] स्वदत्ताडिमुण⁶ पुण्यं परदत्ता(त्ता)-
 30 नुपालनं [१*] पर[द]त्तापहारेण स्व[द*]त्तं निष्फलं भवेत् ॥ [२*] श्री ॥
 31 श्रीचन्द्रमौलीश्वरस्वामो सहायं

TRANSLATION

(abridged).

L. 1. In the year 1608 of the Śālivāhana Śaka.

L. 2. In the year Prabhava, Vaiśākha, full-moon, Saturday.

Ll. 3-16. On the day of a lunar eclipse, Mahādēvēndra Sarasvatī, the choicest of the disciples of Chandrasēkhara Sarasvatī, who has established himself at the Śāradā pīṭha at Kāñchi otherwise called Satyavrata, the ornament of the whole world, in which are the temples of Ekāmrañātha-Mahādēva Kāmākshi-Dēvī, adored by the 33 crores of gods, and which is the chief seat of Hastigiri-nāṭha's visible presence; he who delights crowds of learned people with his benedictory compositions, a stream of honey, that flows from the wreaths of jasmine which adorn the braided hair of Sarasvatī, the beloved of Brahmā, and having an unrivalled nectarean sweetness; who always takes delight in the Advaita philosophy; who is rich in a constant adornment of śānti and dānti; who is ornamented with a character celebrated as supporting the whole circle of worlds; who advocates the religion of the Vēda and Vēdānta, after rooting out the heretic faiths, which were so many thorns; who is enthroned on the seat of the Paramahansa Parivrajakāchārya Śrī Śaṅkarāchārya—

Ll. 17-27. made to Rāmā Śāstrin, of the Āśvalāyana sūtra and Kāmākāyana Viśvāmitra gōtra, belonging to the Hōyāsāna Kanneḍi sect of Brāhmapas, a copper-plate grant of an agrahāra in Mēlupāka near Ajāru, in the jāgīr of Chāngalapattā (Chingleput), granted to the teacher by Akkanna and Mādanna of Gōlkonḍa. It is bounded on the north and the west by the lake and on the south by the village of Mēlupāka. The lands of the village are to be supplied with the water of the Kaṇṇāru. Besides this 2 house-sites, 2 pagodas a year, 3 marakkala per kalam for kūṇukoyi and dēśamukhi, and some minor sources of income are granted to Chandramaulīśvara-Svāmin (Maṭha).⁷

Ll. 28-30. The usual admonitory verses.

L. 31. Invokes the help of Śrī Chandramaulīśvara-Svāmin.

¹ Read वक्रणारुल.² Read निवेशनं.³ Between the letters लु and नु is inserted the figure २ in Nāgarī. This may partly explain the reading निरा in the next foot-note.⁴ [Mr. T. A. Gopinatha Rao reads 'मननु' (his *Copper-plate Inscriptions of the Kāmākōṭi-pīṭha*, p. 135 text-line 26) which like मराननु gives no meaning. The reading intended was evidently निराडुनु.—H. K. S.]⁵ Read 'दच्युत पद'.⁶ Read 'दिमुण'.⁷ [The author and Mr. Gopinatha Rao have both committed the same mistake in the matter of the object of the grant. The donee Rāmā Śāstrin was given: (1) the māya (l. 22), i.e. exemption from payment of fee to the mortgagees (talayidukāṇḍu) and the holders (āyākaṇḍu) of the sub-channels, for using water; (2) two vārākas as annuity from the maṭha; (3) the mēra (share) of 3 aḍḍas on a kalam of paddy due to the supervising Dēśamukhi and of 1 aḍḍa due to the god Chandramaulīśvara in the village of Mēlupāka.—Ed.]

No. 27.—PURLE PLATES OF INDRAVARMAN: THE [GANGA] YEAR 149.

By G. RAMADAS, B.A.

The subjoined plates were secured by me from a cultivator in Purlo, a village near Palakonda. It was stated that they were discovered in a pot exposed to view in a crumbling wall on the bank of the river opposite to where Purlo lies.

They are three in number, each measuring $6\frac{1}{8}$ " by $2\frac{3}{8}$ ". The margins of the inscribed inner side of the first and the third plates and both sides of the second plate are raised for the protection of the writing, which is in a good state of preservation, except in two places in ll. 12 and 14. The plates are strung on a ring, which was uncut when they came into my hands. It is $\frac{3}{4}$ " thick and 3" in diameter; its two ends are secured under an oval seal ($\frac{1}{2}$ " by 1" in diameter), which bears on a countersunk surface an impression which indistinctly appears to be a bull standing to the proper right.

The language is correct Sanskrit, and the composition closely resembles that of the Chicacole plates of Indravarman.¹

The characters resemble those of the Chicacole plates of Dēvēndravarman, son of Guṇārjuna.² The slight difference may be due to the style or the skill of the engraver.

Orthography.—The *Upadhāniya* is invariably expressed by a sign representing the Telugu intensive *r* ౠ, e.g. in ll. 5, 10, 19, 20, 21. The *Jihvāmālīya* is represented by a sign indicating *m*, e.g. in ll. 16 and 20. Consonants following *r* are doubled, e.g. in ll. 2, 3, 8, 9, 11, 13, 15, 22, 23, 27, 28, 30, 31. The following are exceptions:—in line 10 (*chandrārka*); ll. 16 and 18 (*ṛjuna*). Consonants preceding *r* are not doubled. Of palaeographic interest is the vowel letter *ē* (l. 18), inasmuch as it is in this plate that it is first found.

The plates record the grant of the village Bhukkukura in the Kūraka rāshṭra to Bhavadattaśarman, who was a student of *Ṛig-Vēda*, well-versed in *Vēdas* and *Vēdāṅgas*, an inhabitant of Tirilīṅga, and who belonged to the Kausika gōtra.

The donor of the grant was the Gāṅga king Indravarman, son of Dānārjuna. As the *prāśasti* of the grant is the same as that of the Chicacole grant of Indravarman above referred to, no comment is required.

The grant was made on the full-moon day of Kārttika and was engraved on the 20th day of Pushya in the year 149 of the prospering victorious reign. This refers to the Gāṅga era, generally mentioned in the Kālīṅga grants. This grant, therefore, appears to be three years posterior to that of the Chicacole plates of Indravarman,³ dated 146. This son of Dānārjuna was, probably, the grandson and successor of the Indravarman of the Chicacole plates.

The order for the grant was issued by the Mahāmahattara Śivaśarman, who may have been the son of the Mahāmahattara Gaurīśarman of the grant of Indravarman,² dated 128; and father of Mahattara Śavaranandīśarman of the Chicacole grant of Guṇārjuna's son Dēvēndravarman.⁴

The writer of the grant was Khaṇḍichandra, son of Āditya-Bhōgika. The Chicacole grant of Guṇārjuna's son Dēvēndravarman is said to have been engraved by Śarvachandra, the

¹ Archaeological Survey of Southern India, Vol. IV, *Tamil and Sanskrit Inscriptions*, by Jas. Burgess, Part III, No. 17, pp. 161 sqq.

² *Ep. Ind.*, Vol. III, No. 21, p. 130.

³ Archaeological Survey of Southern India, Vol. IV, *Tamil and Sanskrit Inscriptions*, by Jas. Burgess, Part III, No. 18, pp. 164 sqq.

⁴ *Ep. Ind.*, Vol. III, No. 21, p. 131.

son of Khandichandra-Bhogika; and Āditya, the son of Vijayachandra, is stated to have engraved the Chicacole grant of Indravarman, dated 128. The Chicacole grant of Indravarman, dated 146, is stated to have been engraved by the state *Bhogika*, probably Āditya. The office of the engraver appears to have been hereditary, like that of the *ājāpti*.

The composer of the grant was the 'Minister-General' Śāmbapura-Upādhyāya, the son of Dharmachandra, the chief of the elephants (*Hastyaadhyaksha*).

Of the localities mentioned in the grant the following require mention:—

Dantapura.—The royal residence from which the grant was issued was evidently in the kingdom of Kalinga.

Dantapura is mentioned in the *Daladavaṃsa*. It is said that the left canine tooth of the lower jaw of Buddha was brought by one of his disciples to Kalinga and a large *stūpa* was built over it. In course of time a large city rose round the *stūpa*, and it was called Dantapura. The Buddhists all lived in a village close by. The people of Ceylon, attracted by the miracles worked by the tooth, established a colony not far from Dantapura. Ultimately, when the *stūpa* was destroyed by the malice of the Brahmins, the tooth was taken away to Ceylon.

On the way from Chicacole to Siddhāntam (Siddhārthaka-grāma, a Buddhist village) and close to the latter place a large tract of land is shown as the site of the fort of Dantavakra. Valuable jewels, images of all kinds, coins and such other articles used formerly to be found there by the cultivators. Even now the people believe that there was once immense wealth there. About twelve miles north of Siddhāntam and on the same side of the Nāgāvali is the village Hiramandalam, which name is only a corruption of Īramanḍala (the Tamil Īla-manḍalam), the ancient name of Ceylon. Siddhāntam must have been the village where the Buddhists lived. These facts prove that Dantapura stood on the place which is now shown as the site of the fort of Dantavakra.

Kūraka rāṣṭra has, perhaps, given its name to the village of Kurchavalsa, about four miles north-west of Siddhāntam. *Rāṣṭra* properly means 'a kingdom.' As parts of the Kalinga kingdom were termed *vishayas* in the Rāgolu Plates of Śaktivarman¹ (Kalinga itself was a *vishaya* and Varāhavartini was a *vishaya* of Kalinga), why is this district here called a *rāṣṭra*? Perhaps, this was at first an independent kingdom, but was subsequently conquered and subdued by the kings of Kalinga.

Bhukkukura is **Bukkur** in the Pālakoṇḍa *Tāluk* and is opposite to Purle on the river. It was on the Bukkur bank of the river that the plates are said to have been discovered.

From the position of Kurchavalsa and Bukkur it may be seen that the *Kūraka rāṣṭra* corresponds to the modern Pālakoṇḍa *Tāluk*.

Tiriliṅga is clearly **Triliṅga**.

TEXT.

First Plate.

- 1 श्रीं स्वस्ति विजयवतो दन्तपुरवासकाश्चन्द्रावलमिखरप्रतिष्ठ-
- 2 तस्य चराचरगुरोस्त्वकलभुवननिर्माणेकसूचधारस्व भगवतो गो-
- 3 कर्णस्वामिनचरणकमलयुगलप्रणामादिगतकलिकलहो मा-
- 4 ङ्गामलकुलतिलकस्त्रासिधारापरिस्त्रादिगतसकलकलिहवि-

¹ *Ep. Ind.*, Vol. XII, No. 1.

² This is expressed in the original by the symbol of a spiral.

- 5 राज्ये विततचतुर्दधिसलिलतरङ्गमेखलावनितलाम-
 6 लयथाः अनेकसमरसंचद्विजयजनितजयशब्दप्रतापोपन-
 7 तसमस्तसामन्तचूडामणिप्रभामञ्जरीपुञ्चरञ्जितचरणो माता-
 8 पिढपादानुध्वातः श्रीमहानाथैवसूतुः श्रीमान्महाराजेन्द्रव-

Second Plate ; First side.

- 9 र्मां कूरकराट्टे भुक्कुरच्छेदकर्ण्यकान्कुटुम्बिनस्समाज्ञापयति [1*] वि-
 10 दितमस्तु वो यथायं च्छेदस्सर्व्वकरभरैपरिहृत्याचन्दार्कप्रतिष्ठं क-
 11 त्वा मातापिबोराकनश्च पुण्याभिहृदये कार्तिकपौर्णमास्यां सलिलपु[र्व्व*]-
 12 कं कौशिकसगोत्राय [व]ज्रवसन्नञ्जचारिणे तिरिन्निङ्गवास्त-
 13 व्याय वेदवेदाङ्गपारगाय भवदत्तशर्म्मेणे सस्मत्तस्तदेवं
 14 विदित्वा यथोचि[तमो]गभागमुपनयन्तः[.] सुखं प्रतिवसतेति [॥*] सीमा-
 15 लिङ्गानि चाव प्रदक्षिणक्रमेण बोधव्यानि [1*] पूर्व्वेण वल्मीकादारभ्य पुरुष-
 16 च्छाययार्जुनवृक्षस्ततो वल्मीकस्ततो वल्मीकसहितङ्करञ्जवृक्षः दक्षि-

Second Plate ; Second side.

- 17 येन करञ्जवृक्षाण्यमृति पुरुषच्छायया पाषाणास्तयः [1*] पश्चिमे-
 18 न पाषाणाण्यमृति पु[र्व्व*]पच्छायया पाषाण एव ततोर्जुनवृक्षस्तत-
 19 ऽप्राणाः [1*] उत्तरेण पाषाणाण्यमृति पुरुषच्छायया तिमिरह-
 20 च्छस्ततऽप्राणास्ततः पाटसन्धिक्रमेण पाषाणस्तत-
 21 ऽप्राणा एव ततो वल्मीक इति [॥*] भविष्यतश्च राज्ञेन्द्रा-
 22 पयति [1*] धर्मक्रमविक्रमाणामन्यतमयोगादवाप्य मही-
 23 सु(म)नुशासद्विरयन्दानधर्मोनुपालनोयो(यः) [1*] व्यासगीताद्याव श्रो-
 24 काः [1*] बहुभिर्व्वसुधा दत्ता बहुभिचानुपालिता [1*] यस्य यस्य

Third Plate.

- 25 यदा भूमिस्तस्य तस्य तदा फलम् [॥१*] स्वदत्तां परदत्तां वा यज्ञाद्रथ
 26 युधिष्ठिर [1*] महीमहीमतां च्छेद दानाच्छेयोनुपालनम् [॥२*] षष्टि-^१
 27 वर्ष्वसहस्राणि स्वर्ग्यं तिष्ठति भूमिदः [1*] आचक्षेता चानुमन्ता च तान्येव
 28 नरत्वे वसेदिति [॥३*] आत्मा महामहत्तरशिवशर्मा [1*] प्र[व*]र्द्धमान-
 29 विजयराज्यसंवत्सरा[.] १०० ४० ८ पुष्य दि ३०^२ लिखितमिदं शास-
 30 नं हस्त्वक्षयचक्षयचन्द्रसुनुना सर्व्वाधिक्रतेन शास्वपुरोपाख्याये-
 31 मोलीकृष्णमादित्यभोगिकतनयेन खण्डिचन्द्रेणेति ॥

^१ Read षष्टि.

^२ [The symbol following द्वि represents 20 and not 30. After this comes a punctuation represented by a spiral.

First Plate.

1 ॐ नमो भगवते वासुदेवाय ॥ १ ॥
 2 गङ्गायाम्बुजोत्पत्तौ श्रीगणेशाय नमः ॥ २ ॥
 3 श्रीगणेशाय नमः ॥ ३ ॥
 4 श्रीगणेशाय नमः ॥ ४ ॥
 5 श्रीगणेशाय नमः ॥ ५ ॥
 6 श्रीगणेशाय नमः ॥ ६ ॥
 7 श्रीगणेशाय नमः ॥ ७ ॥
 8 श्रीगणेशाय नमः ॥ ८ ॥

Second Plate : first side.

10 श्रीगणेशाय नमः ॥ १० ॥
 11 श्रीगणेशाय नमः ॥ ११ ॥
 12 श्रीगणेशाय नमः ॥ १२ ॥
 13 श्रीगणेशाय नमः ॥ १३ ॥
 14 श्रीगणेशाय नमः ॥ १४ ॥
 15 श्रीगणेशाय नमः ॥ १५ ॥
 16 श्रीगणेशाय नमः ॥ १६ ॥

Second Plate : second side.

18 श्रीगणेशाय नमः ॥ १८ ॥
 19 श्रीगणेशाय नमः ॥ १९ ॥
 20 श्रीगणेशाय नमः ॥ २० ॥
 21 श्रीगणेशाय नमः ॥ २१ ॥
 22 श्रीगणेशाय नमः ॥ २२ ॥
 23 श्रीगणेशाय नमः ॥ २३ ॥
 24 श्रीगणेशाय नमः ॥ २४ ॥

Third Plate.

26 श्रीगणेशाय नमः ॥ २६ ॥
 27 श्रीगणेशाय नमः ॥ २७ ॥
 28 श्रीगणेशाय नमः ॥ २८ ॥
 29 श्रीगणेशाय नमः ॥ २९ ॥
 30 श्रीगणेशाय नमः ॥ ३० ॥

TRANSLATION.

(Line 1.) Om! Hail! From (his) victorious residence (*vāsakāt*) at (the city of) **Dantapura** the son of the glorious **Dānārjaya**, the glorious **Mahārāja Indravarman**—who has had the stains of the Kali age washed away by obeisance to the lotus feet of the divine (God) **Gōkarṇa-Svāmin**, the lord of the movable and immovable (creation), the sole architect for the creation of the whole universe, who is established on the summit of the mountain **Mahendra**—who is the ornament of the family of the **Gāṅgas**—who has obtained the supreme sovereignty over the whole of **Kaliṅga** by the quivering of the edge of his own sword; whose fame is stainless over the earth, which is girt about by the waves of the water of the four wide-spreading oceans; whose feet are tinted by the mass of the clusters of blossoms which are the lustre of the crest-jewels of all the chieftains who have been made to bow down by his prestige of the cries of triumph occasioned by victory in the contests of many battles; and who meditates on the feet of (his) parents—issues the (following) order to all the householders cultivating the division of **Bhukkukura** in the **Kūraka-rāṣṭra** :—

(L. 10.) Know ye! This land, having been exempted from all taxes (and) having been established (as a village) to continue as long as the moon and the sun may last, has been given, for the increase of the religious merit of (our) parents and of ourselves, with an accompaniment of libations of water, on the full-moon-day in the month of **Kārttika**, to **Bhavadattaśarman**, of the **Kauśika gōtra**, a student of the **Rig-Veda**, a resident of **Tiriliṅga** and well-versed in **Vēdas** and **Vēdāṅgas**. Having known this, dwell ye in happiness, tendering (to him) the proper share of the profit therefrom.

(L. 14.) The marks of the boundaries in the *pradakṣiṇa* (right to left) order may here be noted thus :—On the east, beginning with an ant-hill, (there are) at (a distance which equals) the shadow of a man,¹ an *Arjuna* tree, then an ant-hill, then a *Karañja* tree together with an ant-hill. On the south, from the *Karañja* tree, at (a distance which equals) the shadow of a man, three boulders. On the west, beginning with the boulder, at (a distance which equals) the shadow of a man (there is) a boulder only, then an *Arjuna* tree, then a boulder. On the north, beginning with the boulder, at (a distance which equals) the shadow of a man (there is) a *Timira* tree,² then a boulder, then in the form of a door-joining (there is) a boulder and then a single boulder (and) then an ant-hill.

(L. 21.) And he (the king) admonishes future kings :—This meritorious gift should be preserved by those (kings) who rule the earth, having obtained it by right, inheritance, or conquest, one or other means. With reference to this (subject) there are verses sung by **Vyāsa** :—

[The three customary verses.]

(L. 28.) (By) the order of the **Mahā-Mahattara Śivaśarman**—this edict was written by **Śāmbapura-Upādhyāya**, son of the **Hasty-adhyakṣa**—the chief of the elephants—the *sarv-adhikṛita* **Dharmachandra**, on the 20th day in the month of **Pushya** of the year 100 40 9 of the augmenting victorious reign; and was engraved by **Khaṇḍichandra**, son of **Āditya-Bhōgika**.

¹ On *puruṣa-cāchādyā* cf. *Ep. Ind.*, Vol. III, p. 134, n. 1.

² [*Timira* is the Sanskrit translation of the Telugu *chikufi*, which is the name of the tree *acroticon pictorius*.—H. K. B.]

No. 28.—TUPPAD-KURHATTI INSCRIPTION OF THE REIGN OF AKALAVARSHA
KRISHNA III: SAKA 868.

By LIONEL D. BARNETT.

Tuppad-Kurhatti is a village of Navalgund Taluk, Dhārwar District, and lies in lat. $15^{\circ}32\frac{1}{2}'$ and long. $75^{\circ}32\frac{1}{2}'$, about $9\frac{1}{2}$ miles nearly east of Navalgund town. Its name is spelt as "Tapadkurhatti" in the *Postal Directory of the Bombay Circle*, "Tupad Kurhatti" in the Bombay Survey sheet 332, and "Toopud Kooruttee" in the old Indian Atlas sheet 41. The name, correctly spelt, is *Tuppada Kurīhatti*, "Kurīhatti of the Butter," apparently on account of the excellence or abundance of the butter produced in the village. *Kurīhatti*, in Old Kanarese *Kurīpattī*, means "ram's fold," and we find a semi-sanskritised variant of this in *Mēshada-pattī* (l. 31). Apparently the full name in ancient times was *Karapa-Guripattī*, "Kuripattī of the Office" (ll. 12-13). The stone bearing the present record was found in front of the temple of Māruti in the village, broken into two or three pieces. Ink-impressions of it were made for the late Dr. Fleet, and are now in the British Museum; from them I have edited the text.—The stone is a rectangular block; the top is surmounted by three triangular finials, one in the middle and one at each corner. It contains on top two bands, each of which is divided by two columns into three compartments. The lower band has some sculptures, namely a *linga* on a stand in the central compartment, a squatting figure in the proper right compartment, who holds something like a broom or a chowrie in his left hand, and a cow with sucking calf in the left compartment. Below this is an inscribed area about 1 ft. $11\frac{1}{2}$ in. wide and 3 ft. $4\frac{1}{2}$ in. high.—The character is good Kanarese of the period. Most of the letters are between $\frac{1}{2}$ in. and 1 in. high, though some are a little taller. The vowel signs $\tilde{}$ and $\circ$ are usually formed in the later manner; but occasionally they are written in the ancient fashion (e.g. *Beṭvola*, l. 8, *°yycōlam*, l. 19). The archaic subscript *l* in *illa* (l. 20) is also noteworthy. The palatal $\tilde{n}$ appears in *viñyāna* (l. 11), a mistake for *viñāna* which shews that *jñ* was pronounced by the writer in the same manner as by modern Tamils.—The language is Old Kanarese, except in the formal verses 1 and 2 (ll. 23-27). The $\tilde{}$ is preserved (*iḍu*, l. 14; *nāḷ-gāmuṇḍara*, l. 17; *ṣṭṭ*, ll. 21, 22; *aḷṭ*, ll. 22, 23), except in one case, where it is written as *r* (*nār-ggāmuṇḍam*, l. 14). Final *m* is sporadically changed to *v* before vowels in *°pāḍivav* (l. 6) and *neṣavav* (l. 19). There is an archaic participle-form in *kādom* (l. 21, in a formula). Lexically noteworthy are *neṣapa*, from the Sanskrit *nicṣāna* (l. 19), the locative verb-noun *modal* (ll. 29, 30: Kittel gives only *mudu* and its parts), and *hastā*, apparently with the meaning of *pakṣa* (l. 30). We find a genitive used as a semi-nominative in *Āyachayyana māḍisida dēgulakke* (l. 15: cf. my note in *Journ. Roy. As. Soc.*, 1918, p. 105).

The record opens by referring itself in ll. 1-3 to the reign of Akāḷavarsha (the Rāṣṭrakūṭa Krishna III), and then states that in the year Parābhava, Śaka 868, while his viceroy Satyavākya Koṅṅuṇivarma Permānaḍi, entitled "lord of Kōḷālapura best of cities" and "master of Nanda-giri," was governing Puligere and Beṭvola (ll. 3-10), and the latter's subordinate Āyachayya was administering Karapa-Guripattī (ll. 10-13), certain local officials granted lands for the maintenance of a temple founded by Āyachayya (ll. 13-20). Then come formulae of the usual kind (ll. 20-27), followed by a verse recording that on a certain date some years previously the god Āyachēśvara (i.e. the form of Śiva worshipped in the above-mentioned temple founded by Āyachayya) revealed himself in the town (ll. 28-31); this may have been the event which led to the establishment of the temple, as was the case at Kurgōḍ (above, p. 278). The viceroy Satyavākya-Koṅṅuṇivarma Permānaḍi is evidently the same as the Gaṅga Būtuga, the son-in-law of the Rāṣṭrakūṭa Amoghavarsha-Vaddiga, and hence a brother-in-law of Krishna III (see *Dyn. Kanar. Distr.*, pp. 304, 419, 421, and the Gāwarvāḍ inscr. above).

¹ See note on translation, below.

We have thus two dates in the inscription, the one for the grant to the temple and the other for the revelation of the god. The first is specified in ll. 3-6 as Śaka 868, Parābhava; Bhādrapada śu. 1; Sunday. This is irregular according to the Southern Cycle, in which Parābhava is equated with Śaka 868 *expired*; for by the *Sūrya-siddhānta* the *tithi* śu. 1 was current on Friday, July 31, A.D. 946, and Mr. Sewell, who has kindly examined the dates for this paper, points out that by the *Ārya-siddhānta* śu. 1 was expunged. It follows therefore that the date intended was Śaka 868 *current*, Parābhava, according to the Northern Cycle, by which the *tithi* śu. 1 was connected with **Monday, 11 August, A.D. 945**, and ended on that day 16 h. 5 m. after mean sunrise (for Ujjain); it was, therefore, current during the last 8 h. 26 m. of the preceding Sunday, which, hence, by a slight irregularity might be coupled with it (cf. Mr. Venkatasubbiah's *Some Śaka Dates in Inscriptions*, p. 69).

The second date is given on ll. 28-30 as Śaka 864 (current), Śubhakṛit; Jyāishṭha śu. 15 (apparently); Thursday. These data also imply the use of the Northern Cycle, according to which the *tithi* was connected with **Thursday, 13 May, A.D. 941**, and ended 15 h. 55 m. after mean sunrise for Ujjain. Mr. Sewell informs me that practically the same results are obtained by applying the *Ārya-siddhānta*: calculating for true motions of sun and moon, the difference is only 34 m., and calculating for mean motions, it is 1 h. 38 m.

The geographical names mentioned are Kōlālapura (l. 7), Nanda-giri (l. 7), the Three-hundreds of Puligere and Belvola (l. 8), Karaṇa-Guripattī (l. 13) with the sanskritised form Mēshada-pattī (l. 31), and Dēvaṅgēri (l. 18). Kōlālapura is Kolhāpur.¹ On Karaṇa-Guripattī see above. Dēvaṅgēri is perhaps the modern Deogēri, in the neighbourhood of Gadag town.

TEXT.²

[Metres: v. 1, *Anuṣṭubh*; v. 2, *Śālinī*; v. 3, *Mattābhavikṛīḍā*.]

- 1 Svasty-Akālavarsha-dēva-Śrī-Prithuvī³-vallabha-mahārājādhira-
- 2 ja-paramēśvara-paramabhūṭārara vijaya-rājyam-uttarōttar-ābhivri(vri)-
- 3 ddi-pravarddhamānam-ā-chandr-ārka-tāram-baram salutt-ire [*] Sa(śa)ka-nripa-
- kā-
- 4 l-āṭita-samvatsara-sa(śa)taṅga]-eṇṭu-nūra aruvatt-eṇṭaneya
- 5 Parābhava-samvatsaram pravarttise tad-varsh-ābhyā(bhya)ntarada Bhādrapada-
- 6 su(śu)ddha-pāḍivav-Ādityavāradandu Satyavākya-Koṃguṇivarmma-dha-
- 7 rmma-mahārājādhirāja[m] Kōlālapuravar-śeva(śva)ram Nanda-giri-nātham
- 8 śrīmat-Permmānādiga]-Puligere-mūnūruvam Belvola-mūnū-
- 9 ruvam duṣṭa-nigraha-ṣi(śi)ṣṭa-pratipālanadim suka(kha)-samkha(ka)-
- 10 tā(thā)-vinōdadin-ā[utt-ire [*] Permmāḍiya pāda-padm-ōpaj-
- 11 vi ananta-guṇa-vimala-viñyā(jñā)na-lakṣmī-lakṣita-vakṣa[s*]-
- 12 sṭhalam-parama-māhēśva(śva)ram śrīmat-Āyachayyaṃ Kara-
- 13 ṇa-Guripattīyan-abhyantara-siddhiy-āle [*] Belvola-mūnūra
- 14 nār-ggāmundaṃ Tōḍayyanum⁴-aruvar-ggāmundaḡum-ildu Āyacha-
- 15 yyana māḍisida dēgulakke biṭṭa keyyi rāja-māna-matta-
- 16 r-ayvattu 50 tōṭṭakk-endu koṭṭa mattar-ondū 1 idarke arasara de-
- 17 sege siddh-āyaṃ poṃ-gadyāṇam-erāḍu 2 nāl-gāmundaṃ de-
- 18 gaṃ siddh-āya[m*] poṃ-gadyāṇam-erāḍu 2 Dēvaṅgēriyol-āl-ka-
- 19 yyolam-ay-gayyolam maneya nesaṇav-irppatta nālku
- 20 24 int-1 keygam-manegam perad-ondun-terey-illa [*] idam
- 21 [kā]d-ātam liṅgamam kavileyuman-āl-kōṭiyuma[m*] kādom

¹ [Kōlālapura is generally identified with Kōlār in the Mysore State: Dr. Fleet's *Kanarese Dynasties*, p. 297.—H. K. S.]

² From the ink-impressions.

³ Read *Prithivī*.

⁴ Or possibly *Tōḍayyanum*.

- 22 idan-ālid-ātam lingamam kavileyum-āḷ-kōṭiyam Vāraṇṇa-
 23 siyuman-āḷida paṇcha-mahā-pātakan-akkum Sva-datt[5*]m-pa-
 24 ra-datt[5*]m vā yō harā[ta vasundha]rām [1*] aśaṣṭim varisha¹-sahasrāṇi(ṇi)
 25 viaṣṭhāyam jāyatō kri(kṛi)[miḥ] [|| 1*] [Sāmā]nyō-yam dharmma-āstu[r-nṛi]-
 26 pāpān kāḷe kāḷe pāṇiyo ahavabdhī² [1*] sarm[m]ā(rvvā)n-āṣṭāh(n) bhāgi[nab]
 27 pārtthivēndr[ān*] bhūyō bhūyō yāchatō Rāmacha[m*]dra[h] [|| 2*]
 28 Sa(sa)ka-kālam chavū-shaṣṭiy-āṣṭa-sa(sa)tamun-tān-āge [sarm]vatsa[ram]
 29 suka-santam Subhakri³-pravarttane modal-Jāṣṭam-mahā-su(sa)ddha-nāma-
 30 ka-hastha(sta)m vari(re ?)y-ānta[gaṇ ?]⁴ ti[thi ?] modal-vāram Bṛihaspatyadanda
 ka-
 31 ram⁵-Mēshada-paṭṭi-nāma-purado[-pratyakṣam-Āyachōsva(śva)ram [3*]

TRANSLATION.

(Lines 1-3) Hail ! while the victorious reign of king Akālavaraṣa, the darling of Fortune and Earth, great Emperor, supreme Lord, supreme Master, was advancing in a course of successively increasing prosperity, (to endure) as long as moon, sun, and stars :—

(Lines 3-10) while the cyclic year Parābhava, the eight-hundred and sixty-eighth of the centuries of years elapsed from the time of the Śaka king, was current, on Sunday, the first (lunar day) of the bright fortnight of Bhādrapada in that year, when Satyavākya Koṅguṇi-varma the great emperor of righteousness, lord of Kōḷālapura best of cities, master of Nandagiri, Permāṇḍi, was governing the Puligere Three-hundred and the Belvola Three-hundred, so as to suppress the wicked and to protect the excellent, with enjoyment of pleasant conversations :—

(Lines 10-13) while he who finds sustenance at Permāṇḍi's lotus-feet, he whose breast is marked by (the presence of) the genius of endless virtue and stainless wisdom, a supreme worshipper of Mahāśvara, Āyachayya, was administering Karaṇa-Guripaṭṭi with internal authority :—

(Lines 13-20) Tonḍayya, the county-Gāmuḍa of the Belvola Three-hundred, and the Six Gāmuḍas in concert granted for the temple constructed by Āyachayya a field, fifty mattar by the king's measure, (and) gave for a garden one mattar. On this, for the share of the king the fixed revenue (shall be) two gold gadyāṇas, for the share of the county-Gāmuḍas the fixed revenue two gold gadyāṇas. (They also gave) twenty-four dwelling-houses of seven cubits and five cubits (in width) at Dēvaṅgēri. Thus on this field and houses there is not a single other impost.

(Lines 20-23 : a prose formula of the usual type.)

(Verses 1-2 : common Sanskrit formulae.)

(Verse 3) When the Śaka date was eight-hundred and sixty-four, while the cyclic year Subhakṛit pleasant and peaceful was in progress, while Jyāishṭha (and) the fortnight named the great bright one were going on, during the course of the last lunar day (of the fortnight), on Thursday, Āyachōśvara verily revealed himself in the town named Mēshada-paṭṭi.


¹ Read *varsha*.

² Read *āhavadbhī*.

³ Read *Subhākṛit*.

⁴ I give the above emendations in the first half of the line with considerable diffidence. The use of *karta* in the sense of *paṭṭa* is new to me, though both words may be used in chronograms to denote a pair. *Fari* may also be the same as *darī*, i.e. *paṭṭa*, and, if so, the emendation *śatagaṇ* will be wrong. But in spite of these difficulties the above emendations seem to meet the requirements of the case better than any others.

⁵ It is possible that *Karava-Mēshada-paṭṭi* should be read as a compound, corresponding to *Karaṇa-Guripaṭṭi* of ll. 13-15 (para. "141" corresponding to *karaṇa*, "office," "treasury").



No. 29.—A NOTE ON KING CHANDRA OF THE MEHARALI INSCRIPTION.

By R. D. BANERJEE, M.A.

A tall slender pillar of iron, almost entirely pure, stands in the courtyard of Masjid Quwwat-ul-Islam within a few feet from the Qutb Minār. Among the various inscriptions incised on it, the largest is a record of six lines, in characters of the fourth century A.D. The final edition of this inscription is to be found in Dr. Fleet's *Gupta Inscriptions*.¹ According to this record a king named Chandra had defeated a combination of his enemies in Eastern Bengal (*Vaṅga*), had crossed the seven mouths of the Indus during his wars, defeated the *Vāhlikas*, and set up a standard of Vishṇu on a hill called Vishṇupada. Scholars have offered numerous suggestions concerning the identity of this prince. Dr. Fleet was of opinion that this king Chandra was probably Chandragupta I of the early Gupta dynasty.² Dr. V. A. Smith thought that this king Chandra was the same as king Chandragupta II of the early Gupta dynasty and in the first two editions of his *Early History of India* assigned the inscription on the iron pillar at Mēharauli to the son of Samudragupta. Mahamahopādhyāya Hara-Prasād Śāstri is of opinion that this king Chandra is Chandravarman, son of Simhavarman of Pushkarapā, whose inscription has been found at Susunā in the Bankura District of Bengal.³ Recently Mr. R. G. Basak has thought fit to revert to the theory of the late Dr. J. F. Fleet concerning the identity of the prince mentioned in the Mēharauli pillar inscription and identifies him with Chandragupta I, the father of Samudragupta.⁴

Mr. Basak's paper opens with a statement the accuracy of which is doubtful and which, so far as is known, cannot be supported by Epigraphical evidence. Mr. Basak says: "In the early part of the fourth century A.D. there was a great defeat of the people of Bengal (*Vaṅga*) by a king named Chandra"; but the record on the iron pillar at Mēharauli merely states that the king defeated "a combination of his enemies in the Vanga countries."⁵ The plural is used instead of the singular, which is significant. The combination may have been of people who had no relation with the people of Bengal, but who had either established small principalities in Eastern Bengal or had been driven to take shelter in that region. There is no mention of the "people of Bengal" in this record, and we are not in a position to determine whether the "people of Bengal" were able to take part in these struggles at that period or not.

The principal argument on which Mr. Basak bases his identification of king Chandra of the Mēharauli pillar with king Chandragupta I of the Gupta dynasty is the statement on the iron pillar inscription that king Chandra "attained sole supreme sovereignty in the world, acquired by his own arm and (enjoyed) for a long time." According to Mr. Basak this statement "applies more to an early Gupta ruler of the fourth century than to any local king of any of the small states then ruling independently in Northern India."⁶ Mr. Basak assigns no reasons for his statement, and consequently it is difficult to trace the trend of his thought. Evidently the glamour of the early Gupta empire and its glory in later days enticed him to put forward this bold statement. Mr. Basak goes on to state: "So it is very likely that Samudragupta's father Chandragupta I, whom we know to have been the first *Mahārājādhirāja* of the Gupta line, began to establish the empire by going out for making conquests in Bengal, in part of the Punjab and also in the South and perhaps succeeded in incorporating portions at least of these provinces into his own kingdom, which after his death passed into Samudragupta's hands."⁷ It is true that Chandragupta I, the son of Ghaṭōtkachagupta, was the first *Mahārājādhirāja* of the Gupta dynasty; but there is absolutely no evidence which can lead us to believe that he was

¹ *Corpus Inscriptionum Indicarum*, Vol. III, p. 141.² *Epi. Ind.*, Vol. XIII, p. 133.³ *Fleet's Corpus Inscriptionum Indicarum*, Vol. III, p. 141.⁴ *Ibid.*⁵ *Ibid.*, p. 140, note I.⁶ *Ind. Ant.*, Vol. XLVIII, 1919, p. 98.⁷ *Ind. Ant.*, Vol. XLVIII, p. 101.

capable of leading an army into the Punjab or the south or that he ruled for a long time. He may or may not have been in possession of Bengal. The coins bearing his name and effigy and that of his consort Kumaradēvi the Lichchhavi, which an earlier generation of Numismatists assigned to this prince, are now taken as medals issued by the Emperor Samudragupta in memory of his parents.¹

The Méharauli inscription of Chandra states that he enjoyed suzerainty for a long time. But it is impossible to admit that Chandragupta I reigned for a long time. There is a consensus of opinion among orientalist on this point, and, as far as is known, Mr. Basak is the only advocate of this opinion. If we dismiss the doubtful evidence of the Bodh Gayā inscription of Trīkamala or Turamala of the year 64² and the Gayā plate of the time of Samudragupta of the year 9 (?), the oldest known inscription of the Gupta dynasty which is dated is the Udayagiri inscription of Chandragupta II of the year 82=400 A.D.³ Now the initial year of the Gupta era is generally admitted to be the time of the accession, or rather the coronation, of Chandragupta I sometime in 318-19 A.D. Udayagiri, where this inscription is to be found, is in Eastern Mālava, a province which was conquered or subjugated by Chandragupta II. This is proved by the existence of a new class of silver coins of Chandragupta II based on the Mālava and Saurāshtra fabric of silver coins which were introduced by Chandragupta II in imitation of the silver *drachmæ* of the Western Satraps.⁴ The conqueror of a new province or country generally conciliates the subjects of his newly conquered province by issuing coins of the same type which was in vogue immediately before the conquest rather than offend them by issuing a type unknown previously. This was done by Maḥmūd bin Sabuktigin,⁵ Muḥammad bin Sām⁶ and his immediate successors in the Punjab and Delhi,⁷ and by Akbar in Gujarat.⁸ The conquest of a province and its settlement generally takes some time; and, if we assign fifteen or twenty years for it, we have sixty or sixty-five years left for the reigns of Samudragupta and Chandragupta. It is hardly possible even to think of a short reign for Samudragupta when we consider the amount of work he did to conquer and consolidate the Empire. By common consent forty-five or fifty years have been assigned to Samudragupta, and the majority of Indologists agree with the late Dr. V. A. Smith in assigning a very short reign of ten or fifteen years to Chandragupta I and a long reign of at least fifty years⁹ to his son and successor Samudragupta. So it is impossible to maintain that Chandragupta I enjoyed a long reign, and consequently it is not possible to identify him with king Chandra of the Méharauli pillar inscription, who enjoyed the suzerainty, acquired with his own arms, for a long time.

In the second place is it possible to maintain that Chandragupta I led an expedition into the Punjab and Afghanistan and the Dekkhan? The negative evidence of the Allahabad pillar inscription is decisive on this point. If Samudragupta's father had done any campaigning in the North-West or the South, then it is perfectly certain that an able panegyrist of the type of *Sandhivigrahika-Kumārāmātya-Mahādandanāyaka* Harishēpa would have mentioned it and availed himself of such occurrences to extol the might of his master Samudragupta still further. The silence of the Allahabad *prastāvi* on this point enables us to state with a tolerable degree of confidence that Chandragupta did not campaign in the land of the five rivers or Afghanistan or lead an army into the Dekkhan. It is a pity that the first three lines of the Allahabad *prastāvi* can neither be completely read nor partially restored. It would have cleared up all doubts

¹ Allan's *British Museum Catalogue of Indian Coins, Gupta Dynasties*, pp. lxiv-lxviii.

² Cunningham's *Mahābodhi*, pl. XXV.

³ Fleet's *Corpus Inscriptionum Indicarum*, Vol. III, p. 25.

⁴ Allan's *British Museum Catalogue of Indian Coins, Gupta Dynasties*, p. lxxvi.

⁵ Cunningham's *Coins of Medieval India*, pp. 65-66.

⁶ Nelson Wright, *Catalogue of Coins in the Indian Museum, Calcutta*, Vol. II, p. 17.

⁷ *Ibid.*, pp. 19-37.

⁸ *Ibid.*, Vol. III, p. 37.

⁹ *Early History of India*, Third Edition, pp. 280-81.

about the beginning of the Gupta dynasty. The opening line of this record mentions Samudragupta's kinsmen, who seem to have had done something about the beginning of his reign.¹ Then, the list of kings and countries conquered by Samudragupta gives us a good idea of the states surrounding the parent state of the Gupta Empire, i.e. Magadha, and the rigid silence of Harishēpa about the achievements of Chandragupta I in these regions proves that that monarch secured his own independence and did little else. The first mention of Chandragupta I is to be found in the Mathurā fragmentary inscription of the time (?) of his grandson Chandragupta II.² Neither the Allahabad³ nor the Erap⁴ inscription mentions him, a fact which leads us to believe that the kingdom of Magadha was acknowledged as the paramount power in India only during the time of Samudragupta and the title of *Maharajadhiraja* was probably bestowed on Chandragupta I by his descendants. Chandragupta I may have been the real founder of the kingdom of Magadha and freed it from the yoke of the Scythian foreigner. Beyond this nothing can be said about Chandragupta I.

Mr. Basak questions: "Where is the evidence that Bengal had ever been in the possession of Chandravarman?"⁵ But he does not pause to think what evidence there is of the possession of Bengal by Chandragupta I. Copper-plate grants of the time of Kumāragupta and Budhagupta have been discovered in Northern Bengal. These are the Dhanaidaha⁶ and Damodarpur⁷ grants of Kumāragupta I and the Damodarpur grant of Budhagupta. But it does not seem to have struck Prof. Basak that these copper-plates cannot prove that Chandragupta I had any hold over any part of Bengal.

Another argument adduced by Mr. Basak in favour of his theory about the inclusion of Bengal in the kingdom of Chandragupta is the discovery of the coins of the Emperors of the early Gupta dynasty in Eastern and Western Bengal. Only one or two coins of Chandragupta I have been found in Bengal, and these coins too are not regarded by Allan, the latest authority on the subject, as being genuine issues of Chandragupta I, but as medals struck in memory of his parents by his son Samudragupta. Coins of Chandragupta II, Kumāragupta I and Skandagupta have been found in large numbers and indicate that probably Eastern and Western Bengal were included in the Empire of the Guptas in the fifth century A.D.

To sum up; it is not possible to admit that Chandragupta I of the early Gupta dynasty had a long reign; therefore he cannot possibly be the same person as king Chandra of the Meharauli inscription. Then, the existing evidence in both the Epigraphic and the Numismatic fields is insufficient to prove that Bengal was included in the kingdom of Chandragupta I, the first monarch of the Gupta dynasty, or that he campaigned in the Indus Delta. Finally Paurāṇic evidence, as quoted by Mr. Pargiter, proves very distinctly that Bengal was not included within the dominions of Chandragupta I. Mr. Pargiter says: "The Guptas are mentioned as reigning over the country comprised within Prayāga, Sāketa and Magadha." Mr. Pargiter concludes very correctly that this was "exactly the territory which was possessed at his death by Chandragupta I, who founded the Gupta dynasty in A.D. 319-20 and reigned till 326 or 330 (or even till 335 perhaps), before it was extended by the conquests of his son and successor Samudragupta."⁸ It is, therefore, almost certain that Bengal was never included within the dominions of Chandragupta I. In order to reconcile this directly hostile piece of evidence to his own theory Mr. Basak states: "Or it may be supposed that the Magadha of the Purāṇas probably included portion of Bengal conquered,"⁹ a statement which need not be taken seriously.

¹ Fleet's *Corpus Inscriptionum Indicarum*, Vol. III, p. 6.

² *Ibid.*, pp. 26-27.

³ *Ibid.*, pp. 6-10.

⁴ *Ibid.*, p. 20.

⁵ *Ind. Ant.*, Vol. XLVIII, p. 101.

⁶ *J. A. S. B.*, New Series, Vol. V, pp. 460-61, pl. ix.

⁷ R. Chanda's "*Indo-Aryan Races*," p. 273.

⁸ Pargiter's *Dynasties of the Kali Age*, p. xii.

⁹ *Ind. Ant.*, Vol. XLVIII, p. 101.

It is, therefore, certain that it is hardly possible to identify Chandragupta I of the early Gupta dynasty with king Chandra of the Mēharauli pillar inscription. We may now revert to Mr. Basak's question as to whether we possess any evidence which indicates that Bengal was at any time in the possession of Chandravarman. The answer is in the affirmative. We have evidence of the possession of a part, at least, of Bengal by Chandravarman in the Susuniā rock inscription of Chandravarman, son of Simhavarman, king of Pushkarapā.¹ Mr. Basak has taken this inscription to be a pilgrim's record without assigning sufficient reasons. So far as is known, there is no evidence to prove that Susuniā hill was at any time a place for pilgrimage of sufficient importance to draw devotees from the Western end of India. No remains have been found on the hill which might indicate that there was any famous shrine on this hill or near the inscription. It is very difficult to understand why Mr. Basak takes this inscription to be the record of a pilgrimage of king Chandravarman of Pushkarapā simply because he carved the discus of Vishṇu on a hill of Western Bengal. The inscription proves that a king named Chandravarman from Pushkarapā (modern Pokhara in the Jodhpur State) had come as far as Western Bengal proper and left his mark there in the form of a short record with one of the emblems of his principal deity incised on the hill, the only prominent landmark in the country, which is perhaps the only hill in Bengal proper. Let us connect the fact gleaned from this very short record with those obtained from the Mēharauli inscription of Chandra. The latter speaks of a king named Chandra, who had defeated a combination of his enemies in the *Vaṅga countries*. The full name of king Chandra may be either Chandranātha, Chandravarman or Chandragupta. In the Susuniā inscription we have a confirmation of one of the statements of the Mēharauli inscription that a king named Chandravarman had left the mark of his visit in Bengal. Then, both inscriptions are *Vaiṣṇava*; king Chandra had raised a staff of Viṣṇu on the Viṣṇupada hill, while Chandravarman had incised the wheel of Viṣṇu on the Susuniā hill. Whereas it is impossible to identify this Chandra with Chandragupta I of the early Gupta dynasty, the only alternative left open is to identify this Chandra of the Mēharauli pillar inscription with Chandravarman, son of Simhavarman, of the Susuniā rock inscription. The statement of the Mēharauli pillar inscription fits in very well with the case of Chandravarman, as he must have had a long reign.

The mention of Chandravarman among the chieftains of Āryāvarta, who were uprooted by Samudragupta, shows that that dynasty had come to an end in the North. Subsequent inscriptions prove that two more generations continued to rule independently in Western Mālava and the dynasty was finally subjugated during the reign of Kumāragupta I. In this connection certain inaccuracies which Mr. Basak has used to refute the statements of Mahamahopādhyāya Hara-Prasād Śāstri should be considered:—

The first of these is Mr. Basak's idea of the extent of the dominion of the early Guptas in Mālava. He says: "We know from Epigraphic records that in A.D. 404 Chandragupta II was on the Imperial Gupta throne. Hence we may safely suppose that Mahārāja Naravarman was Chandragupta II's feudatory in the Western regions."² The Mandasor inscription of Naravarman contains no reference to the suzerainty of the Gupta dynasty, and it is hardly correct to suppose that he had submitted to the Guptas. The only possible conclusion is that Naravarman had somehow or other evaded the yoke of the Guptas down to the year 461 V.E. = 404 A.D. The Gangdhar inscription of his son Viśhavarman³ clearly proves that Naravarman maintained his independence throughout and did not submit to the Guptas.

In the second of these extraordinary statements Mr. Basak asks us to believe that both Viśhavarman and his son Bandhavarman were feudatories of Kumāragupta I. He says: "We

¹ *Epi. Ind.*, Vol. XIII, p. 133.

² *Ind. Ant.*, Vol. XLVIII, p. 93.

³ *Fleet's Corpus Inscriptionum Indicarum*, Vol. III, pp. 74-75.

gather from other records that his (Naravarman's) son Viśvavarman and his son Bandhuvarman were feudatories of Kumāragupta I¹; and in a footnote he refers us to inscriptions Nos. 17 and 18 of Fleet's Gupta inscriptions. These are the Gangdhar inscription of Viśvavarman, son of Naravarman, of the year 480 V.E., and the Mandasor inscription of the year 493 V.E. of Bandhuvarman, the son of Viśvavarman. A careful scrutiny of the long record found at Gangdhar reveals nothing about a suzerainty of the Gupta Emperors over Viśvavarman, and the inevitable conclusion is that at the time of this record (480 V.E.=423-4 A.D.) Viśvavarman did not acknowledge the Gupta Emperors of the North as his suzerains. Turning to the Mandasor inscription of the time of Bandhuvarman and his suzerain Kumāragupta I, we find that Bandhuvarman was the ruler or governor of Daśapura when Kumāragupta was ruling and that Viśvavarman is mentioned as a king who was the father of Bandhuvarman. The past tense of the verb *to be* (*babhūva*) clearly indicates that Viśvavarman had ceased to exist. The verses about Viśvavarman were introduced as a parenthesis to show the descent of Bandhuvarman. The real connection is between *Kumāraguptā prithivīm prakāśati* (l. 13) and *Bandhuvarmanā Daśapuram-idam pālayati* (l. 16). Consequently it must be admitted that the Mandasor inscription of Bandhuvarman does not contain any reference or proof as to a suzerainty of the Early Gupta Emperors over Viśvavarman, king of Western Mālava, though the record clearly indicates that Viśvavarman's son Bandhuvarman was a feudatory of the Early Gupta Emperor Kumāragupta I. Therefore we cannot accept Mr. Basak's statement that Naravarman's son Viśvavarman was a feudatory of Kumāragupta I. Mr. Basak's idea apparently is that the dynasty of Jayavarman ruled the whole of Mālava from Daśapura; but the findspots of inscriptions of Naravarman and his son prove that they were rulers of a portion only of Western Mālava. Naravarman's inscription was found at Mandasor, while that of his son Viśvavarman was found at Gangdhar or Gangrar, Lat. 23° 56' N., Long. 75° 41' E., in the Gwalior State (sheet No. 35, Atlas of India, Survey of India Map printed in 1899). The tract of country in which these two inscriptions were found lies along the southern border of Mewar and runs along a range of hills. This country appears to have sheltered the descendants of Śiṃhavarman after the defeat of Chandravarman. The Udayagiri inscription of the year 82¹ and the Sāñchi inscription of the year 93,² both of the reign of Chandragupta II, prove that Naravarman and Viśvavarman had no hold on this part of Mālava.

We have, therefore, no reason to put any faith in the following statement:—"Samudragupta probably destroyed the independence only of the nine kings of Northern India among whom Chandravarman was one, and allowed them after their utter defeat to rule in their respective States as Gupta feudatories."³ It is clear from the statement of Harishāpa's *Pratāpti* that the nine kings of Āryāvarta were uprooted, i.e. their kingdom assimilated into the Empire (l. 21), while the kings of the south were captured and liberated, i.e. they were reinstated. The inscriptions of Chandravarman's brother Naravarman and his son Viśvavarman indicate very clearly that after his defeat by Samudragupta either Chandravarman himself or his brother Naravarman migrated into Mālava. There, in the hilly country in the North-West corner, adjacent to modern Mewar, they managed to maintain their independence till 423-4 A.D., and were subjugated by the Early Gupta Emperors at some date between 424 and 437 A.D. There is no doubt about the fact that Bandhuvarman, son of Viśvavarman and grandson of Naravarman, had in 437-38 A.D. lost his independence.

¹ *Ibid.*, p. 25.² *Ibid.*, pp. 30 and 34.³ *Ind. Ant.*, Vol. XLVIII, p. 99.

INDEX.¹

A		PAGE		PAGE
a, form of, ...		157, 164	adri, ...	100, 105
-a, Kanarese accusative ending, ...		266	Advaita doctrine, ...	233, 234, 357
ā, form of, ...		121	āgama, ...	101, 106, 317
ā-mātrā, form of, ...		144, 153	āgāmi, ...	318, 346
ābāha and bādha, ...		128 n. 7	Agara (?), vi., ...	321
Abdul Hasam, a Golconda k., ...		353	Agastī, ...	204
Abdullah Qutb Shāh, a Golconda k., ...		353	Agastya, ...	316
Ābhata, m., ...		205	Agastya, a gōtra, ...	81, 209, 215-21 ⁶
Abhaya-Siva, ...		283	āghāta, ...	187
Ābhidharma-lōka, a book, ...		291	Aghōra, an aspect of Śiva, ...	274 n. 2
Abhinava-Vijaya-Bukkarāya-samudra, vi., ...		69, 71, 82	agnihōtra, ...	151
abhitvaramāga, ...		327	Agni-Kula, a race, ...	369
Ābhō, m., ...		206	agrabāra, ...	358
Ābhū, m., ...		207	ahamahārikā, ...	301
āchāri, ...		225	ahamya, ...	159
Achasa, m., ...		205	Ahichchhatra, vi., ...	569
Achchhōda, a lake, ...		73, 80, 80 n. 3	Ahōbala, a shrine, ...	100, 102, 108, 171, 240
Āchharasa II., a Sinda ch., ...		268, 272, 276	ai-mātrā, form of, ...	144
Achhatyana (?), a gapa, ...		148, 152	Albirada-rāya-rāhuta-vāsyā-aka-bhujānga, sur. of the Vijayanagara k. Rāma-rāja, ...	211, 223
Āchi-dēva III., a Sinda ch., ...		268	Aināna-Malukka, ch., ...	210, 211, 231
Āchgi II., a Sinda ch., ...		268	Ain-ul-Mulk, ch., ...	211
Āchgi III., a Sinda ch., ...		268	Airāvata, ...	305
Achyuta, ...		101, 103	Airru-Bhatta, m., ...	314, 320
Achyuta-Rāya, a Vijayanagara k., 216, 230, 235, 311, 312, 316, 318, 321, 322, 323, 343, 353			Ājāru, vi., ...	358-9
ādado, ...		189	Ājātasatru, ...	326, 329
ādagunti, ...		266	Ājusha, m., ...	268
ādga, a measure, ...		359 & n. 7	Ākālavarsha, sur. of the Rāshtrakūṭa k. Krish- narāja I. & III., ...	123, 125, 126, 128, 129, 364-6
ādha, ...		138, 161	akale, ...	266
Adhiva, vi., ...		193, 196, 200	Ākhaṇḍala-Indra, ...	344
Ādi-Kēśava, a divinity, ...		197, 199	Ākitoru, vi., ...	345, 353
Ādi-Kēśava-ghaṭṭa, a place, ...		198, 199, 200	Akkā-Bhatta, m., ...	314, 315, 319, 321
Āditya, te. of, ...		126, 127, 129	Akkale-Bhatta, m., ...	342
Āditya Bhōgika, m., ...		360-3	Akkanma, a Golconda minister, ...	354-6, 358-9
Ādityavarman, a Maukhari k., ...		112, 115, 119	ākshapaṭalika. S. a. Mahā°, ...	109, 104, 327
Ādivarāha, a Pratihāra k., ...		179	akshata-tritiyā, ...	198-9

¹ The figures refer to pages; n. after a figure to footnotes, and add. to Additions and Corrections. The following other abbreviations are used:—ch., = chief; co., = country; di., = district, division; do., = the same, ditto; dy., = dynasty; E., = Eastern; feud., = feudatory; k., = king; m., = man; mt., = mountain; ri., = river; s. a., = see also; sur., = surname; te., = temple; vi., = village, town; W., = Western; wo., = woman.

	PAGE		PAGE
akshinī, ...	315, 346	Andhra, a people, ...	112, 117, 120, 140, 327, 330
akūthinēsa, ...	110 n. 1	Āndhra inscription of Śi-i-Paṇḍavī, ...	153
Ākūti-Vishṇu-Bhaṭṭa, m., ...	212	Āndhra-dēśa, province, ...	88, 90, 93, 96
Ālāda, m., ...	208	Āndhras, inscriptions of the, ...	140
Alagaddha (Lagarddha ?), m., ...	198	Āṅga, co., ...	73, 79, 170, 173, 316
Alakā, cf., ...	72, 79	āṅgaraksha, ...	327
Alas grant of Govinda II., ...	1 n. 5, 122	Āṅgiras, a prarara, ...	158, 161
Ālhaṇa, m., ...	202, 203 209	Ani-uddha, m., ...	99
Ālhū, m., ...	202	Annadātā, m., ...	69, 70, 71, 73, 80
ajidons, ...	189	Annadāmīrya, m., ...	75, 81
ājke, ...	189	Āṇṇapa, m., ...	74, 76, 81, 82
Allārya, m., ...	76, 82	Annaveṃa, a Eṣṣī k., ...	70
Allūraka, vi., ...	148	Ān-si, co., ...	290, 292
alphabet—		āntahpurika, ...	194, 198
Acute-angled, ...	No. 6	Antam (Annam)-Bhaṭṭa, m., ...	213
Bengali, ...	Nos. 10, 23	Antarai, vi., ...	126, 129
Brāhmī, ...	No. 9	antarāṅga, ...	160
Gāṅga, ...	No. 24	Antembavaragūḍa, sur. of the Vijayanagara k.	
Kādamba, ...	No. 11	Rāma-Rāja, ...	211
Kanarese, ...	Nos. 2, 14, 16, 17, 19, 22, 23	annāsikā, use of, ...	187
Kharoṣṭhī, ...	Nos. 7, 20	annavāra, > n., ...	122
Nandī-nāgarī, ...	Nos. 2, 12, 16, 17, 22, 25	„ doubling after, ...	69, 97
Nāgarī, ...	Nos. 16, 26	„ for n., ...	192
Northern, ...	Nos. 5, 13, 21	„ form of, ...	157
Telugu, ...	Nos. 3, 28	„ redundant, ...	147, 168, 210, 311, 341
Southern, ...	No. 8	„ use of, ...	68, 69, 122, 164,
Amarāvati, vi., ...	72, 79		168, 177, 266
Āmbāśāchārya, sur., ...	87	anviya, ...	150
Āmbārāma, vi., ...	148, 150, 152	Āpāpa, m., ...	331, 335, 336
Āmmāl—Nadādūr-ammāl, ...	87	Āpastamba-sūtra, ...	216, 313, 317, 342, 346
Āmmāl-āchārya, sur., ...	87	Appā-Dēvi, a Pratiṭhāra queen, ...	173, 183
Amṛitadhara, m., ...	202, 209	Appa Koṇḍa, m., ...	343
Amṛayillā, a place, ...	155, 161	Appalarāja, m., ...	341-2, 346
Āṇḍarū, vi., ...	195, 196, 200	Appale-Bhaṭṭa, m., ...	342
Āṇḍaurī, vi., ...	200	Appana, m., ...	74, 81
Ānandajñāna-Yōgin, a Kāśhī āchārya, ...	234	Appaṇa-āchārya, m., ...	75, 81
Ānāṅga—Kāma, ...	308, 309 n. 2	apporoge, ...	189
Ānāṅgārāya. See Madanāṅgārāya, ...	148, 152	Āratika-mallārū, sur., ...	346
Ānanta-Bhaṭṭa, m., ...	212, 213, 214, 315, 321	Āra inscription of Kanishka II., ...	130ff.
Ānantarāja, minister of the Vijayanagara k.		Āra, a place, ...	130, 132, 136
Buṭko I., ...	98, 102, 103-104, 107, 109	ara, ...	189, 191
Ānantarāja, a tank, ...	103, 104, 109	araghaṭṭa, ...	296, 303
Ānantarāja-sāgara, a tank, ...	99	arahanta, ...	295
Āpḍāl, wife of Paśāra-Bhaṭṭa VII., ...	85	arahata, ...	176, 186
Āndhaka, a giant, ...	119, 120	Ārakere, vi., ...	267, 273, 277
Āndhra, dyn., ...	159	Āraṇiyahāṇ, vi., ...	267, 273, 277

The figures refer to pages; n. after a figure to footnotes, and add. to Additions and Corrections. The following other abbreviations are used; — al. = chief; co. = country; di. = district, division; do. = the same, ditto; dy. = dynasty; E. = Eastern; feud. = feudatory; k. = king; m. = man; mt. = mountain; vi. = river; v. a. = see also; sur. = surname; te. = temple; vi. = village, town; W. = Western; wo. = woman.

	PAGE		PAGE
Bāṇa, <i>dy.</i>	234	Bhāradvāja, a <i>gōtra</i> ,	69, 70, 73, 80-82, 158, 161, 202-209, 212-216, 314-315
Banavāsi, <i>di.</i>	239	Bharadvāja, a <i>pravara</i> ,	153
Bandhuvārman, <i>k.</i>	370-1	bharaka,	300, 310
Bangarh grant of Mahipāla I.	324	Bharata, <i>k.</i> ,	72, 79
bāṇijya,	91	Bharata, <i>co.</i> ,	271, 274
Barabar Hill Cave,	112	Bharata-Khaṇḍa,	90
Bāṛhaspatya, a <i>pravara</i> ,	161	Bharata-Kaśētra,	279
Barmadēvarasa, a <i>Sīda</i> <i>cā.</i> ,	269	Bhārata-varaṇa, <i>co.</i> ,	88, 89, 90, 95
Basava-amātya, <i>m.</i> ,	215	Bharatha, <i>m.</i> ,	203
Basavā-Bhaṭṭa, <i>m.</i> ,	342	Bharathi, <i>vi.</i> ,	198, 199, 200
Basavappa, <i>m.</i> ,	215	Bhargava-Śiva,	270, 282
Basavarāja, <i>m.</i> ,	215	Bhārgava, a <i>gōtra</i> ,	203-205, 208-209
Bastar, <i>vi.</i> ,	269	Bhartṛi-paṭṭa, a <i>Gaṇika</i> <i>k.</i> ,	177, 181, 187
Bēchaliya = Bēchirāja,	237, 273, 277	Bhartṛi-vadāna, a <i>Cāḍamāna</i> <i>cā.</i> ,	179 n. 1
Bēcharasa = Bēchirāja,	267, 272, 276	Bhāṣa-ātīlāṅghī-bhūpāla, <i>sur. of</i> <i>Kṛiṣṇa-dēva-</i> <i>rāṇa</i> II.,	170 n. 2
Bēchirāja, <i>m.</i> ,	267, 272, 276	Bhāṣhege-tappuva-rāyana-gaṇḍa, <i>sur. of</i> <i>Vijaya-</i> <i>nagara</i> <i>kk.</i> ,	170 n. 2, 173, 344
Belagavatti, <i>vi.</i> ,	269	Bhāsi(Śaśi)dhara,	209
Bellare, <i>di.</i> ,	269	Bhāskara, <i>m.</i> ,	202, 203, 207, 209
Bejrola Three-hundred, <i>di.</i> ,	364-6	Bhāskara-Bhaṭṭa, <i>m.</i> ,	314, 319
Bemra, <i>vi.</i> ,	190	Bhāskara Bhavadūra, a <i>Vijayanagara</i> <i>prince</i> ,	98, 101-2, 104, 105, 106, 107, 109
Bengara, <i>co.</i> See Chengara,	83, 91, 96	bhaṭa,	327
betel-nuts,	182	Bhaṭṭa-Parāśara, <i>m.</i> ,	88, 89 n. 2, 93, 96
Bēvina-haḷḷi, <i>vi.</i> ,	210, 231	Bhaṭṭaputra, a <i>title</i> ,	323, 330
Bēvina-haḷḷi grant of Sadāśiva-Rāya,	210	Bhaṭṭar, a <i>family</i> ,	85, 86
bh, form of,	68, 157	bhaṭṭāraka,	126, 127, 129
bha, symbol of the moon,	101, 105	Bhaṭṭari, a <i>Vaiṣṇava</i> <i>teacher</i> ,	84
Bhābhū, <i>m.</i> ,	204, 209	Bhavadūra, <i>sur. of the</i> <i>Vijayanagara</i> <i>prince</i> <i>Bhāskara</i> ,	98, 102, 106 n. 8, 108
Bhādānū, <i>vi.</i> ,	198, 199, 200	Bhavagaṇḍa, a <i>Kāśṭhākrānta</i> <i>queen</i> ,	122, 124, 127
Bhadrāchala, a <i>shrine</i> ,	354	Bhavadattaśarman, <i>m.</i> ,	360, 362-3
Bhadrāśvara, <i>m.</i> ,	209	Bhavaśarman, <i>m.</i> ,	209
Bhadrāśvaradēva, <i>m.</i> ,	158, 161	Bhāyī, <i>vi.</i> ,	195, 196, 200
bhāga,	184, 186, 327, 328	Bhima,	272, 276
Bhāgama, <i>vi.</i> ,	195, 196, 200	Bhima, a <i>Sīda</i> <i>feud</i> ,	268, 276
Bhagavata, <i>m.</i> ,	204	Bhima II. = Irmaḍi-Bhima, a <i>Sīda</i> <i>prince</i> ,	286 n. 5
Bhagavati = Durgā,	178, 183	Bhīmasēna, <i>k.</i> ,	140
Bhāgirathi = Ganges,	193, 194, 196, 327, 330	bhōga,	184, 186, 195, 196, 199, 200, 327, 328
Bhāgya-dēvi, a <i>Pāla</i> <i>queen</i> ,	328, 329		
Bhairava = Śiva,	97, 104, 109		
Bhairava, <i>m.</i> ,	213		
Bhairava-Bhaṭṭa, <i>m.</i> ,	213		
Bhālana, <i>m.</i> ,	206, 207		
Bhāṇḍadaha, <i>vi.</i> ,	196, 196, 200		
bhāṇḍāgārika,	194		
Bhandak Plates of Kṛiṣṇarāja I.,	121ff., 121		
Bhānu-Bhaṭṭa, <i>m.</i> ,	214, 314, 318		
Bhānugupta, a <i>Gupta</i> <i>k.</i> ,	369		

The figures refer to pages; n. after a figure to footnotes, and add. to Additions and Corrections. The following other abbreviations are used: — *cā.* = chief; *co.* = country; *di.* = district, division; *do.* = the same, ditto; *dy.* = dynasty; *E.* = Eastern; *feud.* = feudatory; *k.* = king; *m.* = man; *mt.* = mountain; *vi.* = river; *s. a.* = see also; *sur.* = surname; *te.* = temple; *vi.* = village, town; *W.* = Western; *wo.* = woman.

	PAGE		PAGE
bhōgapatī,	126, 129	Bṛīhaj-Jābāla-Upanishad, a book,	274 n. 2
Bhōgāvati,	271, 275	Bṛīhaspati, a pravara,	158, 161
Bhōgāvati, Lord of, title of Sinda chiefs,	268,	Bṛīhatālū, vi.,	195, 200
	269, 277, 280, 281, 283	Bṛīhatyañchalāma, vi.,	195, 200
bhōgika,	150, 152, 361	broom figured,	364
bhōgika. See Mahābhōgika,	160	Buddha,	240, 295, 327
Bhōja, dyn.,	345	Buddhavatasa, m.,	147, 148, 150, 151, 152
Bhōja-dēva, a Pratihāra k.,	178, 179, 179 n. 3, 180, 183, 184	Buddhism,	357
Bhōjapāla, m.,	205	Budha,	171, 216, 323
Bhōjda-Bhatta, m.,	213	Budhagupta, a Gupta k.,	369
bhraṇa-bhitti,	104, 109	Bukka I., a Vijayanagara k.,	98, 107
bhrama-jala-gatī,	98, 99, 109 n. 4	Bukkamā, a Vijayanagara queen,	171, 217, 230, 323
Bhukkuḥura, dī.,	360-3	Bukka-Rāya, a Vijayanagara k.,	69, 71, 79
Bhūmaka, a Kshatrapa,	294	Bukkarāyasamadrām-Appa-Koṇḍa, m.,	343
Bhūmanātha, a deity,	273, 277	bull figured,	360
Bhūmarasa, m.,	215	Buśai-Bhatta, m.,	213, 214
bhūmi-chchhidra,	150, 152, 161	Būtuga Nanniya, a Gaṅga k.,	330, 364
bhūmi-chchhidra-nyāya,	327, 330		
Bhūtanātha, m.,	314, 319	C	
bhū-vara,	98	Censor, a title,	141, 142
Bhūyikā-dēvi, a Pratihāra queen,	178, 183	calf figured,	364
biḷa,	100, 105	censor,	156
Bijapur, vi.,	211	cā, form of,	121, 325
Bijayagadh inscription,	123	cā, symbolic,	100, 105
Bijjala, a Kalachurya k.,	268	Chāhamāpa, a family,	177, 179 n. 1, 180, 181, 182, 184, 186
Bijjala, a Sinda cā,	269	Chakkana, m.,	338
birds, figured,	205	Chakra, m.,	203
Biyyana-hatti, vi.,	267, 273, 277	Chakrapāci, m.,	343
boar, emblem,	147, 151, 341	Chākū, m.,	208
boar, seal,	168	Chalukya, W., dy.,	122, 127, 128 n. 6, 148, 149, 150, 151, 152, 189, 268, 269, 271, 274, 275, 279, 281, 282
Bōdha, a Kāścī ācārya,	294	Chamākha, vi.,	195, 196, 200
Bōdhāyana-Sūtra,	314-5	Chāmunda-Rāja, a Paramāra k.,	182, 187, 296, 300, 307
Bōdhisattva,	295	chaṇḍāla,	327, 330
Brahma-Bhatta, m.,	214	Chaṇḍapa, a Paramāra prince,	296, 299, 305
Brahmā-bhatta, m.,	343	Chandavali, vi.,	198, 199, 200
brahmaḍāya,	126, 129	Chanḍila, dy.,	179 n. 4
brahmaḍāya,	335	Chāṇḍō, m.,	206
Brahmaditya, m.,	209	Chandra-Chandra-dēva, a Kanyākubya k.,	196
Brahman, m.,	204, 205, 206	Chandra, k.,	367-371
Brahmānanda, m.,	204	Chandra, a poet,	296, 303, 310
Brahmānandaghana, a Kāścī ācārya,	234	Chandra-bhattārīkā-dēvi, a Pratihāra queen,	178, 183
Brāhmaṇa,	193		
brahmāṇḍa,	172		
Brahmarshi,	306		
Brāhmī inscriptions, dating of,	136		

The figures refer to pages; *n.* after a figure to footnotes, and *add.* to Additions and Corrections. The following other abbreviations are used:—*ch.* = chief; *co.* = country; *di.* = district, division; *do.* = the same, ditto; *dy.* = dynasty; *E.* = Eastern; *feud.* = feudatory; *k.* = king; *m.* = man; *mt.* = mountain; *ri.* = river; *s. a.* = see also; *sur.* = surname; *ts.* = temple; *vi.* = village, town; *W.* = Western; *wo.* = woman.

	PAGE		PAGE
Chandrachūḍa, a <i>Kāśchī śāhārya</i> , ...	169, 233, 234, 235, 357	chhaṅga, ...	296, 303, 310
Chandra-dēva, a <i>Gaṇaḍaśāla k.</i> , ...	168	Chhatēmbu, <i>vi.</i> , ...	198, 199, 200
Chandra-dēva, a <i>Kaṇauj k.</i> , ...	192	Chhīhīla Atharva-charaṇa-dvivēdin, <i>m.</i> , ...	205
Chandra-Dikshita, <i>m.</i> , ...	314, 319	Chhinda, <i>dy.</i> , ...	269
Chandrāditya, a <i>Kanyākubya k.</i> , ...	193, 194, 195, 197, 198, 199	Chhītallaka, a <i>field</i> , ...	182, 187
Chandragupta I. & II., <i>Gupta k.</i> , ...	367-9	Chhōṭa, <i>m.</i> , ...	208
Chandra-mādhava, a <i>divinity</i> , ...	10, 197, 199, 200	Chidambaram, a <i>shrine</i> , ...	240, 323
Chandramaulīśvara-svāmin, a <i>divinity</i> , ...	357, 359 & n. 7	Chidānandaghana, a <i>Kāśchī śāhārya</i> , ...	234
Chandrapāla, <i>feud.</i> , ...	185	Chiddhana, a <i>Kāśchī śāhārya</i> , ...	234
Chandrappārya, <i>m.</i> , ...	76, 82	Chidvilāsa, a <i>Kāśchī śāhārya</i> , ...	234
Chandrasekhara-Sarasvatī, a <i>Kāśchī śāhārya</i> , ...	169, 173, 175, 234, 235, 354, 359-9	Chikka-Purushōttama, <i>m.</i> , ...	343
Chandrāsya, a <i>gōtra</i> , ...	206	Chilāda, <i>vi.</i> , ...	195, 196, 200
Chandrarman, a <i>Pushkaraṇḍ k.</i> , ...	367, 369	chinnageykada, ...	266
Chandrāvati, <i>vi.</i> , ...	192, 197, 199, 200	chinnageykada-nakharāṅga, ...	266, 273
Chāṅgalapatta, <i>vi.</i> , ...	358-9	Chinnakadabūru, <i>vi.</i> , ...	153
Chāṅgalipatta, a <i>Simā</i> , ...	173	Chippagiri Rāghava-Bhaṭṭa, <i>m.</i> , ...	343
Charaka-vāṭaka, <i>vi.</i> , ...	88, 89, 94, 96	Chirivill, <i>vi.</i> , ...	195, 196, 201
charaṇa, <i>Taittiriya</i> , ...	335, 336	Chir-Stūpa, ...	237
Charada pedestal inscription, ...	132	Chitankha, a <i>Kāśchī śāhārya</i> , ...	234
chara, ...	126, 151, 152, 186	Chitsakhēndra, a <i>Kāśchī śāhārya</i> , ...	234
Chārudatta, <i>m.</i> , ...	337	Chittēra, <i>m.</i> , ...	76, 82
chāṭa, ...	150, 327	Chitti-Bhaṭṭa, <i>m.</i> , ...	314, 319
Chathatārā, <i>vi.</i> , ...	195, 196, 200	Chīyanēndil, <i>vi.</i> , ...	313, 317, 323
chatta, ...	160, 161	Chōḍi-Bhaṭṭa, <i>m.</i> , ...	315, 321
Chattāra II., a <i>Sinda ch.</i> , ...	269	Chōḷa, <i>dy.</i> , ...	84, 85, 125, 129, 171, 175, 240
chāturmāsya, ...	140	Chōḷa, a <i>people</i> , ...	240, 266, 271, 275
Chaturvēdin Rāva, ...	152	Chōḷa-śāśa, a <i>drama</i> , ...	87 n. 1
Chatur-śloki, a <i>poem</i> , ...	86	chowrie figured, ...	364
Chauḍi-Bhaṭṭa, <i>m.</i> , ...	314, 319	Chudavāsa, <i>vi.</i> , ...	301
Chāḷiya, a <i>gōtra</i> , ...	165, 167	Chudavāsa-dvādāśaka, <i>di.</i> , ...	195, 196
Chauḍārya, <i>m.</i> , ...	70, 75, 81	Chalukya = Chalukya, ...	124, 127
chaurōdharanika, ...	180, 327	Chuta-pallikā, <i>vi.</i> , ...	325, 327, 330
chansarā, ...	176, 188	Compounded words at beginning of verse, ...	101, 105
Chāvuga, <i>m.</i> , ...	209	Conch shells, ...	156, 192
Chāvati, <i>vi.</i> , ...	325, 327, 330	Conjeeveram. <i>See</i> Kāśchī, ...	240
Chāvugda II., a <i>Sinda ch.</i> , ...	268	conjunct consonants, form of, ...	232
Chēngara, <i>co.</i> , ...	84, 88, 91, 96	consonants doubled after annavāra, ...	97
Chennakēśava, a <i>divinity</i> , ...	341, 345-6, 353	cow figured, ...	364
Chennāri-pāndya (pāṇḍi), <i>vi.</i> , ...	313, 317, 323	cup for worship, ...	156
Chēra, <i>dy.</i> , ...	171, 176		
Chēra, a <i>people</i> , ...	240		
chā, form of, ...	157		

D

d, form of, ...	144, 157
d for dā, ...	88, 123
Dādli-Bhaṭṭa, <i>m.</i> , ...	243
Dadiga, a <i>Gaṅga prince</i> , ...	223

The figures refer to pages; n. after a figure to footnotes, and add. to Additions and Corrections. The following other abbreviations are used:—*ch.* = chief; *co.* = country; *di.* = district, division; *do.* = the same, ditto; *dy.* = dynasty; *E.* = Eastern; *feud.* = feudatory; *k.* = king; *m.* = man; *mt.* = mountain; *ri.* = river; *s.* a. = see also; *sur.* = surname; *t.* = temple; *vi.* = village, town; *w.* = Western; *w.* = woman.

	PAGE		PAGE
Dakṣha, ...	344	dates— <i>contd.</i>	
dagger figured, ...	341	expressed by ordinary numerical words, 100,	
Dakṣha, a <i>gōtra</i> , ...	206	103, 108, 113, 118,	
dakta = datta, ...	147, 149, 150-1	120, 123, 126, 129,	
dakṣiṇā, ...	167	133, 135, 143, 165-7,	
Dālā, m., ...	204, 209	169, 173, 175, 192-4,	
<i>Daladavama</i> , a book, ...	361	196-200, 233, 239,	
Dālā, m., ...	207	240, 297, 303, 312,	
dam of tank, ...	99, 104, 109	317, 323, 365-6	
Dāmara, m., ...	203, 204, 205, 207	Dati, m., ...	134, 287
Dambarsainha, a <i>Paramāra</i> prince, ...	296, 298, 304	Dattam-Bhaṭṭa, m., ...	212
Dāmōdara, m., ...	180, 186	danṣādhuaśḍhanika, ...	327
Dānārava, a <i>Gaṅga</i> k., ...	360, 362	danṣādhika, ...	160
danḍanāyaka, ...	160, 185, 327	days of the month, lunar—	
Danḍapāllo, vi., ...	68	first fortnight, 1st, ...	155
dāṇḍapālaka, ...	160, 327	bright fortnight, 1st, ...	177, 181, 187, 365-6
Danḍē-halli, a <i>stāla</i> , ...	69, 71, 73, 80, 80 a. 2, 83	3rd, ...	192, 197-200, 297, 303, 310
dāṇḍika, ...	327	5th, ...	88, 94, 96
Dantapura, vi., ...	361, 363	9th, ...	153
Dantavakra, a fort, ...	361	11th, ...	69, 73, 80
Dantidurga, a <i>Rāṣṭrakūṭa</i> k., ...	123, 123, 125, 128	12th, ...	211, 221, 231, 342, 345, 353
Darbha, a <i>gōtra</i> , ...	208	14th, ...	100, 103, 108
Dasabala = Buddha, ...	328	15th, ...	354, 358-9, 465-6
dasāpachāra, ...	327	full moon, ...	169, 173, 175, 267, 273,
dasāparādha, ...	161, 191	277, 331, 335-6, 360, 362-3	
dasāparādhika, ...	327	dark fortnight, 3rd, ...	123, 126, 129
Dasapura, vi., ...	177, 178, 184, 371	5th, ...	177, 178, 184
Dasaratha, ...	149, 151, 204	13th, ...	312, 317, 323
Dasahota, m., ...	133, 134, 143, 144	15th, ...	193, 194, 196
Dasavorapa, ...	133	new moon (<i>amāvāsyā</i>), ...	140, 148, 151, 152,
dates—		165-7, 192-4, 196,	
expressed by decimal figures, 100, 103, 108,		267, 272, 277	
133, 135, 143,		days of the month, solar—	
155, 158, 162,		1st, ...	155
177, 178,		12th, ...	325, 328, 330
181-2, 184,		15th, ...	192-4, 196, 289-295
187, 192-4,		16th, ...	158, 162
196, 267,		20th, ...	360, 362-3
272-3, 277,		25th, ...	133, 135, 143
289, 295, 297,		days of the week—	
303, 325, 328,		Āditya (Sun.), ...	365-6
330, 354, 358-9,		Bhānu (Sun.), ...	342, 345, 353
360, 362-3		Bhauma (Tu.), ...	312, 317, 323
expressed by numerical words, 69, 73, 80,		Bṛhaspati (Thur.), ...	365-6
88, 94, 96,		Gura (Thur.), ...	88, 94, 96, 100, 103, 108
100, 103, 108,		Indu (Mon.), ...	211, 231-3
211, 221, 231,		Ravi (Sun.), ...	192-4, 196
342, 345, 353			

The figures refer to pages; n. after a figure to footnotes, and *add.* to Additions and Corrections. The following other abbreviations are used:—*ch.* = chief; *co.* = country; *di.* = district, division; *do.* = the same, ditto; *dy.* = dynasty; *E.* = Eastern; *feud.* = feudatory; *k.* = king; *m.* = man; *mt.* = mountain; *ri.* = river; *s. a.* = see also; *ser.* = surname; *te.* = temple; *vi.* = village, town; *W.* = Western; *wo.* = woman.

	PAGE		PAGE
days of the week— <i>contd.</i>		Dowal inscription, ...	131, 136
Śani (Sat.), ...	192, 197-200	dh, form of, ...	68, 121, 325
Sōma (Mon.), ...	69, 73, 80, 267, 272-8, 277	Dhādīvāhā, name of a field, ...	182, 188
Sthira (Sat.), ...	354, 358-9	Dhāhāḍa, m., ...	205
Śakra (Fri.), ...	297-305, 310	Dhājāma, m., ...	204
Dāyīm, m., ...	202, 203	Dhāmē, m., ...	205
Dāliya, m., ...	208	Dhāmbū, m., ...	206
Dādū, m., ...	205	Dhanada = Kuvēra, ...	271
Dēlhaṇa, m., ...	202, 207, 208	Dhansāśura, m., ...	178, 184
Dēmāmbikā, a Vijayanagara queen, 69, 70, 70 n.	7, 72, 79, 79 n. 4	Dharaṇēndra, a Serpent k., ...	269
Dēsaḥ, m., ...	202	Dharaṇīdhara, m., ...	202, 204, 206, 207, 208
dēsamukhi, an impost, ...	354, 359	Dhārā-padraka, vi., ...	181, 186
Dēśū, m., ...	203	Dharāśraya-Jayasinhavarman, a Chalukya prince, ...	148
Dēūli, vi., ...	198, 199, 201	Dhātī, m., ...	204
Dēva, vi., ...	88, 89, 94, 96	Dharmā-Bhaṭṭa, m., ...	213, 214
Dēvadatta, m., ...	203	dharma-chakra, ...	325
Dēvadhara, a Perōkita, ...	207	Dharmachandra, m., ...	362-3
Dēvadhara, m., ...	205, 206, 209	dharmaḍhyaksha. See Maḥādharmaḍhyaksha, ...	160
Dēvagarbha, m., ...	202	Dharmarājika-Stūpa, ...	287, 295
Dēvakara, m., ...	207	Dharmaśarman, m., ...	166, 167
Dēvaki, a Vijayanagara queen, 171, 217-236, 240, 323		Dharma-Pāla, a Pāla k., ...	326, 329
Dēvāṅgīrī, vi., ...	365-6	dharmēta, ...	266, 272, 277
Dēvaṅa-Bhaṭṭa, m., ...	213	Dhārō, m., ...	207
Dēvapa, m., ...	75, 81	Dhātīśarman, m., ...	166, 167
Dēvapāla, a Pratihāra k., ...	179, 180	Dhaumya, a gōtra, ...	208-6
Dēva-Pāla, a Pāla k., ...	326, 329	Dhāvāṇa, m., ...	209
Dēvaputra, a Kushana title, ...	143, 289, 295	Dhavana-Svāmin, m., ...	203, 206
Dēvaradha (dhara), m., ...	205	Dhāyīm, m., ...	203
Dēvarakoṇḍa Sūri-Bhaṭṭa, m., ...	343	Dhūka, a Governor, ...	181
Dēvarāja, a Pratihāra k., ...	87, 179, 182, 187	dhimān, attribute, ...	212, 213, 214, 215
Dēvarāya I., a Vijayanagara k., ...	69, 70, 72, 79	dhimātām varah, attribute, ...	214
Dēvarāya II., a Vijayanagara k., ...	170 n. 2	dhrita for dhṛita, ...	110
Dēvarō-Bhaṭṭa, m., ...	314, 320	Dhūndhumāra, ...	149, 151
Dēvagrājan, m., ...	88, 105, 109	Dīghavaṇṭa, vi., ...	198, 199, 201
Dēvarehl, ...	203	Dinakara, m., ...	207
Dēvara-Bhaṭṭa, m., ...	314, 319	diā, masculine, ...	98
Dēvārya, m., ...	74, 81	Ditaphri, m., ...	287
Dēvasakti, a Pratihāra k., ...	178, 179, 183	Divākaksha, vi., ...	195, 196, 201
Dēvaśarman, m., ...	206, 207, 209	Divākara, m., ...	207, 208
Dēva-Svāmin, m., ...	203, 209	Divākara-Bhaṭṭa, m., ...	315, 321
Dēva-tadāka, a place (tank ?), ...	126, 129	Doḍavattī, a place, ...	267, 273, 277
Dēvathādhī, a family, ...	178	dōraka, ...	303
Dēvayāni, ...	171, 214-230	Dōrasamudra, vi., ...	268
Dēvēndravarmān, a Gaṅga k., ...	360	Dramiḍa, co., ...	92
Dēvēśvara, m., ...	205, 206	dramma, ...	302, 303, 309, 310
		Drōṇa, m., ...	205

The figures refer to pages; n. after a figure to footnotes, and add. to Additions and Corrections. The following other abbreviations are used:—*ch.* = chief; *co.* = country; *di.* = district, division; *do.* = the same, ditto; *dy.* = dynasty; *E.* = Eastern; *feud.* = feudatory; *k.* = king; *m.* = man; *mt.* = mountain; *vi.* = river; *s. a.* = see also; *sur.* = surname; *te.* = temple; *vi.* = village, town; *W.* = Western; *wo.* = woman.

	PAGE
<i>drōṇa</i> , a measure of land, ...	158, 161
<i>Duggappārya</i> , m., ...	70, 71, 75, 81
<i>Dūṇā</i> , vi., ...	195, 196, 201
<i>Durlabha-Rāja</i> , a <i>Chāḍamāpa k.</i> , ...	180, 181, 185, 186
<i>Durvinita</i> , a <i>Gaṅga k.</i> , ...	338
<i>Dasha-sārdūla-mardana</i> , sur. of <i>Krishṇa-dēva-</i> <i>Rāya</i> , ...	173
<i>dūtaka</i> , ...	158
<i>dūtaprēṣaṇika</i> , ...	327
<i>Dvādaśa-grāmi</i> , di., ...	150, 152
<i>Dvā-ravati</i> , vi., ...	91
<i>Deva-sloki</i> , a poem, ...	86
<i>Dvijōttama</i> , attribute, ...	213
<i>dy j or g</i> , ...	286

E

<i>ē</i> , form of, ...	364
<i>ē</i> , form of, ...	121, 121 n. 5, 130, 157, 390
<i>ē</i> for <i>a</i> , ...	146
<i>ē</i> , medial, form of, ...	121, 153
Earth represented by <i>mā</i> , ...	100, 105
<i>Ēchi-Bhaṭṭa</i> , m., ...	213
eclipse, lunar, ...	267, 273, 277
eclipse, solar, ...	129, 146, 148, 151-2, 155, 193-4, 196, 267, 277
<i>Edavatti</i> , di., ...	269
edict, characteristics of an, ...	99, 100, 105
<i>Edilpur</i> grant of <i>Kēśava-Sōna</i> , ...	157
<i>Edūra</i> , vi., ...	71, 82
<i>Ein-ool-Mulk</i> Geelany, ...	211
<i>Ekūba</i> , m., ...	315, 321
<i>ēka-bhōgya</i> , ...	313, 318
<i>Ekāmanātha</i> , a divinity, ...	358-9
<i>Ēka-vira</i> , sur. of <i>Acāyuta-Rāya</i> , ...	315
<i>Ellārya</i> , m., ...	75, 82
<i>Ellora</i> temple, ...	127
<i>Embār</i> , m., ...	85
<i>envodu</i> , ...	189
equinox, autumnal, ...	167
era—	
<i>Ganga</i> , ...	360, 362-3
<i>Kali</i> , ...	100, 103, 108
<i>Kanishka</i> , ...	133, 135, 143

era—contd.

<i>Śaka</i> , ...	69, 73, 80, 88, 94, 96, 100, 103, 108, 123, 126, 129, 169, 173, 175, 211, 221, 231, 233, 239, 240, 267, 272-3, 277, 297, 303, 312, 317, 323, 342, 345, 353, 354, 358-9, 365-6
<i>Śalivāhana</i> — <i>Śaka</i> , ...	169, 173, 175, 211, 221, 231, 233, 239, 240, 354, 358-9
<i>Vikrama</i> , ...	113, 118, 120, 177, 178, 181, 182, 184, 187, 192-4, 196-200
<i>Erambarage</i> , vi., ...	268
<i>Ereyappa</i> — <i>Rājamalla Satyavākya</i> , a <i>Gaṅga k.</i> , ...	339
<i>erjhuṇa</i> , ...	204

F

<i>f</i> , form of, ...	285
fire, symbolized by <i>ra</i> , ...	101, 105

G

<i>g</i> , form of, ...	121, 121 n. 5, 164, 305
<i>Gachchhū</i> , m., ...	209
<i>Gadasaṇḍā</i> , vi., ...	198, 199, 201
<i>Gādhi</i> , father of <i>Viśvāmitra</i> , ...	296, 298, 304
<i>Gadya-traya-vyākhyāna</i> , a book, ...	85
<i>gadyāṇa</i> , a measure, ...	355-6
<i>Gāga</i> , m., ...	292
<i>Gāgū</i> , m., ...	206
<i>Gāhadvāla</i> , a <i>Kanyākubja</i> family, ...	183
<i>gaḥapati</i> , ...	154
<i>Gahilāda</i> , m., ...	209
<i>Gahilā</i> , m., ...	208
<i>Gaja</i> , m., ...	203
<i>Gajapati</i> , dy., ...	171
<i>Gaj-augha</i> — <i>gaṇḍa</i> — <i>bhārūṇa</i> , a <i>Vijayanagara</i> <i>title</i> , ...	342, 345
<i>Gāka</i> , m., ...	209
<i>Gālava</i> , a <i>gōtra</i> , ...	204, 209
<i>Gāhi</i> , m., ...	204, 205
<i>gamāgamika</i> , ...	327
<i>Gāngū</i> , m., ...	207
<i>Gaṇasavara</i> , m., ...	205
<i>gāmūḍa</i> , ...	190, 191, 363-6
<i>gaṇa</i> , ...	148

The figures refer to pages; n. after a figure to footnotes, and add. to Additions and Corrections. The following other abbreviations are used:—*ch.* = chief; *co.* = country; *di.* = district, division; *do.* = the same, ditto; *dy.* = dynasty; *E.* = Eastern; *feud.* = feudatory; *k.* = king; *m.* = man; *mt.* = mountain; *ri.* = river; *s. a.* = see also; *sur.* = surname; *te.* = temple; *vi.* = village, town; *W.* = Western; *wo.* = woman.

	PAGE		PAGE
gaṇa-bhōgya, ...	210, 313, 346	genitive plural denoting nationality, ...	288
Gaṇapa, a <i>Teliṅga</i> k., ...	83, 90, 95	Ghaḍaaita, <i>vi.</i> , ...	198, 199, 201
Gaṇapati, ...	213	ghana, ...	176, 189
Gaṇapati-Amātya, m., ...	215	Ghargharā, <i>vi.</i> , ...	103, 194, 196
gaṇastha. <i>See</i> Mahāgaṇastha, ...	160	ghataka, ...	309
Gaṇḍa, a <i>Chandēla</i> prince, ...	179 n. 4	Ghaṭikāśatam-ammāl, <i>sur.</i> , ...	87
Gandhāra, <i>co.</i> , ...	290, 291	ghaṭīyantra, ...	345
Gaṇḍ, m., ...	204	Ghōṣṭāvarshi, <i>vi.</i> , ...	178 n. 1, 181, 182, 187, 188
Gaṇḍa, <i>dy.</i> , ...	331, 332, 335, 340, 360-4	Ghōṣṭāvarshikā, <i>vi.</i> , ...	177, 178, 179 n. 1, 181, 184, 186
Gaṇḍā, <i>vi.</i> , ...	102, 108, 107, 199, 328	Gira (I)dhara, m., ...	206
Gaṇḍādhara, m., ...	190, 200, 202, 203, 204-5, 207, 208	Giri-Bhaṭṭa, m., ...	213, 343
Gaṇḍādhara, a <i>Kāśchī āchārya</i> , ...	234	gōchara, ...	327
Gaṇḍahadā, <i>vi.</i> , ...	198, 199, 201	Gōchara-Vihāra, ...	194
Jaṇḍa, m., ...	74, 76, 81, 82	Gōchī (vī)nda, m., ...	207
Gaṇḍapa-Bhaṭṭa, m., ...	212, 214	Gōdāvari, <i>vi.</i> , ...	84, 88, 91, 96
Gaṇḍa-Pallava, <i>dy.</i> , ...	334	Godhana, m., ...	205, 208
gaṇḍarim, ...	266, 271	Gōdhana Paṇḍita, m., ...	207
Gāṇḍa, m., ...	208	godigar, ...	190
Gaṇḍaviḍi, <i>co.</i> , ...	331, 340	Gōṣṭjara, <i>vi.</i> , ...	198, 199, 201
Gaṇḍilhar, <i>vi.</i> , ...	371	Gōkalikā, a <i>maṇḍala</i> , ...	325, 327, 330
Gaṇḍilhar inscription, ...	139	Gōkarṇa, a <i>shrine</i> , ...	171, 194, 195, 196, 199, 240, 316, 323
Ganges, <i>vi.</i> <i>See</i> Gaṅgā.		Gokarṇa-svāmin, a <i>divinity</i> , ...	361-3
gāṅḍōya, <i>gold</i> , ...	98, 105	gōkula, ...	194, 195, 198
Gāṅḍōya-dēva, k., ...	158	Golconda, <i>vi.</i> , ...	354-8
Glāṅḍ, m., ...	205, 206	Gōlhaṇa, m., ...	202, 205, 207
Gaṇḍa, a <i>Teliṅga</i> prince, ...	83, 84, 92, 96	Gōlhō, m., ...	207
Garibhilla, an <i>Ujjayinī</i> k., ...	293	Gōmati, <i>vi.</i> , ...	193, 194, 196
Garga, m., ...	205, 209	Gondophernes, a <i>Śaka-Pahlava</i> k., ...	289
Gargarakata, <i>vi.</i> , ...	114, 115, 118, 120	Gōpāla, m., ...	203
Gargya, a <i>gōtra</i> , ...	82, 212-4, 315	Gōpāla-dēva, a <i>Pāla</i> k., ...	326, 328, 329
Garṇḍa, figure of, ...	192, 306	Gōpāla Paṇḍita, m., ...	213
Garṇḍa-divāja = Vishṇu, ...	300, 306	Gōpaṇa, m., ...	76, 81
garva, ...	127 n. 1	Gōpati, m., ...	202, 206, 208
Gaṇḍa, a <i>people</i> , ...	112, 117, 120, 327	Gōpinātha, m., ...	70, 74, 80, 314, 315
<i>Gaṇḍa-lēkha-mālā</i> , a <i>book</i> , ...	324, 329 n. 2	Gōṣṇahāṇa, <i>vi.</i> , ...	267, 268, 273, 277
ganhuika, ...	155 n. 5, 327	Gō-sahasra, a <i>maṇḍana</i> , ...	173
Gaṇḍya, a <i>gōtra</i> , ...	207	gōtras—	
Gauri = Durgā, ...	270, 273, 298, 303	Agastya, ...	81, 209, 215-6, 343
Gauri-Bhaṭṭa, m., ...	315, 320	Ātrēya, ...	81, 209, 213-4, 314-5, 343
Gaurisārman, m., ...	360	Bhāradvāja, ...	69, 70, 73, 80-2, 158, 161, 202-9, 212-6, 314-5, 342-3
Gauro-Bhaṭṭa, m., ...	343	Bhārgava, ...	203-5, 208-9
Gautama, m., ...	206	Chandratrēya, ...	206
Gautama, a <i>gōtra</i> , 81-2, 202, 204, 206-9, 212, 214-5, 314		Chāḷiyya, ...	165, 167
gavyūti, ...	129 n. 1	Daksha, ...	205
Gayādhara, m., ...	202, 203, 205, 208, 209		
genitive for nominative, ...	364		

The figures refer to pages; n. after a figure to footnotes, and *add.* to Additions and Corrections. The following other abbreviations are used:—*ch.* = chief; *co.* = country; *di.* = district, division; *do.* = the same, ditto; *dy.* = dynasty; *E.* = Eastern; *feud.* = feudatory; *k.* = king; *m.* = man; *mt.* = mountain; *vi.* = river; *s. a.* = see also; *sur.* = surname; *te.* = temple; *vi.* = village, town; *W.* = Western; *wo.* = woman.

	PAGE		PAGE
<i>gōtras—contd.</i>		<i>gōtras—concl'd.</i>	
Darbha, ...	208	Sākara, ...	202, 204
Dhaunya, ...	208-6	Sākarākaha, ...	204, 207-9
Gālava, ...	204, 209	Śaunaka, ...	202
Garga, ...	167, 208, 206	Śaṅsraṇa, ...	208-6, 209
Gārgya, ...	82, 212-4, 315	Sāvara, ...	204, 206-7, 209
Gaṇya, ...	207	Śrāvishṭha, ...	165, 167
Gautama, ...	81-2, 202, 204, 206-9, 212, 214-5, 314	Śrīvata, ...	81-2, 212, 214, 315, 342-3
Harita, ...	81, 85, 208, 214-5, 314-5, 343	Upamanyu, ...	202-4, 206-9
Hārta, ...	148, 152, 281, 283	Vādhūla, ...	342
Jāmadagnya-Vata, ...	82, 213, 314-5	Valandata, ...	165, 167
Jaśa, ...	207	Vandhala, ...	202-3
Jātūkarna, ...	207	Vasishṭha, ...	70-1, 73, 80-2, 202-9, 213, 327, 330, 343
Jivantyāyana, ...	208, 208	Vata, ...	202-3, 206-9, 335-6
Kaimbala, ...	165	Vishṇuvriddha, ...	81
Kālā, ...	165-7	Vishṇuvaridhana, ...	82
Kāva, ...	209, 214	Viśvāmītra, ...	81-2, 314-5
Kāva-Śyāvāśva, ...	214	Vriha, ...	81, 82
Kāṇvāyana, ...	332, 335-6	Gotrahā = Indra, ...	300
Kapi, ...	213, 216	<i>gōtra</i> , ...	165
Kapila, ...	315	Gōdī, <i>vi.</i> , ...	198, 199, 201
Kapishṭhala, ...	202, 204, 208-9	Gōve, <i>vi.</i> , ...	268
Kāśyapa, ...	81, 167, 202-4, 206-9, 212-5, 272, 276, 313-5, 342-3	Gōvinda, <i>m.</i> , ...	74, 80, 204, 206, 207, 272, 273, 276, 277
Kātyāyana, ...	207	Gōvinda I., a <i>Rāshṭrakūṭa k.</i> , ...	122, 124, 127
Kātyāyana-killā, ...	206	Gōvinda II., a <i>Rāshṭrakūṭa k.</i> , ...	122
Kaṇḍīya, ...	81-2, 208-9, 212-5, 342-3	Gōvinda III., a <i>Rāshṭrakūṭa k.</i> , ...	147
Kanśika, ...	80-2, 202-4, 207-8, 213-4, 314-5, 342-3, 360, 362-3	Gōvinda IV., a <i>Rāshṭrakūṭa k.</i> , ...	157
Kautsa, ...	109 a, 6, 167, 209	Gōvindhachandra, a <i>Kanṣakūṭa k.</i> , ...	193
Kōta, ...	167	Gōvinda-pura, <i>vi.</i> , ...	352
Kutā, ...	343	Gōvindh-rāja, a <i>Chāḥamāna k.</i> , ...	180, 181, 185, 186
Kṛishṇātrēya, ...	202-4, 206-7, 209	Gōyī, <i>m.</i> , ...	206
Kuśika, ...	81, 209	Grahavarman, a <i>Maukhari k.</i> , ...	113
Mānavya, ...	149, 151, 166-7	grāmapati, ...	327
Mandgalya, ...	208, 314-5	grāmakūṭa, ...	150
Mauna, ...	209	Granafryaka, <i>m.</i> , ...	287 a, 3
Maunya, ...	202, 207-8	Grōppahgāll, <i>vi.</i> , ...	68, 94
Parāśara, ...	203-4, 206, 208-9, 212-4, 315, 325, 327, 330	Guḍūru, <i>vi.</i> , ...	231
Pippalāda, ...	207	Guhla, a <i>family</i> , ...	181
Śakti, ...	327, 330	Gulavata, <i>vi.</i> , ...	195, 196, 201
Śālakhāyana, ...	82	gumika, ...	155
Śāṅkṛitya, ...	202-4, 206-8	gufja, ...	162
Śāṇḍilya, ...	81, 202-4, 206-9, 314-5	Gupta character, ...	110
		Gupta, <i>dyn.</i> , ...	367, 371
		Gupta era, ...	110, 114
		Gurjara grant, spurious, ...	146

The figures refer to pages; a. after a figure to footnotes, and *add.* to Additions and Corrections. The following other abbreviations are used:—*ch.* = chief; *co.* = country; *di.* = district, division; *do.* = the same, ditto; *dy.* = dynasty; *E.* = Eastern; *feud.* = feudatory; *k.* = king; *m.* = man; *mt.* = mountain; *ri.* = river; *s. a.* = see also; *sur.* = surname; *ts.* = temple; *vi.* = village, town; *W.* = Western; *w.* = woman.

	PAGE		PAGE
Gurjara, a people, ...	266, 271, 275	Harivarman, a <i>Maukhari k.</i> , ...	112, 115, 119
Gurjara-Pratihāra empire, ...	158	Harivarman, a <i>Kodamba k.</i> , ...	163, 164, 165, 167
Gur-shi, a race, ...	288	Harivarman, <i>m.</i> , ...	202
<i>Guru-paramparā-prabhāsa</i> , a book, ...	86 n. 1, 87 n. 1	Harivarman, a <i>Gaṅga k.</i> , ...	332, 334, 337
<i>Guru-rāja-ratna-mālā-stava</i> , a poem, ...	233	Harsha, a <i>Kanauj k.</i> , ...	113
<i>Guru-ratna-mālā-stava</i> , a poem, ...	170	<i>Harsha-charita</i> , a book, ...	112, 113
Gushapa, a race, ...	288	Harsha-dēva, a <i>Kanauj k.</i> , ...	148, 149, 157
Gut-shi, a race, ...	288	Ha-sha-dēva-Sīyaka II., a <i>Mālava k.</i> , ...	296
gutta, ...	189, 190, 191	Harshaguptā, a <i>Maukhari queen</i> , ...	112
Gutti, a <i>valita</i> , ...	341, 345, 353	Hahtnagar image inscription, ...	131, 135
Guzan, ...	142	hata = paksha, ...	304, 306 n. 4
H		Hastigirinatha, a <i>divinity</i> , ...	358-9
h, form of, ...	157, 325	Hastināvatī, a <i>valita</i> (revenue circle), ...	231
h initial <g>, ...	206	Hastipada, <i>vi.</i> , ...	325, 327, 330
ha, symbolic, ...	100, 105	Hastikalla-nātha, a <i>divinity</i> , ...	133
Hadapavula, an <i>official</i> , ...	267	Hastiyadhyaksha, an <i>official title</i> , ...	301-3
Hāhe-Kallu, a <i>place</i> , ...	272, 277	hatta, ...	296, 302
Halavūr, <i>vi.</i> , ...	269, 270	Havari's <i>Journal</i> , ...	354-6
Hamgave, <i>vi.</i> , ...	267, 277, 273	Hayapati, a <i>dy.</i> , ...	180
Hampapa, <i>m.</i> , ...	76, 81	Hegrapa, <i>m.</i> , ...	76, 81
Hamparasa, <i>m.</i> , ...	215	Hegrapa-āchārya, <i>m.</i> , ...	76, 82
Hara, <i>m.</i> , ...	155 n. 8, 194, 196, 211, 212, 231, 280, 282, 313, 318	Hēmāchala, a <i>shrine</i> , ...	173
Harāhā, <i>vi.</i> , ...	110	Hēmādi, an <i>author</i> , ...	100, 102, 106 n. 7, 107, 107 n. 6
hāraka, ...	296, 310	Hēmāgarbha, a <i>maḥādāna</i> , ...	172
Haravira, a <i>Sinda ch.</i> , ...	269	Hēmāmbikā, a <i>Vijayanagara queen</i> , ...	70, 70 n. 7, 71
Hari, <i>m.</i> , ...	101, 106, 194, 196, 202, 204, 207, 208, 210, 212, 231, 280, 282, 313, 318	Hēmanta-Sēna, a <i>Sāna k.</i> , ...	159, 163
Hari-Bhatta, <i>m.</i> , ...	213	Hēmāsava, a <i>maḥādāna</i> , ...	172
Haridaśva = Indra, ...	298	Hēramba = Gaṇēśa	101, 103
Harigbōsha, <i>m.</i> , ...	158, 162	Hērambapāla, a <i>Pratihāra k.</i> , ...	179, 180
Harihara, a <i>Vijayanagara prince</i> , ...	69, 98, 102, 171	Hidda inscription, ...	136
Harihara II., a <i>Vijayanagara k.</i> , ...	98, 102, 167	Hien-to, <i>co.</i> , ...	221, 222
Hariharēśvara, a <i>prince</i> , ...	72, 73	Higē, <i>m.</i> , ...	207
Hari-Rishēśvara, a <i>divinity</i> , ...	177, 178, 184	hi-han, a <i>Kushana title = jabga</i> , ...	290
Harishēśvara, a <i>divinity</i> , ...	176	Himāchala, <i>mt.</i> , ...	88, 89, 90
Harisāman, <i>m.</i> , ...	208	Himādi, <i>mt.</i> , ...	344
Harischandra, <i>m.</i> , ...	203	Himālaya, <i>mt.</i> , ...	90, 95, 125, 128
Harita, a <i>gōtra</i> , ...	81, 85, 208, 214-5, 214-5	Himavat, <i>mt.</i> , ...	274
Haritāla-Maṅgalam, <i>vi.</i> , ...	313, 317, 323	Hindu-rāya-suvatrāpa, <i>sur. of Vijayanagara</i> <i>k.</i> , ...	173, 345
Hārīti, a <i>gōtra</i> , ...	148, 152, 281, 283	Hiramaṇḍala, <i>vi.</i> , ...	361
Hārīti-putra, <i>sur. of Chalukya dy.</i> , ...	149, 150, 151	Hiranya, <i>m.</i> , ...	213
Hārīti-putra, <i>sur. of Kodamba dy.</i> , ...	166, 167	Hiranya-Bhatta, <i>m.</i> , ...	214
Harivaṅka-Purāṇa, a book, ...	179 n. 2	Hiranyakēśin śāstra, ...	148, 152
		Hiranyāśva-ratha, a <i>maḥādāna</i> , ...	172
		Hirya-Bāchamalla = Piriya, ...	273

The figures refer to pages; n. after a figure to footnotes, and *add.* to Additions and Corrections. The following other abbreviations are used: — *ch.* = chief; *co.* = country; *di.* = district, division; *do.* = the same, ditto; *dy.* = dynasty; *E.* = Eastern; *feud.* = feudatory; *k.* = king; *m.* = man; *mt.* = mountain; *vi.* = river; *s. a.* = see also; *sur.* = surname; *te.* = temple; *vi.* = village, town; *W.* = Western; *wo.* = woman.

	PAGE		PAGE
Hiang nu, a race, ...	289	Iśvara = Śiva, ...	289, 282
hole, ...	286	Iśvara, a Sinda ch., ...	269, 270
Hōyāsāna (Hoyisana) Kannedī soci, ...	354, 357-9	Iśvaravarman, a Maukhari k., ...	112, 112 n. 6, 116, 119
Hoyasala, dy., ...	265, 268	Iśvarasēna, an Abhira k., ...	140
Hydayadhara, a Kāyastha, ...	193, 195, 196	Itihāsa, ...	101, 106, 355, 336
Hrishikēsa Bhattacharya, m., ...	325, 330		J
hriyā for hriyā, ...	110, 116	j, form of, ...	121, 121 n. 5, 189, 325
Hull, di., ...	60, 72, 10	ja, symbol of the sun, ...	100, 105
Hūṇa, a people, ...	327	Jā, m., ...	207
Huvishka, a Kushana k., ...	293	jabga, a Kushana title, ...	289
		Jagaddihara, m., ...	206
I		Jagadēkamalla, a W. Chalukya k., ...	266 n. 5, 268
i for a, ...	146	Jaganmātā, wo., ...	94, 96
i, form of, ...	157	Jāgrū, m., ...	204
ī initial, form of, ...	341	Jahmañi, m., ...	208
ī, medial, form of, ...	157, 341	Jāhnaveya, a family, ...	332, 334, 336
ī confused, ...	146, 232, 311	Jaina cosmography, ...	334
ilaguhi, ...	107 n. 7	Jaina temples, ...	192
Ik-hvaku, dy., ...	92, 140	Jainism, ...	165, 357
Indafri, m., ...	134, 287, 295	Jajjanaga, m., ...	178, 184
Indiyi, vi., ...	198, 199, 201	jāla, ...	290, 309
Indirā, ...	345	Jalaothi, a place, ...	169, 161
Inrāditya-dēva, a divinity, ...	177, 181, 182, 186, 187	Jālha, m., ...	205
Indra-Rāja, a Rākshakūta k., ...	122, 124, 127	Jalhaqa, m., ...	207
Indrarāja, a Chāhamāna feud., ...	177, 180, 181,	Jālho, m., ...	205, 208, 209
	182, 185, 186	Jāli-halli, vi., ...	231
Indravarman, a Guṅga k., ...	360, 362-3	Jālū, m., ...	204
Indu-varma-sikhamañi, a Vijayanagara title, ...	345	Jāmādagnya-Vatse, a gōtra, ...	82, 213, 314-5
Inscription of Iśanavarman, ...	110, 116, 118	Jamaka, m., ...	209
Intaphri, m., ...	287	Jambā-Bhatta, ...	342
irkkeyano, ...	266	Jambū-dvipa, ...	270-1, 274, 327, 330
Irmañi-Bhlma (Bhlma II.), a Sinda prince, ...	266	Jamna, m., ...	76, 81
	n. 5, 272	Jāna, m., ...	209
Irmañi-Rāchamalla = Rāchamalla II., a Sinda		Janārdana, m., ...	204, 206
k., ...	266, 267, 271, 272-3, 275,	Janārdanāna, m., ...	343
	276, 280, 281	Jānā, m., ...	203
Irungōle, a Sinda k., ...	280, 283	Jangli Guḍa, name of a rock, ...	153
Irungula, a Sinda k., ...	266, 271, 272, 276	Jannaya, m., ...	315, 320
Iśāns, an aspect of Śiva, ...	274 n. 2	Janni-Bhatta, m., ...	213
Iśanavarman, a Maukhari k., ...	110, 112, 112 n. 6,	Jānū, m., ...	209
	113, 114, 119, 120	Janānanda, m., ...	207
Isarūcha, m., ...	209	Jaaka, a gōtra, ...	207
Isatā-dāvi, a Pratihāra queen, ...	178, 183	Jāta, m., ...	203, 205
Iśvara, a Vijayanagara k., ...	171, 174, 217-230,	Jātarna, a Sinda ch., ...	269
	232, 323		

The figures refer to pages; s. after a figure to footnotes, and add. to Additions and Corrections. The following other abbreviations are used:—*cl.* = chief; *co.* = country; *dt.* = district, division; *do.* = the same, ditto; *dy.* = dynasty; *E.* = Eastern; *feud.* = feudatory; *k.* = king; *m.* = man; *mt.* = mountain; *ri.* = river; *s. a.* = see also; *sur.* = surname; *te.* = temple; *vi.* = village, town; *W.* = Western; *wo.* = woman.

	PAGE		PAGE
Jātūkarna, a <i>gōtra</i> , ...	207	Kakka-dēva, a <i>Paramāra prince</i> , ...	296, 299 n. 1, 304
Jaya-chōla, a <i>Maṇḍala</i> , ...	173, 175, 232, 239	Kakka-Rāja, a <i>Rāṣṭrakūṣa k.</i> , ...	122, 124, 125, 127, 129
Jayantikōṇḍa, a <i>Maṇḍala</i> , ...	175	Kakkuka, a <i>Pratihāra k.</i> , ...	179
Jayantikōṇḍa-chōla, a <i>Maṇḍala</i> , ...	232, 313, 317, 323	Kākustha, a <i>Pratihāra k.</i> , ...	179
Jaya-Pāla, a <i>Pāla k.</i> , ...	208, 326, 329	Kākusthavarma, a <i>Kadamba k.</i> , ...	334
Jayaśarma, m., ...	208	Kāla, <i>destiny</i> , ...	300, 307
Jayaśvāmīni, a <i>Maṅkhari queen</i> , ...	112	kalā, ...	330
Jayateja Dattīya, a <i>Gaṅga k.</i> , ...	339	Kalacharya, <i>dy.</i> , ...	268, 269
Jayavarman, k., ...	140	Kālahaṣṭi, m., ...	314, 319
Jētha = Jyēṣṭha, ...	143	Kālahaṣṭi, a <i>shrine</i> , ...	171, 240, 316, 323
Jhaoli copper-plate inscription, ...	132, 137	Kālaka, m., ...	293
jhari, ...	358	Kālakāchārya-kathānaka, a <i>book</i> , ...	293, 294
jhā for jīh, ...	97	Kñjakāṭṭara, <i>vi.</i> , ...	232, 235
Jigapā, <i>vi.</i> , ...	195, 196, 201	kalam, a <i>measure</i> , ...	354, 359 & n. 7
Jihvāmullīya, form of, ...	360	Kālmukha, a <i>Śaiva sect</i> , ...	267, 272, 277
Jintō-grāma, <i>vi.</i> , ...	267, 273, 277	Kālās, a <i>gōtra</i> , ...	165-7
Jitroga, a <i>Khotan royal family</i> , ...	133	Kalattūr, <i>vi.</i> , ...	169, 173, 175
Jivantyāyana, a <i>gōtra</i> , ...	203, 208	Kaldarra inscription, ...	131, 136
jū, form of, ...	122	Kali ago, ...	102, 103, 106, 119, 120, 125, 129, 172
Jñānānanda, a <i>Kāśchī āchārya</i> , ...	234	Kaliaga, <i>co.</i> , ...	73, 79, 84, 88, 90, 170, 173, 175, 316, 361, 363
Jnagadh rock inscription, ...	140	Kālīnga, <i>dyn.</i> , ...	345
Jvālmukha, <i>sur. of the Maṅkhari k. Harivar-</i> <i>man</i> , ...	112, 115, 119	Kāliyūr-kōṣṭha, <i>di.</i> , ...	232
K		Kallamadi, <i>vi.</i> , ...	346, 351-3
k, form of, ...	153, 157, 164, 325	Kalpa, ...	162
ka, symbolic, ...	100, 105	Kalpa-taru, a <i>maṅḍāra</i> , ...	172, 302
kachcha, ...	177, 187-8, 346	Kalpa-vriksha, ...	302
Kadalādi, <i>vi.</i> , ...	311, 313, 315, 317, 321, 323	Kalvivana, a <i>place</i> , ...	145, 148, 150, 152
Kadalādi plates of Achyuta-Rāja, ...	310ff.	Kalyāṇa, <i>vi.</i> , ...	266, 267, 271, 275
Kadamba, <i>dy.</i> , ...	165, 166, 167, 268, 269, 333, 334	Kalyē, m., ...	206
Kadambajige Thousand, <i>di.</i> , ...	269	Kāma, ...	240, 323
Kadamkariya, ...	91	Kāmā-Bhaṭṭa, m., ...	213, 314, 315, 319, 321
Kadhivō, <i>vi.</i> , ...	195, 196, 201	Kāma-dhenu, a <i>maṅḍāra</i> , ...	172, 298, 302, 304
kādon, ...	364	Kamaguli, m., ...	134, 297
Kadphises, a <i>Kushana k. S. a. Kujāla-Kadphises</i> and <i>Vima-Kadphises</i> , ...	135, 143, 288, 293	Kamakāyana-Viśvāmītra, a <i>gōtra</i> , ...	354, 357-9
Kadnācha, m., ...	203	Kamakūṭi, a <i>pīṭha</i> , ...	231
Kadnātha, m., ...	203	Kāmākshī, a <i>divinity</i> , ...	357-9
Kāhīnki-Gaṅgā, <i>vi.</i> , ...	178, 184	Kāmākshī pīṭha, a <i>religious post</i> , ...	357
Kallāsa, <i>mt.</i> , ...	280, 283	Kamalāsana, ...	194
Kalubala, a <i>gōtra</i> , ...	165, 166, 167	Kāmaṇa-Bhaṭṭa, m., ...	212
Kalsara, a <i>title</i> , ...	132, 135, 141, 144	Kāmarasa Timma-āṁṣṭya, <i> feud.</i> , ...	215, 216
Kaithnōpī, <i>vi.</i> , ...	198, 199, 201	kanata, ...	277 n. 1
Kaivalya-Yōgin, a <i>Kāśchī āchārya</i> , ...	234	Kamavali, <i>vi. See Laghuk.</i>	
kāka, a <i>land measure</i> , ...	158, 161	Kāmaya, m., ...	74, 81
		Kāmb(h)ōja a <i>people</i> , ...	345

The figures refer to pages; n. after a figure to footnotes, and *add.* to Additions and Corrections. The following other abbreviations are used: — *ch.* = chief; *co.* = country; *di.* = district, division, *do.* = the same, ditto; *dy.* = dynasty; *E.* = Eastern; *feud.* = feudatory; *k.* = king; *m.* = man; *mt.* = mountain; *ri.* = river; *s. a.* = see also; *sur.* = surname; *te.* = temple; *vi.* = village, town, *W.* = Western; *w.* = woman.

	PAGE		PAGE
Kamma, a caste, ...	281, 283	Karkatāka, a lagna, ...	103, 108, 123
kaminata, ...	266, 272, 277	Kārlī inscription of Pujumāvi, ...	140
Kammayyana, a <i>Sinda</i> ch., ...	268	Kārmāṇḍya, vi., ...	148
Kampaṇa, a <i>Vijayanagara</i> prince, ...	98, 102, 107	Karmatva, an estate, ...	335, 336
Kanaka-kari-ratha, a <i>maḥādāna</i> , ...	172	Karṇāṭa, co., ...	230, 298, 297, 299, 304, 342, 344
Kanaka-sabhā, a <i>shrine</i> , ...	172	Karṇāṭa, a <i>people</i> , ...	327
Kanaka-sada, a <i>shrine</i> , ...	171	karōṭi, ...	270
Kanaka-tulā-pūrṇa, a <i>maḥādāna</i> , ...	172	karsha, ...	309
Kanakōcharā, a <i>place</i> , ...	148, 150, 152	Kārtavīrya, ...	160, 153
Kananj. See Kanyākubja, ...	193	Kārttikēya, ...	167
Kāśchadi, m., ...	150, 152	Kasavā-Bhaṭṭa, m., ...	213, 214
Kāśchi, di., ...	232	Kashgar, co., ...	142
Kāśchi, vi., 87, 125, 128, 169, 172, 233, 240, 316,		Kāshmīr, co., ...	290, 291, 292
	323, 334, 345, 356-9	Kāśivāsa-Kriyāśakti, a <i>Śaiva</i> teacher, ...	70
kanḍūla, ...	295, 298, 299	Kaspeirai, a <i>people</i> , ...	291
Kaṅgāniya-halli, vi., ...	78, 83	Kasperia, co., ...	291
Kaṇha, m., ...	209	Kasna, a <i>place</i> , ...	134
Kanika, a <i>Guzan</i> k., ...	142	Kāśyapa, a <i>gōtra</i> , . 81, 167, 202-4, 206-9, 212-5,	
Kanishka, a <i>Kushana</i> k., . 130, 141, 143, 288, 289, 292			272, 275, 313-5, 341-2, 346
Kaṇka-dēva, a <i>Paramāra</i> prince, ...	296, 299	Kaṭagara, vi., ...	313, 317, 323
Kaṇkalāṣ, vi., ...	198, 199, 201	Kātaprabha, m., ...	70
Kannāru, vi., ...	359	Kāthāli, vi., ...	198, 199, 201
kāṅgoyi, an <i>impost</i> , ...	354, 359	Kāthāli, a <i>pattalā</i> , . 193, 194, 195, 197, 199, 200	
Kanuma, vi., ...	341, 346, 349-353	Kātyāyana, a <i>gōtra</i> , ...	207
Kanuma Grant of Sadāśiva-Rāya, ...	341sqq.	Kātyāyana-kila, a <i>gōtra</i> , ...	206
Karva, a <i>gōtra</i> , ...	209, 214	Kātyāyani = Durgā, ...	183
Kārva Basav-āmātya-lōkhara, m., ...	215	Kanḍīnya, a <i>gōtra</i> , ...	81-2, 208-9, 212-5
Kārva-Śyāvāsa, a <i>gōtra</i> , ...	214	Kanḍu-Bhaṭṭa, m., ...	212
Kārvāyana, a <i>gōtra</i> , ...	332, 335-6	Kausalyā, ...	71, 240
Kanyākubja, vi., 84, 88, 90, 95, 179 n. 3, 192, 193,		Kausika, a <i>gōtra</i> , ...	80-2, 202-4, 207-8, 213-4,
	194, 198, 199		314-5, 360, 362-3
Kao-fu, co., ...	290, 291, 292	Kaustubha, a <i>gem</i> , ...	119, 309, 345
kapardaka-purāṇa, a <i>coin</i> , ...	158, 161	Kautsa, a <i>gōtra</i> , ...	98, 109, 109 n. 6, 167, 209
Kāpaya-Nāyaka, m., ...	83, 91, 95	Kāvēri, vi., ...	88, 89, 92, 171
Kapiddha, vi., ...	126, 129	Kāvī grant, ...	122
Kapila, a <i>gōtra</i> , ...	31	Kaviā, m., ...	134, 287, 287 n. 3
Kapila, co., ...	290, 290 n. 5, 291, 292	kāvodu, ...	189
Kapishthala, a <i>gōtra</i> , ...	202, 204, 208-9	Kāyastha, ...	195, 196, 296, 303, 310
Kapsa = Kadphises, ...	294	Kēlavādi-nāḍu, di., ...	231
kara, a <i>tax</i> , ...	161, 184, 186, 195, 196, 199, 200, 327	Kelavādi Three-hundred, di., ...	228
Karahāta, Lord of, a <i>Sinda</i> title, ...	268, 345	Kēraḷa, co., ...	125, 128
Karam-Mēhadapatti, vi., ...	366 n. 5	Kēraḷ-ūṭpatti, a <i>book</i> , ...	170
karapa, ...	366 n. 5	Kēśami-Nāyaka, a <i>Teliaga</i> k., ...	83, 90, 95
Karapa, a <i>Maḥāsāmānta</i> , ...	162	Kēśava, m., ...	74, 75, 76, 81, 82, 202, 203, 207,
Karapa-Guripatti, di., ...	364-6		208, 209
Kāratika, vi., ...	231	Kēśava-Adhvarin, m., ...	314, 319
Karivaraha, sur. of <i>Śālicāhana</i> , ...	157		

The figures refer to pages; n. after a figure to footnotes, and *add.* to Additions and Corrections. The following other abbreviations are used:—*ch.* = chief; *co.* = country; *di.* = district, division; *do.* = the same, ditto; *dy.* = dynasty; *E.* = Eastern; *feud.* = feudatory; *k.* = king; *m.* = man; *mt.* = mountain; *vi.* = river; *s.* a. = see also; *sur.* = surname; *te.* = temple; *vi.* = village, town; *W.* = Western; *wo.* = woman.

	PAGE		PAGE
Kesava-Bhatta, m., ...	343	Köknüllü Vikramāditya, a <i>Chalukya k.</i> , ...	148, 149, 151
Kesavāditya, m., ...	187	Kolāpa-pura, vi., ...	364, 365 & n. 1, 366
Kesavanātha, a <i>divinity</i> , ...	346	Kollakanandivāra-pattalā, di., ...	193, 194, 195, 201
Kesava-sēna, a <i>Sēna k.</i> , ...	157	Kolhām, vi., ...	88
Kesava-Yajvan, m., ...	314, 319	kolvorh, ...	150, 191
<i>kā</i> , form of, ...	121, 121 n. 5, 189, 325	Kommaṇa, m., ...	76, 82
Khade, ...	133, 143	Kōna, a <i>proviser</i> , ...	84, 88, 91, 94, 96
Khajuraho inscription of Yaśovarman, ...	180	Koṇḍu-Bhatta, m., ...	213, 214, 314, 319, 343
Khajuri, vi., ...	195, 196, 201	Kōṇēri-Bhatta, m., ...	214, 315, 321
Khalu, m., ...	208	Kōṇēri-dēva, m., ...	215
Khandanāka, a <i>Maḥāsēnāpati</i> , ...	155	Koṅgaṇi, a <i>Gaṅga sur.</i> , ...	334, 337, 338
Khāṇḍayillā, a <i>place</i> , ...	158, 161	Koṅgaṇivarman, a <i>Gaṅga k.</i> , ...	331, 331 n. 3, 337
Khāṇḍichandra, m., ...	360, 362-3	Koṅgaṇividdha, a <i>Gaṅga k.</i> , ...	333
khāṇḍaka, a <i>measure</i> , ...	331, 335, 336	Koṅgaṇivarman = Koṅgaṇivarman, a <i>Gaṅga k.</i> , ...	331, 332, 335, 336, 337
khāri, a <i>measure</i> , ...	105, 109	Konta, a <i>family</i> , ...	155
khārikā, ...	73, 95	Kōphēn, co., ...	292
Kharōshthī, ...	130, 135	Kōphēnē, co., ...	292
Kharōshthī inscriptions, dating of, ...	135, 141	Kōphēn, vi., ...	292
Kharpura-pudra, vi., ...	178, 184	Koppale, vi., ...	269
Khaśa, a <i>people</i> , ...	327	Kōrnkoṇḍa, vi., ...	84, 88, 89, 91, 96
Khawat, a <i>place</i> , ...	293	Kōsaṇḍa, vi., ...	198, 199, 201
khila, ...	158, 161	kōsavālu, a <i>land measure</i> , ...	176, 187
Khōmmāṇa, father of Bhārtipatta k., ...	177, 181, 187	Koṣhano, ...	288
Khotan, co., ...	142	Kōṭi, a <i>principality</i> , ...	84, 88, 89, 92, 96
Khottiga, a <i>Rāshtrakūṭa k.</i> , ...	296	kōṭikā, a <i>measure</i> , ...	302, 309
Khushapa = Kushapa, ...	288, 295	Kōṭivarsha-vishaya, di., ...	325, 327, 330
Kia-pi-shi = Kapiśa, co., ...	290	Kō (Kau)tan, a <i>gōtra</i> , ...	167
Kie-chu, co., ...	291	kōttaka, ...	313
Kilaka year, ...	342, 345, 353	Kōttallapagga, vi., ...	83, 88, 89, 93-4, 96
Kinnara, ...	305	Kōttapala, ...	327
Kipi, m., ...	297	koṭtor, ...	199, 191
Ki-pin, co., ...	289, 290, 290 n. 5, 291, 292, 293	Kṛpāsāmkara, a <i>Kāñchī āchārya</i> , ...	234
Kiriya-Mādhava = Mādhava II., a <i>Gaṅga k.</i> , ...	332	kṛshī, ...	91
Kirttirāja, m., ...	302, 309	Kṛishṇa = Kṛishṇa-Rāja I., <i>q.v.</i> , ...	127, 129
Klankūḍa Seventy, di., ...	288	Kṛishṇa, m., ...	206, 209
Kithālcha, m., ...	206	Kṛishṇā, vi., ...	344
kiṭikā, ...	176, 186	Kṛishṇa-Bhatta, m., ...	212, 213, 214, 342
K'in-tsin-K'io, a <i>Yue-chī k.</i> , ...	290	Kṛishṇa-dēva-Rāja, a <i>Vijayanagara k.</i> , ...	168, 169, 170, 174
kā written kākā, ...	68	Kṛishṇāditya, m., ...	329, 330
Koa, vi., ...	292	Kṛishṇādityasarma, Bhaṭṭaputra, m., ...	325, 330
Kōki, m., ...	202	Kṛishṇamarāja, m., ...	341-2, 346
Kōkili, a <i>Teluga-Chōḍa k.</i> , ...	145	Kṛishṇa Paṇḍita, m., ...	69, 71, 73, 74, 79, 80
Kōkkata, a <i>commander-in-chief</i> , ...	180, 185	Kṛishṇa-Rāja I., a <i>Rāshtrakūṭa k.</i> , ...	121, 122, 122 n. 6, 125, 128
Kōkkili, an <i>E. Chalukya k.</i> , ...	145		
Kōkkilī, a <i>Chōḍa k.</i> , ...	145		

The figures refer to pages; n. after a figure to footnotes, and *add.* to Additions and Corrections. The following other abbreviations are used:—*ch.* = chief; *co.* = country; *di.* = district, division; *do.* = the same, ditto; *dy.* = dynasty; *E.* = Eastern; *fund.* = fundatory; *k.* = king; *m.* = man; *mt.* = mountain; *ri.* = river; *s. a.* = see also; *sur.* = surname; *te.* = temple; *vi.* = village, town; *W.* = Western; *wo.* = woman.

	PAGE	PAGE	
<i>Kṛishṇarāja-vijaya, a poem,</i>	232	<i>Kumārāmātya, an official,</i>	327
<i>Kṛishṇa-Rāya = Kṛishṇa-dēva-Rāya, a</i>	<i>Vijaya-</i>	<i>Kumārāsanti, m.,</i>	114, 118, 120
<i>nagara k.,</i>	172, 173, 175, 230, 235, 240,	<i>Kumārāśarman, m.,</i>	166, 167, 331, 335, 336
	321, 323	<i>Kumbhaghōṣa, a shrine,</i>	316, 323, 353, 357
<i>Kṛishṇarāja-pura, vi.,</i>	174, 175	<i>Kumbhaghōṣam, a shrine = Kumbhaghōṣa,</i>	171, 240
<i>Kṛishṇatrēya, a gōtra,</i>	202-4, 206-7, 209	<i>Kūṣa, a Teliṅga k.,</i>	83, 90, 92, 95
<i>Kṛishṇavarman, a Gaṅga k.,</i>	332, 334, 337	<i>Kuśāla-Stūpa,</i>	237
<i>kṛita years,</i>	139, 140	<i>Kūṣṭhā, m.,</i>	206
<i>kṛiti,</i>	98, 102, 106 n. 7	<i>Kuṣṭhāma, vi.,</i>	195, 196, 201
<i>kṛitin, sur.,</i>	213-4	<i>Kannaturu, vi.,</i>	313, 317
<i>Kṛiyā-dīpa, a book,</i>	86	<i>Kuṣṭha-Āchārya, m.,</i>	338
<i>Kṛiyāsakti, Kāśivāsa, a Śaiva teacher,</i>	70	<i>Kantala, co.,</i>	265, 266, 267, 271, 274, 275, 278,
<i>Kṛiyāsakti-Dēśika, m.,</i>	69, 73, 79		279, 282
<i>Kṛiyāsakti-pura, vi.,</i>	69, 71, 73, 80, 80 n. 2	<i>Kapparma, m.,</i>	189, 190, 191
<i>kṣā, form of,</i>	122	<i>Kūraka, a rāshtra,</i>	360-3
<i>Kṣhamā-shōḍaṭī, a book,</i>	86	<i>Kūram, vi.,</i>	85
<i>Kṣhatrabandhu, a legendary k.,</i>	88, 93	<i>Kurata-pallikā, vi.,</i>	325, 327, 330
<i>Kṣhatrapa,</i>	140, 141, 294	<i>Kūrattālvāg, sur.,</i>	85, 86 n. 1
<i>Kāśmēśvara, a divinity,</i>	111, 120	<i>Kuravāṭa, co.,</i>	88, 91, 96
<i>kāhētra-kara,</i>	328	<i>Kuravāṭaka, co.,</i>	84
<i>kāhētrapa,</i>	327	<i>Kurugōḍ, vi. See Kurugōḍu,</i>	265
<i>Kāhira-naḍi, vi.,</i>	169	<i>Kurugōḍ inscriptions,</i>	265ff.
<i>Kāhira-Svāmin, m.,</i>	203	<i>Kuṛihattī, vi.,</i>	364
<i>Kāhitipāla, a Pratikāra k.,</i>	179, 180	<i>kūrma,</i>	103, 106
<i>kāhā, form of,</i>	122	<i>Kurugōḍu, vi.,</i>	265, 266, 267, 271, 272, 273, 275,
<i>kī for ti,</i>	146		277, 278, 279, 280, 281, 282, 283
<i>kw, form of,</i>	121	<i>Kuṣhāṇa, dy.,</i>	130, 139
<i>Kūchirāma, m.,</i>	76, 82	<i>Kuṣhāṇa, a race,</i>	288, 289, 291, 292, 293, 294
<i>Kudana-halli, vi.,</i>	78, 83	<i>Kuṣhāṇa-putra,</i>	283
<i>Kuḍiyāntaṇḍal, vi.,</i>	231, 232, 235	<i>Kuṣhi, a race,</i>	288
<i>Kuḍiyāntaṇḍal grant of Vīra-Nṛsiṃha,</i>	231	<i>Kuśika, a gōtra,</i>	81, 209
<i>Kuḍumvama, a place,</i>	158, 161	<i>kusuluka,</i>	143
<i>Kuei-Shuang = Kuṣhāṇa,</i>	294	<i>Kuvalayāpīḍa,</i>	344
<i>Kuhila, m.,</i>	204		
<i>Kujāira, m.,</i>	208		
<i>Kujāla-Kadphisea, a Kuṣhāṇa k.,</i>	143, 289, 290, 294		
<i>Kūkataṣ-konḍa Dādi-Bhaṭṭa, m.,</i>	343		
<i>Kūkē, m.,</i>	206		
<i>kūl,</i>	189, 191		
<i>Kulika, a people,</i>	327		
<i>Kumārādatta, m.,</i>	155		
<i>Kumāra-dēvi, a Gupta queen,</i>	368		
<i>Kumāra-Dhūrjati, a poet,</i>	232		
<i>Kumārāgiri-Nātha, a minister,</i>	98, 105, 109		
<i>Kumārāgopta, a Gupta k.,</i>	369-371		
<i>Kumārāgupta, a Magadhā k.,</i>	113		

	PAGE
<i>l, form of,</i>	144, 189
<i>l, sound of,</i>	145, 147
<i>l, written l,</i>	68
<i>l, intervocalic,</i>	146
<i>l, use of,</i>	192
<i>l, preserved or written r,</i>	364
<i>l and h,</i>	189
<i>lagadā,</i>	296, 302, 303, 309, 310
<i>Lagarddha (Alagarddha ?), m.,</i>	126
<i>Laghukamavali, vi.,</i>	195, 196, 200

L

<i>l, form of,</i>	144, 189
<i>l, sound of,</i>	145, 147
<i>l, written l,</i>	68
<i>l, intervocalic,</i>	146
<i>l, use of,</i>	192
<i>l, preserved or written r,</i>	364
<i>l and l,</i>	189
<i>lagadā,</i>	296, 302, 303, 309, 310
<i>Lagarddha (Alagarddha ?), m.,</i>	126
<i>Laghukamavali, vi.,</i>	195, 196, 200

The figures refer to pages; n. after a figure to footnotes, and add. to Additions and Corrections. The following other abbreviations are used: —*ch.* = chief; *co.* = country; *di.* = district, division; *do.* = the same, ditto; *dy.* = dynasty; *E.* = Eastern; *feud.* = feudatory; *k.* = king; *m.* = man; *mt.* = mountain; *ri.* = river; *s. p.* = see also; *sur.* = surname; *te.* = temple; *vi.* = village, town; *W.* = Western; *w.* = woman.

	PAGE		PAGE
Mahābhūta, a <i>maśādāna</i> , ...	172	Mahā-Vishṇu-Bhaṭṭa, m., ...	212
maśādāna, ...	308 n. 5	Mahendra, <i>mt.</i> , ...	361-3
maśādānaṇāyaka, ...	327	Mahendrapāla, a <i>Pratihāra k.</i> , 178, 180, 181, 183	
Mahādēva, m., ...	206, 314, 319	Mahendrapāla-dēva II., a <i>Pratihāra k.</i> , 177, 178, 179	
Mahādēva, a <i>Kāūchi āchārya</i> , ...	233, 234, 235	Mahendrāyudha, a <i>Pratihāra k.</i> , ...	179
Mahādēva = Śiva, ...	295, 298	Mahēśvara, ...	199, 202, 207
Mahādēva-Sarasvatī, a <i>Kāūchi āchārya</i> , 232, 235, 240, 354, 356-9		Mahēśvara, a <i>Kāūchi āchārya</i> , ...	234
Mahādēvi-Dēvi, a <i>Pratihāra queen</i> , ...	178, 183	Māhēśvara, ...	365
maśādharmādhyakṣa, an <i>official title</i> , ...	160	Mahidapāla, a <i>Pratihāra k.</i> , ...	179
Mahā-Gaṇapati, m., ...	212	Mahidhara, m., ...	202, 204, 205, 207, 325, 328, 330
maśāgaṇastha, an <i>official title</i> , ...	180	Mahidhara Bhairava, m., ...	343
Mahā-Gōpāla-Bhaṭṭa, m., ...	212	Mahidhara-miśra Paṇḍita, ...	207
maśājana, ...	189, 190	Mahinārāma, <i>vi.</i> , ...	147, 148, 150, 152
Mahākāla, ...	180, 290, 292	Mahipāla, a <i>Pratihāra k.</i> , ...	179, 180
Mahā-Kṛṣṇa-Bhaṭṭa, m., ...	212	Mahī-Pāla I., a <i>Pāla k.</i> , ...	325, 326, 327, 328, 330
maśāksapaṭalika, an <i>official title</i> , ...	327	Mahī-Pāla I., grant of, ...	324
maśākomārāmātya, an <i>official title</i> , ...	327	Mahipati, m., ...	202
Mahāliṅga-Bhaṭṭa, <i>sur.</i> , ...	315, 320	Mahōdadhī, m., ...	206
Mahā-Mahādēva-Bhaṭṭa, m., ...	212	Mahōdaya = Kanauj, 177, 179, 180, 183, 183 n. 3, 184 n. 15	
maśāmahattara, an <i>official title</i> , ...	360, 362-3	maśōdaya, ...	233, 240
maśāmaṇḍalēśvara, a <i>title</i> , 266, 268, 269, 272, 273, 276, 278, 279, 290, 281, 282, 283		Māhula, m., ...	202
Mahāmaṇḍalēśvara Piriya-Rāchamalla-dēvarasa, 276, 277		Mallāpura-Mādarasa, m., ...	215, 216
Mahā-Mudgala-Bhaṭṭa, m., ...	212	Māiri, a <i>Kāotun king</i> , ...	133
maśāmandrādīkṛita, an <i>official title</i> , ...	160	māitri, ...	328
Mahānandī-tīrtha, a <i>tīrtha</i> , ...	171	Majnāda, <i>vi.</i> , ...	197, 199, 200, 201
maśāpūlpati, an <i>official title</i> , ...	160	Makara-saṅkrama, ...	323
maśā-pradhāna, a <i>minister</i> , ...	281	maṅkarikā, ...	197
maśāpratihāra, an <i>official title</i> , ...	160	Mālava, <i>co. or people</i> , 293, 294, 296, 297, 299, 305, 327, 370-1	
Mahā-Rāmachandra, m., ...	212	Mālava era referred to, ...	140, 289, 294
Mahā-Rāmachandrārya, m., ...	212	Mālava coins, ...	368
Mahārāṣṭra, <i>co.</i> , ...	84, 88, 90	Mākya mountains, ...	326, 330
maharāṣi ('arshi), ...	203, 209	Maldēvi, <i>ri.</i> , ...	99
maśāsabda, ...	283	Mālā, m., ...	207
maśāśmanta, a <i>title</i> , ...	269	Mālāni, <i>vi.</i> , ...	195, 196, 201
maśāśādhivigrahika, a <i>minister</i> , ...	160, 327	Malik Kafur, <i>k.</i> , ...	87
Mahāśarman, m., ...	203	Malivāda, <i>vi.</i> , ...	198, 199, 201
Mahāśeṇa = Kārttikēya, ...	149, 151, 166	Malla-kshētra, an <i>estate</i> , ...	148, 150, 152
maśāśēnāpati, an <i>official title</i> , ...	155, 160	Mallāya, m., ...	174, 315, 322, 342
Mahāśōṇa, m., ...	208	Mallayāschāri, m., ...	235
Mahāsū, m., ...	207	Mallayāśāri, m. (= 'chāri), ...	240
mahattara, ...	150	Mallapārya, m., ...	75, 81
Māhava, m., ...	202, 205	Mallārya, m., ...	75, 76, 81, 82
		Malli-Bhaṭṭa, m., ...	214
		Mallu-Bhaṭṭa, m., ...	342

The figures refer to pages; *n.* after a figure to footnotes, and *add.* to Additions and Corrections. The following other abbreviations are used: —*ch.* = chief; *co.* = country; *di.* = district, division; *du.* = the same, ditto; *dy.* = dynasty; *E.* = Eastern; *feud.* = feudatory; *k.* = king; *m.* = man; *mt.* = mountain; *ri.* = river; *s. a.* = see also; *sur.* = surname; *te.* = temple; *vi.* = village, town; *W.* = Western; *wa.* = woman.

	PAGE		PAGE
Maipāiyakka, <i>wo.</i> , ...	267, 273, 278	Mārgasahāyēśvara, a <i>divinity</i> , ...	312
Malu, <i>m.</i> , ...	203	Mārgasira, ...	267
Maluyi, <i>vi.</i> , ...	198, 199, 201	Mārgi, <i>m.</i> , ...	337
Mālvā. <i>See</i> Mālava, ...	305	Mārikēśi, <i>m.</i> , ...	339
Māmbākam, <i>vi.</i> , ...	313, 317	Mārishēṣa, <i>m.</i> , ...	337
Māmē, <i>m.</i> , ...	209	Maru, <i>co.</i> , ...	330
Mānabhūsha, <i>k.</i> , ...	171	Māsū, <i>m.</i> , ...	208
mānaka, a <i>measure</i> , ...	302, 309	Matamata-simha, <i>sur. of Śālicālana</i> , ...	157
Maṣappākkam, <i>vi.</i> , ...	169, 173	mātarā, ...	147
Mānasa, <i>lake</i> , ...	73, 80, 80 n. 3	maṭha, ...	354, 359 & n. 7
Mānavya, a <i>gōtra</i> , ...	149, 151, 166-7	Māṭha-Bhaṭṭa, <i>m.</i> , ...	314, 318
Mañchikoṇḍa, <i>sur.</i> , ...	88, 90, 95	Mathurā, <i>vi.</i> , ...	131, 139
Mañchikoṇḍa, <i>province</i> , ...	89	Mathurā capital inscriptions, ...	132
Mañchikoṇḍa, a <i>family</i> , ...	90, 95	Mātridinna-grāma, <i>vi.</i> , ...	148, 149, 150, 152
maṇḍalēśa, ...	296, 302, 309	Mātrivarma, <i>m.</i> , ...	337
Maṇḍalēśvara-Mahālēśa, a <i>form of Śiva</i> , ...	295	matter, ...	277, 278, 365-6
Maṇḍana, a <i>Paramāra k.</i> , ...	296	Mandalya, a <i>gōtra</i> , ...	268, 314-5
Maṇḍana-dēva, a <i>Paramāra prince</i> , 297, 299,		Maakhari, <i>dy.</i> , ...	110, 111, 112, 114
	302, 303, 305, 309	Maana, a <i>gōtra</i> , ...	209
Maṇḍanādarman, <i>m.</i> , ...	166, 167	Mayajamitna, <i>vi.</i> , ...	198, 199, 201
Maṇḍapikā, <i>vi.</i> , ...	180, 181, 185	Māyādhara, <i>m.</i> , ...	203
Mandara, <i>mt.</i> , ...	308	Māyī-Bhaṭṭa, <i>m.</i> , ...	214
Mandasar inscription, ...	139	Mayiri, a <i>Kāśāta k.</i> , ...	133
Māṇḍa, <i>vi.</i> , ...	198, 199, 201	Māchāmbikā, <i>wo.</i> , ...	69, 80
Māṅga-Bhaṭṭa, <i>m.</i> , ...	315, 321	Māda, a <i>people</i> , ...	327, 330
Māṅga, <i>m.</i> , ...	75, 81	Māharauli inscription, ...	367-371
māṇi, a <i>measure</i> , ...	162, 167	Māi-nāṭṭa-Vedāntin, <i>sur.</i> , ...	86
Maṇḍa, <i>vi.</i> , ...	198, 199, 201	Melupāka, <i>vi.</i> , ...	354, 358-9
Māṇikīāla inscription, ...	131, 132, 136	Mēlupāka Grant of Mahādēvēndra Sarasvatī, 353sqq.	
Maṇimay Aubhala-Bhaṭṭa, <i>m.</i> , ...	343	Mēru, <i>mt.</i> , ...	101, 106, 127, 298, 303
Manishin Giri-Bhaṭṭa, <i>m.</i> , ...	214	Mēhadapatti, <i>vi.</i> , ...	364-6
Manishin Rāmachandra, <i>m.</i> , ...	314, 318	metro, irregular, ...	168
Maṇivūr, <i>vi.</i> , ...	267, 268, 273, 278	metta, ...	176
Manōratha, <i>m.</i> , ...	206	Mēyārya, <i>m.</i> , ...	75, 81
Manu, ...	119, 204, 271	mā written <i>agā</i> , ...	110
Mānya, ...	359 & n. 7	Mihira, a <i>Pratīhāra k.</i> , ...	179
mara, a <i>measure</i> , ...	354, 359	Mihiravarman, <i>m.</i> , ...	114, 118, 120
Māra, <i>m.</i> , ...	74, 81	mīmāṃsā, ...	325, 327, 330
Māra-Bhaṭṭa, <i>sur.</i> , ...	315, 320	Minadhvaṣa, ...	200 n. 1
Māraja, a <i>Vijayanagara prince</i> , ...	98, 102, 107	Mina-samkrānti, ...	181, 186
Mārārya, <i>m.</i> , ...	74, 81	Mir Zūla-Salyid Mustapha, ...	355
Māra-simha Lōka-Tripētra, a <i>Gaṅga k.</i> , ...	239	Mitrādarman, <i>m.</i> , ...	167
Mārasinga Ereyappa Lōka-Tripētra, a <i>Gaṅga</i>		Mōchcha, <i>name of a field</i> , ...	182, 188
<i>Vararāja</i> , ...	339	modal, ...	364
Marataka-pūti, <i>vi.</i> , ...	312	Moika, <i>m.</i> , ...	134
Marāṭhi, the letter <i>l</i> in, ...	145	Mōkhali-Mankhari, ...	112

The figures refer to pages: n. after a figure to footnotes, and add. to Additions and Corrections. The following other abbreviations are used:—*ch.* = chief; *co.* = country; *di.* = district, division; *do.* = the same, ditto; *dy.* = dynasty; *E.* = Eastern; *feud.* = feudatory; *k.* = king; *m.* = man; *mt.* = mountain; *vi.* = river; *s. a. s.* = see also; *sur.* = surname; *te.* = temple; *vi.* = village, town; *W.* = Western; *wo.* = woman.

	PAGE		PAGE
Nailatti grant of Vallāṅka-Ścna, ...	156	Narayanāgal Twelve, <i>di.</i> , ...	268
naivēdyā, ...	125	Natigolige Forty, <i>di.</i> , ...	289
Nakōcharā. See Kanakōcharā, ...	148, 152	Narmadā, <i>ri.</i> , ...	296, 297, 299, 304, 344
nakshatra—		Natyana (P). See Achhatyana, ...	148
Pushya, ...	100, 103, 108	naukā-bhāṭaka, ...	195
Śravaṇa, ...	69, 73, 80	Nava-Kāma, a <i>Gaṅga k.</i> , ...	338
Viśākṣā, ...	169, 173, 175	Navasārikā, <i>vi.</i> , ...	148
Nāḷa, ...	72, 79	Naya, Kharōshthi inscription from, ...	133
nala, <i>measure</i> , ...	153	Nāyaka, a <i>family</i> , ...	90
nāla, <i>cultivable land</i> , ...	158, 161	āḥ, form of, ...	122
Nala, ...	171, 237, 240, 280, 283, 317	āḥ, form of, ...	122
Nālhaṇa, <i>m.</i> , ...	202	āḥ, form of, ...	122
Nalla-Nūka, a <i>Redḍi ch.</i> , ...	70	nala-vidā, ...	266, 266 n. 4, 271
Nāmaṇa-Bhātta, <i>m.</i> , ...	212, 213, 214	Neṣal, <i>co.</i> , ...	234, 235
Nānā, <i>m.</i> , ...	206, 208	nesaga, ...	364
Nanda-giri, <i>mt.</i> , ...	354-6	āḥ, form of, ...	122
Nandana, ...	272, 276	āḥ for āḥ and āḥ, ...	110
Nanda-pura, <i>ri.</i> , ...	93, 105, 109	āḥri, form of, ...	122
Nandi, figure of, ...	265, 280, 282	āḥ written āḥ, ...	110
Nandimāḥa, ...	280, 282	ni [buddha], 'registered', ...	326 and n. 1
Nāndi-pura-dvāri, <i>ri.</i> , ...	123, 127, 129	nidhi, ...	174, 318, 346
Nandīśarman, <i>m.</i> , ...	166, 167	Niḥsaṅka-malla, <i>sur. of Śālicāhana</i> , ...	157
Nandīvarman, <i>m.</i> , ...	337	nikshēpa, ...	174, 318, 346
Nandīyā, <i>ri.</i> , ...	181	Nirahalla, <i>ri.</i> , ...	267, 272, 277
Nānē, <i>m.</i> , ...	206	Nirbhaya, a <i>Pratīḍara k.</i> , ...	179
Nāngipūndi, <i>ri.</i> , ...	88, 89, 94, 96	nirvāga, ...	295
Nāḷajaya-anātya, <i>m.</i> , ...	215	Nirvināta, a <i>Gaṅga k.</i> , ...	333, 337
Nāṇṇa, <i>m.</i> , ...	206	niti, ...	128, 335
Nān-tun, <i>ri.</i> , ...	292	Nittimārga—Raṇavikramayya, a <i>Gaṅga k.</i> , ...	339
Nānū, <i>m.</i> , ...	206	Nityapramudita-dēva, a <i>divinity</i> , ...	177, 181, 186
Napuhā for Nahnahā, ...	149, 151	nivartana, ...	126, 129, 150
Nāra-Avadhānu, <i>m.</i> , ...	342	Nivritti, a <i>śāśīra</i> , ...	171
Nārada, ...	280	āḥ, form of, ...	121
Narahari, <i>m.</i> , ...	342	as written as, ...	98
Narapati, <i>m.</i> , ...	207	as for as, ...	98
Narasa, a <i>Vijayanagara k.</i> , ...	171, 174, 175, 230, 232, 240, 323	Ṣoacha, <i>vi.</i> , ...	295
Narasamma-samudra, <i>ri.</i> , ...	346, 348	Noḷambavāḍi Thirty-two Thousand, <i>di.</i> , ...	269
Narasayya, <i>m.</i> , ...	343	Note on King Chandra of the Mēharuḷli In-	
Narasimha, <i>m.</i> , ...	202, 208, 314, 320, 342	scription, ...	367-371
Narasimha, <i>m.</i> , ...	342	Nrīga, ...	149, 151, 171, 173, 240, 317
Narasimha-Adhvarin, <i>m.</i> , ...	314, 320	Nrīhari, <i>m.</i> , ...	74, 75, 76, 81, 82
Narasimha-Suddhi, <i>m.</i> , ...	212, 214	Nrīsiṅha, <i>m.</i> , ...	74, 81
Nārāyaṇa, <i>m.</i> , ...	203, 204, 205, 206, 208, 209, 283, 314, 320	Nrīsiṅha-Adhvarin, <i>m.</i> , ...	314, 320
Nārāyaṇa-Bhātta, <i>m.</i> , ...	212, 214, 313, 318, 343	Nrīsiṅha-Bhātta, <i>m.</i> , ...	212
Nārāyaṇa-Pāla, a <i>Pāla k.</i> , ...	326, 329	st, form of, ...	121
Naravarman, <i>k.</i> , ...	139, 370-1	Nūka-Bhūpāla, <i>k.</i> , ...	69, 70, 72, 79

The figures refer to pages; n. after a figure to footnotes, and *add.* to Additions and Corrections. The following other abbreviations are used:—*ch.* = chief; *co.* = country; *di.* = district, division; *do.* = the same, ditto; *dy.* = dynasty; *E.* = Eastern; *feud.* = feudatory; *k.* = king; *m.* = man; *mt.* = mountain; *ri.* = river; *s. a.* = see also; *sur.* = surname; *te.* = temple; *vi.* = village, town; *W.* = Western; *wo.* = woman.

	PAGE		PAGE
numerals, Telugu-Kannada, ...	68, 83, 210, 310	palikā, ...	176, 182, 187, 188, 309
numerical symbols, ...	173	Pallava, <i>dy.</i> , ...	140, 332, 333, 335, 336
O		pañcaka, a <i>measure</i> , ...	290, 302, 309
ō, form of, ...	157	Pānāra, <i>province</i> , ...	84, 88, 91, 94, 96
ō before surda, ...	147	Pāna-rāṣṭra, <i>co.</i> , ...	334
Ōbāmbikā, a <i>Vijayanagara queen</i> , ...	312	Pañchabrahma, a <i>mantra</i> , ...	274 n. 2
Ōbala, <i>m.</i> , ...	74, 80	Pañcābrahma-Upaniṣad, a <i>book</i> , ...	274 n. 2
Obind inscription, ...	132, 137	Pañchāla, a <i>people</i> , ...	193
oil, ...	182	Pañchalāṅgali, a <i>maḥādāna</i> , ...	172
Onpadināyirappaḍi-eyākkhyānam, a <i>work</i> , ...	85 n. 1	pañcha-mahā-śabda, ...	231
Orissa, <i>co.</i> , ...	175	Pāndava, ...	102, 107
Orvāyālūr, <i>vi.</i> , ...	267, 273, 277	pāṇḍi, ...	190, 191
Ośadhīpaty-upamāyita-gaṇḍa, a <i>Vijayanagara title</i> , ...	344	Pāṇḍya, <i>co.</i> , ...	84, 88, 90
Ōṣumbhalā, <i>vi.</i> , ...	148	Pāṇḍya, <i>dy.</i> , ...	125, 128, 171, 175
Ōvāsu-dēva, <i>m.</i> , ...	158, 161, 162, 163	Pāṇḍya, a <i>people</i> , ...	240, 266, 271, 275
P		Pañgaḷa, <i>di.</i> , ...	313, 317
p, form of, ...	121, 157, 232	Pāṇḍhara, <i>m.</i> , ...	203, 204
p initial > h, ...	266	Paṇi-haṭi, <i>vi.</i> , ...	195, 196, 201
Pada-Dōḍē, <i>m.</i> , ...	203	pāṇi-śākhā, ...	156
Pada-Kēśava, <i>m.</i> , ...	208	Panjtar inscription, ...	131, 134, 136
Paḍaviḍu, <i>co.</i> , ...	173, 175, 232, 313, 317, 323	Pañktirātha-Daśaratha, ...	171, 240
Padmākāṣa-Vishṇu, ...	172	Pāpāra, <i>m.</i> , ...	337
Padmālayā-Lakṣmī, ...	163	Pāpata, <i>m.</i> , ...	204, 208
Padmaṇa, <i>m.</i> , ...	76, 82	Pāpya, <i>m.</i> , ...	206
Padmanābha, <i>m.</i> , ...	202, 204	paramabhaṭṭāraka, a <i>title</i> , ...	193, 197, 198, 275, 279, 281, 365
Padmanābha-Vishṇu, ...	334, 335	parama-māhēśvara, a <i>title</i> , ...	193, 194, 197
Padmē, <i>m.</i> , ...	202	Paramāra, <i>m. and race</i> , ...	290, 293, 304
Pahākara, <i>m.</i> , ...	204, 206, 207	Paramārtha, a <i>Buddhist writer</i> , ...	291
Paiśāchi dialects, the letter <i>l</i> in, ...	145	paramēśvara, a <i>title</i> , ...	193, 194, 197, 198, 199, 275, 279-81, 365
Paithaṇ grant, ...	122	Para-rāja-bhayaṅkara, <i>sur. of Achyuta-Rāja</i> , ...	316
Paja inscription, ...	131, 133, 135, 136	Para-rāja-bhayaṅkara, <i>sur. of Kṛṣṇa-dēva-Rāja</i> , ...	173
pāka-daṇḍa, ...	189	Parāśara, <i>m.</i> , ...	206, 309
Pakaḍi, <i>vi.</i> , ...	198, 199, 201	Parāśara, a <i>gōtra</i> , ...	203-4, 206, 208-9, 212-4, 315, 325, 327, 330
pakeha, dating by, ...	140	Parāśara, a <i>pravara</i> , ...	325, 327, 330
Pāla, <i>dy.</i> , ...	182, 325, 329 n. 1	Parāśara-Bhaṭṭa, a <i>teacher</i> , ...	83, 84, 85, 86, 86 n. 1, 87, 88, 93, 94, 96
Pālapūr, <i>vi.</i> , ...	313, 317, 323	Parāśara-śāla, a <i>hill</i> , ...	84
Pālār, <i>vi.</i> , ...	175	Parasīva, a <i>Kāśchī āchārya</i> , ...	233, 234
Palāśa-kūpikā, <i>vi.</i> , ...	181, 187	Paripūrṇabōdha, a <i>Kāśchī āchārya</i> , ...	234
Palātu-Dhēri pedestal inscription, ...	132	Partabgarh inscription of Samvat 1003, ...	176ff.
Pālēru, an <i>estate</i> , ...	89, 95	Pārtha, ...	272, 276
Palganna, a <i>koffaka</i> , ...	313, 317, 323		
Pālhaṇa, <i>m.</i> , ...	209		
Pālḥē, <i>m.</i> , ...	203, 206		

The figures refer to pages; n. after a figure to footnotes, and add. to Additions and Corrections. The following abbreviations are used: —*ch.* = chief; *co.* = country; *di.* = district, division; *do.* = the same, ditto; *dy.* = dynasty; *E.* = Eastern; *fund.* = fundatory; *k.* = king; *m.* = man; *mt.* = mountain; *ri.* = river; *s. a.* = see also; *sur.* = surname; *te.* = temple; *vi.* = village, town; *W.* = Western; *wo.* = woman.

	PAGE		PAGE
Paruvi, a <i>vishaya</i> , ...	331, 335, 336	Piriya-Rāchamalla = Rāchamalla I., a <i>Sinda</i>	
Paruvi, a <i>tanā</i> , ...	331, 335, 336	prince, ...	267, 272, 276
Parvata-Bhaṭṭa, m., ...	214	Pūthana, m., ...	203
Pārvatī, ...	270, 273, 280, 282	Pūthē, m., ...	205
Pārvatīnātha, m., ...	343	Pūthū, m., ...	205
pāshāpa, ...	346	Pūṭṭisārman, m., ...	166, 167
Pāsū, m., ...	208	Ponnā-pura, vi., ...	210, 231
Pāsupāya, ...	91	Porigere, vi., ...	188, 189, 190
Paṇḍupatisārman, m., ...	187	Poruṇāmīlā, vi., ...	97, 100, 102, 108
pātaka, ...	158, 161	Poruṇāmīlā Tank Inscription, ...	97ff.
Pātāja-Chakravartin, sur. of a <i>Sinda</i> k., ...	281, 283	Pōshali, vi., ...	325, 328, 330
Pātāla-chakravartin, title of a <i>Nāga</i> ruler, ...	273, 277	Posha puri, vi., ...	134, 143
Pāṭalika, vi., ...	334	Pōshana-nirbhara-bhū-nava-khaṇḍa, a <i>Fijaya-</i>	
Patana, vi., ...	198, 199, 201	nagara title, ...	344
Paṭṇendal, vi., ...	311, 313, 315, 321	Po-t'iao = Vāṇadēva, ...	141, 144
pathadharasa, ...	132	Poyasa Kannada, a sect, ...	313
pathaka, ...	178	pp, form of, ...	68
Pāṭha-Sāstra, a book, ...	103, 106	Prabhākara, m., ...	204, 205
Patika, a <i>Kaśatrapa</i> , ...	131, 135, 139	Prabhānaka-charita, a book, ...	179 n. 3
pāṭivratya, ...	344	prābhṛitīkṛite, ...	327
pattalā, ...	195, 196, 199	prabha-sakti, ...	329
Pañjōmī, ...	281, 284	Prachegabudha, ...	295
Paṇḍarika, a sacrifice, ...	149, 151	Pradhāna, a minister, ...	281
Pavaṇāha, m., ...	202, 203, 205, 206, 208	Prajāpatisārman, m., ...	166, 167
Pavaṇāha-pura, vi., ...	198, 199, 201	Prajāśāghana, a <i>Kāncī āchārya</i> , ...	23
Peddana, m., ...	74, 81	prakṛiti, ...	189 n. 1, 190
Peddi-Bhaṭṭa, m., ...	213	Pralaya-inahā-varāha, sur. of <i>Kṛishṇa Rāja</i>	
Pendattāra Kōṅgaṇi, m., ...	338	I., ...	125, 127, 129
Pendlikūntu-chervu, vi., ...	88, 94	Prāṇyādri = Himālaya, ...	330
Penukonda copper-plate grant, ...	163	Prallayannūr, vi., ...	169, 175
Penukonda plates of Mādhava II., ...	331	Prāntapāla, ...	327
Penuṅḡonda, vi., ...	88, 89, 94	Prapatitva, ...	299
Periya-purāṇam, a book, ...	334	Prasādhanā-dēvi, a <i>Pratihāra</i> queen, ...	178, 183
Periya Tiru-muḍiy-ṇḍaieu, a book, ...	88	Pratihāra. See Mahāpratihāra, ...	160
Permādi I., a <i>Sinda</i> ch., ...	268	Pratihāra, dy., ...	179, 180, 183 n. 13, 194
Permādi II., a <i>Sinda</i> ch., ...	268	pratyādāya, ...	195, 196
Permānadi, a <i>Gaṅga</i> k., ...	364-6	Pratyāṇḍaka Four-thousand, di., ...	268
Perudattakāra-Kōṅgaṇi, m., ...	338	pratyāya, ...	161, 327
Perudattakāra = Kōṅgaṇi Perudattakāra, ...	338	Prasachana-Sūtra, a book, ...	216
pā, form of, ...	157	pravara, ...	153
Phra-ṇo, a <i>Stūpa</i> , ...	142	pravarae—	
Phaṇi-Bhaṭṭa, m., ...	212, 345	Aṅgira, ...	158, 161
Pīlapati. See Mahāpīlapati, ...	160	Bharadvāja, ...	158
Pinakini, vi., ...	345, 353	Bṛihaspati, ...	158, 161
Pinākinī-sthala, a place, ...	344	Parāśara, ...	325, 330
Pinnaka, vi., ...	48, 151, 152	Śakti, ...	325, 330
Pippalāda, a <i>gōtra</i> , ...	207	Vasishtha, ...	325, 330
		pravihhaga, ...	167

The figures refer to pages; n. after a figure to footnotes, and add. to Additions and Corrections. The following other abbreviations are used:—ch., = chief; co., = country; di., = district, division; do., = the same, ditto; dy., = dynasty; E., = Eastern; feud., = feudatory; k., = king; m., = man; mt., = mountain; vi., = river; s. a., = see also; sur., = surname; te., = temple; vi., = village, town; W., = Western; wo., = woman.

	PAGE		PAGE
<i>Prayōga-ratna-mālā</i> , a <i>Śrauta</i> book, ...	70	<i>r</i> , use of, ...	98
Prithivi-Koṅgaṇi, a <i>Gaṅga</i> k., ...	338	<i>ra</i> , symbol of fire, ...	101, 105
Prithivi-Koṅgaṇi Śivamāra, a <i>Gaṅga</i> k., ...	338	Rāchamalla I., a <i>Sinda</i> k., ...	266, 266 n. 5, 267, 269, 271, 276, 277, 278, 279, 283
Prithivi-Koṅgaṇi Śrī-Purnusha, a <i>Gaṅga</i> k., ...	339	Rāchamalla II., a <i>Sinda</i> k., ...	265, 266, 267, 269, 269 n. 1, 276, 277, 279, 280, 282, 283
pūlaka, ...	296, 302, 309	Rāchamallaśvara = Rāchamalla I., a <i>Sinda</i> k., ...	279, 281, 283
Pulakēśin, a name, ...	145	Rāchchhata, m., ...	207
Pulakēśin II., a <i>Chalukya</i> k., ...	148, 149, 151	Rāchūri Timmā-Bhaṭṭa, m., ...	343
Puligeṇe, vi., ...	188, 364-6	Rāgha, a <i>Maṇḍala</i> , ...	157, 158, 159, 162
Pulikara, vi., ...	188	Rāghava, m., ...	203, 208, 214
Pulinda, a tribe, ...	162	Rāghava-Bhaṭṭa, m., ...	342, 343
Pullam-Bhaṭṭa, m., ...	212	Rāghanaṭha-Sudhā, m., ...	212
Pulamāvi, an <i>Andhra</i> k., ...	140, 153, 154, 155	Rāghasya- <i>traya</i> , a book, ...	83
Punācha, m., ...	209	Rāhila, m., ...	208
punctuation marks, ...	119	Rājamalla = Śatyavākya-Koṅgaṇivarman, a <i>Gaṅga</i> k., ...	339
Paṇḍravanīhana, a <i>bhukti</i> , ...	325, 327, 330	rājāmātya, ...	327
Panyajatta, vi., ...	169, 173, 175	rājanyaka, ...	160, 327
Paramdara = Indra, ...	360	Rajapāla, m., ...	202, 204, 206
Parāṇa, ...	101, 106, 317, 335, 338	rāja-putra, ...	327
Parāṇa Aṅbhala-Bhaṭṭa, m., ...	343	rāja-si[ṅ]gha, ...	122, 124
Parāṇa-purnusha, ...	299	rājasthānīya, ...	327
Purāsa, m., ...	206	rājasūya, ...	149, 151
Parigeṇe, vi., ...	188	Rājā, m., ...	204, 205
Parikara, vi., ...	188	Rājīni-tadāka, a place (tank?), ...	126, 129
Pārṣabōdha, a <i>Kāuchī āchārya</i> , ...	234	Rājya-Pāla, a <i>Pāla</i> k., ...	326, 329
parāhita, ...	160	Rājyapāla, a <i>Pratihāra</i> k., ...	179, 179 n. 4
Parūras, ...	101, 106, 171, 240, 323	Rājynāī, sister of Harsha of Kanauj, ...	113
purnusha-chchhāyā, a measure, ...	362, 363 n. 1	Rāihā, m., ...	204
Purnushōttama, m., ...	204, 209	Rāmā = Śitā, ...	284
Purnushōttama = Vishnu, ...	308	Rāma, a k., ...	171, 172, 179, 205, 207, 230, 240, 281, 284, 326, 329
Purnushōttama-Bhaṭṭa, m., ...	212, 213, 342	Rāmabhadra-dēva, a <i>Pratihāra</i> k., ...	178, 179, 183
Puskara, vi., ...	367, 370	Rāma-Bhaṭṭa, m., ...	343
Pushī, wife of Ganapati, ...	100, 105	Rāmā-Bhaṭṭa, m., ...	314, 315, 318
Pushya, a <i>nakṣatra</i> , ...	100, 103, 108	Rāmachandra, ...	75, 81, 212
Pushya, day, ...	103, 108	Rāmachandra-Dikshita, m., ...	311, 312, 313, 315, 317, 323
Pushyabhūti, ancestor of Harsha, ...	111	Rāma-charita, a book, ...	329 n. 1
P'u-ta, co., ...	290	Rāmadāsa, a saint, ...	354-5
pūti, ...	161, 327	Rāma-dēva, a <i>Pratihāra</i> k., ...	149, 151, 179
puttiga, ...	190, 191		

R

<i>r</i> , form of, ...	153
<i>r</i> sign omitted, ...	311
<i>r</i> , doubling with, ...	110, 325
<i>r</i> , doubling after, ...	69, 98, 146, 157, 164, 177, 192, 210, 360
<i>r</i> , form of, ...	210, 341

The figures refer to pages; n. after a figure to footnotes, and add. to Additions and Corrections. The following other abbreviations are used: —*ch.* = chief; *co.* = country; *di.* = district, division; *do.* = the same, ditto; *dy.* = dynasty; *E.* = Eastern; *feud.* = feudatory; *k.* = king; *m.* = man; *mt.* = mountain; *ri.* = river; *s.* = see also; *sur.* = surname; *te.* = temple; *vi.* = village, town; *W.* = Western; *wo.* = woman.

	PAGE		PAGE
Rāmākṛishṇa, m., ...	71, 74	Rig-vēda, ...	81, 82, 105, 109, 212-5, 314-5
Rāma-Mītra, m., ...	85, 86	Rig-vēdin, ...	315
Rāmānuja, ...	85, 86, 86 n. 1	Rilbhā, m., ...	202
Rāmānujārya, ...	95	Rilhū, m., ...	209
Rāmarāja, m., ...	210, 211	rieli, ...	204, 208
Rāma-Rāja, a <i>Karnāta k.</i> , ...	342, 344, 353	Rishikēśa = Hrishī ² , ...	328, 330
Rāmārya, m., ...	75, 81	Risū, m., ...	20
Rāmasanundra, vi., ...	210, 231	ritu syllable, ...	100, 105
Rāmā-Sāstrin, m., ...	354, 357-9	Rōhana, a <i>mountain</i> , ...	101, 106, 106 n. 6
Rāmasaṭṭa, a <i>shrine</i> , ...	171, 240	Rōhipi, ...	281, 284
Rāmēśa, a <i>divinity</i> , ...	70, 74, 80	Rōsha-krita-pratipārthiva-daṇḍa, sur. of <i>Vijaya-</i>	
Rāmēśvara-Bhaṭṭa, m., ...	213, 214	nagara k., ...	173
Rāmēśvaram, a <i>shrine</i> , ...	171, 174	ru written ri, ...	98
Rāmēśvara Manishin, m., ...	213	rā, form of, ...	144
Rāga-chapḍa, sur. of <i>Krishṇa-dēva-Rāja</i> , ...	173	Rudra syllable, ...	100, 105
rāpaka, ...	160	Rudra-Bhaṭṭa, m., ...	314, 319
Rānavikramayya, a <i>Gaṅga k.</i> , ...	339	Rudradāman, a <i>Satrap</i> , ...	140
Rānē, m., ...	204	rudrākaha, ...	170, 173, 175
Raṅga, k., ...	344, 353	rūpaka, ...	302, 309
Raṅga, a <i>Vijayanagara ch.</i> , ...	219, 230	rūva, ...	189, 190, 191
Raṅganātha, a <i>divinity</i> , ...	85, 86, 88, 96	rr, form of, ...	266 n. 1
Raṅganātha-svāmin, a <i>divinity</i> , ...	83	ry, form of, ...	176
Raṅgaya, m., ...	81		
rāshṭra, ...	150, 361-3		
Rāshtrakūta, dy., ...	123, 124, 127, 127 n. 7, 128 n. 6, 147, 296, 326,	S	
	329, 333	s, form of, ...	144, 157, 164
rāshtrapati, an <i>official</i> , ...	126, 129	s, form of, ...	121, 121 n. 5, 144
Ratikara, m., ...	206	s and s̄, ...	98, 177, 192, 210, 295, 325
Ratna-dhenu, a <i>malādāna</i> , ...	172	s, s̄, ś confused, ...	169, 311, 341
Randakundl, a <i>sīmā</i> , ...	231	sa, symbol of wind, ...	101, 105
Ravala, m., ...	76, 81, 82	Sabbhāpati Svayambhū, a <i>port</i> , ...	175, 216, 231, 315, 322, 323, 352-3
Rāvana, ...	209	Sachchidanānandaghana, a <i>Kāñcī āchārya</i> , ...	234
Ravisānti, m., ...	114, 118, 120	Sachchidghana, a <i>Kāñcī āchārya</i> , ...	234
Ravivarman, a <i>Kadamba k.</i> , ...	166	Sachchidvilāsa, a <i>Kāñcī āchārya</i> , ...	234
Rāyasa Venkatādri, feud., ...	215, 216	Sachchitankha, a <i>Kāñcī āchārya</i> , ...	234
Reddī, dy., ...	70, 70 n. 8	Sadāsiva, ...	157
rēkhā-daṇḍa, a <i>measure</i> , ...	99, 104, 109	Sadāsiva, a <i>Vijayanagara k.</i> , ...	230, 233, 234, 342, 344-6, 352-3
relics of Buddha, ...	284	Sadāsiva-Brahmendra, a <i>Kāñcī āchārya</i> , ...	234
Rōva, m., ...	146, 148, 151	Sadāsiva-Rāja, m., ...	210, 211
Rōvāditya, m., ...	146	Sadāsiva-Sarasvatī, a <i>Kāñcī āchārya</i> , ...	169, 173, 175, 232, 233, 234, 240, 357
Rōvagapa, m., ...	146, 151, 152	sādharma, ...	177, 186
ri and ra, ...	102		
ri written ri, ...	68		
ri for ri, ...	122, 146, 192		
ri and ru confused, ...	98		

The figures refer to pages; *a.* after a figure to footnotes, and *add.* to Additions and Corrections. The following other abbreviations are used: *ch.* = chief; *co.* = country; *di.* = district, division; *de.* = the same, ditto; *dy.* = dynasty; *E.* = Eastern; *feud.* = feudatory; *k.* = king; *m.* = man; *mf.* = mountain; *ri.* = river; *s. a.* = see also; *swr.* = surname; *te.* = temple; *vi.* = village, town; *W.* = Western; *wo.* = woman.

	PAGE		PAGE
Sādhanā, a family, ...	296, 303, 310	Śaṅkara, m., ...	205, 314, 320
Sādhu-Bhaṭṭa, m., ...	88	Śaṅkara, m., ...	207
Sāditya-Liṅga-Bhaṭṭa, m., ...	314, 319	Śaṅkara-Śiva, ...	159, 162, 280
Sadyōjāta, an aspect of Śiva, ...	274, 274 n. 2	Śaṅkara-Āchārya, ...	233-4, 235, 357-9
saffron, ...	182	Śaṅkarāchārya-maṭha at Kāñchī, ...	169, 170, 232, 233
Sagula-avāmin-Dikshita, m., ...	148, 150, 151, 152	Śaṅkara-nanda, a Kāñchī āchārya, ...	234
Sahāraṇa, m., ...	204, 206, 207, 209	Śaṅkara-yōgin, a Kāñchī āchārya, ...	233, 235
Sāhasāṅka, k., ...	157, 159, 162	Śaṅkarārya, a Kāñchī āchārya, ...	235
Sahasra-nāma-bhāṣya, a book, ...	86	Śaṅkarēndra, a Kāñchī āchārya, ...	234
Sāhi, dy., ...	293	saṅk-rānti, ...	127
Sāhu, m., ...	202	Sammattī, a family, ...	70
Sal-Śaka, ...	291	Sammata. See Sammattī, ...	70 n. 1
Saigotta, Śivimāra, a Gaṅga k., ...	333	Saṁsaptaka, ...	160, 163
Śaiva, a sect, ...	85	Saṁtāna-dra, ...	344
Sal-wang, a race, ...	289, 290	samuddanda, ...	281
Saiyid Mustapha, a Goleonda noble, ...	355	Samandra-gupta, a Gupta k., ...	332, 367-371
Śaka names, ...	134	saṁvartarō, ...	184, 184 n. 15
Śaka, a race, ...	290, 291, 292, 293, 294	Saṁvat, era, ...	110
Sāketa, vi., ...	142	saṁvatāraṇa, ...	133
śākhā. See veda, śākhā, sūtra.		saṁvatāraye, ...	133
Śākhi, dy., ...	293	Sandhi neglected, ...	69, 110, 147, 164
Śakti, a gōtra, ...	327, 330	sāndhivigrahika, ...	158, 162, 327
Śakti, a pravara, ...	325, 330	sāndhivigrahika. See Mahāsāndhivigrahika, ...	160
Salakhū, m., ...	203	Sāndi-Bhaṭṭa, m., ...	315, 321
Śālanākāyana, a gōtra, ...	82	Sāṇḍilya, a gōtra, ...	81, 202-4, 206-9, 314-5
Śālanākāyana, dy., ...	141	Saṅgā-Bhaṭṭa, m., ...	314, 318
Salhaṇa, m., ...	207	Sangoli plates of Harivarman, ...	163ff.
Sālū, m., ...	207	Sanjan plates of Rudravarman, ...	144ff.
Śālivāhana, prince, ...	157	Saṅkama, a Kalachurya k., ...	268
Śālivāhana, era, ...	231, 354, 358-9	śānkha, ...	273 n. 1, 325
sa-lōhida, ...	295	Śāṅkhaṇḍī, m., ...	207
sālōkya, ...	280	Saṅkhavāyī, vi., ...	198, 199, 201
Śalākika, a family, ...	147	Sāṅkritya, a gōtra, ...	202-4, 206-8
saṁ representing 100, ...	184 n. 16	Sāṅkū, m., ...	206
Sāmaga, ...	315	santa, a measure, ...	296, 309
Sāmāṅga grant of Dantidurga, ...	121 n. 5, 122, 123	Sāntaliga, di., ...	289
Sāmanta-sēna, a Sēna k., ...	157, 159, 162	Śānti texta, ...	127
Sāma-veda, ...	216, 314	Śāntinātha, a Jain Tīrthamkara, ...	197
Sāma-vedin, ...	313	Śāntivarman, a Kadamba k., ...	166
samaya, ...	18, 189 n. 1	Sapātakasīrisā, vi., ...	198, 199
Śāmba, m., ...	155	Sapta mātarah, ...	149
Śāmbapura-upādhyāya, m., ...	361-3	Sapt-āmbhōdhi, a mahādāna, ...	172
saṁbatāraṇa, ...	133	Saptanātha, m., ...	76, 82
Śambhu-Śiva, ...	216, 280, 240, 270, 273-4, 297, 303	Sapta-sūtatī, ...	106 n. 7
Saṁgama, a Vijayanagara k., ...	102, 106, 107	Śarabhoji, a Tanjore k., ...	357
Saṁgama, a shrine, ...	171, 318, 323	Śārada-pīṭha, a Kāñchī religious post, ...	354, 356-9

The figures refer to pages; n. after a figure to footnotes, and add. to Additions and Corrections. The following other abbreviations are used:—*cl.* = chief; *co.* = country; *di.* = district, division; *do.* = the same, ditto; *dy.* = dynasty; *E.* = Eastern; *feud.* = feudatory; *k.* = king; *m.* = man; *mt.* = mountain; *ri.* = river; *s. a.* = see also; *sur.* = surname; *te.* = temple; *vi.* = village, town; *W.* = Western; *wo.* = woman.

	PAGE		PAGE
Sarayū, <i>ri.</i>	193, 194, 196	Sāvana year,	140
Sarisoḍa, <i>ri.</i>	193, 195, 196	Savara, a people,	163
Sārkara, a <i>gōtra</i> ,	202, 204	Śāvaranandīśarman, <i>m.</i> ,	360
Sārkarakha, a <i>gōtra</i> ,	204, 207-9	Sāvarga, a <i>gōtra</i> ,	204, 206-7, 209
Sarvā-Bhaṭṭa, <i>m.</i> ,	212	Sāvilēva = Sāgidēva, <i>m.</i> ,	281, 284
Sarvādhikṛta, an official title,	362-3	Sāviti, <i>wo.</i> ,	281, 284
Sarvajña, a <i>Kāuchī āchārya</i> ,	234	seal,	147, 157, 168, 192, 324, 331, 341, 360
sarva-mānya,	73, 211, 313, 317, 346, 348	Sēdīva-Kaṣētra, an estate,	148, 150, 151, 152
Sarvanandin, a Jain <i>Muni</i> ,	334	Sēdvill, <i>ri.</i> ,	195, 196, 201
Śarvavarman, a <i>Maukhari k.</i> ,	111, 113, 114	Sēna, <i>dy.</i> ,	157
Śasabindu, a legendary <i>k.</i> ,	102, 107, 107 n. 3	sēnāpati. See Mahāsēnāpati,	160
śāsana, characteristics of a,	99, 100, 105	Sēnchalavana, <i>ri.</i> ,	195, 196, 201
śāsana,	158, 159, 161	Sēsha-Bhaṭṭa, <i>m.</i> ,	212
Śaśidēva, <i>m.</i> ,	325	Sēsha-bhuj-ākṛiti-rakhaṇa-śaṇḍa, <i>sur. of</i> <i>Kṛishṇa-dēva-Rāya</i> ,	173
śāstra,	120, 336	Sēshādri, a mountain,	344
Śāta, <i>m.</i> ,	202	Sē(rō)sha-kṛita-pratipārthiva-śaṇḍa, <i>sur. of</i> <i>Kṛishṇa-dēva-Rāya</i> ,	173
Śātāhani-ṛattha, <i>di.</i> ,	154	Sēsha Mānavanta, <i>m.</i> ,	213
Śātānandaka,	301 n. 4	setti,	190, 191
Śātavāhana, <i>dy.</i> ,	153, 154, 155	Sēta = Rāmasēta,	125, 128, 171, 173, 344
Śātavahani-hāra, <i>di.</i> ,	154, 155	sēta-bandha,	327, 330
Śātō, <i>m.</i> ,	263	śā, <i>f</i> and <i>s</i> ,	169, 311
Śāthū, <i>wa.</i> ,	202	Shakardarra inscription,	132, 136
śūtra,	186	śāk, form of,	130
śaṭṭugāyana,	266, 273	śātr, form of,	122
Satya, <i>m.</i> ,	182, 188	Siddha,	298, 303
Satyabōdha, a <i>Kāuchī āchārya</i> ,	234	Siddhāntam, <i>vi.</i> ,	361
Satyarāja, a <i>Paramāra prince</i> ,	296, 299, 305	Siddhapa, <i>m.</i> ,	182, 183
Satyāśraya-kula, the <i>Chalukya dy.</i> ,	271, 275, 279, 281	siddha-sādhyā,	312, 346
Satyāśraya Pulakāśin II. <i>Prābhivallabha</i> ,	144	Siddhavata, a place,	109, 102
	149, 151, 152	Siddhavata-nātha, a divinity,	108
Satyavākya Kōṅgaṇivarman Rājamalla, a <i>Gaṇga k.</i> ,	339	Siddhi Timmā-Bhaṭṭa, <i>m.</i> ,	342
Satyavākya Kōṅgaṇivarman Permānsi, a <i>Gaṇga k.</i> ,	364-6	Siddhi Timmārya, <i>m.</i> ,	343
Satyavrata = Kāśchī,	358-9	Siddhi Tirumālārya, <i>m.</i> ,	342
saukhāsikā,	93	Siharachhita, <i>m.</i> ,	181
seal,	272, 277	Sihila, <i>m.</i> ,	181
Śaulika, a people,	112	Sija, <i>m.</i> ,	209
śaulika,	327	Sibē, <i>m.</i> ,	207
Saumitri = Lakshmana,	326, 329	Silpin,	325
Saunya,	101, 106	Silū, <i>m.</i> ,	209
Śaunaka, a <i>gōtra</i> ,	202	simā,	175
Saurāshtra coins,	368	Sina, <i>m.</i> ,	203
Śauri = Vishnu,	71, 78	śim-ālī,	161
Sauśravasa, a <i>gōtra</i> ,	203-6, 209	sinaya,	147, 150
sauvastika,	368	Sinha-Sūri, a Jain author,	334

The figures refer to pages; *n.* after a figure to footnotes, and *add.* to Additions and Corrections. The following other abbreviations are used:—*ch.* = chief; *co.* = country; *di.* = district, division; *do.* = the same, ditto; *dy.* = dynasty; *E.* = Eastern; *feud.* = feudatory; *k.* = king; *m.* = man; *mt.* = mountain; *ri.* = river; *s. a.* = see also; *sur.* = surname; *te.* = temple; *vi.* = village, town; *W.* = Western; *wo.* = woman.

PAGE	PAGE
Sihavarman, <i>sur. of the Gaṅga k. Mā-</i> <i>dhava III.</i> , ... 333	Śiva-Yōgin, a <i>Kāśchī āchārya</i> 234
Sihavarman, a <i>Pallava k.</i> , ... 332, 333, 334, 335, 336, 337	Śivimāra-Saigottā, a <i>Gaṅga k.</i> , ... 333
Sihavarman, a <i>Puekkaranā k.</i> , ... 367, 370	Skanda-nadi, <i>ri.</i> , ... 313, 317, 323
Sinda, <i>dy.</i> , ... 266, 268-72, 275-77, 280-83	Skandagupta, a <i>Gupta k.</i> , ... 369
Sinda, <i>patriarch of Sinda dy.</i> , ... 266, 269, 270, 271, 283	Skandanāga, <i>m.</i> , ... 155
Sindanūr, <i>vi.</i> , ... 270	Skandaśarmab, <i>m.</i> , ... 167
Sindarāja, a <i>Sinda feud.</i> , ... 268	Skandavarman, a <i>Pallava k.</i> , ... 332, 333, 334, 335, 336
Sindarasa, a <i>Sinda ch.</i> , ... 269	Skārah Dhēri inscription, ... 181, 186
Sindavādī, <i>co.</i> , ... 267, 270	Smara-Kāma, ... 280, 299
Sindhū, <i>ri.</i> , ... 260, 270	smṛiti, ... 101, 106, 198-99
Sindhurāja, <i>k. of Dhārā.</i> , ... 157	Sōdala, <i>m.</i> , ... 206
Sindhurāja, a <i>Paramāra prince.</i> , ... 296, 297, 308	Sōdasa, a <i>kshatrapa.</i> , ... 141
Śiṅgaṇa-Āchārya, <i>m.</i> , ... 70, 74, 75, 81	Sōdasa, inscription of, ... 139
Śiṅgaṇa-Bhaṭṭa, <i>m.</i> , ... 218	Soked (Sākēta), <i>vi.</i> , ... 142
Śiṅgaṇappādī, <i>vi.</i> , ... 313, 317, 321	Sōkhē, <i>m.</i> , ... 205
Śiṅgaṇārya, <i>m.</i> , ... 69, 73-4, 80-1	Solar race, ... 70 n. 8, 79 n. 4, 102, 107, 111, 342, 346
Śiṅgarasa II., a <i>Sinda ch.</i> , ... 268	Sōma, ... 70
Śiṅgari Dikshita, <i>m.</i> , ... 342	Sōma, <i>m.</i> , ... 205
Śiṅgari Yajvan, <i>m.</i> , ... 342	Sōma, a <i>Sinda prince.</i> , ... 264, 272
Śiṅgari Sudhī, <i>m.</i> , ... 214	Sōma, <i>k.</i> , ... 272, 276
Śiṅgārya, <i>m.</i> , ... 75-6, 81, 82	Sōma-Bhaṭṭa, <i>m.</i> , ... 213, 342
Śiṅgaṭṭā, <i>ri.</i> , ... 158, 159, 161	Sōmadatta, <i>m.</i> , ... 202, 206
Śiṅgayā, a <i>Telinga prince.</i> , ... 83, 84, 92, 96	Sōmana-halli, <i>vi.</i> , ... 231
Siri, <i>m.</i> , ... 206	Sōmanātha-Bhaṭṭa, <i>m.</i> , ... 212, 314, 319
Śirikuppa Timmā-Bhaṭṭa, <i>m.</i> , ... 342	Sōmapa, <i>m.</i> , ... 75, 81
Śirivara, <i>vi.</i> , ... 345, 350	Sōmasēkharānanda, a <i>Kāśchī āchārya.</i> , ... 235
Siriya-dēvi I., a <i>Sinda queen.</i> , ... 268	Sōmaṭa, <i>m.</i> , ... 204
Siriya-dēvi II., a <i>Sinda queen.</i> , ... 268	Sōmēśvara, <i>m.</i> , ... 205, 208
Σποπτελαμαιοί, ... 154	Sōmēśvara IV., Tribhuvanamalla, a <i>W. Chal-</i> <i>kya k.</i> , ... 265, 266, 271, 275, 278, 279, 281-2
Śiruguppa Timmā-Bhaṭṭa, <i>m.</i> , ... 343	Sōpa, <i>ri.</i> , ... 344
Śirukuppa Timmā-Bhaṭṭa, <i>m.</i> , ... 342	Sōpāchala, a <i>śrine.</i> , ... 172
Śittileppākam, <i>vi.</i> , ... 232, 235	Sōpadahā, <i>vi.</i> , ... 195, 196, 202
Śiva, ... 266, 269, 270, 280	Sōpādri, a <i>śrine.</i> , ... 316, 323
Śiva, eight forms of, ... 105 n. 10	Sōpaka, <i>vi.</i> , ... 195, 196, 201
Śiva temple, merit of constructing, ... 101, 106	Sōpāsāla, a <i>śrine.</i> , ... 171
Śivachētas, title of <i>Kāśchī āchāryas.</i> , ... 233	sovage, ... 189
Śivācha, <i>m.</i> , ... 202	Sōvala-dēvi, a <i>Sinda queen.</i> , ... 266, 271, 276, 279, 280, 283
Śivamāra, a <i>Gaṅga k.</i> , ... 338	space, symbolized by <i>ta.</i> , ... 101, 105
Śiva-nāna-riddhiyār, a <i>book.</i> , ... 274 n. 2	Spargaphotos, <i>m.</i> , ... 133 n. 7, 134 n. 1
Śivānanda, <i>m.</i> , ... 205	Śravaṇa, a <i>nakṣatra.</i> , ... 69, 73, 80
Śivaśarman, <i>m.</i> , ... 166, 167, 360, 362-3	Śrāvishṭha, a <i>gōtra.</i> , ... 165, 167
Śivastambha, <i>m.</i> , ... 193, 195, 196	
Śiva-Svayambhū, a <i>divinity.</i> , ... 267, 273, 274, 275	

The figures refer to pages; n. after a figure to footnotes, and add. to Additions and Corrections. The following other abbreviations are used: —*ch.* = chief; *co.* = country; *di.* = district, division; *do.* = the same, ditto; *dy.* = dynasty; *E.* = Eastern; *feud.* = feudatory; *k.* = king; *m.* = man; *mt.* = mountain; *ri.* = river; *s. a.* = see also; *sur.* = surname; *te.* = temple; *vi.* = village, town; *W.* = Western; *wo.* = woman.

	PAGE		PAGE
Śrīhāṣya, a book, ...	85, 87-8	Śrīvataschihna-gura, sur. of 'Parāśara-Bhaṭṭa	
Śrī-Chhandōga-charaṇa t ipāthīn, ...	208	VII., ...	85
Śrī-Dādiga, m., ...	208	Śrīvataschihna-Miśra, m., ...	93, 96
Śrīdhara, m., ...	202, 204, 206-9, 296, 303, 310	Śrī-Venkṭeśa, signature of Vijayanagara dy., ...	168
Śrīdhara-Bhaṭṭa, m., ...	213	Śrī-Vidagdha, signature of Mahendra-pāla	
Śrīgiri-Śrīdallam, a shrine, ...	101, 106	II., ...	178, 184, 186, 187
Śrī-gaṇa-ratna-kūṭa, a book, ...	86	Śrī-Vidyānidhi-Bhaṭṭa, m., ...	315, 321
Śrī-Haraha, a k., ...	125, 129	Śrī-Vijaya, sur. of the Gaṅga & Kṛṣṇavarman, ...	234
Śrī-Harsha, a Mālava k., ...	206, 299, 305	Śrī-Virūpāksha, m., ...	314, 315, 319, 323
Śrīkaṇṭha-Śiva, ...	159, 162	Śrī-Virūpāksha-Bhaṭṭa, m., ...	315, 321
Śrīkaṇṭhēśvara, m., ...	314, 319	Śrī-Virūpāksha, a Vijayanagara signature, 174, 231, 240, 311, 315, 322-353	
Śrīkara, m., ...	209	Śrīvirūpākshasthāna, a shrine, ...	171
Śrīkaraya, ...	231	Śrūta-prakāśikā, a book, ...	87
Śrīkumbha, m., ...	203	Śrūtaprakāśik-āchārya, sur., ...	87
Śrī-Koṇḍa Rāma-Bhaṭṭa, m., ...	343	Śruti, ...	101, 106, 119
Śrīṅga of a tank, ...	108, 108	Śrīkṛṣṇa Śilāditya, a Chālukya k., ...	148, 149
Śrīpāla, m., ...	337	st, form of, ...	285
Śrīparvata, a shrine, ...	100, 102, 108	stands, cups, ...	156
Śrī-prithivī-vallabha, a Chālukya title, ...	126, 148, 149, 151, 179, 365	sth, form of, ...	285
Śrī-pura, vi., ...	267, 278, 277	stūpa, ...	284, 287
Śrīpurusha, a Gaṅga k., ...	238	su, form of, ...	121
Śrīrāma, m., ...	74, 81	Śubhākara, m., ...	205
Śrī-Rāmēśvara, m., ...	213	Śubhāṅkara, m., ...	204, 207, 208
Śrī-Rāmēśvara-Bhaṭṭa, m., ...	213	Śubhasarman, m., ...	209
Śrīraṅgam, vi., ...	85, 88, 89, 92, 93, 96, 171, 175, 240	Śubhataṅga, sur. of the Rāshtrakūṭa k., Kṛṣṇa-Rāja I., ...	123, 125, 128
Śrīraṅgam Plates of Mummaḍi-Nāyaka, ...	83	Sobrahmanya, m., ...	314, 320
Śrīraṅganātha-Bhaṭṭa, m., ...	88, 96	Sudarāna-Bhaṭṭa, m., ...	87, 88
Śrīraṅganātha-svāmin, a divinity, ...	83, 94	Śuḍasa, k., ...	139
Śrīraṅgarāja-Bhaṭṭa, m., ...	88, 89 n. 2	Śuddhānanda, Kāṇchi āchārya, ...	234
Śrīraṅga-rāja-stava, a poem, ...	86	Sūdhā, m., ...	204
Śrīraṅga-vardhana, sur. of Mummaḍi-Nāyaka, ...	84	Sudhāhara, ...	318
Śrī-Rig-vāla-charaṇa chaturvēdin, ...	202	Sudhī, sur., ...	212-214
Śrīśaila, ...	101, 106, 171, 172	Sue Vihar, a place, ...	133
Śrī-Saṅkara, a Kāṇchi āchārya, ...	234	Sue Vihar inscription, ...	131, 136
Śrīsarman, feud., ...	180, 181, 185	Sugata-Buddha, ...	330
Śrī-stava, a poem, ...	85	Sūgā, et., ...	267, 268, 273, 278
Śrī-Triyambaka, a Vijayanagara dy. signature, 68, 78, 83		Śūlika, a people, ...	112, 117, 120
Śrīvaikunṭha-stava, a poem, ...	85	Samati-Sādhara, a poet, ...	296, 303, 310
Śrīvaishyava, a sect, ...	85, 86 n. 1	Samāru, ...	171
Śrīvata, a gōtra, ...	81-2, 212, 214, 315	Samitrā, ...	171, 240
		sun, ...	168, 341
		sun, eclipse of the. See eclipses, solar.	
		sun, symbolized by fa, ...	100, 105
		Śanāśra, ...	194

The figures refer to pages; n. after a figure to footnotes, and add. to Additions and Corrections. The following other abbreviations are used: —*ch.* = chief; *co.* = country; *di.* = district, division; *do.* = the same, ditto; *dy.* = dynasty; *E.* = Eastern; *feud.* = feudatory; *k.* = king; *m.* = man; *mt.* = mountain; *ri.* = river; *s. a.* = see also; *sur.* = surname; *te.* = temple; *vi.* = village, town; *W.* = Western; *w.* = woman.

	PAGE		PAGE
<i>Sundarabāhu-stava, a poem,</i>	85	Tachhasilā, <i>vi.</i> = Takhasilā,	295
Sundarī-Dēvī, <i>a Pratihāra Queen,</i>	178, 183	Tadagūla-Mādhava = Mādhava III., <i>a</i>	
Sūpā, <i>m.,</i>	209	<i>Gaṅga k.,</i>	332, 337
Sūpata, <i>m.,</i>	205, 206	Tādipāka, <i>a principality,</i>	84, 88, 89, 92, 96
Sūri-Bhaṭṭa, <i>m.,</i>	315, 320	Taila III., <i>a W. Chalukya k.,</i>	268
Sarakōpāgaḍḍiā, <i>a place,</i>	159, 161	Taittiriya śākhā,	151, 152
Saratrāga,	170 n. 2	Takanli, <i>vi.,</i>	198, 199, 201
Saratīha = Sarat,	293	Takaura, <i>vi.,</i>	198, 199, 201
Sarēndro, <i>a Kāśhī āchārya,</i>	234	Takht-i-Bāhl inscription,	131, 133, 135
Sarēśvara, <i>a disciple of Śamkara-āchārya,</i>	234	takkil,	266, 272
Sāri, <i>sur.,</i>	212	Takhasilā, <i>vi.,</i>	284, 289, 291, 293, 295
Sāri-Bhaṭṭa, <i>m.,</i>	343	Talabhāma, <i>vi.,</i>	201
Sarīṭṭilūru, <i>vi.,</i>	232, 235	Talahuti, <i>vi.,</i>	195, 196, 201
Sāri-varya, <i>m.,</i>	213	talāka,	154
Sārya, <i>m.,</i>	76, 82	Tālakuṭe, <i>vi.,</i>	71, 82
Sārya-grahaṇa,	272	Talavargika-Harishada, <i>m.,</i>	178, 183
Sāryaprakāśa Rao = Mādanna,	355	talayidokāṇḍu,	359 & n. 7
Sāryārya, <i>m.,</i>	75, 81	Tālikōṭa, battle of,	211
Sāryavarman, <i>a Maukhari k.,</i>	110, 111, 117, 120	Tāmaravāṭaka, <i>vi.,</i>	88, 89, 94
Sushamā,	92	tāmbra,	169, 174
Sasthitavarman, <i>a Maukhari k.,</i>	113 n. 6	tamcha-rājya = Tañjai (Tanjore),	171, 217, 237
Sasuniā hill inscription,	367, 370	tāmraśāna,	352
Sūta, <i>m.,</i>	206	tāmraśāsanikṛitya,	161
sūtra. See veda, śākhā, sūtra.		Tapi-deagam, <i>a book,</i>	88
anttee, rite,	267, 267 n. 2	Tānisha, <i>a Golconda k.,</i>	352
Sva-kul-āmbhōja-bhāskara, <i>sur. of Dantidurga,</i>	127	Tapi-slōki, <i>a poem,</i>	86
Svalpa-dakṣiṇā-vīthi, <i>vi.,</i>	158, 161	taṅka,	134
Svāmīdēva = Sāgīdēva, <i>m.,</i>	281, 284	tank-building,	97, 101, 106, 108
svāmin, <i>a title,</i>	235, 293	Taṇva, <i>a locality,</i>	287, 295
Svapata, <i>m.,</i>	204	Tārā's mountain,	281, 284
Svargadvāra, <i>a firtha,</i>	193, 194, 196	Tarika, <i>a people,</i>	327
Svarṇa-giri, <i>a maḥādāna,</i>	302	Tārīkh-i-Yamīni, <i>a book,</i>	179
Svarṇa-kahmā, <i>a maḥādāna,</i>	172	tarka,	325, 327
Svarṇa-māra, <i>a maḥādāna,</i>	172	taṭāka-mātrikā,	98, 102, 108, 108 n. 1
svargapāli, <i>vi.,</i>	187	Taṭāyikā, <i>a place,</i>	148, 150, 152
svastika,	308	Tatparusha, <i>aspect of Śiva,</i>	274 n. 2
Svayambhū, <i>a divinity,</i>	272, 276, 277, 279, 280, 283	tavaṇi,	296
Śvēta-varāha, <i>a kalpa,</i>	103, 106	tavaṇim,	310 n. 2
Swāt bas-relief of Siṃhamitra,	132	Taxila, <i>vi.</i> = Takhasilā,	284, 289, 293
Swāt Buddha statuette inscription,	132	Taxila inscription of Patika	131, 135, 136
		Taxila inscription of a Khushaṇa k.,	136
		Taxila inscription of the year 136,	294
		Taxila vase inscription,	131
		te, form of,	121
		Tēdāva, <i>vi.,</i>	165, 167
		Tekkekal, <i>vi.,</i>	267, 268, 273, 277

T

t, form of,	68, 157, 164, 232
† final,	122, 157
ts, symbol of space,	100, 101, 105

The figures refer to pages; n. after a figure to footnotes, and add. to Additions and Corrections. The following other abbreviations are used: —*ch.* = chief; *co.* = country; *di.* = district, division; *do.* = the same, ditto; *dy.* = dynasty; *E.* = Eastern; *fund.* = fundatory; *k.* = king; *m.* = man; *mt.* = mountain; *ri.* = river; *s. a.* = see also; *sur.* = surname; *ts.* = temple; *vi.* = village, town; *W.* = Western; *wo.* = woman.

	PAGE		PAGE
Teliāga, co., ...	85, 95	Tirukkajukkugram, vi., ...	169, 175
Telugu, a people, ...	266, 271, 275, 276	Tirumala, m., ...	211, 313, 314, 315, 318, 320, 321
Telaṅga, a people, ...	271	Tirumaladāri, a road, ...	71
tā, form of, ...	68	Tirumālai, a book, ...	88
Thīrū, m., ...	204	Tirumalārya, m., ...	342-3
tāṭā for tāk, ...	97	Tirumale, vi., ...	83
Tien-chu, co., ...	292	Tirupati, a shrine, ...	240
tiger, device, ...	283	Tiravarangattamudapār, m., ...	85
Tihuna-Svāmin, m., ...	203	Tiruvāymoṭi, a book, ...	86 n. 1
Tikama, m., ...	203, 209	Tiruveṅkata-Bhaṭṭa, m., ...	88
Tikapa, m., ...	76, 81, 82	Tiṭā, m., ...	205
Tiliāga, ...	90	Titbu, m., ...	204
Timira, a tree, ...	362, 363 & n. 2	Tiṭi, m., ...	206
Timma. See Timma-amātya.		Toṇḍarāḍipodiy-ālvār, a Vaiṣṇava saint, ...	88
Timma, minister of the Vijayanagara k.		Toṇḍayya, m., ...	365-6, 366 n. 4
Achyuta, ...	216	tōṇira, ...	295, 298
Timma, a Vijayanagara k., ...	171, 174, 232, 323	Toshaya-rūpa-jit-āsama-kāṇḍa, a Vijayanagara	
Timma-amātya, feud., ...	216	title, ...	344
Timma-Bhaṭṭa, m., ...	212, 314, 315, 318, 320, 321,	Trailōkya-mōhana-dēva, a divinity, ...	177, 182, 187
	342-3	tri-bhūgya, ...	313
Timma-Dikshita, m., ...	314, 320	Tribhavanamalla, sur. of the W. Chalukya k.	
Timmāmbā, a Vijayanagara princess, ...	230, 344, 353	Sōmēśvara IV., ...	266
Timmaṇa, m., ...	75, 81	Tribhavanamalla-Vīra-Sōmēśvara, a Chalukya	
Timmaṇa-Bhaṭṭa, m., ...	212, 213	k., ...	271, 275, 278, 279, 281, 282
Timmaṇa Sudhi, m., ...	214	Triḷamata, k., ...	139
Timmaṇa-amātya, m., ...	215	Triḷochana, m., ...	209
Timmaṇpuram Timma-Bhaṭṭa, m., ...	343	Triḷochana-pāla, a Pratihāra k., ...	179, 179 n. 4
Timmaṇpuram Tirumalārya, m., ...	343	Triśāṅku, ...	193, 197
Timmarāja, feud. of Sādātiva-Rāya, ...	216	Trivikrama-Vishṇu, ...	272, 276, 301, 307
Timmarasa, m., ...	215	Trivikramanātha, a purōhita, ...	178
Timmarāya, m., ...	341-2, 346	Tryambaka-Siva, ...	73, 80
Timmaṇv-Adhvarin, m., ...	213	tā in Kharoṣṭhī inscriptions, ...	133
Timmaṇvājalu, m., ...	314, 320	tāk written tātā, ...	97
Timmaya, m., ...	74, 75, 76, 81, 82, 314, 320	Tulāpurnahā, a maṭṭāḍana, ...	172, 197
Timmaya-amātya, m., ...	215	Tulava, dy., ...	171, 217, 232
Tippā-Bhaṭṭa, m., ...	314, 320	tundalita, ...	358
Tippāji, a Vijayanagara queen, ...	171, 230, 232,	Tuṅga, a Rāṣṭrakūṭa k., ...	326, 329
	240, 323	Tuṅgā, vi., ...	344
Tippaṇa-Bhaṭṭa, m., ...	213, 214	Tuṅgabhadra, vi., ...	102, 107, 173, 175, 231,
Tippaṇārya, m., ...	76, 82		240, 273, 278, 312, 317, 323, 341, 345, 353
Tippāryya, m., ...	76	Tappad-Kurhaṭṭi, vi., ...	364
Tippaya, m., ...	74, 81	Tappad-Kurhaṭṭi inscription of the reign of	
Tippayya, m., ...	314, 319	Akāḷavaraha Kriṣṇa III., ...	364
Tirilinga-Tirillōga, co., ...	360-3	Tarashka, a people, ...	293
Tirikkalā-Kunnarēṇḍāru, vi., ...	169, 173	tarashkakaṇḍa, ...	196, 196, 199, 200
tīrtha, ...	183	Tarvasa, ...	240, 323

The figures refer to pages; n. after a figure to footnotes, and add. to Additions and Corrections. The following other abbreviations are used: —ch. = chief; co. = country; di. = district, division; do. = the same, ditto; dy. = dynasty; E. = Eastern; feud. = feudatory; k. = king; m. = man; mt. = mountain; vi. = river; s. a. = see also; sur. = surname; to. = temple; vi. = village, town; W. = Western; w. = woman.

	PAGE		PAGE
te, form of, ...	235	Upendra = Vishnu, ...	325, 329
Tvaṣṭri, <i>sur. of Viroṇa</i> , ...	235	Uppaṇa-Bhaṭṭa, m., ...	314, 320
Tvaṣṭrisarman, m., ...	166, 167	Uppuṅgāli, vi., ...	88, 94, 96
U		Uppavalla, vi., ...	267, 273, 277
u, form of, ...	121	Uraśaka, m., ...	287, 295
u, medial, form of, ...	121	Uru-kavi, <i>sur. of the poet Sabhāpati</i> , ...	174
ū confused, ...	146, 232, 311	Urūmiya, ...	134
ū, form of, ...	157	utkalāla, ...	301
uchchulumpichakāra, ...	295, 301	utāha, ...	189, 191
Udabhaṇḍa, vi., ...	291	utta, ...	82 s. 1
Udaya, a mountain, ...	119, 171	Uttara-Kōśala, ...	194, 196
Udayagiri, a place, ...	100, 102, 107, 107 n. 4, 108, 368	Uttarāpatha, ...	149, 151
Udayambākam, vi., ...	168, 169, 173, 175	Uttara-Rādha, a maṇḍala, ...	161
Udayambākam grant of Kṛṣṇa-dāva-Rāya, ...	168ff.	utthapanaka, ...	296, 302
udbhayād, ...	266	Utukūra Tīmā-Bhaṭṭa, m., ...	342
Uddāṇḍa-Bhaṭṭa, m., ...	58	V	
uddēsa, ...	327	e, form of, ...	121, 144, 157, 232, 265-6, 325
Uddhavāli(ka), a place, ...	148, 150, 152	e and ē confused, ...	122, 177, 192, 325
Ujēdī, vi., ...	195, 196, 201	Vadama, a sect, ...	85
Udharaṇa, m., ...	203	Vaddamāni Liṅga-Bhaṭṭa, m., ...	242
udūdhā, ...	290 n. 11	Vaddamāni Liṅga-Bhaṭṭa, m., ...	243
Udumvara-manti, vi., ...	126, 127, 129	Vadthalā, vi., ...	195, 196, 202
Udyāna, co., ...	291	Vādhalā, m., ...	206
Ujjain, vi. See Ujjayini, ...	177	Vāgviṇaya-Bhaṭṭa, m., ...	86
Ujjayini, vi., ...	177, 180, 185, 201, 293	Vaha, ...	177, 187
ukkēra, ...	206	Vāhada, m., ...	204, 205
ujvār, ...	189, 191	Vāhika, a people, ...	367
ujvor, ...	189, 191	Vāhmaṇa, m., ...	209
Umā, ...	281, 284	Vahudhara, m., ...	202
Umraṇvati, vi., ...	129	Vāhula, m., ...	207
Umvara, vi., ...	126, 129	Vakṛyanātha, m., ...	314, 320
Umvara-manti, vi., ...	126, 129	Vaijayanti, vi., ...	165, 166, 167
Undharaumhā, vi., ...	195, 196, 202	vaikalpya (for vaikalya ?)	301
Undiyāka, a field, ...	182, 187	Vaikuntha, ...	180, 183
unmāna, ...	158, 161	Vaikunthasārman, m., ...	166, 167
unmantra, ...	281	Vairisikha, a Paramāra k., ...	296, 298, 304
unmuktāphalam, ...	279	Vaiśeṣika philosophy, ...	273
upachāra (shōḍaṣa), ...	341	Vaiśpava, a sect, ...	85
upadhmaniya, form of, ...	360	vaiśvadeva, a rite, ...	152, 157
upadhmaniya, use of, ...	164	Vaivasvata, ...	103, 108, 111, 115, 119
Upaguptā, a Maukhari queen, ...	112	Vājasanīyī-Sākhā, ...	314, 325
Upalācha, vi., ...	195, 196, 202	Vajreshka (?), a Kushāpa k., ...	130, 135, 143
uparika, ...	327	Vajreshka (?), a Kushāpa k., ...	143
Upamanyu, a gōtra, ...	201-4, 206-9		

The figures refer to pages; n. after a figure to footnotes, and add. to Additions and Corrections. The following other abbreviations are used: —cā. = chief; co. = country; di. = district, division; do. = the same, ditto; dy. = dynasty; E. = Eastern; feud. = feudatory; k. = king; m. = man; mt. = mountain; ri. = river; s. a. = see also; sur. = surname; te. = temple; vi. = village, town; W. = Western; wo. = woman.

	PAGE		PAGE
Vajjaya, a prince, ...	84 n. 2	Varantantu, m., ...	105, 109
Vajrata, k., ...	125, 128	Vardhamāna, a śākṣī, ...	158, 161
Vāk-pāla, a Pāla k., ...	325, 329	Vardhamāna, m., ...	206
Vala, ...	306	Varēṭhā, vi., ...	198, 199, 202
Valabhi grant, spurious, ...	146	vari, ...	366 n. 4
Valabhi = Indra, ...	300, 306	Varidaḍu Narasayya, m., ...	343
Valakāṭṭūra, a śimā, ...	235	Varṇikā, ...	309
Vālaṇa, m., ...	208	Varaṇasārman, m., ...	167
Valandata, a gōtra, ...	155, 167	varuṣa = varuṣa, ...	169, 174
Vālā, m., ...	202	Vasādhana, m., ...	205
Vallabha, m., ...	75, 76, 81, 82	vāsaka, ...	70 n. 3
Vallabha, title of the W. Chalukya dy., ...	125, 128	Vasanta-Bhaṭṭa, m., ...	342
Vallabha-rāja, title of the W. Chalukya dy., ...	125, 128	Vasantatilaka-bhāṇa, a drama, ...	87
Vallakāṭṭhā, vi., ...	158, 159, 161	Vasimāna, a Khotan k., ...	133
Vallāla-Sēna, a Sēna k., ...	155, 158, 160, 162, 163	Vāsihka, a Kuṣāṇa k., ...	135, 149
Vālū, m., ...	204	Vasishṭha, a gōtra, ...	70-1, 73, 80-2, 202-9, 213, 327, 330
Vāmadēva, aspect of Śiva, ...	204, 274 n. 2	Vasishṭha, a pravara, ...	325, 330
Vamṇā, vi., ...	198, 199, 202	Vasishṭha, ...	296, 298, 303
Vāmana-Bhaṭṭa, m., ...	213, 325, 328, 330	Vasishṭha-Gōḍāvari, vi., ...	89, 94, 96
Vāmananaga, m., ...	126, 127, 129	Vāsiṭhputa-sāmi-Siri-Puṣṇmāvi (II.), k., ...	154
Vāmana-Svāmin, m., ...	203	vāsta, ...	158, 161
Vārṇadhara, m., ...	204, 205	Vāsu (Ōvāsu), m., ...	158, 160, 163
Vana-mūlā, ...	299, 305	Vāsudēva, ...	102, 107, 135, 194, 196, 198, 200, 204, 209
Vanamālin, ...	305 n. 1	Vāsuki, ...	206
Vanaśarman, m., ...	167	Vasurāta, m., ...	203, 208
Vandhula, a gōtra, ...	202-3	Vasusārman, m., ...	166, 167
Vaṅga, co., ...	73, 79, 170, 173, 316, 367-70	Vataka, ...	73-4
Vaṅkūnai, a paṭṭalā, ...	197, 199, 200, 202	vāṭava, ...	300
vaṅsa, ...	177	Vaṭayakṣhiḍi-Dēvi, a deity, ...	177, 178, 182, 184, 188
Vāpū, m., ...	205	Vāṭhu, m., ...	207
vāpa, ...	296, 316	Vata, m., ...	203, 208
Varada-Bhaṭṭa, m., ...	314, 315, 320	Vata, a gōtra, ...	202-3, 206-9, 335-6
Varada-āchārya, an author, ...	87	Vataśrāja, a Pratihāra k., ...	178, 179, 183
Varadarāja-stava, a poem, ...	85	Vāyih, m., ...	205
Varadaviśhvārya, m., ...	87	Vavvūlika, a field, ...	181, 187
varāṣa, a coin, ...	354, 359 & n. 7	vāda, śākhā, sūtra—	
Varāṣa incarnation, ...	71, 78, 90, 147, 170, 174, 216, 230	Āpṣatamba-s., ...	85, 216, 313, 317, 342, 346
Varāṣa-dēva, m., ...	158, 161	Atharva-v., ...	165-7
Varāṣa-pullī, vi., ...	187	Bōdhāyana-s., ...	314-5
Varakāṭṭāru, a śimā, ...	232	Drāhyāyana-s., ...	343
Varaṇā, vi., ...	193, 194, 196, 197, 199	Hiranyakṣī-s., ...	151
Vāraṇasī = Benares, ...	366	Kanṭhuma-ś., ...	158, 161
Vāraṇasī Koṇḍu-Bhaṭṭa, m., ...	343	Pravachana-s., ...	216
Vāraṇasivam, ...	189, 191		
Varaṇsigila, an estate, ...	148, 150, 152		

The figures refer to pages; n. after a figure to footnotes, and add. to Additions and Corrections. The following other abbreviations are used:—śā.—chief; co.—country; di.—district, division; ds.—the same, ditto; dy.—dynasty; E.—Eastern; feud.—feudatory; k.—king; m.—man; mt.—mountain; ri.—river; s. a.—see also; sur.—surname; te.—temple; vi.—village, town; W.—Western; w.,—woman.

	PAGE		PAGE
vēda, śākhā, sūtra— <i>contd.</i>		Vijayāditya, a <i>W. Chalukya k.</i> ,	146, 189
Rig-v., ...	61, 62, 212-6, 314-5, 343, 360, 362-3	Vijayakīrti, a <i>Khotan k.</i> , ...	142
Sāma-v., ...	216, 314	Vijayanagara, <i>dy.</i> , ...	69, 98 n. 1, 107 n. 1, 169, 211, 232, 317, 323, 331, 341
Taittiriya-ś., ...	148, 151	Vijayanagara, <i>vi.</i> , ...	70, 79, 102, 107, 167, 240
Vājasaneyi-ś., ...	272, 276, 314, 325, 327	Vijayapāla, a <i>Pratihāra k.</i> , ...	179, 180
Yajur-v., ...	71, 81-2, 85, 212-5, 313-5, 317, 342-3, 360, 362-3	Vijayarāya-ndaiyar, a <i>prince</i> , ...	70 n. 1
Vēda, ...	120, 178, 198, 199, 200, 207, 317	Vijaya-śādhāra, <i>m.</i> , ...	296, 303, 310
Vēda, Atharva, ...	165, 166	Vijaya-samudra, a <i>tank</i> , ...	69, 80
“ Sāma, ...	158, 161	Vijaya-sēna, a <i>Sēna k.</i> , ...	157, 159, 160, 162
Vēdāchārya-Bhaṭṭa, <i>m.</i> , ...	87, 88, 88 n. 2, 93, 96	Vijayasinhha, a <i>Khotan k.</i> , ...	142
Vēdam Raghava-Bhaṭṭa, <i>m.</i> , ...	342	Vikkaya, a <i>Sinda cā.</i> , ...	268
Vēdānga, ...	360, 362-3	Vikrama, <i>era</i> , ...	110, 112, 114
Vēdānta, ...	317, 346, 357-9	Vikrama era referred to. <i>S. a. era</i> , ...	139-141
Vēdānta-dēśika, <i>sur. of Venkatasāthārya</i> , ...	87, 88	Vikrama, a <i>Sinda cā.</i> , ...	268
Vēdāntadēśika-vaishnava-prakāśikā, a <i>book</i> , ...	87	Vikramāditya I., a <i>W. Chalukya k.</i> , ...	146
Vēdānta-vēdyā, <i>m.</i> , ...	86, 93, 96	Vikramāditya II., “ “ “	189, 190
Vēdavyāsa, <i>sur. of Sudartana-Bhaṭṭa</i> , ...	87	Vikramāditya VI., “ “ “	268
Vēdaya, <i>m.</i> , ...	315, 321	Vikramāditya, a <i>Mālava k.</i> , ...	293, 294
Veļimala, <i>di.</i> , ...	173, 175	Vikramāditya, <i>sur. of Gāṅgāya-dēva</i> , ...	158
Vēmasāni, a <i>Reddī queen</i> , ...	70	Vikramāditya, <i>m.</i> , ...	325, 328, 330
Vēmmaṇa-Bhaṭṭa, <i>m.</i> , ...	214	Vikrama-pura, a <i>camp</i> , ...	158, 160
Vendikē Basava-amātya, <i>m.</i> , ...	215	Vilachchhē, <i>vi.</i> , ...	151, 152
Vēnkata-dēva-Rāja, a <i>Vijayanagara k.</i> , ...	230, 343-4, 353	Vilāsa-dēvi, <i>q. of Vijaya-Sēna</i> , ...	158, 160, 161, 163
Vēnkatādri, <i>sur.</i> , ...	171, 172, 216, 216	Vilāsa-pura, <i>vi.</i> , ...	325, 327, 330
Vēnkatasāthārya—a <i>Śrī-Paishāra teacher</i> , ...	87	Villia, <i>m.</i> , ...	208
Vēnkatēśvara, <i>m.</i> , ...	315, 320	Villhaṇa, <i>m.</i> , ...	203
Vēnkatay[ya], <i>m.</i> , ...	343	Villha Śrī-Yajur-vēda-charaṇē chatur-vēdin, <i>m.</i> , ...	204
Vēnnarasa, <i>m.</i> , ...	215	Villūru, <i>vi.</i> , ...	88, 89, 94, 96
Vēparaka, <i>vi.</i> , ...	155	Vima-Kadphises, a <i>Kushāna k.</i> , ...	141, 280, 290, 293, 294
Vibhishāṇa, ...	88	vināśpaka, ...	293, 302
Vidagdhā, <i>m.</i> , ...	161	Vināyaka-Bhaṭṭa, <i>m.</i> , ...	214
Vidhi-Karaṇi Gaṅgādhara, <i>m.</i> , ...	209	Vināyaka-pāla-dēva, a <i>Pratihāra k.</i> , ...	178, 179, 180, 183
Vidyādhara, <i>m.</i> , ...	209	Vīṇyāna, ...	364-5
Vidyādhara, a <i>Chāṇḍēla prince</i> , ...	179 n. 4	viprēndra, <i>m.</i> , ...	212
Vidyāghana, a <i>Kāśchī śāchārya</i> , ...	234	Virabhadra, ...	280, 282
Vidyākara, <i>m.</i> , ...	309	Virāja Basava-rāja, <i>m.</i> , ...	215
Vidyānaguri—Vijayanagara, ...	230, 344, 353	vir-ābhishēka, ...	84
Vidyātirtha, a <i>Kāśchī śāchārya</i> , ...	234	Vira-Bhūpati, a <i>Vijayanagara k.</i> , ...	70 n. 6
Vigraha-Pāla, a <i>Pāla k.</i> , ...	325, 326, 327, 329, 330	Vira-Bukka, <i>sur. of Vijaya-Bhūpati</i> , ...	70
Vijaya-Bhūpati, a <i>Vijayanagara k.</i> , ...	69, 72, 79, 80	Vira-dēva, a <i>Sinda cā.</i> , ...	269
Vijaya-Bhūpati, Dandapalle plate of, ...	68	Vira-Kalidēva, a <i>divinity</i> , ...	282
Vijaya-Bukkarāya-samudra, <i>vi.</i> , ...	70, 71	virāna, use of, ...	69
Vijayachandra, <i>m.</i> , ...	361	Viramarasa, <i>m.</i> , ...	215
Vijayadēvavarman, <i>k.</i> , ...	141		

The figures refer to pages; n. after a figure to footnotes, and *add.* to Additions and Corrections. The following other abbreviations are used:—*cā.*—chief; *co.*—country; *di.*—district, division; *do.*—the same, ditto; *dy.*—dynasty; *E.*—Eastern; *feud.*—feudatory; *k.*—king; *m.*—man; *mt.*—mountain; *ri.*—river; *s. a.*—see also; *sur.*—surname; *te.*—temple; *vi.*—village, town; *W.*—Western; *wo.*—woman.

	PAGE		PAGE
Viraṅga, <i>m.</i>	231, 240, 342, 352-3	Viśvāmītra, <i>a gōtra</i> ,	81-2, 314-5
Viraṅga-āchārya, <i>m.</i>	174, 175, 216, 235, 240,	Viśvanātha-Bhaṭṭa, <i>m.</i> ,	214
	315, 322, 323, 352-3	Viśvarūpa, <i>m.</i> ,	204, 208
Viraṅgāsūri, <i>m.</i> = Viraṅga-āchārya,	240	Viśvarāman, <i>k.</i> ,	140, 370-1
Vira-Nṛsiṃha, <i>a Vijayanagara k.</i> ,	171, 175, 230	Viśveśvara, <i>m.</i> ,	208
	231, 232, 233,	Viṭā-Bhaṭṭa, <i>m.</i> ,	314, 319
	235, 240, 323	Viṭhala, <i>m.</i> ,	314, 320
Vira-Obajadēva, <i>a Chōla k.</i> ,	70 n. 1	Viṭhu, <i>m.</i> ,	202, 204, 207, 208, 209
Viraṅga-mātya, <i>m.</i> ,	215	Viṭhala, <i>m.</i> ,	76, 82
Vira-pratāpa, <i>sur. of Kṛishṇa-dēva-Rāya II.</i> ,	173, 175	Viṭthalēśvara, <i>a divinity</i> ,	231, 341, 345, 353
Viraśeṣa-Svāmin, <i>k.</i> ,	140	Viṭṭhanna-Odeya, <i>m.</i> ,	70
Vira-Śrī-Nārasiṃha = Vira-Nṛsiṃha, <i>a Vijayana-</i>		Viyadi, <i>a place</i> ,	148, 150, 152
<i>gara k.</i> ,	232, 240	Vṛiḥadrībhēvaṃkānai, <i>a pattalā</i> ,	193, 195, 196, 202
Viravarman, <i>a Gaṅga k.</i> ,	333	Vṛiḥadrībhē-ḍēvarātha, <i>a pattalā</i> ,	197, 198, 199, 202
Vira-Vijaya, <i>sur. of Vijaya-Bāṇpati</i> ,	70	Vṛiḥatālā, <i>vi.</i> ,	195, 196
Virūchi-pura, <i>m.</i> , <i>a shrine</i> ,	280, 282, 312, 316, 323	Vṛiḥatyañchalāma, <i>vi.</i> ,	195, 196
Virūpākṣa = Śiva,	102, 107, 173, 175,	Vṛiḥa, <i>a gōtra</i> ,	82
	312, 317, 323	vṛiḥabha-saṃkara nala, <i>a measure</i> ,	158, 161
Virupparṇa, <i>m.</i> ,	215	vṛiḥa-viṃśōpaka,	296, 302, 309
Virvaḷḷa, <i>vi.</i> ,	317, 323	Vṛiḥṇa, <i>a gōtra</i> ,	81
Viśākhā,	169, 173, 175	Vṛitika, <i>m.</i> ,	202, 208
visarga, at end of verse,	100, 105	Vṛitti, <i>a shrine</i> ,	316
„ omitted,	177	vṛitti, <i>aṣṭa</i> ,	211, 231, 313, 315, 322
„ redundant,	147, 311	Vadharāmānyl, <i>vi.</i> ,	198, 199, 202
„ sandhi of,	97	vadhaka, <i>a measure</i> ,	296, 302, 309
„ use of,	164, 168, 341	vy, form of,	144
vishaya,	261	Vyāghra-tatāka, <i>a place (tank)</i> ,	148, 150, 152
vishaya-dāna, <i>a tax</i> ,	196	vyākaraṇa,	325, 327
vishayapati, <i>an official title</i> ,	126, 129, 150, 160, 327	Vyāsa,	203
Vishṇu,	202		
Vishṇugōpa, <i>a Gaṅga k.</i> ,	332, 333, 334		
Vishṇukōpa = Vishṇugōpa,	332		
Vishṇupada, <i>a hill</i> ,	307, 370		
Vishṇuśarma, <i>m.</i> ,	166, 167		
Vishṇuvardhana, <i>k.</i> ,	139		
Vishṇuvanibhāsa I., <i>a Hoysala k.</i> ,	265		
Vishṇuvardhana, <i>a gōtra</i> ,	82		
Vishṇuvardhana, <i>a gōtra</i> ,	81		
viśṭi-prātibhēdikā,	152		
Vishṇu,	165, 166		
Vishṇu-saṃkrānti,	325, 328, 330		
Vissaga, <i>m.</i> ,	76, 82		
Viśva-saṃkrānti = Viśuva,	328, 330		
Viśva-chakra, <i>a mahādāna</i> ,	172		
Viśvakarma-āchārya, <i>m.</i> ,	337, 338, 339		
Viśvāmītra,	296, 304		

W

Wardak vase inscription,	132, 137
Water symbolized by <i>ga</i> ,	100, 105
Wind symbolized by <i>sa</i> ,	101, 105
Wu-cha, <i>vi.</i> ,	292
Wu-i-shan-li, <i>vi.</i> ,	291
Wu-k'ung, <i>a writer</i> ,	290
Wu-sun, <i>a race</i> ,	289
Wu-ta-kia-han-ch'a, <i>vi.</i> ,	291

Y

y, doubling before,	164
y, form of,	121, 232, 265-6
y in yṛta, etc.,	95

The figures refer to pages; *n.* after a figure to footnotes, and *add.* to Additions and Corrections. The following other abbreviations are used: *ch.* = chief; *co.* = country; *di.* = district, division; *do.* = the same, ditto; *dy.* = dynasty; *E.* = Eastern; *feud.* = feudatory; *k.* = king; *m.* = man; *mt.* = mountain; *ri.* = river; *s.* = see also; *sur.* = surname; *te.* = temple; *vi.* = village, town; *W.* = Western; *wo.* = woman.


	PAGE		PAGE
<i>ga</i> , symbol of water, ...	100, 105	years— <i>contd.</i>	
<i>Yādvā</i> , a race, ... 79 n. 1,	101, 100, 269	<i>Saka</i> 604, ...	123, 125, 129
<i>Yadu</i> , ...	101, 103, 171	804, ...	305-6
<i>Yajūn</i> , m., ...	202	868, ...	305-4
<i>Yajur-vēda</i> , ... 71, 81-2, 212-5, 312-5,	317	1095, ...	267, 272, 277
<i>Yajur-vēlins</i> , ...	315	1103, ...	267, 273, 277
<i>Yallārī-Bhatta</i> , m., ...	213, 214	1136 (error for <i>Vikrama</i>), ...	297, 303, 310
<i>Yamaka-ratnākara</i> , a poem, ...	85	1280, ...	88, 94, 96
<i>Yandāti Nara-simha</i> , m., ...	342	1291, ...	100, 103, 108
<i>Yasāhpāla</i> , a <i>Pratibāra k.</i> , ...	179, 205	1332, ...	69, 73, 80
<i>Yasāicha</i> , m., ...	209	1429, ...	233, 239, 240
<i>Yasā[h]kara</i> , m., ...	209	1450, ...	109, 174, 175
<i>Yasāhārman</i> , m., ...	167	1451, ...	312, 317, 323
<i>Yasāpāla</i> , m., ...	202	1470, ...	342, 345, 353
<i>Yasāōdōva</i> , m., ...	302, 309	1473, ...	211, 221, 231
<i>Yasāōdhara</i> , m., ...	202, 204, 208	1608, ...	354, 358-9
<i>Yasāvarman</i> , k., ...	180	<i>Vikrama</i> (?) 136, ...	284, 289, 295
<i>Yāsū</i> , m., ...	204	<i>Vikrama</i> 611, ...	110, 113, 118, 120
<i>Yati-rāja</i> , title of <i>Kāñchī āchāryas</i> , ...	233, 234	999, ...	177, 181, 187
<i>yavaga</i> , a <i>Kushāpa</i> title, ...	289	1003, ...	177, 178, 181, 182, 184
<i>Yayāti</i> , ... 101, 106, 116, 119, 171, 240,	323	1136 (written <i>Śaka</i>), ...	297, 303, 310
<i>Yayīm</i> , m., ...	204	1150, ...	192-4, 196
years—		1156, ...	192, 197-200
<i>Gaṅga</i> 149, ...	360, 362-3	regnal, ...	155, 158, 162, 185, 187, 325, 328, 330
<i>Kilaka</i> , ...	342, 345, 353	<i>Yāllā-Bhatta</i> , m., ...	315, 321
of the Cycle—		<i>Yen-kuo-chen</i> , a <i>Fue-chi k.</i> , ...	290
<i>Parābhava</i> , ...	365-6	<i>Yōga</i> , m., ...	76, 82
<i>Plava</i> , ...	267, 273, 277	<i>yōga</i> , <i>Lakṣmi-nārāyaṇa</i> , ...	69, 80
<i>Prabhava</i> , ...	354, 358-9	<i>yōga-paṭṭa</i> , ...	309
<i>Samya</i> , ...	100, 103, 108	<i>Yōga-Svāmin</i> , m., ...	202
<i>Subhakrit</i> , ...	365-6	<i>Yōgē</i> , m., ...	202
<i>Śukla</i> , ...	233, 239, 240	<i>Yōgēśvara</i> , m., ...	207
<i>Vijaya</i> , ...	267, 272, 277	<i>Ysamōtika</i> , a <i>Kāśātrapa</i> , ...	294
<i>Vikritin</i> , ...	69, 73, 80	<i>Yue-chi</i> , a race, ...	141, 288, 289, 292
<i>Virōdhakrit</i> , ...	211, 221, 231	<i>yuga</i> , ...	103, 108
<i>Virōdhin</i> , ... 169, 173, 175, 312, 317, 323		<i>yugāḍiparvan</i> , ...	198, 200
<i>Kali</i> 4470, ...	100, 103, 108		
<i>Kanishka</i> 41, ...	133, 135, 143		

Z

Zeda inscription, ... 131, 136

The figures refer to pages; n. after a figure to footnotes, and *add.* to Additions and Corrections. The following other abbreviations are used:—*cA.* = chief; *co.* = country; *di.* = district, division; *do.* = the same, ditto; *dy.* = dynasty; *E.* = Eastern; *feud.* = feudatory; *k.* = king; *m.* = man; *mt.* = mountain; *ri.* = river; *s. a.* = see also; *sur.* = surname; *te.* = temple; *vi.* = village, town; *W.* = Western; *wo.* = woman.





Central Archaeological Library,

NEW DELHI.

69329

Call No. R $\frac{417.05}{E.I.}$

India, Archaeological
Author Survey of India .

Epigraphia Indica .

"A book that is shut is but a block"

CENTRAL ARCHAEOLOGICAL LIBRARY
GOVT. OF INDIA
Department of Archaeology
NEW DELHI.

Please help us to keep the book
clean and moving.